



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>


A 3.A.1903.4

Harvard University
Library of
The Medical School
and
The School of Public Health



The Gift of





MANUAL OF ANATOMY.



NUNQUAM ALIUD NATURA, ALIUD SAPIENTIA DICIT.

^c
MANUAL
OF
PRACTICAL ANATOMY

BY

D. J. CUNNINGHAM,

M.D. (EDIN. ET DUBL.), D.SC., LL.D., D.C.L. (OXON.), F.R.S.,
PROFESSOR OF ANATOMY IN THE UNIVERSITY OF EDINBURGH

VOLUME FIRST

UPPER LIMB; LOWER LIMB; ABDOMEN

THIRD EDITION


ILLUSTRATED WITH 205 ENGRAVINGS, MANY IN COLOURS

PHILADELPHIA

J. B. LIPPINCOTT COMPANY

EDINBURGH AND LONDON: YOUNG J. PENTLAND

1903.



A3,A,1903.4

EDINBURGH : PRINTED FOR YOUNG J. FENTLAND, 11 TEVIOT PLACE, AND
38 WEST SMITHFIELD, LONDON, E.C., BY R. AND R. CLARK, LIMITED

All rights reserved.

P R E F A C E.

THE Manual of Practical Anatomy as it is now issued differs very considerably from previous editions. The text has been revised ; many details which are not essential have been cut out, whilst at the same time the author has endeavoured to make the descriptive matter more concise. The book therefore has not grown in bulk.

The sections in which the chief changes will be manifest are those which treat of the thoracic and abdominal viscera. At the time when the first edition was issued, our ideas of the form and relationships of the various viscera were undergoing rapid evolution. The value of the models prepared under the supervision of Professor His had received full recognition, and attempts were being made in various quarters to verify his results by similar and other methods. In the preface to that edition the author took the opportunity of pointing out that such specimens and models could only be regarded as giving one of the many different forms which are assumed by internal organs in connection with changes in the attitude of the body, and in connection with the alterations which are constantly going on in the living individual in the state of the hollow viscera. It was something, however, to be able to describe with some near approximation to truth

the form of the viscera under certain given conditions, even although these conditions might be only repeated in life when the body was in the horizontal position, and when one particular phase of the hollow viscera was present. In the same preface the author ventured to express the belief that before long more extended research would greatly extend our knowledge of the alterations in neighbouring organs which are produced by changes in the degree of expansion or contraction of the hollow viscera. How amply this belief has been warranted is seen in the work of Symington, Young, Birmingham, Addison, Huntington, Robinson, Dixon, Keith, Hepburn, and others. Formalin has been a powerful agent in the hands of these observers; and it so comes about that in the present edition, and largely through the labours of these Anatomists, it has been possible to correct many erroneous impressions on this subject, and also to speak with greater confidence, and with the increased clearness which such confidence brings, upon the topography of the viscera.

But perhaps the most noticeable feature of the present edition will be found in the illustrations. The great majority of the old figures have been withdrawn, and these have been replaced by others which are not only more suitable for the purpose for which they are intended, but also distinctly superior from the artistic point of view. In carrying out this part of the work the author has been so fortunate as to have had the services of Mr. J. T. Murray, an artist who has obtained an almost unrivalled reputation in the treatment of anatomical subjects. Several of the illustrations have been taken from the recently published *Text-book of Anatomy*, and the author has to express his indebtedness to the writers of the various articles which have furnished these for the ready manner in which they allowed their figures to be used for this purpose.

The sources from which all borrowed illustrations are taken are in every case indicated in the text.

The author desires to thank Dr. R. A. Stoney, Chief Demonstrator of Anatomy in Trinity College, for the valuable assistance he has given in the reading of the proof, and also Messrs. William Boxwell, Arthur M'Neight, and John Cunningham for much trouble taken in preparing the dissections from which many of the illustrations have been drawn.

43 FITZWILLIAM PLACE, DUBLIN,

March 1903.

CONTENTS.



THE UPPER LIMB.

	PAGE
INTRODUCTORY,	I
DISSECTION OF THE BACK,	2
PECTORAL REGION AND AXILLARY SPACE,	14
AXILLA,	23
SCAPULAR REGION,	41
FRONT OF THE ARM,	53
BACK OF THE ARM,	73
SHOULDER-JOINT,	79
FOREARM AND HAND,	85
FRONT AND INNER BORDER OF THE FOREARM,	88
WRIST AND PALM,	101
BACK AND OUTER BORDER OF THE FOREARM,	120
DORSAL ASPECT OF THE WRIST AND HAND,	130
ARTICULATIONS,	136

THE LOWER LIMB.

GLUTEAL REGION,	153
POPLITEAL SPACE,	171
BACK OF THE THIGH,	180
FRONT OF THE THIGH,	186
SUPERFICIAL DISSECTION OF THE FRONT OF THE THIGH,	187
DEEP DISSECTION OF THE FRONT OF THE THIGH,	196
INNER SIDE OF THE THIGH,	219
HIP-JOINT,	229
THE LEG,	235

	PAGE
ANTERIOR TIBIO-FIBULAR REGION—DORSUM OF FOOT, .	237
PERONEAL REGION,	249
TIBIAL REGION,	251
POSTERIOR TIBIO-FIBULAR REGION,	252
SOLE OF THE FOOT,	264
KNEE-JOINT,	283
ANKLE-JOINT,	294
TIBIO-FIBULAR JOINTS,	296
ARTICULATIONS OF THE FOOT,	299

ABDOMEN.

MALE PERINEUM,	309
RECTAL TRIANGLE,	313
UROGENITAL TRIANGLE,	318
THE FEMALE PERINEUM,	332
RECTAL TRIANGLE,	337
UROGENITAL TRIANGLE,	337
ABDOMINAL WALL,	344
SURGICAL ANATOMY OF THE ABDOMINAL WALL,	384
ABDOMINAL CAVITY AND ITS CONTENTS,	392
VESSELS ON THE POSTERIOR WALL OF THE ABDOMEN,	485
FASCIA AND MUSCLES ON THE POSTERIOR WALL OF THE ABDOMEN,	492
NERVES ON THE POSTERIOR WALL OF THE ABDOMEN,	495
PELVIS,	501
MALE PELVIS,	502
PELVIC ARTICULATIONS,	559
FEMALE PELVIS,	564
INDEX,	589

LIST OF ILLUSTRATIONS.



FIG.	PAGE
1. Lines of incision for reflection of skin from dorsal aspect of subject,	3
2. Dissection of the Superficial Muscles of the Back,	5
3. Upper Surface of the Right Clavicle,	7
4. Diagram of the Lumbar Fascia,	9
5. Lines of incision for reflection of skin from ventral aspect of the subject,	16
6. Dissection of the Mammary Gland,	18
7. Section through a Mammary Gland,	20
8. Diagram of section through the Axilla of the Left Side,	24
9. Diagram to show relation of Brachial Nerves to Axillary Vessels,	28
10. Diagram of the Costo-coracoid Membrane,	29
11. The Axillary Artery and its Branches,	33
12. Under surface of the Clavicle with the Attachments of the Muscles mapped out,	35
13. Diagram of the Brachial Plexus,	36
14. Ventral aspect of the Scapula with the Attachments of Muscles mapped out,	40
15. Dissection of the Posterior Scapular Region,	44
16. Diagram of the Circumflex Vessels and Nerve,	46
17. Dorsum of Scapula with Attachments of Muscles mapped out,	49
18. Posterior view of the Upper Limb, with the Elbow-joint fully extended. (LUSCHKA),	54
19. Posterior view of the Upper Limb, with the Elbow-joint flexed. (LUSCHKA),	54
20. Cutaneous Nerves on the Front of the Upper Limb,	58
21. Cutaneous Nerves on the Posterior Aspect of the Upper Limb,	59
22. Diagram to show the arrangement of the Intermuscular Septa in the Arm. (TURNER),	62
23. Transverse section through the Lower Third of the Right Upper Arm,	63

FIG.	PAGE
24. Transverse section through the middle of the Right Upper Arm,	65
25. Diagram to show relation of Musculo-spiral Nerve to the Humerus and of Vessels and Nerves to the Intermuscular Septa,	67
26. Anterior aspect of Humerus with Muscular Attachments mapped out,	70
27. Dissection of the Antecubital Fossa,	72
28. Posterior aspect of Humerus with Attachments of Muscles mapped out,	75
29. Dissection of the Posterior Aspect of Upper Arm,	77
30. Coronal or vertical transverse section through the Left Shoulder-joint. (Viewed from behind),	80
31. Shoulder-joint as seen from the front,	82
32. Capsular Ligament cut across and Humerus removed,	84
33. Transverse section through the Upper Third of the Left Forearm,	91
34. Anterior aspect of Bones of Forearm with Muscular Attachments mapped out,	99
35. Diagram of Nerves and Vessels of Hand in relation to Bones and Skin Markings,	102
36. Transverse section through the Wrist at the level of the Second Row of Carpal Bones to show the Carpal Tunnel,	110
37. To illustrate the arrangement of the Synovial Sheaths around the Flexor Tendons,	112
38. Flexor Tendons of the Finger and Vincula Accessoria,	114
39. Palmar aspect of Bones of Carpus and Metacarpus with Muscular Attachments,	116
40. Dorsal aspect of Bones of Carpus and Metacarpus with Muscular Attachments,	122
41. Posterior aspect of Bones of Forearm with Attachments of Muscles mapped out,	125
42. Dissection of the Back of the Forearm and Hand,	127
43. Diagram of Anastomosis around the Elbow-joint,	129
44. Transverse section through Forearm immediately above Wrist-joint to show the arrangement of the Tendons,	132
45. Arrangement of the Flexor and Extensor Tendons of the Middle Finger. (LUSCHKA),	133
46. Vertical section through Humerus and Ulna at the Elbow-joint,	136
47. Inner aspect of the Elbow-joint,	137
48. Anterior aspect of the Elbow-joint,	138
49. Carpal Articular Surfaces of the Radius and of the Triangular Fibro-cartilage of the Wrist	141
50. Coronal section through Radio-carpal, Carpal, and Carpo-metacarpal and Inter-metacarpal Joints,	147
51. Cutaneous Nerves on the posterior aspect of the Lower Limb,	156

LIST OF ILLUSTRATIONS.

xiii

FIG.	PAGE
52. Outer aspect of the Innominate Bone with the Attachments of the Muscles mapped out,	159
53. Dissection of the Gluteal Region,	162
54. Dissection of the Right Popliteal Space,	174
55. Transverse section through the Popliteal Space of the Right Lower Limb,	175
56. Popliteal Artery and its Branches,	178
57. Dissection of the Back of the Left Thigh,	182
58. Front aspect of upper portions of Bones of Leg with Attachments of Muscles mapped out,	183
59. Cutaneous Nerves on the front of the Lower Limb,	193
60. Diagram to show the arrangement of the three Intermuscular Septa and the three Osteo-fascial Compartments of the Thigh. (TURNER),	195
61. Dissection to show the Femoral Sheath and the other structures which pass between Poupart's Ligament and the Innominate Bone,	200
62. Dissection of Scarpa's Triangle,	204
63. Dissection of Hunter's Canal in the Left Lower Limb,	208
64. Transverse section through Hunter's Canal,	209
65. Transverse section through the Middle of the Thigh,	210
66. Front aspect of upper portion of Femur with Attachments of Muscles mapped out,	217
67. Profunda Femoris Artery and its Branches,	221
68. Back aspect of upper portion of Femur with the Attachments of Muscles mapped out,	223
69. To illustrate the distribution of the Obturator Nerve and the general disposition of the Adductor Muscles of the Thigh. (PATERSON),	225
70. Dissection to show the structures surrounding the Thyroid Foramen of the Innominate Bone,	226
71. Dissection of Hip-joint from the front,	230
72. Dissection of Hip-joint from behind,	233
73. Diagrammatic representation of the Fascia of the Leg,	240
74. Transverse section through the Calf of the Leg,	242
75. Dissection of the Dorsum of the Foot,	246
76. Coronal section through the Left Ankle-joint, Astragalus, and Calcaneum. (PATERSON),	248
77. Posterior aspect of lower portion of Femur with Attachments of Muscles mapped out,	255
78. Posterior aspect of Bones of Leg with Attachments of Muscles mapped out,	260
79. Dissection of the Inner Ankle,	262
80. Plantar Fascia and Plantar Cutaneous Nerves. (PATERSON),	265
81. Plantar aspect of Tarsus and Metatarsus with Attachments of Muscles mapped out,	268

FIG.	PAGE
82. Second layer of Muscles and Tendons in the Sole of the Foot,	273
83. The Muscles in the Sole of the Right Foot after removal of the second layer. (PATERSON),	275
84. Arteries and Nerves of the Sole of the Foot,	278
85. The insertions of the Tibialis Posticus and Peroneus Longus Muscles in the Right Foot. (PATERSON),	280
86. Anastomosis on the front of the Right Knee-joint,	281
87. Dissection of Knee-joint from the front,	284
88. The External Lateral Ligament of the Knee-joint,	285
89. Vertical antero-posterior section through the Knee-joint,	288
90. Parts attached to the upper end of the Right Tibia,	293
91. Articular surfaces of Tibia and Fibula which articulate with the Astragalus,	295
92. Vertical section through the Foot. (LUSCHKA),	298
93. Astragalus removed so as to show the socket for its head,	300
94. Outlet of Male Pelvis,	309
95. Lines of incision for reflection of skin in the dissection of the Perineum,	311
96. Diagram of the Pelvic Fascia,	314
97. Dissection of the Perineum,	317
98. Transverse section through the body of the Penis,	320
99. The Root of the Penis and the Triangular Ligament,	321
100. Dorsal or attached aspect of the Penis,	322
101. Deep dissection of the Perineum,	325
102. Vertical section through the Pubic Arch to show the two Perineal Compartments and their contents,	329
103. Deep dissection of the Perineum,	331
104. Outlet of Female Pelvis,	333
105. External Genitalia of the Female,	334
106. Muscles of the Female Perineum. (After PETER THOMPSON),	338
107. Dissection of Female Perineum,	341
108. Lines of incision for reflection of skin from the ventral aspect of the subject,	346
109. Dissection of Anterior Wall of the Abdomen,	349
110. Crest of the Ilium as seen from above,	353
111. Dissection of the External Abdominal Ring,	354
112. Dissection to show the connections of the lower part of the Aponeurosis of the External Oblique Muscle,	355
113. Dissection of the Inguinal Region,	359
114. To illustrate the relation of the lower border of the Internal Oblique Muscle,	360
115. Diagram of the Muscular Strata of the Abdomen (the dotted line represents the Peritoneum),	363
116. Deep dissection of the Anterior Wall of the Abdomen,	364
117. Transverse section through the Abdominal Wall a short distance above the Pubis,	367


LIST OF ILLUSTRATIONS.

XV

FIG.	PAGE
118. Deep dissection of the Inguinal Region,	368
119. Illustrating the descent of the Testicle,	375
120. Dissection of the Left Spermatie Cord. (WALDEYER, modified),	378
121. Transverse section through the left side of the Scrotum and the Left Testicle,	379
122. A. The Right Testis and Epididymis within the Tunica Vaginalis. B. The Right Testis and Epididymis seen from behind. (DIXON),	380
123. Illustrating the structure of the Testicle. (DIXON),	383
124. To show the different peritoneal relations in an ordinary Inguinal Hernia,	387
125. To illustrate the four different varieties of Infantile Hernia. (LOCKWOOD),	388
126. Median section through the terminal part of the Penis,	391
127. Outline of the Abdominal Cavity as seen in mesial section,	394
128. Planes of subdivision of the Abdominal Cavity,	395
129. The Abdominal Viscera as seen from the front after removal of the Jejunum and Ileum with their Mesentery,	399
130. Anterior Surface of the Liver,	401
131. The Spleen (visceral aspect),	404
132. The Œsophagus, Stomach, and Duodenum,	405
133. Stomach of a Child,	406
134. The Stomach removed from its bed so as to display the recess in which it lies,	408
135. From a tracing of a transverse section through the Abdomen,	415
136. To illustrate the continuity of the Peritoneum in the vertical direction in the Female. (BIRMINGHAM),	418
137. Section through the Peritoneal Cavity at the level of the Foramen of Winslow,	421
138. Section at the level of the Umbilicus through the Intervertebral Disc between the third and fourth Lumbar Vertebrae,	422
139. The Mesentery in a subject which was hardened by formalin injection,	428
140. Dissection of the Superior Mesenteric Artery,	431
141. Dissection of the Inferior Mesenteric Artery,	435
142. Peyer's Patch and Solitary Glands from the Intestine of a Child of two years old. (BIRMINGHAM),	440
143. Cæcum which has been distended with air and dried, and then opened to show Ileo-Cæcal Opening and Valve,	442
144. Ileo-Cæcal Opening and Valve from a subject hardened by formalin injection. (BIRMINGHAM),	443
145. The Coeliac Axis System of Vessels,	444
146. Duodenum, Pancreas, and Kidneys. (HIS),	450
147. Dissection of Pancreas from behind to show its Ducts. (BIRMINGHAM),	454

FIG.	PAGE
148. Dissection of the three layers of Muscular Fibres in the Wall of the Stomach,	459
149. A. Pyloric Orifice of Stomach as seen from the Duodenum. B. Longitudinal section through Pylorus and beginning of Duodenum,	460
150. The Bile-Papilla in the interior of the Duodenum. (BIRMINGHAM),	461
151. The Inferior or Visceral Surface of the Liver,	464
152. Posterior Surface of the Liver,	465
153. Liver, Right Kidney, Spleen, and Stomach, as seen from behind,	466
154. Cystic and Hepatic Ducts. (GEGENBAUR, modified),	468
155. Section through Abdomen at the level of the second Lumbar Vertebra,	473
156. Right Kidney and Duodenum,	474
157. Relations of the Left Kidney and the Pancreas,	475
158. Transverse section through Abdomen at the level of the first Lumbar Vertebra,	476
159. Dissection from behind to show the relation of the two Pleural Sacs to the Kidneys,	477
160. To show the form of the Pelvis of the Ureter and the Calices. (From a figure by MAX BRÖDEL),	478
161. Two Renal Papillæ,	479
162. Anterior Surface of Right Suprarenal Capsule,	479
163. Anterior Surface of Left Suprarenal Capsule,	480
164. Posterior Surface of the Anterior Wall of the Thorax and Abdomen. (LUSCHKA),	482
165. Diagram of Lumbar Plexus,	498
166. The Lumbar Plexus,	499
167. Side view of Pelvic Viscera. (From WILSON'S <i>Anatomy</i>),	503
168. The Peritoneum of the Pelvic Cavity,	505
169. Diagram of the Pelvic Wall and Pelvic Floor,	507
170. Dissection to expose the Pelvic Fascia from the outer side. (After THOMSON),	508
171. Dissection of the Pelvic Fascia. (After THOMSON),	509
172. Inner aspect of the Lateral Wall of the Pelvis,	513
173. Vertical section through the Pubic Arch to show the two Perineal Compartments and their contents,	514
174. Diagrammatic representation of coronal section through Pelvis to show the arrangement of the Pelvic Fascia. (DÉLÉPINE),	515
175. Diagrammatic representation of coronal section through the Pelvis to show the arrangement of the Pelvic Fascia. (DÉLÉPINE),	516
176. Representing the Pelvic Fascia in section. (DÉLÉPINE),	517
177. Dissection of the Rectum from the front in a specimen hardened by formalin injection,	519

FIG.	PAGE
178. Dissection of the Rectum from behind. (BIRMINGHAM),	521
179. Coronal section through the whole length of the Anal Canal. (SYMINGTON),	523
180. Bladder hardened <i>in situ</i> . (DIXON),	524
181. Bladder hardened <i>in situ</i> . (DIXON),	525
182. Mesial section through the Pelvis of an Adult Male,	527
183. Mesial section through a Male Pelvis, in which the Bladder is greatly distended,	528
184. Mesial section through the Pelvis of a newly-born full-time Male Infant,	529
185. Basal aspect of Bladder, Seminal Vesicles, and Prostate hardened by formalin injection,	532
186. Horizontal section through the Bladder and Rectum at the level at which the Ureters enter the Bladder,	533
187. Dissection of the two Levatores Ani,	540
188. The Sacral and Sacro-coccygeal Plexuses, as seen from behind,	542
189. The lower part of the Rectum and the Anal Canal opened up. (CHARLES B. BALL),	549
190. Interior of Bladder in region of the Urethral Orifice. (DIXON),	551
191. Diagram of the Bladder, Urethra, and Penis. (DÉLÉPINE),	553
192. Median section through the terminal part of the Penis,	556
193. Transverse section through the body of the Penis,	558
194. Section through the Sacro-iliac Joint. (LUSCHKA),	561
195. Horizontal section through the Symphysis Pubis. (LUSCHKA),	563
196. Mesial section through Female Pelvis,	565
197. Horizontal section through the Urethra, Vagina, and Anal Canal, a short distance above their terminations. (HENLE),	566
198. The Uterus, with the Broad Ligament stretching out from either side of it. (GEGENBAUR),	567
199. Mesial section through the Female Pelvis to show the disposi- tion of the Peritoneum in relation to the Viscera and the Lateral Wall of the Cavity. (DIXON and BIRMINGHAM),	568
200. Mesial section through a Female Pelvis,	571
201. Diagram of the Vulva, Vagina, and the Uterus with its Append- ages. (SYMINGTON),	575
202. The Uterus, with the Broad Ligament stretching out from either side of it. (GEGENBAUR),	576
203. Left Side Wall of Female Pelvis to show position of the Ovary,	578
204. The Ampulla and Fimbriated End of the Fallopian Tube; the Ovary; and the Parovarium. (GEGENBAUR, modified),	579
205. Interior of the Uterus. (LUSCHKA),	584



MANUAL OF ANATOMY.

MANUAL OF PRACTICAL ANATOMY.



THE UPPER LIMB.

THE dissector of the upper limb begins work on the third day after the subject has been placed in the dissecting-room. He will then find the subject stretched out at full length upon its face, with the pelvis and chest supported by blocks (Fig. 1); and while the body remains in this position he must examine those structures which connect the limb to the posterior aspect of the trunk.

Surface Anatomy.—Before proceeding to the actual dissection of any region, the student should make it an invariable practice to familiarise himself with the bony prominences within its area. It is by using these as landmarks that the surgeon is enabled to establish the position of the component parts of the body in the living subject. In the middle line of the back there will be little difficulty in recognising the spines of the vertebræ. These follow each other in consecutive order, and it will be observed, when the finger is passed over them, that they do not, in every case, occupy the mesial plane; some of them may be deflected, in a slight degree, to one side or the other. The spines of the vertebræ are the only parts of the vertebral column which come to the surface; they alone yield direct information, by touch, to the surgeon as to the condition of the spine. At the lower end of the neck, the spine of the seventh cervical vertebra (*vertebra*

prominens) makes a visible projection; and the spines of the first two dorsal vertebræ are likewise very prominent. As a rule, the most evident of the three is that of the first dorsal vertebra. At a lower level, in subjects of good muscular development, a mesial furrow is produced by the prominence of the erector spinæ muscle on each side, and the spines of the vertebræ in this locality may be felt at the bottom of the groove. The furrow attains its greatest depth in the upper part of the lumbar region, and it fades away below at the level of the spine of the third sacral vertebra. The finger should next be passed along the crest of the ilium as it pursues its sigmoid course forwards and outwards. The highest point of the iliac crest corresponds in level with the spine of the fourth lumbar vertebra, and the posterior superior spine of the ilium lies in a slight depression on a level with the second sacral spine. The scapula is for the most part thickly covered by muscles; but, in spite of this, its general outline can be made out. The scapula covers a considerable area of the upper portion of the chest-wall on its posterior aspect. With the hand by the side its superior angle corresponds with the second intercostal space, the root of its spine lies opposite the spine of the third dorsal vertebra, whilst its inferior angle reaches down as far as the seventh, or even the eighth, rib. The scapula is very mobile, and moves to a greater or less degree with every movement of the limb. The spine and acromion process of the scapula are subcutaneous throughout. Below the scapula the lower five ribs can be felt, and the tip of the last rib can be made out to reach a point about two inches above the iliac crest.

DISSECTION OF THE BACK.

In this dissection the following are the parts which require to be examined:—

1. The cutaneous vessels and nerves of the back.
2. The trapezius muscle.
3. The latissimus dorsi muscle.
4. The rhomboid muscles and their nerve of supply.
5. The levator anguli scapulæ muscle.

6. The spinal accessory nerve and the nerves from the cervical plexus which supply the trapezius.
7. The transversalis colli artery and its two terminal branches (viz. the posterior scapular and the superficial cervical).
8. The posterior belly of the omo-hyoid muscle.
9. The suprascapular artery and nerve.-

This dissection must be completed *in two days*, in order that the dissector of the head and neck may be enabled to continue the deeper dissection of the back. The *first day's work* should comprise—(1) the reflection of the skin; (2) the dissection of the cutaneous nerves and vessels; and (3) the cleaning of the latissimus dorsi and trapezius muscles. The remainder of the dissection can be undertaken on *the second day*.




FIG. 1.

Reflection of the Skin.—The following incisions are necessary:—1. From the tip of the coccyx upwards, along the middle line of the body to the spine of the seventh cervical vertebra. 2. From the upper end of the foregoing mesial incision transversely outwards, to the inner border of the acromion process of the scapula. 3. From the lower extremity of the mesial incision in a curved direction outwards and forwards, along the crest of the ilium, to within two inches of the anterior superior iliac spine. 4. An oblique incision from the spine of the first lumbar vertebra, upwards and outwards, to the outer border of the acromion process. The two large flaps which are now mapped out upon the back must be carefully raised from the subjacent fatty tissue. Reflect the upper triangular flap first, and then deal in the same way with the lower flap.

Superficial Fascia.—The fatty layer which is now exposed is termed the *superficial fascia*. It constitutes the cushion upon which the skin rests, rounds off the angularities of the body, and varies in thickness according to the obesity of the subject. In subjects which have been allowed to lie for

some time on the back it is usually more or less infiltrated with fluid which has gradually gravitated into its loose meshes. The superficial fascia constitutes the bed in which the cutaneous vessels and nerves ramify before they enter the skin; and it is separated from the muscles by a tough, but thin, layer of fibrous tissue, devoid of fat, which forms another investment for the body. This aponeurotic membrane receives the name of the *deep fascia*; it can be readily demonstrated by making an incision in the superficial fascia, and raising a small portion of it.

Dissection.—In searching for a cutaneous nerve, cut boldly down through the superficial fascia in the direction in which the nerve runs, until the plane at which the superficial and deep fasciæ blend is reached. It is here that the main trunks are to be found; and in a well-injected subject the cutaneous arteries constitute the best guides. A more rapid way of finding the cutaneous nerves in this region is to reflect in one layer both the superficial and the deep fascia outwards from the vertebral spines. The nerves are seen piercing the muscles. This plan, however, should only be adopted by the senior student.

Cutaneous Vessels and Nerves.—The *cutaneous nerves* of the back are derived from the posterior primary divisions of the spinal nerves. As the latter pass backwards, they divide into external and internal branches. Both of these supply twigs to the muscles amongst which they lie; but one or other also contains some sensory fibres which come to the surface, in the shape of a cutaneous nerve, to supply the skin.

In the *dorsal region* the *upper six* or *seven* cutaneous nerves are the terminations of the internal branches of the posterior primary divisions of the spinal nerves. They become superficial close to the vertebral spines, and are to be sought for near the mesial plane. It is not uncommon to find one or more of them piercing the trapezius one or two inches external to the line of emergence of the others. The branch which comes from the second dorsal nerve is the largest of the series; and it may be traced outwards beyond the spine of the scapula. The *lower five* or *six* cutaneous nerves in the *dorsal region* are the terminal twigs of the external branches of the posterior primary divisions of the spinal nerves; and, consequently, they must be looked for at a short distance from the middle line of the back. They reach the surface by piercing the latissimus dorsi muscle on a line with the angles of the ribs and outer margin of the erector spinæ

muscle. In every case the cutaneous branches derived from the dorsal nerves turn outwards in the superficial fascia, and may be traced for a varying distance in this direction.




FIG. 2.—Dissection of the Superficial Muscles and Nerves of the Back.

It is important to note that the area of skin supplied by each of these cutaneous nerves is placed at a lower level than the origin of the posterior primary division from which it arises.

In the *lumbar region* three cutaneous nerves reach the
1—1a

surface by piercing the lumbar aponeurosis at the outer margin of the erector spinæ, a short distance above the ilium. They are the terminal twigs of the external branches of the posterior primary divisions of the three upper lumbar spinal nerves; and they differ from those above, inasmuch as they turn downwards over the crest of the ilium to supply the skin of the gluteal region (Fig. 2).

The *cutaneous arteries* which accompany these nerves come from the dorsal branches of the intercostal and lumbar arteries.

Muscles connecting the limb to the dorsal aspect of the trunk.—These are five in number, and are arranged in two strata. Two form the *superficial stratum*, viz., the trapezius and the latissimus dorsi. Both are broad, flat muscles which cover the greater part of the dorsal aspect of the trunk, from the occiput above to the ilium below. The trapezius lies over the back of the neck and the chest. The latissimus dorsi is placed lower down. The *deeper stratum* of muscles, composed of the levator anguli scapulæ and the two rhomboid muscles, is placed under cover of the trapezius.

Dissection.—The trapezius muscle should now be cleaned. This muscle belongs only in part to the dissector of the upper limb. The portion of it which lies above the prominent spine of the seventh cervical vertebra is the property of the dissector of the head and neck, and must be dissected by him. Let the two dissectors work in conjunction with each other; and when the entire muscle is exposed, let each give the other an opportunity of studying it in its entirety.

In cleaning the trapezius the limb must be placed in such a position as will render the fibres of the muscle tense. If the dissection is being made on the *right side*, the arm must be placed close to the trunk, and drawn downwards, whilst the scapula is dragged well forwards over the side of the block which supports the chest. A transverse cut is now to be made through the superficial and deep fasciæ, from the seventh cervical spine outwards. This incision will be found to coincide with the direction of the fibres of the muscle at this level. From this point gradually work downwards, raising both fasciæ in a continuous layer from the surface of the muscle. The knife must always be carried in the direction of the muscular fibres: and care must be taken to leave none of the thin, filmy, deep fascia behind. If this rule be attended to, it will be found that, as the dissection progresses, the knife is not, as at first, carried transversely, but obliquely, in accordance with the alteration in the direction of the fibres of the lower portion of the muscle. When this stage is reached, a change in the position of the arm is required in order that the lower oblique fibres may be stretched to the full extent. The scapula must still be kept as far forwards as possible; but the limb must be carried upwards, and placed parallel to the neck. In the case of the *left trapezius*, the student must make the incision through the fascia, along the lower margin

of the muscle, and work upwards to the level of the seventh cervical vertebra. In the first instance the limb must be extended, and, at a later stage, placed by the side, as the transverse fibres of the muscle are reached. In removing the fascia from the trapezius, and indeed throughout the whole dissection of the back, the cutaneous nerves must be carefully preserved, in order that the dissector of the head and neck may have an opportunity of establishing their continuity with the trunks from which they arise.

Trapezius.—The trapezius is a flat, triangular muscle, which lies in its entire extent immediately subjacent to the deep fascia. It has a very wide origin, which extends along the mesial plane, from the occiput above to the level of the last dorsal vertebra below. It arises from—(1) the inner third or less of the superior curved line of the occipital bone and the external occipital protuberance; (2) the ligamentum




FIG. 3.—Upper Surface of the Right Clavicle.

nuchæ and the spine of the seventh cervical vertebra; (3) the tips of the spines of all the dorsal vertebræ, as well as the supraspinous ligaments which bridge across the intervals between them (Fig. 2).

In the lower cervical and upper dorsal regions the tendinous fibres by which the muscle arises lengthen out so as to form a manifest flat tendon, which, taken in conjunction with the corresponding aponeurosis of the opposite side, exhibits an oval outline.

As the fibres of the trapezius pass outwards, they converge to gain an insertion into the two bones of the shoulder-girdle. The *occipital* and *upper cervical fibres* incline downwards, and turning forwards over the shoulder, are inserted into the outer third of the posterior border of the clavicle (Fig. 3); the *lower cervical* and *upper dorsal fibres* pass more or less transversely outwards, to gain an insertion into the inner border of the acromion process and the upper margin of the spine of the

scapula; while the *lower dorsal fibres* are directed upwards and, at the base of the scapula, end in a flat, triangular tendon, which plays over the smooth surface at the root of the scapular spine, and is inserted into a rough tubercle on the spine of the scapula immediately beyond this (Fig. 17, p. 49). To facilitate the movement of the tendon upon the bone a small synovial bursa intervenes between them.

The trapezius is supplied by the *spinal accessory nerve* and by twigs from the *third and fourth cervical nerves*.

Dissection.—The latissimus dorsi is now to be dissected. It is a difficult muscle to clean, not only on account of the varying direction of its fibres, but also because its upper part is generally very thin, and its upper border ill-defined. Near the spines of the vertebræ it is overlapped in its upper part by the trapezius, but in its greater extent it is subcutaneous. Both layers of fascia should be raised at the same time from its surface, and its fibres may be stretched by raising the arm and folding it under the neck. The origin of the latissimus dorsi in the lumbar region is effected through the medium of the superficial lamina of the lumbar fascia, a dense tendinous aponeurosis, which covers the erector spinæ in the loins (Fig. 2). Clean this structure thoroughly. The attachment of the muscle to the crest of the ilium, and its slips of origin from the lower ribs, must be carefully defined; at the same time, the posterior and lower part of the external oblique muscle of the abdomen should be cleaned, so that its relation to the latissimus dorsi may be studied. As the latissimus dorsi sweeps over the inferior angle of the scapula it receives an accession of fibres from that bone. This fleshy slip may be brought into view when the muscle is cleaned by relieving the tension of the muscular fibres, and then turning the upper margin of the muscle outwards. It is apt to be mistaken for a piece of the teres major muscle upon which it lies.

Latissimus Dorsi.—The latissimus dorsi is a wide, flat muscle, which covers the back from the level of the sixth dorsal vertebra down to the crest of the ilium (Fig. 2, p. 5). It arises—(1) from the tips of the spinous processes of the lower six dorsal vertebræ and the supraspinous ligaments in connection with them; (2) from the superficial lamella of the lumbar fascia (Fig. 4); (3) by a thin tendinous origin from a small extent of the outer lip of the crest of the ilium in front of the lumbar fascia (Fig. 2, p. 5); (4) by three or four digitations from the lower three or four ribs; and (5) by a fleshy slip from the dorsal aspect of the inferior angle of the scapula (Fig. 17, p. 49). By means of its origin from the posterior lamella of lumbar fascia, it receives an indirect attachment to the spines of the lumbar and upper sacral vertebræ, and also to the posterior part of the crest of the ilium. The costal slips of origin interdigitate with the lower

digitations of the external oblique muscle of the abdominal wall.

The fibres of the latissimus dorsi converge rapidly as they approach the lower part of the scapula. The highest fibres pass almost horizontally outwards towards this point; the lowest fibres ascend almost vertically; whilst the intermediate fibres show varying degrees of obliquity. As a result of this convergence of fibres, the muscle is greatly reduced in width; and it sweeps over the inferior angle of the scapula in the




FIG. 4.—Diagram of the Lumbar Fascia.

- | | |
|--------------------------------|--------------------------|
| 1. Serratus posticus inferior. | 6. Fascia transversalis. |
| 2. Latissimus dorsi. | 7. Erector spinæ. |
| 3. Transversalis abdominis. | 8. Quadratus lumborum. |
| 4. Obliquus internus. | 9. Psoas. |
| 5. Obliquus externus. | |

form of a thick, fleshy band which winds round the lower margin of the teres major muscle, to gain insertion, by means of a narrow, flat tendon, into the bottom of the bicipital groove of the humerus (Fig. 26, p. 70). This insertion cannot be studied at present, but will be seen later on. With the teres major muscle the latissimus dorsi forms the posterior fold of the axilla. At first placed on the dorsal aspect of the teres major, the latissimus dorsi is folded round its lower

border, and finally at its insertion comes to lie in front of it. To this peculiar relationship of the two muscles is due the full, rounded appearance of the posterior axillary fold.

The latissimus dorsi is supplied by the *middle* or *long subscapular nerve*.

Two Intermuscular Spaces.—A triangular space mapped out by the lower border of the trapezius, the upper border of the latissimus dorsi, and the base of the scapula, will now be noticed (Fig. 2, p. 5). Within these limits a small portion of the rhomboideus major will be seen, and also a varying amount of the chest wall—a part corresponding to the sixth intercostal space and the borders of the ribs which bound it above and below. It is well to note that this is the only part of the thoracic parietes on the posterior aspect of the trunk which is uncovered by muscles. Further, between the last rib and the crest of the ilium the anterior border of the latissimus dorsi will generally be observed to overlap the posterior border of the external oblique muscle of the abdominal wall. Sometimes, however, a narrow triangular interval exists between the two muscles, in which is seen a small part of the internal oblique muscle. This space is termed the *trigonum Petiti* (Fig. 2, p. 5).

Reflection of the Trapezius.—On the *second day* the dissector should begin by reflecting the trapezius. This should be done, if possible, in conjunction with the dissector of the head and neck. Divide the muscle about two inches from the spines of the vertebræ, and throw it outwards towards its insertion. The trapezius is very thin at its origin, and the greatest care must therefore be taken not to injure the subjacent rhomboid muscles. The small *bursa* between the tendon of insertion of the lower part of the trapezius and the triangular root of the spine of the scapula must not be overlooked.

Nerves and Vessels of Supply to the Trapezius.—A dissection of the deep surface of the reflected muscle will reveal the following structures:—

- a. The spinal accessory nerve.
- b. Two or three nerves from the cervical plexus.
- c. The superficial cervical artery.

These constitute the nervous and vascular supply of the trapezius (Fig. 2, p. 5).

The nerves have already been displayed by the dissector of the head and neck, as they cross the posterior triangle of the

neck. The branches from the cervical plexus come from the *third and fourth cervical nerves*. On the deep surface of the trapezius they join with branches of the spinal accessory to form the *subtrapezial plexus*, from which twigs proceed into the substance of the muscle. The terminal twig of the *spinal accessory nerve* can be traced nearly to the lower margin of the trapezius.

The *superficial cervical artery* which accompanies the spinal accessory nerve must be followed to the anterior border of the trapezius, where it will be seen to spring from the *transversalis colli artery*.

Dissection.—The posterior belly of the omo-hyoid and the suprascapular artery and nerve can now be displayed by dissecting towards the upper margin of the scapula, and removing carefully the loose fatty tissue in this locality. The dissector of the head and neck must take part in this dissection, and it is well not to expose these structures for more than an inch from the upper margin of the scapula.

Omo-hyoid.—Suprascapular Artery and Nerve.—The slender *posterior belly of the omo-hyoid muscle* will be seen to arise from the upper border of the scapula immediately behind the suprascapular notch. It also derives fibres from the ligament which bridges across this notch. It is supplied by a twig from the ansa hypoglossi. The *suprascapular artery* will be noticed to enter the supraspinous fossa of the scapula by passing over the suprascapular ligament, whilst the *suprascapular nerve* proceeds into the fossa under cover of that ligament.

Dissection.—Draw the scapula well over the edge of the block which supports the chest of the subject. The two rhomboid muscles are thus rendered tense, and the cleaning of the fleshy fasciculi greatly facilitated. The *nerve to the rhomboids* should be secured at this stage, so that it may be preserved from injury in the further dissection of the region. It can best be detected by dissecting in the interval between the rhomboideus minor and the levator anguli scapulæ about one inch to the inner side of the superior angle of the scapula (Fig. 2, p. 5). It is accompanied by the posterior scapular artery, and it will afterwards be traced upon the deep surface of the rhomboid muscles when they are reflected.

Rhomboid Muscles.—The two rhomboid muscles constitute a thin quadrangular sheet of muscular fibres, which proceeds from the spinous processes of the vertebræ to the base of the scapula.

The *rhomboideus minor* is a narrow, ribbon-like fleshy band which runs parallel to the upper border of the greater rhomboid. It springs from the lower part of the ligamentum nuchæ, the

spine of the seventh cervical vertebra, and frequently also from the spine of the first dorsal vertebra. It is inserted into the base of the scapula opposite the triangular surface at the root of its spine (Fig. 17, p. 49). It is entirely covered by the trapezius.

The *rhomboideus major* arises from the upper four or five dorsal spines, and the corresponding part of the supraspinous ligament. Its fibres run obliquely downwards and outwards, and end in a tendinous cord, which receives insertion into the base of the scapula close to the inferior angle. From this point, up to the commencement of the spine, the tendinous cord is firmly bound to the base of the scapula by areolar tissue (Fig. 17, p. 49). The greater part of the *rhomboideus major* is covered by the trapezius; only a small portion near the inferior angle of the scapula lies immediately subjacent to the deep fascia.

Levator Anguli Scapulæ (*musculus levator scapulæ*).—This is an elongated muscle which arises by four more or less tendinous slips from the posterior tubercles of the transverse processes of the upper four cervical vertebræ, and passes downwards and backwards to be inserted into the base of the scapula from the superior angle to the spine. It is supplied by branches from the *third and fourth cervical nerves*.

Dissection.—In cleaning the levator anguli scapulæ muscle care must be taken of the nerves which pass to it from the cervical plexus, and also of the nerve to the rhomboids and the posterior scapular artery which lie under cover of it near the base of the scapula. The dissector of the head and neck has an interest in the levator anguli scapulæ, and when it has been studied by both dissectors it should be divided midway between its origin and insertion, and the lower portion turned outwards. The nerve to the rhomboids has already been secured in the interval between the *rhomboideus minor* and the levator anguli scapulæ, and it has still further been exposed by the reflection of the latter muscle. It may now be displayed in its whole length, together with the posterior scapular artery, which it accompanies, by reflecting the rhomboid muscles. These should be detached from the ligamentum nuchæ and the vertebral spines, and thrown outwards towards the base of the scapula. In doing this care must be taken of the serratus posticus superior, a thin muscle which lies subjacent, and is apt to be injured.

Nerve to the Rhomboids (*nervus dorsalis scapulæ*).—This nerve is a long slender twig which arises in the neck from the fifth cervical nerve, and usually in common with the upper root of the nerve of Bell. It pierces the scalenus medius, and then proceeds downwards under cover of the levator anguli scapulæ

to the deep surface of the rhomboid muscles to which it is distributed. The nerve to the rhomboids likewise supplies one or two twigs to the levator anguli scapulæ.

The nerve to the rhomboids sometimes pierces the levator anguli scapulæ in two or more branches, which unite in a plexiform manner.

Posterior Scapular Artery.—The posterior scapular artery is a branch of the transversalis colli, and takes origin in the lower part of the neck close to the outer margin of the levator anguli scapulæ. At first it proceeds backwards under cover of this muscle, but soon changing its direction it runs downwards along the base or vertebral border of the scapula under cover of the rhomboid muscles (Fig. 2, p. 5). It gives numerous branches to both ventral and dorsal aspects of the scapula, and its terminal twigs may enter the latissimus dorsi. One large branch usually passes backwards in the interval between the rhomboid muscles, or through the greater rhomboid, to reach the trapezius muscle; and another branch, the *supraspinal*, is given to the supraspinatus muscle, and the structures superficial to it.

Reflection of Latissimus Dorsi.—Divide the muscle by carrying the knife from its upper margin, about three inches from the vertebral spines, obliquely downwards and backwards to a point a little way behind its digitation from the last rib. In raising the inner portion of the muscle care must be taken of the subjacent serratus posticus inferior. The attachment of the latissimus dorsi to the crest of the ilium and to the lumbar aponeurosis can now be verified. The outer part of the muscle is next to be thrown forwards, so that the three costal digitations may be seen from their deep aspect, and also for the purpose of displaying the termination of the *subscapular artery* and the *long subscapular nerve*. These are found upon the deep surface of the muscle at the inferior angle of the scapula.

Lastly, replace the outer portion of the latissimus dorsi muscle, and fix it in position by a stitch or two around one or more of the ribs. This is done so as to preserve the posterior fold of the axilla.

The dissector of the arm now stops work for two days. He has completed the dissection of all the dorsal structures which are allotted to him, and he has nothing further to do until the body is turned.

PECTORAL REGION AND AXILLARY SPACE.

On resuming work the dissector will find the body lying upon its back. The chest is raised to a convenient height by means of blocks. A long board is placed under the shoulders for the purpose of supporting the arms when they are abducted from the sides (Fig. 5).

In dissecting the axilla and chest it will be found advantageous if the dissectors of the arm and of the head and neck arrange to work at different hours. The dissector of the head and neck at this stage is engaged at the posterior triangle of the neck, and this dissection cannot be well done unless the arm be placed close to the side and the shoulder depressed. For the dissection of the axilla the arm should be stretched out at right angles to the chest. A compromise between these two positions always results in discomfort to both dissectors.

Four Days are allowed for the dissection of the pectoral region and the axillary space. The arm must then be removed, so as to allow the dissector of the thorax to commence the dissection of the thoracic wall. The following Table may be found useful in regulating the amount of work which should be undertaken each day:—

First Day.—(a) Surface Anatomy; (b) reflection of skin; (c) cutaneous vessels and nerves of the chest, both on its anterior and lateral aspects; (d) cleaning of the pectoralis major muscle; (e) reflection of the axillary fascia; (f) cleaning of that part of the serratus magnus muscle which lies below the fourth rib.

Second Day.—Dissection of the axillary space from below. This includes the boundaries and contents of the space, in so far as they can be got at without the reflection of any muscle.

Third Day.—(a) Reflection of the clavicular portion of the pectoralis major; (b) the costo-coracoid membrane and the structures piercing it; (c) removal of the membrane; (d) the dissection of the upper part of the axilla; (e) reflection of the sternal part of the pectoralis major.

Fourth Day.—(a) Reflection of pectoralis minor muscle; (b) general revision of the space and study of the axillary vessels and nerves; (c) removal of the middle third of clavicle; (d) subclavius muscle; (e) brachial plexus; (f) nerve of Bell and serratus magnus muscle; (g) separation of limb from the trunk.

Surface Anatomy.—The entire length of the clavicle can be felt under the skin, and as the student follows its curves with his finger he can recognise the origins of the pectoralis major and deltoid muscles along its anterior border. In a few instances these muscles may present an

unbroken line of origin from the sternal to the acromial end of the bone, but in the vast majority of cases a triangular interval is left between them. This is marked on the surface by a shallow depression, termed the *infra-clavicular fossa*, and it is rendered all the more apparent by the prominence of the shoulder on its outer side, and the sharp backward curvature of the clavicle immediately above it. If the finger be placed in this fossa, and pressed backwards and outwards, it will rest upon the inner side of the coracoid process of the scapula. The articulations of the clavicle should also be examined. Little or no prominence is formed by the outer end of the clavicle—its upper surface passes continuously on to the upper surface of the acromion process of the scapula. By moving the limb, however, the joint can easily be detected. In strong contrast to this is the sterno-clavicular joint, where the inner end of the clavicle can be felt as a marked projection, although this is masked to the eye by the sternal part of the sterno-mastoid muscle. The suprasternal notch on the upper border of the manubrium sterni between the clavicles should next be felt, and then the finger can be carried downwards in the middle line and in front of the sternum. A prominent ridge, crossing the bone transversely at the level of the second costal cartilages, indicates the junction between the body and manubrium sterni. The portion of the sternum uncovered by the two greater pectoral muscles is narrow above, but it widens out below, and suddenly, at the lower end of the meso-sternum, the finger sinks into a depression between the cartilages of the seventh pair of ribs, and rests upon the ensiform cartilage. This is termed the *infrasternal fossa*, or pit of the stomach. The costal arches below the first are easily recognised, but the first rib lies deeply under the clavicle, and can only be felt in front at its junction with the manubrium sterni. The arm should now be abducted (*i.e.*, carried outwards from the trunk), when the hollow of the armpit will be brought into view, as well as the two rounded folds which bound it in front and behind. The anterior fold of the axilla is formed by the lower border of the pectoralis major, and to a small extent also by the lower border of the pectoralis minor. The posterior fold, which is formed by the latissimus dorsi as it

winds round the *teres major* muscle, is carried downwards to a lower level than the anterior fold. This, as we shall see later on, is a most important point in connection with the anatomy of the axilla. If the finger be pushed upwards into the axilla, the globular head of the humerus can be felt when the arm is rotated. One other point demands the attention of the student before the dissection is commenced, and that is, the position of the nipple. As a rule it lies superficial to the interspace between the fourth and fifth ribs, and it is situated rather more than four inches from the middle line.

Reflection of Skin.—Incisions—(1) Along the middle line of the body from the upper margin of the manubrium sterni to the tip of the ensiform




FIG. 5.

cartilage; (2) from the lower end of this vertical incision transversely outwards round the side of the body; (3) from the upper extremity of the primary incision outwards along the clavicle to the extremity of the acromion process; (4) from the lower end of the vertical and mesial incision (*i.e.*, tip of the ensiform cartilage) obliquely upwards and outwards along the anterior fold of the axilla to the point at which this joins the upper arm. This last incision may, with advantage, be carried vertically down the arm for two and a half or three inches.

Two triangular flaps of skin are marked out by these incisions, and these are now to be raised from the fatty superficial fascia. It is well to encircle the areola and nipple with the knife, and leave the skin covering them undisturbed.

Superficial Fascia.—The superficial fascia presents here, as elsewhere, the usual characters, but, as a rule, the fat is not so plentiful. As it passes over the clavicle to the upper part of the chest and summit of the shoulder, it will be seen

in most cases to present a faintly ruddy striated appearance. Should this not at first be apparent, the removal of some of the superficial fat will render it visible. This appearance is due to the presence of a number of sparse scattered muscular fasciculi which stream down over the clavicle, to obtain origin in the superficial fascia over the pectoralis major and deltoid muscles. In the neck they form a thin, cutaneous, fleshy stratum, called the *platysma myoides*. The superficial fascia in this region is also peculiar in so far as it has developed within it the mammary gland. It should now be dissected with the view of exposing the gland as well as the cutaneous vessels and nerves which make it their bed before entering the skin.

Cutaneous Nerves and Arteries.—There are three distinct groups of cutaneous nerves for the supply of the skin on the anterior and lateral aspects of the chest. These are—

1. The descending cutaneous—from the cervical plexus.
2. The anterior cutaneous, }
3. The lateral cutaneous, } from the intercostal nerves.

The *descending cutaneous nerves* arise in the neck from the third and fourth cervical nerves, and, spreading out as they descend, they cross the clavicle under cover of the *platysma myoides*. They are classified according to their position into the sternal, the clavicular, and the acromial branches. The *sternal branch* is the smallest of the series, and crosses the inner part of the clavicle to end in the skin immediately below. The *clavicular branches* pass over the middle of the clavicle, and extend downwards for some distance, in the superficial fascia over the pectoralis major. The *acromial branch* crosses the outer third of the clavicle, and will be afterwards followed to the skin of the shoulder.

These nerves can readily be found by cutting down upon the clavicle through the *platysma* muscle, and in the direction of its fibres.

The *anterior cutaneous nerves* are the minute terminal twigs of the intercostal trunks, and they become superficial by piercing the pectoralis major muscle and deep fascia close to the margin of the sternum. One will be found in each intercostal space, and they are accompanied by the *perforating branches* of the internal mammary artery, which (when injected)

serve as the best guides to the nerves. They give slender twigs to the skin over the sternum, and larger branches which are directed outwards, and may be traced as far as the anterior fold of the axilla.

The *lateral cutaneous nerves*, much larger than the preceding, arise from the intercostal nerves, and appear on the side of the chest, along a line situated a little behind the anterior fold of the axilla. They pierce the chest wall in the



FIG. 6.—Dissection of the Mammary Gland.

interspaces between the ribs, and divide into anterior and posterior branches under cover of the serratus magnus muscle. These will be found appearing between the digitations of the serratus magnus. The *anterior branches* come out, as a rule, about an inch in front of the corresponding posterior branches, and then proceed forwards over the lower border of the pectoralis major muscle. From the lower members of this series some minute twigs are given off, which enter the superficial surface of the digitations of the external oblique muscle of the abdomen. The *posterior branches* run back-

wards to the dorsal aspect of the trunk over the anterior border of the latissimus dorsi muscle.

It is advisable not to attempt to secure the two highest lateral cutaneous nerves (*i.e.*, those issuing from the second and third intercostal spaces) in the meantime. They are best dissected along with the other contents of the axillary space.

Dissection.—If the subject be a female the dissector should endeavour to make out the connections, and also something of the structure, of the mammary gland. The small area of skin which has been left over the areola should be raised towards the summit of the nipple, and bristles may be introduced through the external orifices which will be seen on its surface. Further, by removing the fat which surrounds the organ, the true glandular tissue will be rendered more apparent, although it is only in favourable circumstances that the milk-ducts in the nipple and their ampullæ in the region of the areola can be isolated and rendered apparent.

Mammary Gland (mamma).—In the female the mammary gland forms a rounded prominence on the front, and also to some extent on the lateral aspect, of the chest. It lies in the superficial fascia, and its smooth contour is largely due to the invasion of its substance by the fatty tissue of this layer.

A little below its mid-point, and at a level which usually corresponds to the fourth intercostal space, the mamma is surmounted by a conical elevation termed the *nipple* or *mammilla* (papilla mammæ). This stands in the middle of a circular patch of coloured integument which is called the *areola mammæ*. Within the nipple, and also subjacent to the areola, there is no fat. A curious change of colour occurs in this region during the second month of pregnancy. Of a delicate pink colour in the virgin, the skin of the nipple and areola becomes brown from the deposition of pigment at this time, and it never again resumes its original appearance.

The mammary gland extends in a horizontal direction from the side of the sternum to very nearly the mid-axillary line on the side of the chest; and in a vertical direction from the second costal arch above to the sixth costal cartilage below. About two-thirds of the gland are placed upon the pectoralis major muscle, whilst the remaining part, which corresponds to its inferior and outer third, extends beyond the anterior fold of the axilla, and lies upon the serratus magnus muscle. From the part which lies in relation to the lower border of the pectoralis major a prolongation extends upwards into the axilla, and reaches as high as the third rib.

The mammary gland is not isolated by a capsule from the surrounding fatty tissue of the superficial fascia. Pervading it, and supporting the true glandular substance, there are strands or trabeculæ of connective tissue which constitute its stroma or framework, and which are directly continuous with




FIG. 7.—Section through a Mammary Gland prepared by method recommended by Mr. Harold Stiles.

the fibrous tissue which supports the fat of the superficial fascia. The stroma and gland-substance together constitute a conical mass termed the *corpus mammae*. Processes project out from both the surface and margins of the corpus mammae, and into the hollows between these projections is deposited the fat which gives the smooth contour to the organ. Many of the processes which extend from the surface

are attached to the deep surface of the skin, and give rise to the so-called *ligaments of Cooper*.

The gland substance is arranged in lobes and lobules, and the ducts issuing from these converge towards the areola. Some fifteen or more lactiferous ducts (*ductus lactiferi*) pass in towards the base of the nipple. Subjacent to the areola these ducts expand into fusiform dilatations termed *ampullae* or *sinus lactiferi*, and then contracting they traverse the substance of the nipple, upon the summit of which they open.

In a well-injected subject, twigs from the *intercostal arteries*, and also from the *perforating branches* of the *internal mammary*, may be traced into the mammary gland, and another vessel, called the *external mammary artery*, may be seen winding round the edge of the greater pectoral muscle, or piercing its lower fibres to reach the gland.

By means of *lymphatic vessels* the mammary gland is brought into connection with the sternal glands, and also more directly with the axillary glands. The latter connection is one of much importance to the surgeon in cases where it is necessary to remove the organ for malignant disease.

In the male the mamma (*mamma virilis*) is extremely rudimentary. The nipple is small and pointed, and the areola is surrounded by sparse hairs.

Deep Fascia.—The deep fascia of the pectoral region is a thin membrane which closely invests the pectoralis major. It is attached superiorly to the clavicle, and is firmly connected in the middle line to the front of the sternum. Below, it is continuous with the deep fascia covering the abdominal muscles, and, at the lower border of the great pectoral muscle, it is continuous with the axillary fascia. At the infraclavicular fossa a process from its deep surface dips in between the deltoid and pectoralis major muscles to join the costo-coracoid membrane, whilst, beyond this, the aponeurosis becomes continuous with the fascia covering the deltoid muscle. The axillary fascia and the costo-coracoid membrane will be described later on.

Dissection.—The pectoralis major muscle must now be cleaned, and its division into sternal and clavicular parts clearly made out. The muscular fibres are rendered tense by abducting the arm from the side. On the right side the dissector begins at the lower border of the muscle, whilst on the left side he commences at the upper border. Clean also the anterior margin of the deltoid. In the interval between it and the portion of the

pectoralis major which arises from the clavicle, the *cephalic vein* and, subjacent to this, the *humeral thoracic artery* will be discovered.

Infraclavicular Lymphatic Glands.—In the interval between the adjacent margins of the pectoralis major and deltoid muscles immediately below the clavicle are placed one, or it may be two, lymphatic glands which receive the lymphatic vessels which accompany the cephalic vein. These vessels convey the lymph from the outer side of the arm and the shoulder.

Pectoralis Major.—This powerful muscle extends from the anterior aspect of the chest to the humerus. It is divided by a deep fissure into a clavicular and a costo-sternal portion. This fissure penetrates through the entire thickness of the muscle, the clavicular and costo-sternal portions being thus distinct, except close to their insertion. The *clavicular portion* arises by short tendinous and muscular fibres from an impression on the inner half of the anterior surface of the clavicle (Fig. 3, p. 7). The *costo-sternal portion* takes origin by fleshy fibres from the anterior surface of the sternum, from the aponeurosis of the external oblique muscle, and occasionally from the sixth rib near its cartilage. Under cover of this more superficial origin, and partially independent of it, a variable number of muscular slips spring from the cartilages of the upper six ribs.

The pectoralis major is inserted by a flattened bilaminar tendon into the outer lip of the bicipital groove of the humerus (pectoral ridge), and the fibres of the muscle undergo a re-arrangement as they converge upon this tendon. The greater part of the clavicular portion joins the anterior lamina of the common tendon; some of the innermost clavicular fibres, however, are inserted directly into the humerus below the tendon, whilst a few gain attachment to the deep fascia of the arm, and become adherent to the adjacent part of the deltoid.

The fibres of the costo-sternal portion of the muscle take different directions as they proceed to join both laminae of the tendon of insertion; thus the upper fibres descend slightly, the intermediate fibres pass horizontally outwards, whilst the lower fibres ascend, and, at the same time, gain the deep surface of the rest of the muscle. A smooth, full, and rounded lower border is in this way formed which con-

stitutes the anterior fold of the axilla. The precise manner in which it is attached will be more fully studied at a later stage of the dissection.

The pectoralis major is supplied by the *internal* and *external anterior thoracic nerves*.

Axilla.—The axillary space may be defined as being the hollow or recess between the upper part of the side of the chest and the upper part of the arm. When the limb is abducted from the trunk, and the areolo-fatty tissue which occupies the armpit is removed, the space presents a pyramidal form. The apex, or narrow part of the space, placed immediately to the inner side of the coracoid process, is directed upwards towards the root of the neck, whilst the wider part or base looks downwards. But the space is not absolutely pyramidal in form, for the inner wall formed by the chest is of greater extent than the outer wall formed by the arm. It follows from this, therefore, that the anterior and posterior walls converge as they proceed outwards. Before engaging in the dissection of the space, it is necessary that the student should have some knowledge of its boundaries, and the manner in which its contents are disposed in relation to these.

Boundaries of the Axilla.—The *anterior wall* is formed by the two pectoral muscles and the costo-coracoid membrane. The pectoralis major constitutes the superficial stratum, and is spread out over the entire extent of the anterior wall. The pectoralis minor, which lies subjacent to the greater pectoral muscle, is only in relation to about one-third of the anterior boundary, whilst the interval or gap between this muscle and the clavicle is filled up by the costo-coracoid membrane. The lower border of this wall of the axilla constitutes its *anterior fold*, as already explained. This is formed by the lower margin of the pectoralis major, with a small part of the lower border of the pectoralis minor, which comes into view near the side of the chest.

The *posterior wall* of the axilla is somewhat longer than the anterior wall. It is formed from above downwards by the subscapularis muscle, the tendon of the latissimus dorsi, and the teres major muscle. The subscapularis, lying upon the venter of the scapula, takes by far the largest share in the formation of this boundary. The narrow tendon of the

latissimus dorsi lies in front of the teres major, so that only the lower border of the latter muscle is seen below it. The *posterior fold* of the axilla is formed by the lower border of this wall.

The *inner wall* is constituted by the upper four or five ribs with the intervening intercostal muscles; it is clothed by the corresponding digitations of the serratus magnus muscle.

The *outer wall* is formed by the humerus and the conjoined origin of the coraco-brachialis and short head of the biceps.

The *apex* of the space corresponds with the narrow communication between the axilla and the root of the neck. It is a triangular interval (which can readily be investigated by the finger when the space is dissected) bounded by the clavicle, first rib, and upper margin of the scapula, and




FIG. 8.—Diagram of section through the Axilla of the Left Side.

through it pass from the neck the great axillary vessels and brachial nerves. The wide vaulted *base* of the armpit is closed by the axillary fascia.

Contents of the Axilla.—The axillary artery and vein, with the great brachial nerves, constitute the most important contents of the armpit. Except at the summit of the space, they lie closely applied to the outer wall, and follow it in all the movements of the upper arm. Of the branches which spring from the axillary artery, *two* (viz., the thoracic axis and the long thoracic) are related to the anterior wall; *two* (viz., the posterior circumflex and subscapular) to the posterior wall; *one*, the superior thoracic, to the inner wall; and *one*, the anterior circumflex, to the outer wall.

The *thoracic axis artery* arises high up in the space, and at once proceeds forwards through the costo-coracoid membrane.

The *long thoracic artery* runs inwards along the lower border of the pectoralis minor. The *posterior circumflex artery* arises from the posterior aspect of the main trunk, and at once leaves the space by passing backwards through the posterior wall in the interval between the subscapularis and the teres major muscles. The *subscapular artery* runs inwards along the lower border of the subscapularis muscle. The *anterior circumflex*, a small vessel, proceeds outwards upon the humerus, under cover of the coraco-brachialis and short head of the biceps. The *superior thoracic artery*, also a small vessel, ramifies upon the first intercostal space high up in the axilla.

In making an opening into the axilla from below, for the purpose of allowing a collection of pus to escape, or for any other purpose, it is necessary to bear these relations in mind. The outer wall, where the great axillary vessels are, must be most carefully avoided; so also must be the anterior and posterior walls, where there would be a risk of injuring the long thoracic and subscapular arteries. The inner wall, however, is, comparatively speaking, free from danger, as the small thoracica suprema is placed high up in the space. Therefore enter the knife with the sides of the blade towards the anterior and posterior walls of the space, and with the back of the blade towards the outer wall and axillary vessels. The knife may then be carried inwards towards the chest.

But there are various nerves in relation to the walls of the axilla. Entering the deep surface of the anterior wall are the *two anterior thoracic nerves* for the supply of the two pectoral muscles. Upon the posterior wall are the *three subscapular nerves*, which supply the three muscles which constitute this boundary. Running downwards upon the inner wall is the *nerve of Bell*, or posterior thoracic nerve, while piercing it are the *intercosto-humeral* and upper *lateral cutaneous nerves*.

In addition to the contents already enumerated, numerous lymphatic glands are lodged in the fat of the axillary space.

Axillary Fascia.—This is a dense felted membrane which stretches across the base of the armpit. It is continuous in front with the deep fascia covering the pectoralis major, behind with the sheaths of the latissimus dorsi and teres major muscles, and internally with the deep fascia over the serratus magnus. It is drawn upwards towards the hollow of the axilla. This is chiefly due to the connection of its deep surface with the sheath of the pectoralis minor, but also to its attachment to the areolar tissue which fills the space. In a

well-injected subject a small artery, from the lower part of the axillary trunk, may be observed ramifying upon the fascia.

Dissection.—Begin the dissection of the axilla from below by carefully separating the deep fascia from the lower edge of the pectoralis major muscle, so as to expose and clean the anterior fold of the axilla. Then grasp the edge of the fascia with the hand and pull it backwards, teasing out with the point of the knife the areolar tissue, which holds it in place. By this means the axillary fascia is reflected in one piece, and the upper lateral cutaneous nerves are put on the stretch, and can be followed out.

Lateral Cutaneous Branches of the Second and Third Intercostal Nerves.—As a rule, the first intercostal nerve does not give off a lateral cutaneous nerve. That which springs from the second intercostal nerve is the largest of the series, and differs from the others in not dividing into an anterior and posterior branch. It is termed the *intercosto-humeral nerve*, on account of its being distributed to the skin on the inner and back aspect of the upper part of the arm. To reach this destination it crosses the axilla and pierces the deep fascia. But before doing so it establishes communications and forms a plexiform arrangement in the axilla with the nerve of Wrisberg (the lesser internal cutaneous nerve) and the lateral cutaneous branch of the third intercostal nerve. This plexus may be joined by another twig, which is occasionally present, viz., the minute lateral cutaneous branch of the first intercostal nerve.

The *lateral-cutaneous branch* of the third intercostal nerve divides into an anterior and posterior part, and these are distributed in the ordinary way. From the posterior branch twigs are given to the skin of the axilla, and the terminal twigs are distributed to the integument on the upper part of the inner aspect of the arm.

Lymphatic Glands.—In the subsequent dissection of the axilla the lymphatic glands must be removed as they are brought into view. Many of them are very minute, and are likely to escape the attention of the dissector. The position which they occupy in the space should be carefully noted. They are disposed in three groups—(a) a chain of six or more glands lying close to the axillary vessels, which extends from the lower border of the pectoralis major up into the apex of the axilla and receives the lymphatic vessels ascending from the limb; (b) a group of pectoral glands placed along

the lower border of the pectoralis minor and on the inner wall of the thorax in the angle between the pectoral muscles and the serratus magnus, which are joined by the lymphatics from the outer two-thirds of the mammary gland and the front of the chest; (c) a group of subscapular glands, situated along the lower border of the subscapularis muscle on the posterior wall of the axilla, and into which the lymphatics of the back pour their contents.

A *central group* of glands has been recently described (Leaf). These either lie superficial to the axillary fascia or in a pocket formed by it. Sometimes they are placed upon the deep aspect of the axillary fascia, in which case they are associated with the subscapular group.

Dissection.—The loose areolar tissue and fat must now be cautiously removed from the hollow of the armpit. Begin by dissecting out the *subscapular artery* and the *long subscapular nerve*. The guide to their position is the lower margin of the subscapularis muscle. In relation to the lower border of the pectoralis minor muscle the *long thoracic artery* will be found. A vertical incision along the inner wall, a short distance anterior to the point where this joins the posterior wall, will display the *external respiratory nerve*, or the *nerve of Bell*, upon the axillary surface of the serratus magnus. These structures being secured, the dissector may proceed with his work more boldly, as the remaining contents of the space are not so liable to injury. The *axillary artery* and *vein* and the great *brachial nerves* may next be exposed. Note the close manner in which they cling to the outer wall of the axilla in the various movements of the limb, and then isolate them thoroughly by removing their areolar sheaths, and establish their individual identity. In dissecting these structures care must be taken to secure the small *internal cutaneous* branch of the *musculo-spiral nerve*. This nerve is generally given off within the axilla in common with a muscular branch to the long head of the triceps, and it crosses the latissimus dorsi and teres major tendons on a deeper plane than the branches of the intercosto-humeral nerve. The *lowest subscapular nerve* must now be looked for upon the surface of the subscapularis muscle.

Axillary Artery (*arteria axillaris*).—It is the third part of the axillary artery which is now exposed, and the vein will be seen to lie upon its inner side, and also partly in front of it. It is important to note the position of the large nerves, with reference to the artery, before they are much disturbed by the dissection. The *ulnar nerve* lies in direct contact with its inner side. The *nerve of Wrisberg* (the lesser internal cutaneous nerve) is also internal to the artery, but is separated from it by the axillary vein, to which it is closely applied. The *internal cutaneous nerve*, and the *inner head of the median*, lie in front of the artery; the *musculo-spiral* and *circumflex nerves* are directly behind it; while the *median* and *musculo-*

cutaneous nerves are placed upon its outer side. The latter nerve soon leaves the artery, by deviating outwards and entering the substance of the coraco-brachialis muscle. Its branch of supply to that muscle should be secured at this stage.

In this part of its course the axillary artery gives off three branches—the *subscapular*, which has already been




FIG. 9.—Diagram to show relation of Brachial Nerves to Axillary Vessels.

found; the *posterior circumflex*, which arises from its posterior aspect; and the *anterior circumflex*, a small vessel which runs outwards under cover of the coraco-brachialis, and is apt to be injured in cleaning the nerves.

Dissection.—The axillary space must now be dissected from the front. This is done by reflecting the clavicular part of the pectoralis major. The sternal portion of the muscle is not to be disturbed at present. Divide the clavicular part close to its origin from the clavicle, and throw it downwards and outwards. This must be done with care, because some twigs from the *external anterior thoracic nerve*, and also some of the *pectoral thoracic branches* of the thoracic axis artery, enter its deep surface. These must be cleaned and preserved.

Costo-Coracoid Membrane.—A space or gap between the

clavicle and pectoralis minor is now exposed. This gap, however, is closed by the costo-coracoid membrane, the connections of which must be studied. Trace it outwards to its attachment to the coracoid process, and inwards to its attachment to the first rib. Above, it constitutes the sheath of the subclavius muscle by splitting into an anterior and a posterior layer. These, passing upwards, enclose the muscle, and are attached, the one to the anterior border of the clavicle, and the other to the posterior border of the bone.




FIG. 10.—Diagram of the Costo-coracoid Membrane.

With the view of demonstrating these two layers, divide the anterior lamina transversely close to the clavicle, and throwing it downwards, pass the handle of the scalpel upwards behind the muscle. The posterior attachment can in this manner be verified, and at the same time the nerve to the subclavius will be seen sinking into the deep surface of the muscle.

The density of the membrane diminishes almost immediately below the subclavius, and this so abruptly that a crescentic band is formed, which, on account of its being thicker and stronger than the rest of the membrane, is sometimes called the costo-coracoid, or bicornuate ligament. The lower connections of the membrane are somewhat indefinite, and difficult to establish with precision. In a good subject, however, it will be seen to join the sheath of the axillary

vessels, and also to give a process of fascia to the sheath of the pectoralis minor.

Four structures pierce the costo-coracoid membrane, and these should now be cleaned. They are:—(1) the thoracic axis artery, breaking up into pectoral, clavicular, acromial, and humeral branches; (2) the thoracic axis vein; (3) the cephalic vein; (4) and lastly, the external anterior thoracic nerve.

Dissection.—The costo-coracoid membrane should be removed, and the axillary space entered from above. With a little dissection the contents of the upper part of the space may be exposed. These are the axillary artery, with the axillary vein on its inner side, and partly overlapping it. To the outer side, and to some extent above the vessels, are placed the great brachial nerves. All these important structures are enveloped in a loose, funnel-shaped sheath, which is prolonged into the axilla from the deep cervical fascia. Crossing behind the artery, and therefore lying very deeply, is the external respiratory nerve, or nerve of Bell. A small branch, called the superior thoracic, takes origin from this part of the axillary artery. Lastly, the cephalic and thoracic axis veins must be traced to their junction with the axillary vein.

The sternal part of the pectoralis major muscle may now be divided about its middle, and the two portions thrown outwards and inwards. Several nerves will be observed entering its deep surface, and these must be preserved. They come from the external and internal anterior thoracic nerves. One or more from the latter pierce the pectoralis minor, and are now seen emerging from its anterior surface. The pectoralis minor must be cleaned and its attachments defined.

Pectoralis Minor.—This is a fan-shaped muscle, which extends from the thoracic wall to the scapula. It arises by three flat, tendinous slips from the third, fourth, and fifth ribs, close to their cartilages. Between the ribs these slips are prolonged into the anterior intercostal aponeuroses. From this origin the fibres proceed outwards and upwards, and converge upon a stout tendon, which is inserted into the front part of the inner border and upper surface of the coracoid process (Fig. 14, p. 40). The pectoralis minor is supplied by the internal anterior thoracic nerve.

Dissection.—The axillary vessels and the brachial nerves can now be cleaned throughout their entire extent, but the pectoralis minor muscle should not be reflected until the relations of these important structures have been thoroughly studied.

Axillary Artery (*arteria axillaris*).—The axillary artery is a portion of the great arterial trunk which carries blood for the supply of the upper limb. It begins above at the outer

border of the first rib, where it is continuous with the sub-clavian artery, and it ends below at the lower border of the teres major muscle, where it becomes continuous with the brachial artery. Its course through the axilla varies with the position of the limb. When the arm is abducted from the trunk (as it is when the axilla is being dissected), a straight line, drawn from the centre of the clavicle to a point below the anterior fold of the axilla, and immediately to the inner side of the slight prominence caused by the coraco-brachialis muscle, will, with tolerable accuracy, indicate the course pursued by the vessel.

The relations of the axillary artery vary very much as it traverses the armpit; and with the view of obtaining a greater precision of description, anatomists are in the habit of arbitrarily dividing the vessel into three parts. The *first part* extends from the outer border of the first rib to the upper border of the pectoralis minor; the *second part* lies under cover of that muscle; the *third part* extends from the lower border of the pectoralis minor to the lower border of the teres major.

The *first part* of the axillary artery lies very deeply. It is covered by the skin, superficial fascia, deep fascia, clavicular part of the pectoralis major, and the costo-coracoid membrane. But, even when these are removed, the vessel is not completely exposed, because it is enveloped, along with the axillary vein and great nerves, by a funnel-shaped sheath, which is prolonged upon them from the deep cervical fascia. Further, it is crossed by the cephalic and thoracic axis veins, and the loop of communication between the two anterior thoracic nerves likewise lies in front of it. *Posteriorly*, this part of the vessel is supported by the first intercostal space and the first digitation of the serratus magnus muscle, and the nerve of Bell crosses behind it. To its *inner side*, and somewhat overlapping it, is the axillary vein, whilst *above* and to its *outer side* are the large brachial nerve-trunks.

The *second part* of the axillary artery is placed behind the two pectoral muscles, and has the three cords of the brachial plexus disposed around it. Thus the inner cord lies upon its inner side, the outer cord upon its outer side, and the posterior cord behind it. The axillary vein is still upon its inner side, but is separated from the artery by the

inner nerve-cord. Strictly speaking, it is not in apposition with any muscle posteriorly, being separated from the subscapularis muscle by areolo-fatty tissue.

The *third* and *longest part* of the axillary artery is superficial in its lower half. This is due to the fact that the posterior wall of the axilla extends lower down than the anterior wall. Whilst, therefore, it is covered in its upper half by the pectoralis major, below this it is only covered by the integument and fasciæ. *Behind*, it rests, from above downwards, on the subscapularis, the tendon of the latissimus dorsi, and the lower margin of the teres major. To its *outer side*, is the coraco-brachialis muscle; whilst to its *inner side*, is the axillary vein. The brachial nerve-cords have now given place to their large branches, and these are disposed around the vessel. The precise positions which they occupy in the undisturbed condition of parts, and when the arm is abducted from the side, have been already described on page 27.

The **Branches of the Axillary Artery** have been observed at different stages of the dissection. They may now be more fully examined. They are:—

Superior thoracic,	} from the first part.	Alar thoracic,	} from the third part.
Thoracic axis, .		Subscapular, .	
Long thoracic, .	} from the second part.	Anterior circumflex,	
		Posterior circumflex,	

Superior Thoracic Artery (arteria thoracica suprema).—This is a small branch which springs from the axillary at the lower border of the subclavius muscle and ramifies upon the upper part of the inner wall of the axilla. It supplies twigs to the serratus magnus muscle, the intercostal muscles, and the pectoral muscles.

thoracic
arteria **Thoracic Axis** (arteria thoracicoacromialis).—The thoracic axis is a short wide trunk, which is usually described as arising from the first part of the axillary artery. As a rule, however, it takes origin under cover of the pectoralis minor, and winds round the upper border of that muscle. Piercing the costo-coracoid membrane, it immediately divides into numerous branches, which diverge widely from each other. These receive different names, and are arranged as follows:—(a) The *clavicular branch* (ramus clavicularis), a small twig, runs upwards to the clavicle and then turns inwards along that

bone between the clavicular part of the pectoralis major and the costo-coracoid membrane. (b) The *pectoral branches* (rami pectorales), of larger size, proceed downwards between the two pectoral muscles, give branches to both, and anastomose with the long thoracic and intercostal arteries. (c) The *acromial branch* (ramus acromialis) runs outwards upon the tendon of the pectoralis minor and the coracoid process. Some of its twigs supply the deltoid, whilst others pierce it to reach the upper surface of the acromion process. It




FIG. 11.—The Axillary Artery and its Branches.

anastomoses with the suprascapular and posterior circumflex arteries. (d) The *humeral branch* (ramus deltoideus), as a rule, takes origin from a trunk common to it and the preceding artery, and it runs downwards in the intermuscular interval between the pectoralis major and the deltoid. To both of these muscles it gives twigs.

Long Thoracic Artery (arteria thoracica lateralis).—This vessel takes the lower border of the pectoralis minor as its guide, and proceeds downwards and inwards to the side of the chest. It gives branches to the pectoral muscles, the serratus

magnus, and the mammary gland, and anastomoses with twigs from the intercostal arteries. It gives off, as a rule, an *external mammary branch*, which winds round or pierces the lower border of the pectoralis major to reach the mammary gland.

Alar Thoracic.—This small artery supplies the fat and lymphatic glands in the axilla, and rarely arises as a separate branch from the axillary artery. Its place is usually taken by twigs from the subscapular and long thoracic arteries.

✓ **Subscapular Artery** (*arteria subscapularis*).—This is the largest branch of the axillary artery, and it arises opposite the lower border of the subscapularis muscle. Following this, it runs downwards and backwards, in company with the long subscapular nerve, to the inferior angle of the scapula, where its terminal twigs anastomose with the posterior scapular artery. Not far from its origin the subscapular artery gives off a large branch, the *dorsalis scapulæ* (*arteria circumflexa scapulæ*), which winds round the axillary border of the scapula, in close contact with the bone, to reach its dorsal aspect. Numerous smaller twigs are given to the neighbouring muscles, viz., the subscapularis, latissimus dorsi, and serratus magnus.

Circumflex Arteries.—These are two in number, and as a rule they both arise from the axillary at the same level, a short distance below the origin of the subscapular artery. The *posterior circumflex* (*arteria circumflexa humeri posterior*) is much the larger of the two. Only a small portion of it can be seen at the present stage. It springs from the posterior aspect of the axillary, and at once proceeds backwards with the circumflex nerve close to the inner and under aspect of the head of the humerus, and in the interval between the subscapularis and teres major muscles. The small *anterior circumflex artery* (*arteria circumflexa humeri anterior*) takes origin from the outer aspect of the axillary, and runs outwards in front of the surgical neck of the humerus, under cover of the coraco-brachialis and short head of the biceps. Reaching the bicipital groove, it divides into two branches. Of these one is directed upwards with the long head of the biceps to the shoulder-joint; the other continues onwards to the under surface of the deltoid, and finally anastomoses with some of the terminal twigs of the posterior circumflex artery.

Axillary Vein (*vena axillaris*).—This venous trunk is the continuation upwards of the basilic vein of the upper arm. Beginning at the lower border of the *teres major*, it becomes the subclavian vein at the outer margin of the first rib. At the lower margin of the *subscapularis* it receives the two *vena comites* of the brachial artery, and above the level of the *pectoralis minor* it is joined by the cephalic vein. Its other tributaries correspond, more or less closely, to the branches of the axillary artery.

Subclavius Muscle.—The subclavius muscle may now be cleaned and its attachments defined. It is a small muscle, placed below the clavicle, and it is enclosed in a stout sheath




FIG. 12.—Under Surface of the Clavicle with the Attachments of the Muscles mapped out.

derived from the costo-coracoid membrane. It takes origin by a short rounded tendon, from the upper surface of the first costal arch at the junction of the rib with its cartilage, and the small fleshy belly is inserted into the shallow groove on the under surface of the clavicle. Its nerve of supply comes from the fifth and sixth cervical nerves, and has been previously noticed, p. 29.

Dissection.—The middle third of the clavicle should now be removed, and the subclavius muscle reflected, in order that a connected view of the structures which pass from the side of the neck into the axilla may be obtained. The dissector of the head and neck should also take part in this dissection. At the same time the *pectoralis minor* may be divided about an inch and a half from its insertion, and the two parts thrown inwards and outwards. In doing this care must be taken of the internal anterior thoracic nerve which pierces its deep surface. When the continuity of the axillary and subclavian vessels has been satisfactorily displayed they may be ligatured in two places at the level of the clavicle and then divided between the ligatures. By throwing the axillary vessels downwards the examination of the brachial nerves will be greatly facilitated. The dense

connective tissue which surrounds these large nerves should be completely removed and the arrangement of the brachial plexus studied.

Brachial Plexus (plexus brachialis).—This important plexus is formed by the anterior primary divisions of the four lower




FIG. 13.—Diagram of the Brachial Plexus.

S¹, S², S³.—The three subscapular nerves. Cir.—Circumflex nerve.

cervical nerves and the greater part of the large anterior primary division of the first dorsal nerve. Above, the plexus is further reinforced by a small twig of communication which passes from the fourth to the fifth cervical nerve, whilst below, a similar connecting twig not infrequently passes upwards, in

front of the neck of the second rib, from the second to the first dorsal nerve. The manner in which these great nerves unite to form the plexus is very constant. The *fifth* and *sixth* nerves unite to form an *upper trunk*; the *seventh* remains single and proceeds downwards as a *middle trunk*; whilst the *eighth* cervical and *first dorsal* nerves join close to the intervertebral foramina to constitute a *third* or *lower trunk*. A short distance above the clavicle each of these three trunks splits into an *anterior* and a *posterior division*. Raise the three anterior divisions on the handle of the knife, and it will be seen that all the three posterior divisions unite to form the *posterior cord* of the plexus, and, further, that the innermost of these divisions is much smaller than the other two. Of the three anterior divisions the *two outer* join to constitute the *outer cord*, whilst the *innermost* is carried downwards by itself as the *inner cord* of the plexus. From the three cords of the plexus are given off the branches which supply the upper limb.

From the above description it will be seen that the plexus, from changes which are effected in the arrangement of its fibres, may be divided into four stages:—

- First Stage*, . . Five separate nerves (viz., four lower cervical and first dorsal).
- Second Stage*, . . Three nerve-trunks (viz., an upper, middle, and lower).
- Third Stage*, . . Three anterior divisions and three posterior divisions.
- Fourth Stage*, . . Three nerve-cords (viz., an outer, inner, and a posterior).

The first two of these stages are generally observed in the lower part of the posterior triangle of the neck, and the two last behind the clavicle and in the upper part of the axilla. It must be understood, however, that the points at which division and union of the different parts of the plexus take place are subject to much variation.

Infraclavicular Branches of the Brachial Plexus.—The branches of the brachial plexus are usually classified into two groups, viz., those which arise above the level of the clavicle, and those which take origin within the axilla. The latter group of nerves must now be studied by the dissector of the upper limb. They consist of a number of short branches, which end in the muscles forming the anterior and posterior

walls of the axilla, and a series of large terminal branches, which are prolonged downwards into the upper arm. They are:—

1. *Axillary branches*—

From outer cord :

External anterior thoracic (from C. v., C. vi., C. vii.).

From inner cord :

Internal anterior thoracic (from C. viii., D. i.).

From posterior cord :

Three subscapular nerves (from C. v., C. vi., C. vii., C. viii.).

2. *Brachial branches*—

From outer cord :

Musculo-cutaneous (from C. v., C. vi.).

Outer head of median (from C. vi., C. vii.).

From inner cord :

Inner head of median (from C. viii., D. i.).

Ulnar (from C. viii., D. i.).

Internal cutaneous (from C. viii., D. i.).

Lesser internal cutaneous (from D. i.).

From posterior cord :

Circumflex (from C. v., C. vi.).

Musculo-spiral (from C. v., C. vi., C. vii., C. viii.).

In the above table the different spinal nerves from which the fibres which compose the several nerves are derived are indicated.

Anterior Thoracic Nerves (*nervi thoracici anteriores*).—

These are the branches of supply to the pectoral muscles, or, in other words, to the two muscles which form the anterior wall of the axilla. The *external anterior thoracic nerve* springs from the outer cord of the plexus, pierces the costo-coracoid membrane above the level of the pectoralis minor, and breaks up into branches which sink into the deep surface of the pectoralis major. The *internal anterior thoracic nerve*, somewhat smaller, arises from the inner cord of the plexus, and passing forwards between the axillary artery and vein enters the deep surface of the pectoralis minor. After supplying this muscle its terminal filaments emerge from its anterior surface, and sink into the pectoralis major. The pectoralis major is therefore supplied by both anterior thoracic nerves ; the pectoralis minor by the internal anterior thoracic nerve alone. Close to their origin the two nerves are usually united by an arch or loop, thrown over the front of the axillary artery ; in other cases they may join in a plexiform manner, before proceeding to their destinations.

Subscapular Nerves (nervi subscapulares).—The three subscapular nerves spring from the posterior cord of the plexus, and supply the three muscles which form the posterior wall of the axilla. The *upper subscapular nerve* is placed high up in the axilla. It is very short, sometimes double, and it sinks into the substance of the subscapularis muscle. The *long or middle subscapular nerve* accompanies the subscapular artery and supplies the latissimus dorsi. The *lower subscapular nerve* gives twigs to the lower border of the subscapularis muscle, and ends in the teres major.

Dissection.—The cords of the brachial plexus may now be divided. Begin with the inner and outer cords, because when these are thrown downwards a better view of the posterior cord and the three subscapular nerves will be obtained. When the posterior cord is cut the arm should be forcibly dragged away from the trunk, so as to put the serratus magnus on the stretch.

Posterior Thoracic Nerve (nervus thoracicus longus).—The *external respiratory nerve of Bell*, or the posterior thoracic nerve, as it passes downwards upon the outer surface of the serratus magnus, may now be studied in its whole length. It is the nerve of supply to the serratus magnus, and it arises in the root of the neck by three roots from the brachial plexus. The upper two roots (one from the fifth cervical and the other from the sixth cervical nerve) pierce the scalenus medius, and uniting into one stem give off branches to the upper part of the serratus magnus. The third root takes origin from the seventh cervical nerve, and passes in front of the scalenus medius. It runs downwards for a considerable distance on the surface of the serratus magnus, before it unites with the other part of the nerve. The entire nerve, thus formed, can be followed to the lower part of the serratus, giving twigs to each of its digitations.

Serratus Magnus Muscle.—The serratus magnus arises by fleshy digitations from the upper eight or nine ribs, about midway between their angles and cartilages. These slips are arranged on the chest wall, so as to present a gentle curve convex forwards. The lower three or four interdigitate with the external oblique muscle of the abdomen. The serratus magnus is inserted into the entire length of the vertebral border of the scapula. The muscle falls naturally into three parts. (a) The *upper part*, composed of the large first digita-

tion alone, arises from the first and second ribs, and from a tendinous arch between them. The fibres converge, to be inserted into a somewhat triangular surface on the ventral




FIG. 14.—Ventral aspect of the Scapula with the Attachments of Muscles mapped out.

aspect of the superior angle of the scapula. (b) The *middle part* consists of two digitations which take origin from the second and third ribs. The upper slip is very broad, and springs from the lower border of the second rib. The fibres

diverge to form a thin muscular sheet, which is inserted into the anterior lip of the vertebral border of the scapula, between the insertions of the upper and lower portions. (c) The *lower part* is formed by the remaining digitations of the muscle. These converge to form a thick mass, which is inserted into a rough surface upon the ventral aspect of the inferior angle of the scapula. The deep surface of the serratus magnus is in contact with the chest wall.

Removal of the Arm from the Body.—Draw the arm forcibly from the side and cut through the serratus magnus, the omo-hyoid, and the latissimus dorsi muscles, also the suprascapular artery and nerve, and the vessels and nerves in relation to the trapezius and rhomboids, if these have not been previously divided. The arm will then be found to be free, and it may be carried to one of the tables which are reserved for the dissection of separate parts.

SHOULDER—SCAPULAR REGION.

In the dissection of this region the following parts must be studied:—

1. Cutaneous nerves of the shoulder.
2. Deep fascia.
3. Deltoid muscle.
4. Sub-acromial bursa.
5. Anterior and posterior circumflex vessels.
6. Circumflex nerve.
7. Dorsalis scapulæ artery.
8. Subscapularis muscle.
9. Supraspinatus, infraspinatus, teres minor, and teres major muscles.
10. Bursæ in connection with the shoulder-joint.
11. Suprascapular nerve and artery.
12. Acromio-clavicular joint, and the coraco-acromial arch.

Muscles inserted into the Clavicle and Scapula.—The insertions of the muscles which have already been divided should first engage the attention of the student. These should be carefully defined and the precise extent of each studied. Begin with the *omo-hyoid*, which springs from the superior border of the scapula; then deal in the same way with the *levator anguli scapulæ*, *rhomboidæ minor* and *major*, which are attached to the vertebral border of the bone, and the *serratus magnus*, which is inserted into the ventral aspect of the superior and inferior angles, and the intervening portion of the vertebral border of the scapula. The insertion of the *pectoralis minor* into the coracoid process, and of the *trapezius* into both clavicle and scapula, should also be thoroughly examined. When this has been done these divided muscles may be removed,

with the exception of about half an inch of each, which it is advisable to leave attached to the bones for future reference.

Dissection.—A block should now be placed in the axilla, and the skin removed from the upper and outer aspects of the shoulder as low down as the insertion of the deltoid. Commence in front and proceed from before backwards, taking care to leave the fatty superficial fascia in its place.

Cutaneous Nerves.—In the superficial fascia, which is thus laid bare, cutaneous nerves from two different sources must be secured and traced, in order that the area of skin supplied by each may be recognised. They are:—

1. Acromial branches from the third and fourth cervical nerves.
2. Cutaneous branches from the circumflex nerve.

The *acromial branches* have already been observed crossing the outer third of the clavicle and the insertion of the trapezius under cover of the platysma. They have been divided in removing the limb. If the cut ends be secured and followed, they will be found to spread out over the outer and back part of the upper portion of the deltoid region.

The *cutaneous branches* of the *circumflex nerve* consist—(a) of a large branch which turns round the posterior border of the deltoid muscle, and (b) of several fine filaments from the same source, which pierce the substance of the deltoid muscle, and appear at irregular intervals on its surface. The latter are difficult to secure, but the main branch can be easily found by carefully dividing the superficial fascia along the posterior border of the deltoid. On everting this border very little dissection is required to expose the nerve hooking round it about two and a half inches above the deltoid insertion. It breaks up into branches which supply the skin over the lower portion of the deltoid region.

Deep Fascia.—A firm but thin fascia covers the subscapularis muscle. Into this some of the fibres of the serratus magnus are usually inserted at the vertebral border of the scapula. The strongest and most conspicuous fascia in this region is that which covers the exposed part of the infraspinatus muscle on the dorsal aspect of the scapula. It is firmly attached to the limits of the fossa in which that muscle lies, and presents other very apparent connections. Thus a strong septum will be noticed to dip in between the infraspinatus and teres minor muscles, and then as it proceeds

forwards it gives a thin covering to the *teres minor*, *teres major*, and the *deltoid*. Indeed, it may be said to split into two lamellæ—a superficial and a deep,—which as they pass forwards enclose between them the *deltoid muscle*.

Dissection.—Depress the scapula and retain it in this position by means of hooks. The fibres of the *deltoid* are thus rendered tense, and the coarse fasciculi of the muscle may be cleaned.

Deltoid Muscle.—The *deltoid muscle*, as its name implies, is triangular in form. It is composed of coarse fasciculi, and covers the shoulder-joint. It arises from the anterior border of the outer third or half of the clavicle (Fig. 3, p. 7), from the outer border of the acromion process, and from the lower border of the spine of the scapula (Fig. 17, p. 49). Its origin closely corresponds with the insertion of the *trapezius*. The fasciculi of which the muscle is formed converge rapidly as they are traced downwards, and finally they present a pointed tendinous insertion into the *deltoid eminence* on the middle of the outer surface of the shaft of the humerus (Fig. 26, p. 70). Its nerves of supply come from the *circumflex nerve*.

Dissection.—The limb should now be placed on its posterior aspect, and the posterior circumflex artery and the circumflex nerve traced backwards through the quadrilateral space. The boundaries of the space at the same time should be defined and cleaned.

Quadrilateral and Triangular Spaces.—The quadrilateral space is purely the result of dissection; it has no real existence until the parts are artificially separated from each other. When viewed from the front, the boundaries will be seen to be formed—(a) *externally*, by the upper part of the shaft of the humerus; (b) *internally*, by the long head of the triceps; (c) *above*, by the lower margin of the subscapularis; (d) and *below*, by the upper border of the *teres major*. When viewed from behind, the *upper boundary* of the quadrilateral space will be seen to be formed by the *teres minor*; the other boundaries are the same as those seen from the front.

The term *triangular space* is the name given to another intermuscular interval which becomes apparent when the muscles in this region are cleaned and separated. It is placed nearer the inferior angle of the scapula, and the long head of the triceps intervenes between it and the quadrilateral space. It is bounded *above* by the subscapularis; *below* by

the *teres major*; and *externally* by the long head of the *triceps*. The *dorsalis scapulae* artery should be followed into this space, and cleaned up to the point where it disappears around the axillary border of the scapula under cover of the *teres minor*.




FIG. 15.—Dissection of the Posterior Scapular Region.

Dissection.—Having now traced the posterior circumflex artery and the circumflex nerve as far as possible through the quadrilateral space, the position of the limb should be reversed. Turn it so that its dorsal surface is uppermost, and everting slightly the posterior border of the deltoid, define the boundaries of the space as they are seen from behind. At the same time clean the circumflex vessels and nerves as they issue from the space to reach the deep surface of the deltoid muscle. Care must be taken not to injure the branch which the circumflex nerve gives to the *teres minor*.

The deltoid muscle may now be divided close to its origin and thrown downwards; in doing this preserve the acromial branch of the thoracic

axis which runs in the line of incision beneath the deltoid. A large bursa which lies between the deltoid and upper aspect of the capsule of the shoulder-joint must also be kept intact.

Parts under cover of the Deltoid.—The deltoid covers the upper part of the humerus, and is wrapped round the shoulder-joint so as to envelop it behind, externally, and in front. The full rounded appearance of the shoulder will now be seen to be due to the muscle passing over the expanded upper end of the humerus. When the head of the bone is displaced the muscle passes more or less vertically downwards from its origin, and the dislocation is recognised by the squareness or flatness of the shoulder. Behind, the deltoid covers the muscles which arise from the dorsal aspect of the scapula as they pass outwards to reach the great tuberosity of the humerus; in front, it covers the upper part of the biceps muscle, and overlaps the coracoid process and the muscles attached to it. In relation also to the deep surface of the deltoid are the circumflex vessels and nerve.

Subacromial Bursa.—This is a large bursal sac which intervenes between the acromion process and deltoid above, and the upper aspect of the capsule of the shoulder-joint below. It facilitates the play of the upper end of the humerus with its capsule, on the under aspect of the acromion process and deltoid. Pinch a portion of it up with the forceps and make an incision into it.¹ The finger may then be introduced into its interior and its extent and connections explored. In some cases it is divided by internal partitions into two or more chambers or loculi.

Dissection.—The branches of the posterior circumflex artery and the circumflex nerve should now be dissected out on the deep surface of the deltoid muscle.


Circumflex Vessels.—The *posterior circumflex artery* (arteria circumflexa humeri posterior) has been already observed to arise within the axilla from the posterior aspect of the axillary artery a short distance below the subscapular branch. It at once proceeds backwards through the quadrilateral space, and, winding round the surgical neck of the humerus, it is distributed in numerous branches to the deep surface of the deltoid muscle. Several twigs are also given to the shoulder-joint and the integument. It anastomoses with the acromial branch of the thoracic axis and the anterior circumflex artery,

¹ If the wall of the bursa be quite entire a blowpipe may be thrust into it. It can then be distended, and if unilocular it may be inflated to about the size of a hen's egg. It varies, however, much in size in different individuals.

and also by one or more twigs which it sends downwards to the long head of the triceps, with the superior profunda branch of the brachial artery.

The termination of the *anterior circumflex artery* (arteria circumflexa humeri anterior) can now be more satisfactorily studied, and its anastomosis with the posterior circumflex established if the injection has flowed well. By this anastomosis the arterial ring which encircles the upper part of the shaft of the humerus is completed.

Circumflex Nerve (nervus axillaris).—This nerve accompanies the posterior circumflex artery, and supplies—(a) *muscular branches* to the deltoid and teres minor; (b) *cutaneous branches* to the skin over the lower part of the deltoid; and (c)



H. Transverse section of the humerus immediately below the tuberosities.

A.A. Axillary artery.

P.C. Posterior circumflex artery.

A.C. Anterior circumflex artery.

C.N. Circumflex nerve.

a. Articular branch.

T.M. Branch to teres minor.

C. Cutaneous branches.

FIG. 16.—Diagram of the Circumflex Vessels and Nerve.

an *articular twig* to the shoulder-joint. The following is the manner in which it is distributed. It springs from the posterior cord of the brachial plexus, and turning round the lower border of the subscapularis, proceeds backwards with the posterior circumflex artery through the quadrilateral space. Reaching the posterior aspect of the limb, it divides into an anterior and a posterior division. The *articular branch* takes origin from the trunk of the nerve, and enters the joint below the subscapularis muscle. The *posterior division* gives off the branch to the teres minor, and after furnishing a few twigs to the posterior part of the deltoid, is continued onwards as the cutaneous nerve which has already been dissected in the superficial fascia over the lower part of the deltoid (Fig. 16).

The nerve to the teres minor is distinguished by the presence of an oval gangliform swelling upon it. The *anterior division* proceeds round the humerus with the posterior circumflex artery, and ends near the anterior border of the deltoid. It is distributed by many branches to the deep surface of this muscle, whilst a few fine filaments piercing the deltoid reach the skin.

'Teres Major.—The part which the teres major plays in the formation of the quadrilateral and triangular spaces has already been seen. It arises from the oval surface on the dorsum of the scapula close to the inferior angle of the bone (Fig. 17), and also from the septa which the fascia infrapinata sends in to separate it from the infrapinatus and teres minor muscles. It is inserted into the inner lip of the bicipital groove on the upper part of the humerus (Fig. 26, p. 70). It is supplied by the *lowest subscapular nerve*.

Insertions of Latissimus Dorsi and Pectoralis Major.—The narrow, band-like tendon of the latissimus dorsi lies in front of the insertion of the teres major. From the lower margin of this a small fibrous slip will be observed passing downwards, beyond the lower margin of the teres major, to find attachment to the long head of the triceps. This is a rudiment of the dorsi-epitrochlearis muscle of the lower animals. The tendons of the teres major and latissimus dorsi should now be separated from each other. They will be found to be more or less adherent, and a small bursa will be discovered between them. The insertion of the latissimus dorsi into the bottom of the bicipital groove of the humerus may now be satisfactorily studied.

The tendon of insertion of the *pectoralis major*, which is attached to the outer lip of the bicipital groove, may also be conveniently examined at this stage (p. 22). A separation of the sternal and clavicular portions of the muscle will bring into view the two laminae which constitute the tendon, and the following points may be noted in connection with these :—(a) that they are continuous with each other below, or, in other words, that the tendon is simply folded upon itself; (b) that the posterior lamina extends upwards on the humerus to a higher level than the anterior, and that a fibrous expansion proceeds upwards from its superior border, to seek attachment to the capsule of the shoulder-joint and the lesser tuberosity of the humerus; (c) that the lower border is connected with the fascia of the upper arm.

Acromio-clavicular Articulation.—This is a diarthrodial joint, and the ligaments which bind the bones together are :—

Ligaments proper to the joint,	{ 1. Superior 2. Inferior }	capsule.
Accessory ligaments—Coraco-clavicular		{ trapezoid. conoid.

The *superior acromio-clavicular ligament* is a broad band, composed of stout fibres, which is placed on the upper aspect of the joint. The *inferior acromio-clavicular ligament* which closes the joint below is not so strongly developed. In front and behind, these ligaments are connected with each other so as to constitute a capsule. The joint should now be opened, when it will be seen to be lined by a synovial membrane. An imperfect *interarticular fibro-cartilage* is also usually present. It is wedge-shaped, and connected by its base to the superior ligament, whilst its free margin is directed downwards between the bones.

Coraco-clavicular Ligament.—This powerful ligament binds the under surface of the clavicle to the base of the coracoid process. When thoroughly cleaned and defined it will be seen to consist of two parts, which are termed the conoid and the trapezoid ligaments.

The *conoid ligament* (ligamentum conoideum), placed upon the posterior and inner aspect of the trapezoid, is broad above where it is attached to the conoid tubercle of the clavicle (Fig. 12, p. 35), and somewhat narrower below at its attachment to the inner part of the root of the coracoid process. The *trapezoid ligament* (ligamentum trapezoideum) is the anterior and external part. Above it is attached along the trapezoid line of the clavicle (Fig. 12, p. 35), whilst below it is fixed to the upper aspect of the coracoid process. In the recess between these two ligaments a bursa will usually be found.

Coraco-acromial Arch.—It is necessary to examine this arch at the present stage, as the next step in the dissection will, in a great measure, destroy it. It is the arch which overhangs the shoulder-joint and protects it from above. It is formed by the coracoid process, the acromion process, and a ligament—the coraco-acromial—which stretches between them.

The *coraco-acromial ligament* is a strong band of a somewhat triangular shape. By its base it is attached to the outer border of the coracoid process, whilst by its apex it is attached to the extremity of the acromion (Fig. 32, p. 84).

The coraco-acromial arch plays a very important part in the mechanism of the shoulder; it might almost be said to form a secondary socket for the humerus. We have already

noted the large bursa which intervenes between the acromion and the capsule of the shoulder-joint, to facilitate the movements.




FIG. 17.—Dorsum of Scapula with the Attachments of the Muscles mapped out.

Dissection.—The supraspinatus, infraspinatus, and teres minor muscles which arise from the dorsum scapulae, and the subscapularis, which takes origin from the venter scapulae, may now be examined. In order to obtain an uninterrupted view of the supraspinatus muscle, the acromion process must be divided with the saw close to its junction with the spine of the scapula (Fig. 15).

Further, divide the fascia which covers the teres minor muscle, and

reflect it towards the infraspinatus. By this means the septum from the fascia infraspinata, which dips in between the two muscles, will be demonstrated, and their separation rendered easy. Care must be taken not to injure the dorsalis scapulæ artery which passes between the teres minor and the bone.

Supraspinatus.—This muscle arises from the inner two-thirds of the supraspinous fossa, and also to a slight degree from the fascia supraspinata which covers it. From this origin the fibres converge as they pass outwards, and, proceeding under the acromion process, they end in a short, stout tendon, which is inserted into the uppermost of the three impressions on the great tuberosity of the humerus (Fig. 26, p. 70). This tendon is closely adherent to the capsule of the shoulder-joint. The supraspinatus is covered by the trapezius, and in the loose fat which intervenes between this muscle and the fascia supraspinata some twigs of the superficial cervical artery ramify. It is supplied by the *suprascapular nerve*.

Teres Minor.—This is the small muscle which lies along the lower border of the infraspinatus. It arises from an elongated flat impression on the dorsal aspect of the axillary border of the scapula, and from the septa of the fascia infraspinata which intervene between it and the two muscles between which it lies, viz., the infraspinatus and teres major. It is inserted into the lowest of the three impressions on the great tuberosity of the humerus, and also, by fleshy fibres, into the shaft of the bone for about half an inch below this (Fig. 28, p. 75). Towards its insertion it is separated from the teres major by the long head of the triceps. The teres minor is supplied by a branch from the *circumflex nerve*.

Infraspinatus.—This muscle arises from the whole of the infraspinous fossa, with the exception of a small part of it near the neck of the scapula. It also derives fibres from the fascia which covers it. Its tendon of insertion is closely adherent to the capsule of the shoulder-joint, and is attached to the middle impression on the great tuberosity of the humerus (Fig. 28, p. 75). It is supplied by the *suprascapular nerve*.

Subscapularis.—The subscapularis muscle arises from the whole of the subscapular fossa, with the exception of a small portion near the neck of the scapula; it also takes origin from the groove which is present on the ventral aspect of the axillary border of the bone (Fig. 14, p. 40). Its origin is strengthened by tendinous intersections, which are attached

to the ridges which are present on the venter scapulæ. The fleshy fibres thus derived converge upon a stout tendon, which is inserted into the lesser tuberosity of the humerus; a few of the lower fibres, however, gain independent insertion into the shaft of the humerus below the tuberosity (Fig. 26, p. 70).

As the muscle proceeds outwards to its insertion, it passes under an arch formed by the coracoid process and the conjoined origin of the short head of the biceps and coracobrachialis. By dissecting between the upper border of the muscle and the root of the coracoid process, a bursa of some size will be discovered. This bursa communicates with the cavity of the shoulder-joint through an aperture in the capsular ligament: in other words, it is directly continuous with the synovial membrane which lines the joint. This can readily be ascertained by making an incision through its wall. An instrument can then be passed into the joint. The subscapularis is supplied by the *upper* and *lowest subscapular nerves*.

Dissection.—The suprascapular artery and nerve must now be followed to their distribution on the dorsum of the scapula. They have already been traced to the upper border of the scapula. Divide the infraspinatus muscle about an inch and a half from its insertion, taking care not to injure the subjacent vessels. Pull the muscle cautiously backwards, and its nerve of supply with the terminations of the suprascapular and dorsalis scapulæ vessels will be exposed. Treat the supraspinatus muscle in a similar manner (Fig. 15, p. 44).

Suprascapular Artery (arteria transversa scapulæ).—This vessel enters the supraspinous fossa by passing over the ligament which bridges across the suprascapular notch. It divides, under cover of the supraspinatus muscle, into a *supraspinous* and an *infraspinous branch*. The former supplies the supraspinatus muscle, and gives off the chief nutrient artery to the scapula; the latter proceeds downwards in the great scapular notch, and under cover of the spino-glenoid ligament, to reach the deep surface of the infraspinatus muscle to which it is distributed.

At the upper border of the scapula the suprascapular artery gives off a branch (the *subscapular*) which enters the subscapular fossa under cover of the subscapularis muscle.

Suprascapular Nerve.—This nerve accompanies the artery of the same name, but it enters the supraspinous fossa by passing through the suprascapular notch, under cover of the suprascapular ligament. It supplies the supraspinatus, and

ends in the infraspinatus muscle. It usually sends *two articular twigs* to the posterior aspect of the shoulder-joint, viz., one while in the supraspinous fossa, and the second as it lies in the infraspinous fossa.

Dorsalis Scapulæ Artery (*arteria circumflexa scapulæ*).—This vessel has already been observed to arise from the subscapular branch of the axillary, and enter the triangular space. While here, it supplies one or two *ventral branches*, which pass under cover of the subscapular muscle to the venter scapulæ, and a larger *infrascapular branch* which runs downwards in the interval between the teres major and teres minor to the inferior angle of the scapula (Fig. 15, p. 44). After these branches are given off, the dorsalis scapulæ leaves the triangular space by turning round the axillary border of the scapula, under cover of the teres minor. It now enters the infraspinous fossa, where it ramifies and supplies branches to the infraspinatus muscle.

Anastomosis around the Scapula.—A very important and free anastomosis takes place around the scapula. Three main blood-vessels take part in this, viz.—(a) the suprascapular; (b) the posterior scapular; and (c) the subscapular.

The *posterior scapular artery* runs downwards in relation to the base or vertebral border of the scapula, and dispenses branches upon both the dorsal and ventral aspects of the bone. The *subscapular artery* runs downwards and inwards along the axillary border of the scapula, and at the inferior angle some of its terminal branches anastomose with the terminal twigs of the posterior scapular. The *suprascapular artery* at the upper margin of the scapula is brought into communication with the posterior scapular by an anastomosis in the neighbourhood of the superior angle of the bone.

But still more distinct anastomoses take place upon the dorsal and ventral aspects of the bone. In the supraspinous fossa, branches of the *suprascapular* inosculate with twigs from the *posterior scapular*; whilst in the infraspinous fossa, free communications are established between the *dorsalis scapulæ*, the *suprascapular*, and the *posterior scapular*.

On the ventral aspect of the scapula, the ventral branch of the *suprascapular*, the ventral branches of the *dorsalis scapulæ*, and the ventral branches of the *posterior scapular*, join to form a network.

The importance of this free communication between the blood-vessels in relation to the scapula will be manifest when it is remembered that two of the main arteries, viz., the posterior scapular and the suprascapular, spring indirectly from the first part of the subclavian; whilst the third, viz., the subscapular, arises from the third part of the axillary. When, therefore, a ligature is applied to any part of the great arterial trunk of the upper limb, between the first stage of the subclavian and the third part of the axillary, this anastomosis affords ample means of re-establishing the circulation.

Dissection.—Detach the subscapularis from the scapula and lift it outwards to its insertion. This will afford a better view of its relation to the capsule of the shoulder-joint, and also of the subscapular bursa. In a well-injected subject the ventral anastomosis can likewise be made out.

Suprascapular and Spino-glenoid Ligaments.—These are two ligamentous bands, which are placed in relation to the suprascapular artery and nerve. The *suprascapular* or *transverse ligament* bridges across the suprascapular notch of the scapula, and converts it into a foramen. It lies between the artery and nerve: the former being placed above it, and the latter below it. Not infrequently it is ossified. The *spino-glenoid ligament* is a weaker band, which bridges across the suprascapular artery and nerve as they pass through the great scapular notch. On the one hand it is attached to the spine of the scapula, and on the other to the upper part of the neck of the scapula.

FRONT OF THE ARM.

In this dissection the following parts have to be studied:—

1. Cutaneous vessels and nerves.
2. Brachial aponeurosis.
3. Brachial artery and its branches.*
4. Median, ulnar, musculo-spiral, and musculo-cutaneous nerves and the branches of the last two.
5. Biceps, coraco-brachialis, and brachialis anticus muscles.

In conjunction with this dissection, it is convenient to study the triangular space in front of the elbow, and also to trace the cutaneous nerves to their ultimate distribution in the skin of the forearm.

Surface Anatomy.—In a muscular limb the prominence formed by the biceps muscle along the front of the upper arm is very apparent. Every one is familiar with the rounded swelling which it produces when powerfully contracted in the living subject. On either side of the biceps there is a feebly marked furrow, and ascending in each of these there is a large superficial vein. In the outer furrow is the cephalic vein; in the lower part of the inner furrow the basilic vein. In the upper part of the inner or basilic furrow there is an elongated bulging produced by the subjacent coraco-brachialis



FIG. 18.—Posterior view of the Upper Limb, with the Elbow-joint fully extended (Luschka).

1. Humerus.
2. Ulna.
3. Radius.



FIG. 19.—Posterior view of the Upper Limb, with the Elbow-joint flexed (Luschka).

1. Humerus.
2. Ulna.
3. Radius.

muscle. This is useful as a guide to the lower part of the axillary and the upper part of the brachial artery, which lie immediately behind and to the inner side of it. The humerus is thickly clothed by muscles; but towards its lower part the two supracondylar ridges, leading down to the condylar eminences, may be felt. The external ridge is the more salient of the two, and therefore the more evident to touch.

The bony points around the elbow require to be studied with especial care. It is by a proper knowledge of the normal relative positions of these that the surgeon is able to distinguish between the different forms of fracture and dis-

location which so frequently occur in this region. First note the internal condyle of the humerus. This constitutes a prominence, appreciable to the eye; grasp it between the finger and thumb, and note that it inclines backwards as well as inwards. In a well-developed arm, when fully extended, the external condyle does not form a projection on the surface, but can be felt at the bottom of a slight depression on the posterior aspect of the limb. It becomes apparent to the eye as a prominence when the elbow is semi-flexed. The olecranon process of the ulna produces a marked projection on the back of the elbow between the two condyles. It is placed slightly nearer to the internal than to the external condyle. The loose skin which covers the olecranon moves freely over its subcutaneous surface, owing to the interposition of a synovial bursa. The different positions which are assumed by the olecranon, in relation to the condyles of the humerus in the movements of the forearm at the elbow-joint, must be carefully examined. This can best be done by placing the thumb on one condyle, the middle finger on the other, and the forefinger on the olecranon. The limb should then be alternately flexed and extended, so as to make clear the extent of the excursion performed by the olecranon. In full extension at the elbow-joint the three prominences are placed on the ~~same straight line~~; when the forearm is bent at a right angle the three bony points are placed at the angles of an ~~equilateral triangle~~, the apex of which points downwards.

When the arm is extended a marked depression on the back of the elbow indicates the position of the articulation between the radius and the humerus. Immediately below this the head of the radius lies close to the surface, and can readily be felt, especially when it is made to roll under the finger by inducing alternately the movements of pronation and supination. The head of the radius is placed about an inch below the external condyle.

As the skin of the forearm must be reflected in the pursuit of the cutaneous nerves, it is well, at this stage, to study also the external anatomy of this segment of the limb. In its upper half the radius is deeply imbedded in muscles, but in its lower half it can be felt, and its styloid process on the outer side of the wrist can be readily distinguished. On the

dorsal aspect of the lower end of the radius immediately above the radio-carpal joint, and nearer the radial than the ulnar border of the limb, a prominent bony tubercle may be felt. This is the high ridge which forms the outer wall of the sharply cut groove on the back of the radius in which the tendon of the extensor secundi internodii muscle plays.

The sinuous posterior border of the ulna is subcutaneous, and may be followed by the finger throughout its entire length; as the elbow is approached it leads directly on to the subcutaneous surface on the back of the olecranon. In cases of suspected fracture, therefore, this border affords valuable information. The styloid process of the ulna may be detected immediately above the wrist, and it should be observed that this does not extend so low down as the corresponding process of the radius. The rounded lower end of the ulna makes a marked projection on the inner and posterior aspect of the limb immediately above the wrist-joint, and lying in the groove between it and the styloid process the tendon of the extensor carpi ulnaris may be felt.

Reflection of Skin.—The skin should be removed from the limb as far down as the wrist-joint. It is necessary to do this in order that a connected view may be obtained of the cutaneous nerves and the superficial veins. But at the same time the skin should not be cast aside, as it forms a most efficient protective wrapping for the part even after it has been detached. Make one long incision along the middle of the fore aspect of the arm and the forearm down to the wrist. A second incision carried transversely round the lower end of the forearm, immediately above the wrist-joint, will enable the dissector to reflect the skin in two large flaps, outwards and inwards. In the fatty superficial fascia which is then exposed, the superficial structures may be traced. It is well to begin with the nerves, as these are not so apparent, and therefore more liable to injury than the veins. But the dissection of the veins should be carried on concurrently with that of the nerves.

Cutaneous Nerves.—These are very numerous, and are derived from several sources. In addition to the two internal cutaneous nerves, and the terminal cutaneous part of the musculo-cutaneous, which spring from the brachial plexus, there are three branches derived from the musculo-spiral, and one—the intercosto-humeral—from the second intercostal nerve. These seven nerves may be classified into an inner and an outer group as follows:—

- | | |
|---|--|
| 1. Upper external cutaneous branch of musculo-spiral , Radial | } Distributed mainly upon the outer aspect of arm and forearm. |
| 2. Lower external cutaneous branch of musculo-spiral, | |
| 3. Cutaneous part of musculo-cutaneous. | |
| 1. Intercosto-humeral, | } Distributed mainly upon the inner aspect of arm and forearm. |
| 2. Internal cutaneous branch of musculo-spiral, | |
| 3. Lesser internal cutaneous, | |
| 4. Internal cutaneous, | |

The two *external cutaneous branches of the musculo-spiral* pierce the deep fascia about the middle of the outer surface of the upper arm immediately below the insertion of the deltoid, and in close relation to the external intermuscular septum. The smaller *upper branch* appears a short distance above the other. It follows the cephalic vein, and can be traced downwards as far as the elbow. Its filaments are distributed to the skin over the outer and anterior part of the lower half of the upper arm. The larger *lower branch* can be followed as far as the wrist, and not infrequently its terminal filaments may even reach the dorsum of the hand. It supplies the skin on the dorsal aspect of the forearm.¹

The terminal *cutaneous branch of the musculo-cutaneous* will be found in front of the elbow-joint. It pierces the deep fascia on the outer side of the tendon of the biceps. It is a large nerve, and proceeds downwards behind the median cephalic vein. The skin both upon the anterior and posterior aspects of the outer side of the forearm is supplied by this nerve, and it is distributed by two main branches. The larger *anterior branch* can be traced as far as the skin over the ball of the thumb. A few of its terminal twigs pierce the fascia above the wrist, and join the radial artery, by which they are conducted to the back of the carpus. The *posterior branch* may be followed on the dorsal aspect of the limb as far as the wrist.

The *intercosto-humeral nerve* can usually be traced half-way down the upper arm; but the area of skin which it supplies is somewhat variable. The *internal cutaneous branch of the musculo-spiral* proceeds downwards and backwards on a deeper

¹ It should be borne in mind that the skin on the outer aspect of the limb, above these nerves and over the deltoid, is supplied by the cutaneous branches of the circumflex nerve and the supra-acromial branches of the cervical plexus (p. 42).

plane, and crosses under the intercosto-humeral. Its fila-




FIG. 20.—Cutaneous Nerves on the Front of the Upper Limb.

ments extend upon the back of the upper arm as low as the elbow-joint.

The *small internal cutaneous nerve*, or *nerve of Wrisberg*,




FIG. 21.—Cutaneous Nerves on the Posterior Aspect of the Upper Limb.

will be found piercing the deep fascia, to become superficial, half-way down the inner side of the upper arm. Its twigs

may be followed, in the superficial fascia, as far as the olecranon process.

On the inner side of the upper arm, on its dorsal aspect, three nerves therefore have been traced. From within outwards these are: the nerve of Wrisberg, the intercosto-humeral, and the inner cutaneous branch of the musculospiral (Fig. 21).

The *internal cutaneous nerve* is chiefly destined for the supply of the skin of the forearm. It appears through the deep fascia half-way down the inner side of the upper arm close to the basilic vein, and a short distance in front of the nerve of Wrisberg. It at once divides into an anterior and a posterior branch. The *anterior branch* runs downwards behind (but sometimes in front of) the median basilic vein, and it is distributed to the skin over the inner and anterior aspect of the forearm. The *posterior branch*, inclining inwards, proceeds downwards in front of the internal condyle of the humerus, to reach the skin on the inner and dorsal aspect of the forearm.

A small twig is frequently given by the internal cutaneous nerve to the skin over the biceps muscle. This pierces the deep fascia close to the axilla.

Superficial Veins.—The superficial veins in front of the forearm and upper arm may now be followed; but in all probability they are already for the most part exposed.

Four veins will be seen ascending upon the anterior and lateral aspects of the forearm, viz., the *radial vein* upon the outer border; the *anterior* and *posterior ulnar veins* upon the inner border; and the *median vein* upon the front of the forearm. When the median reaches the hollow in front of the elbow, it is joined by a short wide vein, which appears through the deep fascia, and establishes a connection between the median and the deep veins of the forearm. This connecting trunk is called the *profunda vein*. After receiving this tributary, the median at once divides into two branches, which diverge widely from each other, like the limbs of the letter V. The inner branch is called the median-basilic; the outer the median-cephalic.

The *median-basilic* is a short wide vessel which passes upwards and inwards, and as it approaches the front of the internal condyle of the humerus it is joined by the two ulnar

veins. These may enter it separately; but more commonly the anterior ulnar vein joins the larger posterior ulnar vein in the upper part of the forearm, so as to form a common trunk, with a single opening into the median-basilic. The large vein, resulting from the union of the median-basilic and the two ulnar veins, is termed the *basilic vein*. The median-basilic is the vein which is commonly selected when the surgeon has recourse to venesection; and formerly, when the practice of bloodletting was more common than it is now, the relations of this vein were a matter of high importance. The dissector should observe the following points in regard to it:—(1) that it crosses a thickened piece of the deep fascia, termed the *bicipital fascia*; (2) that this fascia separates it from the brachial artery, which it also crosses; and (3) that the anterior part of the internal cutaneous nerve lies behind it, although in many cases it may cross in front of it.

The *median-cephalic vein* is not so large as the median-basilic, and it generally ascends with a greater degree of obliquity. It crosses in front of the cutaneous branch of the musculo-cutaneous nerve, and is joined by the radial vein. The resulting trunk is called the *cephalic vein*.

The *basilic vein* runs upwards on the inner aspect of the upper arm in the slight furrow which marks the limb along the inner margin of the biceps. Half-way up the upper arm it disappears by piercing the fascia close to the spot where the internal cutaneous nerve emerges. At the lower border of the posterior wall of the armpit the basilic forms the axillary vein.

The *cephalic vein* ascends in the groove along the outer margin of the biceps. Its further course has been previously noted. It extends upwards in the interval between the deltoid and the clavicular part of the pectoralis major. It dips backwards through the costo-coracoid membrane, crosses the first part of the axillary artery, and finally opens into the axillary vein.

Lymphatic Glands.—If the superficial fascia be searched upon the inner side of the limb, and immediately above the elbow, one or two minute lymphatic glands in relation to the basilic vein will be found. These are of interest to dissectors, as they are the first to enlarge and become painful in cases of dissection-wound.

Brachial Aponeurosis (fascia brachii).—The deep fascia should now be cleaned by the removal of the fatty superficial layer. It forms a continuous envelope around the upper arm, but at no point does it show a great density or strength. Above, it is continuous with the axillary fascia, and the fascia covering the pectoralis major and the deltoid. The tendons of these two muscles are closely connected with it—a certain proportion of their tendinous fibres running directly into it. Below, it is firmly fixed to the bony prominences around the elbow, and in front it receives an accession of fibres from the tendon of the biceps. These fibres constitute the




FIG. 22.—Diagram (after Turner) to show how the Upper Arm is divided by the intermuscular septa and bone into an anterior and posterior compartment. These compartments are represented in transverse section.

bicipital or semilunar fascia, and form a very distinct band which, continuous with the fascia above and below, bridges across the brachial artery, and is lost upon the pronator radii teres muscle on the inner side of the forearm.

The brachial aponeurosis may be reflected by making an incision through it along the middle line of the front of the arm. In throwing the inner portion inwards, the dissector must leave the bicipital fascia in position. This may be done by separating it artificially from the general aponeurosis by an incision above and below it.

As the foregoing dissection is proceeded with, it becomes evident that septa or partitions pass in between the muscles from the deep surface of the investing brachial aponeurosis. Two of these possess a superior strength, and obtain direct

attachment to the humerus. They are the external and internal intermuscular septa. The connections of these cannot be fully studied at present, but it is important that the student should understand their relations at this stage. In the course of the dissection of the upper arm they will gradually be displayed.

The *internal intermuscular septum* is the stronger and more distinct of the two. It is attached to the internal supracondyloid ridge, and may be followed upwards as high as the insertion of the coraco-brachialis muscle. The *external*




FIG. 23.—Transverse section through the Lower Third of the Right Upper Arm.

intermuscular septum is fixed to the external supracondyloid ridge, and extends up the arm as high as the insertion of the deltoid. The dissector should note that these septa divide the upper arm into an anterior and a posterior osteo-fascial compartment.

Structures in the Anterior Compartment.—The anterior osteo-fascial compartment of the upper arm has been opened into by the reflection of the front part of the brachial aponeurosis. The three muscles which specially belong to this region are the biceps, brachialis anticus, and the coraco-brachialis. The biceps is the most superficial muscle: under

cover of it, and closely applied to the anterior aspect of the humerus, is the brachialis anticus; whilst the coracobrachialis is the slender muscular belly which lies along the inner side of the biceps in its upper part. But, in addition, two muscles of the forearm will be observed extending upwards into the arm, to seek origin from the external supracondyloid ridge of the humerus: they are the supinator longus and the extensor carpi radialis longior. They are closely applied to the outer side of the brachialis anticus. The brachial artery, with its venæ comites, extends through the region in relation to the inner margin of the biceps, and all the terminal branches of the cords of the brachial plexus, with the exception of the circumflex, will be found for some part of their course in this region. The musculo-spiral, it is true, almost at once proceeds to the back of the limb, but it again comes to the front, and may be found in the lower part of the outer side of the arm, by separating the origins of the supinator longus and extensor carpi radialis longior from the brachialis anticus, and dissecting deeply in the interval between them.

Dissection.—In carrying out this somewhat extensive dissection, the main object of the dissector should be to keep the brachial artery as undisturbed as possible until he has satisfied himself as to its relations. He is therefore, in the first instance, advised to clean only those parts of the muscles which are in immediate relationship to the vessel and its branches. The divided brachial nerves, with the axillary artery and vein, should be arranged in proper order, and then tied to a small piece of wood about $1\frac{1}{2}$ inches long (*e.g.*, a piece of a penholder), held transversely. By means of a loop of string this can then be fastened to the coracoid process. By this device the dissection of the upper arm will be greatly facilitated. The dissection of the entire length of the brachial artery should be carried out at one and the same time, and its termination in the radial and ulnar arteries should be defined.

Brachial Artery (arteria brachialis).—The brachial artery is the direct continuation of the axillary trunk into the upper arm. It therefore begins at the lower border of the teres major, and it proceeds downwards to a point a short distance below the bend of the elbow, where it ends opposite the neck of the radius by dividing into two terminal branches—the radial and the ulnar arteries. The course which it pursues is not a straight one: at first it lies upon the inner side of the limb, but it gradually, as it descends, inclines outwards so as to lie finally in front of the arm.

This change of direction must be borne in mind when pressure is applied to the vessel, with the view of controlling the flow of blood within it. Thus, above, the pressure must be directed in an outward and backward direction, so that it may be caught between the fingers and the bone; whilst below, the pressure must be applied in a backward direction.

Throughout its whole length, the brachial artery is superficial: in other words, in order to expose the vessel the skin and fascia alone would require to be removed. The inner margins of the coraco-brachialis and the biceps muscles, however, which lie along its outer side, overlap it to a con-




FIG. 24.—Transverse section through the middle of the Right Upper Arm.

siderable extent, and finally, in the antecubital fossa, it sinks deeply in the interval between the supinator longus on the outside, and the pronator radii teres on the inside. The extent to which the brachial artery is overlapped by the biceps may be seen in the accompanying woodcut (Fig. 24). At the bend of the elbow it is crossed by the bicipital fascia, which, as previously stated, intervenes between it and the median-basilic vein. The basilic vein, in its lower part, is separated from the artery by the deep fascia. It does not lie immediately over it, but to its inner side (Figs. 23 and 24). Higher up, after the vein has pierced the fascia, it comes into

closer relationship with the artery. Two *venæ comites* are closely applied to the brachial artery, and the numerous connecting branches which pass between these veins cross over and under the vessel, so as to make the relationship still more intimate.

Behind, the brachial artery is supported by a succession of structures, as we trace it from above downwards. First, it lies in front of the long head of the triceps, but here the musculo-spiral nerve and the superior profunda artery are interposed; next, it rests upon the inner head of the triceps; then upon the insertion of the coraco-brachialis; and lastly, for the remainder of its course, upon the brachialis anticus.

With the exception of the musculo-cutaneous, all the large nerves of the arm will be seen to lie, for a certain part of their course, in relation to the brachial artery. The *median* accompanies it closely throughout its whole length. At first it lies in front, and to the outer side of the vessel; towards the middle of the arm it crosses superficially to the vessel; from this onwards it is placed along its inner side. The *ulnar* and *internal cutaneous nerves* lie close to its inner side, as far as the insertion of the coraco-brachialis, and then they leave the artery. The former inclines backwards, and, piercing the internal intermuscular septum, enters the posterior compartment of the arm. The internal cutaneous nerve, on the other hand, inclines forwards, and becomes superficial by piercing the brachial aponeurosis. The *musculo-spiral*, for a very short distance, is placed behind the brachial artery, as it lies in front of the long head of the triceps, but soon it leaves the vessel by disappearing in the interval between the long and inner heads of the triceps.

Branches of the Brachial Artery.—A considerable number of branches spring from the brachial artery. Those which arise from its outer aspect are irregular in number, origin, and size. They are termed the *external branches*, and are distributed to the muscles and integument on the front of the arm. The series of *internal branches* which proceed from the inner and posterior aspect of the parent trunk are named as follows as we meet them from above downwards:—

- | | |
|-----------------------|------------------------|
| 1. Superior profunda. | 3. Nutrient. |
| 2. Inferior profunda. | 4. Anastomotica magna. |

The *superior profunda* (arteria profunda brachii) is the

largest of the branches which spring from the brachial trunk. It takes origin about an inch or so below the lower margin of the *teres major*, and associates itself with the musculo-spiral nerve, which it accompanies to the back of the arm. Con-




FIG. 25.—Diagram to show relation of Musculo-spiral Nerve to the Humerus and of Vessels and Nerves to the Intermuscular Septa.

sequently, only a short part of the vessel is seen in the present dissection. It soon disappears from view between the long and inner heads of the triceps.

The *inferior profunda* (arteria collateralis ulnaris superior) is a long slender artery, which can be recognised from the

fact that it follows closely the course which is pursued by the ulnar nerve. Its origin is somewhat uncertain. As a general rule, it issues from the brachial artery opposite the insertion of the coraco-brachialis, but very frequently it will be seen to arise in common with the superior profunda. It pierces the internal intermuscular septum, with the ulnar nerve, and descends behind this aponeurotic partition to the interval between the olecranon and the internal condyle of the humerus.

The *nutrient artery* to the humerus (*arteria nutritia humeri*) may arise directly from the brachial trunk, or take origin from the inferior profunda. It should be sought for at the lower border of the insertion of the coraco-brachialis, and the dissector should not be satisfied until he has traced it into the medullary foramen of the bone. When the nutrient artery is not seen in its usual position, it will probably be found in the dissection of the back of the arm, taking origin from the superior profunda.

The *anastomotica magna* (*arteria collateralis ulnaris inferior*) arises about two inches above the bend of the elbow, and runs inwards upon the brachialis anticus. It soon divides into a small anterior and a larger posterior branch. The *anterior branch* is carried downwards in front of the internal condyle of the humerus in the interval between the brachialis anticus and the pronator radii teres. It anastomoses in this situation with the anterior ulnar recurrent artery. The *posterior branch* pierces the internal intermuscular septum, and will be seen later on in the posterior compartment of the arm.

The two Internal Cutaneous Nerves.—Very little more requires to be said about these nerves. Their origin within the axilla has already been noted, and they have been traced to their distribution from the points where they pierce the investing brachial aponeurosis. It only remains for the dissector to examine them in that part of their course in which they lie under cover of the brachial aponeurosis. It will be observed that they both lie along the inner side of the brachial artery. The *nerve of Wrisberg*, or *lesser internal cutaneous nerve*, gives off, as a rule, no branches in this situation, except one or more twigs of communication to the intercosto-humeral. The *internal cutaneous* gives off the branch which pierces the fascia to supply the skin in front of the biceps.

Median and Ulnar Nerves.—These large nerve trunks do not furnish any branches in the upper arm. The *median* (nervus medianus) arises in the axilla by two heads from the outer and inner cords of the brachial plexus. It proceeds downwards upon the outer and superficial aspect of the axillary and brachial arteries, until it approaches the level of the insertion of the coraco-brachialis. Here it lies in front of the artery. Finally, it reaches the inner side of the vessel, and maintains this position for the rest of its course in the upper arm.

The *ulnar nerve* (nervus ulnaris) is the largest branch of the inner cord of the brachial plexus. It descends upon the inner side of the axillary and brachial arteries, and at the insertion of the coraco-brachialis it encounters the inferior profunda artery. Accompanied by this vessel, it now leaves the brachial artery by passing backwards through the internal intermuscular septum, and it is continued downwards upon the posterior aspect of this aponeurotic partition, to the interval between the olecranon and internal condyle of the humerus.

Dissection.—The muscles should now be thoroughly cleaned, and the musculo-cutaneous nerve and its branches dissected out.

Musculo-cutaneous Nerve (nervus musculocutaneus).—The musculo-cutaneous nerve arises from the outer cord of the brachial plexus, at the lower border of the pectoralis minor. Inclining outwards, it perforates the coraco-brachialis, and appears between the biceps and the brachialis anticus. It proceeds obliquely downwards between these muscles until it reaches the bend of the elbow, where it comes to the surface at the outer border of the tendon of the biceps. From this point onwards it has already been traced as a cutaneous nerve of the forearm (p. 57).

In the upper arm the musculo-cutaneous supplies branches to the three muscles in this region. The branch to the coraco-brachialis is given off before the parent trunk enters the substance of the muscle; the branches to the biceps and brachialis anticus issue from it, as it lies between them.

Coraco-brachialis.—This is an elongated muscle, which takes origin from the tip of the coracoid process in conjunction with the short head of the biceps. It proceeds downwards




FIG. 26.—Anterior aspect of Humerus with Muscular Attachments mapped out.

along the inner margin of the biceps, and obtains insertion into a linear ridge situated upon the inner aspect of the shaft of the humerus about its middle.

Biceps (musculus biceps brachii).—The biceps muscle arises from the scapula by two distinct heads of origin. The *short* or *inner head* (caput breve) springs from the tip of the coracoid process in conjunction with the coracobrachialis (Fig. 14, p. 40). The *long* or *outer head* (caput longum) is a rounded tendon, which occupies the bicipital groove of the humerus. Its origin cannot be studied at this stage of the dissection, because it is placed within the capsule of the shoulder-joint. Suffice it for the present to say, that it arises from an impression on the scapula immediately above the glenoid fossa. Both heads swell out into elongated fleshy bellies, which are closely applied to each other, and afterwards unite in the lower third of the arm. Towards the bend of the elbow the fleshy fibres converge upon a stout, short tendon, which is inserted into the posterior

part of the tuberosity of the radius. This insertion will be more fully examined at a later period, but it may be noticed in the meantime that the tendon is twisted so as to present its margins to the front and back of the limb, and further, that a synovial bursa is interposed between it and the anterior smooth part of the radial tuberosity.

The dissector has already taken notice of the *bicipital* or *semilunar fascia*, and has separated it artificially from the brachial aponeurosis above, and from the deep fascia of the forearm below. Observe now that it springs from the anterior margin of the tendon of the biceps, and that it likewise receives some muscular fibres from the short head of the muscle.

Brachialis Anticus (musculus brachialis).—The brachialis anticus arises from the entire width of the anterior surface of the lower half of the shaft of the humerus, from the internal intermuscular septum, and from a small part of the external intermuscular septum above the supinator longus. The origin from the bone is prolonged upwards in two slips which partially embrace the insertion of the deltoid. The fibres converge to be inserted into the base of the coronoid process of the ulna by a short, thick tendon. The muscle lies partly under cover of the biceps, but projects beyond it on either side. It is overlapped on its inner side by the pronator radii teres, and on the outer side by the supinator longus and extensor carpi radialis longior. Its deep surface is closely connected to the anterior ligament of the elbow-joint. Its chief nerve of supply, from the *musculo-cutaneous*, has already been secured, but it also receives one or two small twigs from the *musculo-spiral*, which are given off under cover of the supinator longus.

Dissection.—Separate the supinator longus muscle from the brachialis anticus, and dissect out the musculo-spiral nerve, and the anterior terminal branch of the superior profunda artery, which lie deeply in the interval between them. Here also the anastomosis between the superior profunda and the radial recurrent arteries may be made out, in a well-injected subject; and the twigs which are given by the musculo-spiral nerve to the brachialis anticus, supinator longus, and extensor carpi radialis longior, looked for.

Triangular Space in front of the Elbow (antecubital fossa).—This is a slight hollow in front of the elbow-joint. It corresponds to the popliteal space of the lower limb, and

within its area the brachial artery divides into its two terminal branches. In the first instance, let the dissector consider the structures which cover it. These have already been removed, and consist of skin, superficial fascia, and deep fascia. In connection with the latter is the semilunar fascia, whilst within




FIG. 27.—Dissection of the Antecubital Fossa.

the superficial fascia are the median-basilic and median-cephalic veins, the anterior division of the internal cutaneous nerve and the cutaneous part of the musculo-cutaneous nerve. These structures constitute the *coverings* of the space.

The space is triangular. Its *base* is directed upwards, and is usually regarded as being formed by a line drawn between the two condyles of the humerus. Its *inner boundary*

is the pronator radii teres, and its *outer boundary* the supinator longus. The meeting of these two muscles below constitutes the *apex*. The boundaries should now be thoroughly cleaned, and then the *contents* of the space may be dissected.

Within the space, as we have already stated, there is the termination of the brachial artery, with the radial and ulnar branches into which it divides. To the outer side of the main vessel is placed the tendon of the biceps, and to its inner side the median nerve. A quantity of loose fat is also present. The ulnar artery leaves the space by passing under cover of the pronator radii teres; the radial artery is continued downwards beyond the apex of the space, overlapped by the supinator longus. The median nerve disappears between the two heads of the pronator radii teres, and the tendon of the biceps inclines backwards between the two bones of the forearm, to reach its insertion into the radial tuberosity.

When the fatty tissue has been thoroughly removed the *floor* of the space will be revealed. This is formed by the brachialis anticus and the supinator brevis muscles. In this situation the brachialis anticus is closely applied to the anterior aspect of the elbow-joint, whilst the supinator brevis is wrapped round the upper part of the radius.

Now divide the bicipital fascia, and separate the bounding muscles widely from each other. Other structures come into view, but they cannot, strictly speaking, be regarded as lying within the space proper. They are—(1) the musculo-spiral nerve, the anterior branch of the superior profunda artery, and the recurrent branch of the radial artery, lying deeply in the interval between the supinator longus and the brachialis anticus; (2) the anterior branch of the anastomotica magna, and the anterior ulnar recurrent branch of the ulnar artery, placed under cover of the pronator radii teres.

BACK OF THE ARM.

In this region the following are the structures which require to be studied:—

1. The triceps muscle.
2. The superior profunda artery, and the musculo-spiral nerve.

3. The inferior profunda artery, and the ulnar nerve.
4. The posterior branch of the anastomotic artery.
5. The subanconeus muscle.

Dissection.—The skin has already been removed from the back of the arm. The deep fascia should now be raised from the surface of the triceps muscle, and its three heads cleaned and isolated from each other. To place the muscle on the stretch, the inferior angle of the scapula should be raised as high as possible, and the forearm flexed at the elbow-joint. The musculo-spiral nerve, together with the superior profunda artery, must at the same time receive the attention of the dissector. They should be followed backwards between the heads of the triceps, and all their branches should be carefully preserved.

Triceps (musculus triceps brachii).—This muscle occupies the entire posterior osteo-fascial compartment of the upper arm. It arises by a *long* or *middle head* from the scapula, and by two short heads, *outer* and *inner*, from the humerus. The fleshy fibres of these three heads join a common tendon, which is inserted into the top of the olecranon process of the ulna. The superficial part of the muscle is, for the most part, formed by the long scapular head and the outer humeral head of the muscle. The inner humeral head is deeply placed; only a very small portion of it appears superficially in the lower part of the arm on each side of the common tendon of insertion.

The *long* or *scapular head* (caput longum) of the triceps arises by a flattened tendon, from the rough triangular impression on the upper part of the axillary border and the lower aspect of the neck of the scapula (Fig. 14, p. 40). This tendon takes origin in the interval between the teres minor and subscapularis muscles.

The *two humeral heads* take origin from the posterior aspect of the humerus; and if it be borne in mind that no fibres arise from the musculo-spiral groove, and that this groove intervenes between the origins of these heads, their connections will be easily understood. The dissector should provide himself with a humerus, and, having first identified the musculo-spiral groove, proceed to map out the areas of attachment of the humeral heads of the triceps as they are exhibited in the dissected part.

The *outer head* (caput laterale) of the triceps arises from the outer and posterior aspect of the shaft of the humerus, above the level of the musculo-spiral groove. It takes origin, by short tendinous fibres, along a line which descends

vertically from the insertion of the *teres minor* above to the upper border of the musculo-spiral groove below. But it also derives fibres from a strong aponeurotic bridge or arch, which is thrown over the groove, so as to give protection to the superior profunda artery and the musculo-spiral nerve. The strength and position of this arch can be tested by thrusting the handle of the knife downwards and outwards in the musculo-spiral groove, and along the course of the nerve and artery under the external head of the triceps. By its lower end the arch is connected with the external intermuscular septum.

The *inner head* (*caput mediale*) of the triceps is placed below the musculo-spiral groove. It sends upwards, on the posterior aspect of the humerus, and along the inner margin of the groove, a narrow pointed fleshy slip, which obtains origin from the bone as high as the insertion of the *teres major* muscle. Below, it widens out and arises by short fibres from the entire breadth of the posterior surface of the humerus. It also




FIG. 28.—Posterior aspect of Humerus with Attachments of Muscles mapped out.

springs from the posterior surface of the internal intermuscular septum, and from the lower part of the corresponding surface of the external intermuscular septum. The inner head of the triceps, therefore, has very much the same origin from the back of the bone that the brachialis anticus has from the front of the bone.

The dissector should now study the *common tendon of insertion* of the triceps. The long and the outer heads end in a broad, flat tendon, which is inserted into the back part of the upper surface of the olecranon process, and at the same time gives off, on the outer side, a strong expansion to the fascia of the forearm as it covers the anconeus muscle. The short fleshy fibres of the inner head are, for the most part, inserted into the deep surface of the common tendon, but a considerable number find direct attachment to the olecranon, whilst a few of the deepest fibres are inserted into the loose posterior part of the capsule of the elbow-joint. These latter fibres have been described as a separate muscle under the name of *subanconeus*. The triceps is supplied by branches from the *musculo-spiral nerve*.

Dissection.—In order that the musculo-spiral nerve and the superior profunda artery may be fully exposed, the external head of the triceps must be divided. Thrust the handle of a knife along the musculo-spiral groove, and under the muscle. This will give the direction in which the outer head of the triceps should be severed. Beyond cleaning the nerve and its branches, and the superior profunda artery, as they lie in the groove, no further dissection is necessary.

Musculo-spiral Nerve (*nervus radialis*).—The musculo-spiral is the direct continuation of the posterior cord of the brachial plexus after it has furnished in the axilla the three subscapular and the circumflex nerves. In the first instance, the musculo-spiral proceeds downwards behind the lower part of the axillary artery and the upper part of the brachial artery. It soon leaves the front of the arm, however, and, inclining backwards with the superior profunda artery, enters the interval between the long and the inner heads of the triceps, and reaches the musculo-spiral groove. In this it is conducted round the back of the shaft of the humerus, under cover of the outer head of the triceps, and on the outer side of the limb it pierces the external intermuscular septum and appears in the anterior compartment of the arm. Here it has already been exposed. It lies deeply in the interval between the brachialis

anticus on the inside, and the supinator longus and extensor carpi radialis longior on the outside. It ends in front of the external condyle of the humerus by dividing into two terminal




FIG. 29.—Dissection of the posterior aspect of Upper Arm. The outer head of the Triceps has been divided so as to expose the Musculo-spiral Groove of Humerus.

branches, viz., the radial and the posterior interosseous. The musculo-spiral nerve presents therefore very different relations as it is traced from its origin to its termination: (1) between the subscapularis, latissimus dorsi, teres major, and long head of the triceps which support it behind, and the axillary and

brachial arteries which are placed in front of it ; (2) between the long and inner heads of the triceps ; (3) in the musculo-spiral groove between the bone and the outer head of the triceps ; (4) in the interval between the brachialis anticus on the inside, and the supinator longus and extensor carpi radialis longior on the outside.

The branches which proceed from the musculo-spiral nerve are partly *muscular* and partly *cutaneous*.

The *cutaneous branches* are three in number, and have already been traced. They are—(1) the *internal cutaneous*, which, as a rule, arises within the axilla, in common with the branch which supplies the long or scapular head of the triceps ; (2) the *upper external cutaneous*, and (3) the *lower external cutaneous*, which come off on the outer side of the arm close to the outer margin of the external intermuscular septum (p. 57).

The *muscular branches* go to the three heads of the triceps, to the anconeus, to the brachialis anticus, to the supinator longus, and to the extensor carpi radialis longior. The branches to the three last muscles spring from the main trunk after it has pierced the external intermuscular septum.

The branch to the inner head of the triceps is sometimes termed the *ulnar collateral nerve*. It is a long slender filament, which runs downwards to supply the lower fibres of the inner head of the triceps, and it receives this name from the close manner in which it is applied to the ulnar nerve in the lower part of its course.

The *branch to the anconeus* is also a long slender twig, which enters the substance of the internal head of the triceps, and appears at first sight to terminate there, but, if traced downwards, it will be found to end in the anconeus.

Superior Profunda Artery (*arteria profunda brachii*).—This artery has been already observed to take origin from the brachial trunk, immediately below the lower margin of the teres major muscle. It accompanies the musculo-spiral nerve, and its relations to the three heads of the triceps and the musculo-spiral groove of the humerus are exactly the same as those of the nerve. When it reaches the external intermuscular septum, at the outer side of the arm, it ends by dividing into two terminal branches—an anterior and a posterior. The *anterior* and *smaller branch* accompanies the

musculo-spiral nerve through the septum, and follows it downwards to the anterior aspect of the external condyle of the humerus, where it anastomoses with the radial recurrent artery. The *posterior larger branch* proceeds downwards on the posterior surface of the external intermuscular septum, and anastomoses on the back of the external condyle of the humerus with the posterior interosseous recurrent artery.

The branches which proceed from the superior profunda artery are chiefly distributed to the three heads of the triceps muscle. One twig runs upwards between the long and outer heads of the muscle, and anastomoses with the posterior circumflex artery. In this way, a link is established between the axillary and brachial systems of branches.

Dissection.—The ulnar nerve, with the inferior profunda artery, and the slender ulnar collateral nerve, can now be advantageously followed, as they proceed downwards upon the posterior aspect of the internal intermuscular septum. They are covered by a thin layer of fleshy fibres belonging to the internal head of the triceps. The posterior branch of the *anastomotica magna*, after it has pierced the internal septum, should also be dissected out. As a rule, a transverse branch passes between this vessel and the posterior terminal part of the superior profunda. It lies upon the back of the humerus, immediately above the elbow-joint, and can be exposed by dividing the triceps muscle a short distance above the olecranon. At the same time the fleshy fibres of the internal head of the triceps, which are inserted into the posterior ligament of the joint, and constitute the *subanconeus muscle*, should be examined. Lastly, raise the lower piece of the triceps from the elbow-joint, and look for a small bursa between the deep surface of the triceps tendon and the upper aspect of the olecranon.

SHOULDER-JOINT.

Before proceeding to the dissection of the forearm it is advisable to study the shoulder-joint (*articulatio humeri*), because if this is deferred too long the ligaments are apt to become dry.

In no joint in the body is the movement so free, and so varied in its character, as in the shoulder-joint. This is rendered necessary by the many functions which are performed by the upper limb. Freedom of motion is provided for in two ways—(1) by the large size of the head of the humerus, in comparison with the small dimensions and shallow character of the glenoid fossa—the socket in which it moves; (2) by the great laxity of the ligamentous structures which connect the humerus with the scapula.

These provisions for allowing an extensive range of movement at this articulation might, at first sight, lead one to doubt the security of the joint. Its strength certainly does not lie in the adaptation of the bony surfaces to one another, nor in the power of its ligaments. It lies—(1) in the intimate manner in which the scapular muscles are arranged around it; (2) in the overhanging coraco-acromial arch which forms, as it were, a secondary socket for the head of the humerus, and effectually prevents any displacement in an upward direction; and (3) in atmospheric pressure, which exercises a powerful influence in keeping the opposed surfaces in contact with each other.

From all points of view, except over a small area below, the loose,




FIG. 30.—Coronal or vertical transverse section through the Left Shoulder-joint. (Viewed from behind.)

ligamentous capsule which envelops the shoulder-joint is supported by muscles, the tendons of which are more or less intimately connected with it. *Above*, it is covered by the supraspinatus; *behind*, the infraspinatus and teres minor are applied to it; *in front* is the subscapularis. *Below*, the capsule is to a certain extent unsupported by muscles, and here it is prolonged downwards, in the form of a fold, in the ordinary easy dependent position of the limb (Fig. 30). When, however, the arm is abducted, this fold is obliterated, and the head of the bone rests upon the inferior part of the capsule, which now receives partial support from two muscles which are stretched under it, viz., the long head of the triceps and the teres major.

Still, this must be regarded as the weakest part of the joint, and consequently dislocation of the head of the humerus, downwards into the axilla through the inferior part of the capsule, is an occurrence of considerable frequency.

Dissection.—Detach the axillary vessels and brachial nerves from the coracoid process to which they have been tied, and throw them downwards. Then proceed to remove the muscles. Divide the conjoined origin of the short head of the biceps and the coraco-brachialis close to the coracoid process, the teres major about its middle, and the long head of the triceps about an inch or two below its origin, and turn them aside. Next deal with the muscles more immediately in relation to the joint, viz., the supraspinatus, the infraspinatus, the teres minor, and the subscapularis. These must be removed with great care and deliberation, because their tendons are closely connected with the subjacent ligamentous capsule. They are not incorporated with the capsule, however, although at first sight they appear to be so, and thus they can be dissected from it. In the case of the subscapularis a protrusion of the synovial membrane, forming a bursa, will be found near its upper border, close to the root of the coracoid process. The capsule of the shoulder-joint may now be cleaned, and its attachments defined.

The *ligaments* in connection with the shoulder-joint are:—

- | | | |
|---------------------------|--|-----------------------|
| 1. The capsular ligament. | | 3. The gleno-humeral. |
| 2. The coraco-humeral. | | 4. The glenoid. |

Capsular Ligament (capsula articularis).—The capsule of the shoulder-joint is a dense and strong ligamentous structure, which envelops the articulation on all sides. It is attached to the scapula around the glenoid cavity, but only above is it directly fixed to the bone. Elsewhere it springs from the fibrous ring or glenoid ligament, which serves to deepen the articular cavity; indeed, in its lower part, it appears to be nearly continuous with the border of the glenoid ligament. Externally it is fixed to the outer part of the anatomical neck of the humerus. The width of the capsule is not uniform throughout. It will be noticed to expand as it passes over the enclosed head of the humerus, and to contract as it reaches its scapular and humeral attachments. The great laxity of the capsule of the shoulder-joint will now be apparent. When the muscles are removed, and air is admitted into the joint, the bony surfaces fall away from each other—the head of the humerus sinking downwards, when the part is held by the scapula, to the extent of an inch.

The capsule of the shoulder-joint is not complete upon all aspects. Its continuity is interrupted by two, and sometimes three, apertures. The largest of these is an opening of some

size, which is placed upon its inner or anterior aspect, near the root of the coracoid process. Through this aperture an extensive protrusion of the synovial membrane takes place in the form of a synovial bursa, which, from its position under the upper part of the subscapularis muscle, receives the name of the *bursa subscapularis*. It is important to note the position and character of this opening, seeing that in some cases the head of the bone may be driven through it in dislocation of




FIG. 31.—Shoulder-joint as seen from the front.

the joint. The *second aperture* is smaller and more distinctly defined. It is placed between the two tuberosities of the humerus, at the upper part of the bicipital groove, and it is through this that the long tendinous head of the biceps gains admission to the interior of the capsule. The synovial membrane also protrudes from this opening, and lines the bicipital groove as low as the insertion of the pectoralis major. It is not often that the *third opening* is seen. It is situated, when present, on the outer or posterior aspect of the capsule, and allows a pocket of synovial membrane to bulge out in the form of a bursa under the infraspinatus muscle.

At certain points the capsule of the shoulder-joint is specially thickened by the addition of fibres, which pass from the scapula to the humerus. Two of these thickened portions receive the names of the *coraco-humeral* and the *gleno-humeral* ligaments. A third is placed on the inferior aspect of the capsule, where it is not supported by muscles, viz., between the long head of the triceps and the subscapularis muscles. It is against this thickened portion of the capsule that the head of the humerus rests when the arm is abducted from the side, and it is sometimes spoken of as the *inferior accessory ligament*, or *inferior gleno-humeral ligament*.

Coraco-humeral Ligament (ligamentum coraco-humerales).—This is placed upon the upper aspect of the joint. It is a broad band of great strength, which is more or less completely incorporated with the capsule. Above, it is fixed to the root and outer border of the coracoid process of the scapula, and it passes from this obliquely downwards and outwards, to gain attachment to the two tuberosities of the humerus. It forms a strong arch over the upper part of the bicipital groove, under which the tendon of the biceps passes.

Gleno-humeral Ligament.—This ligament can only be seen when the joint is opened. The dissector should therefore, at this stage, remove the posterior part of the capsule, and, drawing the bones well apart from each other, look forwards into the cavity. The tendon of the biceps will be observed arching over the head of the humerus, to reach its insertion on the upper aspect of the glenoid cavity. Immediately internal to this, and parallel to it, will be noticed a ridge on the inner aspect of the capsule projecting into the joint. This band is the gleno-humeral ligament (of Flood). It is inserted into a faintly-marked pit on the anatomical neck of the humerus, close to the upper end of the bicipital groove.

As already noted, the thickened band in the inferior part of the capsule is sometimes called the *inferior gleno-humeral ligament*. Another thickening of the front wall of the capsule between this and the gleno-humeral ligament proper has received the name of the *middle gleno-humeral ligament*.

Dissection.—Complete the division of the capsular ligament, and drawing the tendon of the biceps through the intertubercular aperture in the capsule, separate the two bones from each other.

Glenoid Ligament (labrum glenoidale).—The glenoid ligament is the dense fibro-cartilaginous band which sur-

rounds the margin of the glenoid cavity of the scapula, and is attached to its rim. It deepens, and at the same time serves to extend, the articular socket of the scapula. The intimate connection which it presents with the capsule of the joint can now be studied. Two tendons are also closely associated with it, viz. the long head of the triceps below, and the long head of the biceps above.




FIG. 32.—Capsular Ligament cut across and Humerus removed.

Long Head of the Biceps.—The long tendon which receives this name is an important factor in the construction of the shoulder-joint. Entering the capsule through the opening between the two tuberosities of the humerus, it is prolonged over the head of the bone to the top of the glenoid cavity. Its origin should now be examined. It divides into three portions, viz., a large intermediate part, which obtains direct attachment to the scapula, and two smaller lateral parts, which diverge from each other and blend with

the glenoid ligament. The long head of the biceps, by its position within the capsule, and in the deep groove between the tuberosities of the humerus, serves to keep the head of the bone in place, and to steady it in the various movements at the shoulder-joint.

Synovial Membrane.—The synovial membrane lines the interior of the capsular ligament, and is reflected from it upon the anatomical neck of the humerus as far as the articular margin of the head of the bone. The bursal protrusion of the synovial membrane (*bursa subscapularis*) under the tendon of the subscapularis muscle has already been noticed. The tendon of the biceps, as it traverses the joint, is enveloped in a tubular sheath of the membrane, which bulges out through the opening of the capsule in the form of a bursa, which lines the bicipital groove, and receives the name of *bursa intertubercularis*.

Articular Surfaces.—The smooth, glistening articular cartilage, which coats the head of the humerus, is thickest in the centre, and thins as it passes towards the edges. In the case of the glenoid cavity the reverse of this will be noticed. The cartilaginous coating is thinnest in the centre, and becomes thicker as it is traced towards the circumference.

Movements at the Shoulder-joint.—The shoulder is a ball-and-socket joint, and consequently movement in every direction is permitted, viz.—(1) *flexion*, or forward movement; (2) *extension*, or backward movement (checked in its extent by the coraco-humeral ligament); (3) *abduction*, or outward movement (checked by the coraco-acromial arch); (4) *adduction*, or inward movement (limited by the coraco-humeral ligament). In addition to these different forms of angular movement, *rotation* to the extent of a quarter of a circle and *circumduction* are permitted.

The **muscles** chiefly concerned in producing these movements are:—*flexion*—the pectoralis major and the anterior part of the deltoid; *extension*—latissimus dorsi, posterior part of the deltoid, and the teres major; *abduction*—the deltoid and supraspinatus; *adduction*—pectoralis major, coraco-brachialis, teres major, and latissimus dorsi; *rotation inwards*—subscapularis, pectoralis major, latissimus dorsi, teres major; *rotation outwards*—supraspinatus, infraspinatus, and teres minor; *circumduction* is produced by the action of different combinations of these muscles.

FOREARM AND HAND.

Dissection.—The skin has already been removed from the front and back of the forearm. It should now be raised from the dorsum of the hand by making incisions along the radial and ulnar borders. This is

done in order that the superficial structures in this region may be examined in connection with those of the forearm.

Superficial Veins.—On the dorsum of the hand a plexus of superficial veins will be seen. In defining this, care must be taken of the fine cutaneous twigs from the radial nerve and the dorsal branch of the ulnar nerve. From the outer part of the venous plexus the large radial vein takes origin, whilst from its inner part springs the posterior ulnar vein. Both of these vessels have already been traced along the forearm to their terminations. While still upon the dorsum of the hand each communicates with the deep veins in the palm of the hand.

Cutaneous Nerves.—Several cutaneous nerves have already been traced to the integument of the forearm, viz., the anterior and posterior branches of the internal cutaneous nerve to the inner aspect, and the cutaneous part of the musculo-cutaneous and lower external cutaneous branch of the musculo-spiral upon the outer aspect of the limb. Some additional twigs make their appearance by piercing the fascia in the lower third of the forearm.

- | | | |
|---|---|-----------------------|
| 1. The palmar cutaneous branch of the ulnar nerve, | } | on the front aspect. |
| 2. The palmar cutaneous branch of the median nerve, | | |
| 3. The palmar cutaneous branch of the radial nerve, | | |
| 1. The dorsal branch of the ulnar nerve, | } | on the dorsal aspect. |
| 2. The radial nerve, | | |

Palmar Cutaneous Branches.—These are small twigs which supply the skin of the palm. The *twig from the ulnar nerve* takes origin about the middle of the forearm, but it does not at once pierce the deep fascia. It proceeds downwards on the ulnar artery, and becomes superficial immediately above the annular ligament, and close to the outer side of the insertion of the flexor carpi ulnaris tendon into the pisiform bone. It is here, therefore, that it must be sought for (Fig. 20, p. 58).

The *palmar cutaneous branch of the median nerve* appears through the deep fascia in the interval between the tendons of the flexor carpi radialis and the palmaris longus muscles,

immediately above the wrist. It is continued downwards into the palm (Fig. 20, p. 58).

The *palmar branch of the radial nerve* runs close to the outer border of the lower part of the forearm. It does not spring from the trunk of the radial nerve, but from that branch of it which goes to the outer margin of the thumb. It is joined by a twig from the musculo-cutaneous nerve, and proceeds downwards in front of the tendon of the extensor ossis metacarpi pollicis, to end in the skin covering the ball of the thumb (Fig. 20, p. 58).

Dissection.—In tracing the nerves which appear on the back of the limb, it will be necessary to remove the skin from the dorsal aspect of the thumb and fingers. The great flap of skin which is still attached at the roots of the fingers may be detached, and an incision can then be made along the middle of the dorsal aspect of each digit. The skin should be carefully raised from each finger in two flaps and thrown outwards and inwards.

Dorsal Cutaneous Branches.—The *dorsal branch of the ulnar nerve* winds round the inner margin of the wrist to reach the dorsum of the hand. It will be found immediately below the prominence formed by the lower end of the ulna, and it at once divides into three main terminal branches. Of these, the *innermost* runs along the ulnar margin of the dorsum of the hand, and is continued onwards along the inner margin of the little finger. The *second branch* proceeds towards the cleft between the little finger and the ring finger, and divides into two twigs which supply the contiguous sides of these digits. The *third branch* joins a twig from the radial, and the nerve thus formed runs towards the interval between the ring finger and the middle finger, and divides to supply their adjacent margins. Each of these three main branches gives several minute filaments to the integument on the dorsum of the hand (Fig. 21, p. 59).

The *radial nerve* will be found winding round the outer margin of the forearm, about two inches above the extremity of the styloid process of the radius. It at once gives off a long twig which proceeds along the radial margin of the hand and thumb. A little further on the radial nerve breaks up into four terminal branches, which are distributed as follows: the *first* supplies the ulnar side of the thumb; the *second* goes to the radial side of the index finger; the *third* divides to

supply the adjacent sides of the index and middle fingers ; whilst the *fourth* joins with a twig from the dorsal branch of the ulnar (as already described) to supply the contiguous margins of the middle and ring fingers.

It should be noted that, except in the case of the thumb and little finger, the dorsal collateral nerves do not reach the extremities of the digits. The skin on the back of the second and third phalanges of the digits is chiefly supplied by twigs, which proceed backwards from the palmar collateral branches from the median and ulnar nerves. As already stated, it is from the branch of the radial, which goes to the outer side of the thumb, that the *radial palmar cutaneous nerve* arises.

Numerous fine filaments are given to the skin on the dorsum of the hand, and a certain amount of crossing of the adjacent ulnar and radial twigs takes place in this locality ; in other words, twigs from the one nerve invade the territory which is occupied by the other nerve.

Deep Fascia.—The deep fascia which envelops the forearm should now be cleaned by removing the subcutaneous adipose tissue. It is an aponeurosis of great strength and density. More particularly is this the case on the posterior aspect of the limb, and also in the lower third of the forearm, where the fleshy bellies of the subjacent muscles give place to the tendons. In its upper part it receives an accession of fibres from the tendon of the biceps in the form of the bicipital or semilunar fascia. Some fibres are also given to it by the tendon of the triceps. Near the elbow it serves as a surface of origin for the numerous muscles which spring from the condyles of the humerus, and from its deep aspect dense septa pass between the fleshy bellies. These partitions are indicated on the surface by a series of white lines. At the wrist it becomes continuous in front with the *anterior annular ligament*, whilst behind it forms an obliquely placed, thickened band, the *posterior annular ligament*. On the dorsum of the hand the deep fascia is very thin.

FRONT AND INNER BORDER OF THE FOREARM.

In this dissection the following structures will be brought under the notice of the student :—

1. The radial and ulnar arteries and their branches.
2. The median and ulnar nerves and their branches.
3. The posterior interosseous and the radial nerves.
4. The group of pronator and flexor muscles.

Dissection.—With the exception of the palmar cutaneous nerves, the superficial veins and nerves on the front of the forearm may now be turned aside. The deep fascia should also be removed, and on dissecting it inwards round the ulnar border of the forearm it will be found to be firmly attached to the posterior border of the ulna. Near the elbow, as already stated, it gives origin by its deep surface to the group of muscles which spring from the internal condyle of the humerus. Where this is the case, it should be left *in situ*. Attempts to dissect it off will only result in laceration of the surface of the subjacent fleshy bellies. The radial artery should be followed out before the muscles are much disturbed, and at the same time the various muscles which lie upon the anterior surface of the radius, and upon which the vessel rests, should be cleaned.

Radial Artery (*arteria radialis*).—The radial artery is the smaller of the two terminal branches of the brachial artery, but the direction which it takes gives it the appearance of being the continuation of the parent trunk into the forearm. It takes origin in the antecubital fossa opposite the neck of the radius, and it proceeds downwards along the outer side of the front of the limb until it reaches the lower end of the bone. Here it turns round the outer aspect of the wrist and leaves the present dissection. At first it lies between the pronator radii teres and the supinator longus, and is overlapped to some extent on the outer side by the fleshy belly of the latter muscle (Fig. 33). Lower down it is placed between the supinator longus on the outside and the flexor carpi radialis upon the inner side, and this position it maintains as far as the wrist. Where these muscles are fleshy the artery lies at some depth from the surface; but when the tendons make their appearance it assumes a superficial position, and is merely covered by the integument and fasciæ. Throughout its whole length it is closely accompanied by the *venæ comites*, and the radial nerve lies along its outer side in the middle third of the forearm. Above this, the nerve is separated from the vessel by a slight interval; whilst below, the nerve leaves the artery by turning round the outer margin of the forearm under cover of the supinator longus.

Posteriorly the radial artery is supported by the muscles which clothe and find attachment to the front of the radius. At its origin it rests upon the tendon of the biceps; next it lies in front of the supinator brevis, with some adipose tissue

intervening; from this downwards it is in contact with the pronator radii teres, the thin radial head of the flexor sublimis, the flexor longus pollicis, the pronator quadratus, and lastly, the lower end of the radius.

The radial artery is usually selected for the determination of the *pulse*. By placing the tips of the fingers upon the lower part of the forearm, in the interval between the tendons of the supinator longus and flexor carpi radialis, the pulsations of the vessel in the living person can readily be felt.

Branches of the Radial Artery.—In the forearm the radial artery gives off the following branches, viz. :—

1. The radial recurrent.
2. The superficialis volæ.
3. The anterior radial carpal.
4. Muscular.

The *muscular branches* (rami musculares) are very numerous, and proceed from the radial artery at irregular points throughout its whole course in the forearm.

The *radial recurrent artery* (arteria recurrens radialis) is a branch of some size. It takes origin close to the commencement of the radial artery, and in the first instance runs outwards between the supinator longus and the supinator brevis. Here it comes into relation with branches coming from the musculo-spiral nerve, and gives off several twigs for the supply of the muscles arising from the external condyle of the humerus. Somewhat reduced in size, it now turns upwards in the interval between the supinator longus and brachialis anticus, and ends in front of the external condyle of the humerus by anastomosing with the anterior terminal branch of the superior profunda artery.

The *superficialis volæ artery* (ramus volaris superficialis) is a small, variable branch, which arises a short distance above the wrist, and runs downwards to end in the muscles of the ball of the thumb. Sometimes, however, it attains a larger size and a special importance, from its being continued into the palm to complete the superficial palmar arch on the outer side.

The *anterior radial carpal* (ramus carpeus volaris) is a minute twig which springs from the radial at the lower border of the pronator quadratus muscle. It runs inwards under cover of the flexor tendons, and joins the corresponding branch of the ulnar artery to form the *anterior carpal arch*.

Radial and Posterior Interosseous Nerves.—The musculospiral nerve has already been observed to end in front of the elbow, under cover of the supinator longus muscle, in its two terminal branches, the radial and the posterior interosseous. These nerves may now be studied in so far as they lie on the front of the forearm. The *posterior interosseous nerve* (nervus interosseus dorsalis) soon disappears from view by passing backwards on the outer side of the radius through the fibres of the supinator brevis muscle.

The *radial nerve* (nervus cutaneus antibrachii dorsalis) pro-




FIG. 33.—Transverse section through the Upper Third of the Left Forearm.

ceeds downwards under cover of the fleshy belly of the supinator longus. In the middle third of the forearm it lies along the outer side of the radial artery, and then leaves it by winding round the outer margin of the limb, under cover of the tendon of the supinator longus. It has been traced in its further course (p. 87). The radial is a purely cutaneous nerve, and gives off no branches until it gains the dorsal aspect of the lower end of the forearm.

Muscles.—The muscles on the front and inner border of the forearm are arranged in a superficial and a deep group. They comprise the flexors of the wrist and fingers, and also

the pronators. In the *superficial group* we find the pronator radii teres, the flexor carpi radialis, the palmaris longus, the flexor sublimis digitorum, and the flexor carpi ulnaris, in that order from without inwards. The fleshy belly of the flexor sublimis only partially comes to the surface; the chief bulk of it is placed upon a deeper plane than the others. The *deep group* is composed of three muscles, placed in contact with the bones and interosseous membrane of the forearm, viz., the flexor profundus digitorum in relation to the ulna, the flexor longus pollicis in relation to the radius, and the pronator quadratus closely applied to the lower ends of both bones.

Dissection.—The superficial group of muscles should now be dissected. The supinator longus, which lies along the outer side of the forearm, may be cleaned at the same time. In the lower part of the forearm the dissector will observe that the flexor tendons are enveloped by a loose bursal sac as they pass into the palm, under cover of the anterior annular ligament. A good view of this may be obtained by pulling the tendons upwards. If possible, the sac should be retained uninjured, in order that its full extent may be studied when the palm of the hand is opened up. At this stage it is also well to define the anterior annular ligament which bridges across the front of the carpus. The tendon of the palmaris longus passes in front of it, whilst close to the pisiform bone the ulnar artery and nerve are placed upon its anterior surface, and give the dissector the key to its depth. This vessel, with its accompanying nerve, are bound down to the ligament by a slip of fascia, which passes over them from the pisiform bone, and which the student is very apt to mistake for the annular ligament itself. This should not be disturbed in the meantime.

Common Origin of the Superficial Muscles.—The five muscles which constitute the superficial group are very closely associated with each other at the elbow—indeed, they may be said to arise by a common origin from the front of the internal condyle of the humerus. In addition to this they all derive fibres from the investing deep fascia of the limb near the elbow, and the strong fibrous septa which pass into the forearm from the deep surface of this in the intervals between them. The pronator radii teres, the flexor sublimis, and the flexor carpi ulnaris, have likewise additional heads of origin.

Pronator Radii Teres (musculus pronator teres).—This muscle crosses obliquely the upper half of the front of the forearm. It arises by two heads, viz., a humeral and a coronoid. The *humeral head* constitutes the chief bulk of the muscle, and it springs from the upper part of the internal condyle of the humerus, and also slightly by fleshy fibres from the lower part of the internal supracondyloid ridge. The fascia cover-

ing it and the fibrous septum on its inner side also contribute fibres. The *coronoid head* is placed deeply, and it may be recognised from the fact that it intervenes between the median nerve and the ulnar artery. To bring it into view the superficial humeral head must be drawn well inwards. The coronoid head is very variable in size. As a rule, it is a small fleshy slip, but sometimes it is chiefly fibrous. It arises from the inner aspect of the coronoid process of the ulna (Fig. 34, p. 99), and soon joins the deep surface of the humeral head. The muscle thus formed is carried obliquely downwards and outwards, and ends in a tendon which gains insertion into a rough impression upon the middle of the outer surface of the radius (Fig. 34, p. 99). This attachment is placed on the summit of the chief curve of the radius, an arrangement which enables the muscle to exercise its pronating action at a great advantage. Close to its insertion the pronator radii teres is crossed by the radial artery and is covered by the supinator longus muscle. It is supplied by the *median nerve*.

Flexor Carpi Radialis.—The flexor carpi radialis arises from the common tendon, from the fascia of the forearm and the fibrous septa which intervene between it and the adjacent muscles. Its fleshy belly gives place a short distance below the middle of the forearm to a long flattened tendon, which at the wrist traverses the groove on the front of the trapezium in a special compartment of the anterior annular ligament. It is inserted into the palmar aspect of the base of the metacarpal bone of the index, and slightly also into the base of the metacarpal bone of the middle finger. Its relations to the annular ligament, and also its attachment to the metacarpus, will be exposed and studied at a later stage of the dissection. It is supplied by the *median nerve*.

Palmaris Longus.—This is a long slender muscle, which is not always present. It springs from the common origin, the aponeurotic investment of the forearm and the fibrous septum on either side of it. Its tendon pierces the deep fascia immediately above the wrist, and then proceeds downwards in front of the annular ligament to join the strong central portion of the palmar fascia of the hand. Very frequently it gives a slip to the abductor pollicis muscle. It is supplied by the *median nerve*.

Flexor Carpi Ulnaris.—This muscle arises by two heads. One of these is incorporated with the common origin from the humeral condyle; the other springs from the inner aspect of the olecranon process of the ulna, and likewise by an aponeurotic attachment from the posterior border of the same bone in its upper two-thirds. Fibres are also derived from the investing fascia and the intermuscular septum on its outer side. The two heads of origin of the flexor carpi ulnaris bridge across the interval between the internal condyle of the humerus and the olecranon process, and between them the ulnar nerve is prolonged downwards into the forearm. The tendon appears upon the anterior border of the muscle, and is inserted into the pisiform bone. The flexor carpi ulnaris is supplied by the *ulnar nerve*.

Flexor Sublimis Digitorum.—The flexor sublimis receives this name from its being placed upon the superficial aspect of the flexor profundus. For the most part it lies deeper than the other superficial muscles (Fig. 33). It is a powerful muscle which arises from the internal condyle of the humerus by the common tendon, but it also takes origin from the internal lateral ligament of the elbow-joint, from the inner margin of the coronoid process of the ulna, the front of the radius (Fig. 34, p. 99), and the fascial intermuscular septa in relation to it. The radial head of origin is a thin fleshy stratum which is attached to the oblique line of the radius and the anterior border of that bone for a variable distance below the insertion of the pronator radii teres. Four tendons issue from the fleshy mass. These enter the palm by passing under cover of the anterior annular ligament, and go to the four inner digits. Their insertions will be seen later on, but in the meantime note that at the wrist and for a short distance above it they are enveloped by the bursal sac previously mentioned, and also that as they pass behind the annular ligament they lie in pairs—the tendons to the ring and middle fingers being placed in front of those for the index and little fingers. The flexor sublimis digitorum is supplied by the *median nerve*.

Dissection.—The ulnar artery and at the same time the ulnar and median nerves should be followed in their course through the forearm. The artery in the upper part of its course lies very deeply, but its relations can be fully studied and its branches traced by simply slitting up the

intermuscular septum between the flexor sublimis digitorum and the flexor carpi ulnaris.

Ulnar Artery (arteria ulnaris).—This is the larger of the two terminal branches of the brachial trunk, and it takes origin in the antecubital fossa opposite the neck of the radius. At first it inclines obliquely downwards and inwards, and having gained the front of the ulnar side of the forearm, it proceeds vertically downwards to the wrist. Here it enters the palm by passing in front of the anterior annular ligament. In the upper oblique portion of its course the vessel is deeply placed, and is crossed by both heads of the pronator radii teres, the flexor carpi radialis, the palmaris longus, and the flexor sublimis digitorum. In its lower vertical part it is overlapped on the inner side by the flexor carpi ulnaris, but a short distance above the wrist it becomes superficial, and lies in the interval between the tendon of the flexor carpi ulnaris on the inside and the tendons of the flexor sublimis on the outside. On the annular ligament it is placed close to the outer side of the pisiform bone, and is covered by a strong slip of fascia, which passes from that bone to the front of the ligament. Throughout its entire course it is accompanied by two *venæ comites*. It likewise presents relationships with the median and ulnar nerves. The *median nerve*, which lies upon its inner side at its origin, soon crosses it, but as it does so it is separated from the artery by the deep head of the pronator radii teres. The *ulnar nerve* in the upper third of the forearm is separated from the vessel by a wide interval, but in the lower two-thirds of the forearm it closely accompanies the artery, and lies on its inner side.

In the antecubital fossa the ulnar artery rests upon the brachialis anticus; beyond this it is in contact behind with the flexor profundus digitorum; whilst at the wrist the artery lies upon the anterior surface of the anterior annular ligament.

Branches of the Ulnar Artery.—In the forearm the ulnar artery gives off the following branches:—

- | | |
|-------------------------------|----------------------------|
| 1. Anterior ulnar recurrent. | 4. Anterior ulnar carpal. |
| 2. Posterior ulnar recurrent. | 5. Posterior ulnar carpal. |
| 3. Common interosseous. | 6. Muscular twigs. |

The *muscular twigs* are of small size, and come off at variable points for the supply of the neighbouring muscles.

The *anterior ulnar recurrent artery* is the smaller of the two recurrent branches. It runs upwards in front of the internal condyle of the humerus, in the interval between the pronator radii teres and the brachialis anticus muscles, and it anastomoses with the anterior terminal branch of the *anastomotica magna*.

The *posterior ulnar recurrent* passes inwards under cover of the flexor sublimis digitorum, and then turns upwards between the two heads of origin of the flexor carpi ulnaris to gain the interval between the internal condyle of the humerus and the olecranon process on the posterior aspect of the limb. Here it comes into contact with the ulnar nerve, and anastomoses with the posterior terminal branch of the *anastomotica magna* and with the inferior profunda artery.

It is not uncommon to find the two recurrent arteries arising from the ulnar trunk by a short common stem.

The *common interosseous artery* (*arteria interossea communis*) is a short, wide trunk, which takes origin immediately below the recurrent branches, about an inch or so below the commencement of the ulnar artery. It proceeds backwards, and at the upper margin of the interosseous membrane it divides into two terminal branches, viz., the *anterior* and the *posterior interosseous arteries*.

The *ulnar carpal branches* are two small arteries, which partially encircle the wrist. The *anterior ulnar carpal* (*ramus carpeus volaris*) runs outwards, under cover of the tendons of the flexor profundus digitorum, and anastomoses with the anterior radial carpal artery. From the arch thus formed small twigs are given to the front aspect of the carpal bones and joints. The *posterior ulnar carpal artery* (*ramus carpeus dorsalis*) gains the dorsal aspect of the carpus by winding round the ulnar margin of the limb immediately above the pisiform bone, and under cover of the tendon of the flexor carpi ulnaris.

Ulnar Nerve (*nervus ulnaris*).—The ulnar nerve, which was traced in the dissection of the arm as far as the interval between the olecranon and internal condyle of the humerus, enters the forearm between the two heads of the flexor carpi ulnaris. It proceeds downwards upon the flexor profundus digitorum, and under cover of the flexor carpi ulnaris along the front of the ulnar side of the forearm. Close to the

wrist it becomes superficial upon the outer side of the tendon of the flexor carpi ulnaris, and it reaches the palm by passing in front of the anterior annular ligament. In the upper third of the forearm the ulnar nerve is separated from the ulnar artery by an interval, but below this it is closely applied to the inner side of the vessel.

In the forearm the ulnar nerve gives off:—

1. Articular branches to the elbow-joint.
2. Muscular branches, $\left\{ \begin{array}{l} \text{to the flexor carpi ulnaris and the inner} \\ \text{part of the flexor profundus.} \end{array} \right.$
3. Cutaneous branches, $\left\{ \begin{array}{l} \text{palmar cutaneous.} \\ \text{dorsal cutaneous.} \end{array} \right.$

The *articular filaments* come from the ulnar nerve as it lies in the interval between the olecranon and internal condyle of the humerus.

The *muscular branches* are given off high up in the forearm, and supply the flexor carpi ulnaris and the inner part of the flexor profundus digitorum.

The *ulnar palmar cutaneous branch* is a minute twig, which has already been seen piercing the fascia of the forearm immediately above the annular ligament. It arises about the middle of the forearm and proceeds downwards upon the ulnar artery, to the coats of which it gives fine filaments.

The *ulnar dorsal cutaneous branch* is a nerve of some size which springs from the ulnar trunk about two and a half or three inches above the wrist. It winds round the ulnar margin of the forearm under cover of the flexor carpi ulnaris, and reaches the dorsum of the hand immediately below the prominence formed by the lower end of the ulna. From this point onwards it has been traced in the superficial dissection (p. 87).

Median Nerve (nervus medianus).—As its name implies, the median nerve passes down the middle of the forearm; and to obtain an unbroken view of it, it is necessary to reflect the condylar head of the pronator radii teres and the radial head of the flexor sublimis digitorum.

In the upper part of the forearm the median nerve lies in the antecubital fossa upon the inner side of the ulnar artery. It leaves this space by passing between the two heads of the pronator radii teres, and as it does so it crosses the ulnar artery, but is separated from the vessel by the coronoid or

deep head of the muscle. From this point the median nerve is carried downwards between the flexor sublimis and the flexor profundus digitorum. Near the wrist it becomes superficial, and lies in the interval between the tendons of the flexor sublimis on the inside and the flexor carpi radialis on the outer side. Finally it leaves the forearm by passing behind the anterior annular ligament of the wrist. A small artery, the *median branch* of the anterior interosseous, accompanies the median nerve. Sometimes this vessel attains a considerable size.

As the median nerve enters the forearm it gives off numerous branches for the supply of muscles, and near the wrist it supplies the *median palmar cutaneous nerve*, which has already been dissected.

The *muscular branches* supply the pronator radii teres, the flexor carpi radialis, the palmaris longus, and the flexor sublimis digitorum—all the muscles of the superficial group, therefore, with the single exception of the flexor carpi ulnaris.

It likewise supplies a long slender twig—the *anterior interosseous*—which goes to the deep muscles on the front of the forearm.

Deep Structures on the front of the Forearm.—The connections of the deep muscles must now be studied, and at the same time the anterior interosseous artery and nerve must be followed. The flexor profundus is the large muscle which clothes the anterior and inner aspects of the ulna; the flexor longus pollicis is placed upon the anterior surface of the radius; while the pronator quadratus is a quadrate fleshy layer closely applied to both bones immediately above the wrist. The artery and nerve proceed downwards in the interval between the flexor profundus and flexor longus pollicis.

Flexor Profundus Digitorum.—The deep flexor of the fingers springs from the anterior and internal surfaces of the ulna in its upper three-fourths. It likewise derives fibres from the anterior surface of the interosseous membrane and the aponeurosis by which the flexor carpi ulnaris takes origin from the posterior border of the ulna. The fleshy mass gives place to four tendons for the four inner digits, but only one of these—that for the forefinger—becomes separate and distinct in the forearm. They proceed down-

wards behind the anterior annular ligament into the palm. The flexor profundus digitorum is supplied by the *anterior interosseous branch of the median* and by the *ulnar nerve*.

Flexor Longus Pollicis.—

The flexor longus pollicis arises from the anterior surface of the radius over an area which extends from the oblique line above to the upper border of the pronator quadratus below. It also takes origin from the adjacent part of the anterior surface of the interosseous membrane. A rounded tendon issues from the fleshy belly, and proceeds into the palm, under cover of the anterior annular ligament.

In many cases the flexor longus pollicis will be observed to have an additional slender head of origin, from the inner side of the coronoid process of the ulna, or the internal condyle of the humerus. The flexor longus pollicis is supplied by the *anterior interosseous nerve*.

Pronator Quadratus.—

This is a quadrate muscle which takes origin from the anterior surface of the ulna in its lower fourth, and is inserted into the front aspect




FIG. 34.—Anterior aspect of Bones of Forearm with Muscular Attachments mapped out.

of the lower end of the radius. It is supplied by the *anterior interosseous nerve*.

Anterior Interosseous Artery (*arteria interossea volaris*).

—The anterior interosseous artery has been seen to arise from the common interosseous trunk. It runs downwards upon the front of the interosseous membrane, in the interval between the flexor longus pollicis and the flexor profundus digitorum. At the upper border of the pronator quadratus it pierces the interosseous membrane, and gains the posterior aspect of the limb.

It supplies *muscular twigs* to the three deep muscles with which it is in contact. In addition to these it gives off the following branches:—

1. Median.
2. Medullary.
3. Anterior communicating.

The *median artery* is a long delicate vessel, which accompanies the median nerve. The *medullary arteries* are two in number—one for the radius, the other for the ulna. They enter the nutrient foramina of these bones. The *anterior communicating* is a slender artery, which runs downwards, behind the pronator quadratus, to join the anterior carpal arch.

Anterior Interosseous Nerve (*nervus interosseus volaris*).

—This is a branch of the median, and accompanies the artery of the same name. It does not follow it, however, through the interosseous membrane, but is distributed entirely upon the front of the limb. It is the nerve of supply for the flexor longus pollicis, the outer part of the flexor profundus digitorum, and the pronator quadratus, whilst its terminal filament proceeds downwards, behind the last-named muscle, to help in the supply of the carpal joints.

The flexor profundus digitorum is therefore supplied by two nerves, viz., the ulnar and the median. The precise range of supply by each of these nerves is somewhat variable. As a general rule the division of the muscle which belongs to the index finger is supplied by the median and the part belonging to the little finger by the ulnar; whilst the portions belonging to the middle and ring digits receive filaments from both nerves.

WRIST AND PALM.

In this dissection we meet with the following structures :—

1. Palmaris brevis and the palmar cutaneous nerves.
2. Palmar fascia.
3. Superficial palmar arch and its branches.
4. Median and ulnar nerves and their branches.
5. Anterior annular ligament, the flexor tendons, and the flexor sheaths.
6. Lumbrical muscles.
7. Short muscles of the thumb and little finger.
8. Deep palmar arch and its branches.
9. Arteria princeps pollicis and arteria radialis indicis.

Surface Anatomy.—In the centre of the palm the depression, known as the “hollow of the hand,” may be remarked. Along the ulnar border of the palm this is bounded by a rounded elevation, called the *hypothenar eminence*, which is produced by the subjacent short, intrinsic muscles of the little finger. The *thenar eminence*, or ball of the thumb, formed by the short muscles of that digit, is the marked projection which limits the palmar hollow above and on the outer side; whilst the transverse elevation above the roots of the fingers, which corresponds to the metacarpo-phalangeal articulations, constitutes the lower boundary of the central palmar depression. Two pronounced bony projections on the front of the wrist cannot fail to attract attention when the hand is bent backwards. The more prominent of the two is situated at the upper extremity of the thenar eminence, and is formed by the tubercle of the scaphoid bone and the vertical ridge on the front of the trapezium; the other is placed at the upper end of the hypothenar eminence, and is somewhat obscured by the soft parts attached to it. It is caused by the pisiform bone, and when taken firmly between the finger and thumb a slight degree of gliding movement can be communicated to it. Traversing the thick integument of the palm, three strongly marked furrows are apparent. One of these begins at the elevation formed by the scaphoid and trapezium, and curves downwards and outwards around the base of the thenar eminence to the outer margin of the hand. A second crosses the palm transversely. Commencing at the middle of the outer border of the hand, where the first furrow ends, it

runs inwards, but, as a general rule, it fades away upon the hypothenar eminence. The third furrow begins near the cleft between the index and middle fingers, and proceeds




FIG. 35.—Diagram of Nerves and Vessels of Hand in relation to Bones and Skin Markings.

inwards with a gentle curve across the hypothenar eminence to the inner margin of the hand. The transverse cutaneous furrows at the roots of the fingers, and on the palmar aspects of the interphalangeal joints, should also be noticed. The

furrows at the roots of the fingers are placed over the front of the proximal phalanges very nearly one inch below the metacarpo-phalangeal joints. The upper of the two furrows in front of each of the proximal interphalangeal joints is placed immediately over the articulation, whilst in the case of the distal interphalangeal joints the single crease which is usually present corresponds more or less closely to the articulation. On the back of the hand the metacarpal bones can be readily felt, whilst their distal extremities or heads form the prominences known as the "knuckles."

Reflection of Skin.—In the first instance the skin should only be raised from the palm. Two incisions are required—viz., (1) a vertical incision along the middle line of the palm; (2) a transverse cut across the roots of the fingers from the ulnar to the radial margin of the hand. The skin is tightly bound down to the subjacent deep fascia, and it must be raised with care. More especially is it necessary to proceed with caution at the roots of the fingers in order that some transverse fibres constituting a superficial cutaneous ligament may be preserved. In reflecting the inner flap of integument it is well not to lift it quite as far as the ulnar border of the hand, because it is into this portion of skin that the *palmaris brevis* is inserted.

Superficial Structures.—The *superficial fascia* over the central part of the palm is dense and thin. The fat is subdivided into small lobules by fibrous septa which bind the skin to the subjacent palmar fascia. Towards the ulnar and radial margins of the hand the fat becomes softer, and the amount of fibrous tissue in its midst diminishes. In connection with the superficial fascia of the palm we have to study—(1) the *palmaris brevis*; (2) the superficial transverse ligament; and (3) the palmar cutaneous nerves.

The *palmaris brevis* is a small cutaneous muscle embedded in the superficial fascia which covers the upper part of the hypothenar eminence. If it has not already been exposed by the reflection of the skin, carry the knife transversely through the granular fat on the ulnar margin of the palm immediately below the anterior annular ligament. The fleshy bundles of the muscle will come into view. When these have been cleaned, the muscle will be seen to consist of a series of distinct fasciculi, which in its lower part are frequently separated from each other by intervals of varying width. It constitutes a thin fleshy layer, which covers an inch and a half or more of the hypothenar eminence.

Externally it takes origin from the anterior annular ligament and inner border of the central part of the palmar fascia, whilst internally its fasciculi are inserted into the skin over the ulnar margin of the hand.

The *palmar cutaneous nerves* are three in number, and they arise, as already noted, from the ulnar, median, and radial nerves. They should now be traced to their ultimate distribution in the palm of the hand.

The *transverse superficial ligament* is a band of fibres which extends across the palm at the roots of the fingers. It is intimately connected with the skin, and is enclosed within the folds of integument in the clefts between the fingers.

Dissection.—The palmaris brevis should be reflected by detaching its fasciculi from their origin, and turning them inwards. In raising the muscle care must be taken of the ulnar artery and nerve, which lie under cover of it, and a little nerve-filament from the latter should be traced into its substance. The granular fat should next be removed from the palm, and the dense palmar fascia cleaned. Towards the roots of the fingers the digital vessels and nerves, together with the lumbrical muscles, appear in the intervals between the slips into which the palmar fascia divides. These should be defined, and it will be seen that they pass downwards under cover of the superficial transverse ligament. Having noted this point, remove the ligament. The digital arteries and nerves for the inner side of the little finger, and the outer side of the index, appear beyond the area of the central part of the deep fascia, higher up than the others, and are consequently liable to injury, unless it be remembered that they occupy this position.

Palmar Fascia.—The deep fascia of the palm is composed of three portions—a central and two lateral. The *lateral parts* are thin and weak, and are spread over the muscles which constitute the thenar and hypothenar eminences on the outer and inner margins of the palm. The *central portion* of the palmar fascia, on the other hand, is exceedingly strong and dense, and is spread out over the middle of the palm. It counteracts the effect of pressure in this region, and effectually protects the vessels, nerves, and tendons over which it is stretched. Its strength differs considerably in different hands, and it is seen to best advantage in the horny hand of a labourer, or of a mechanic who has been in the habit of handling heavy implements. In shape it is triangular. Above, it is narrow and pointed, and at the wrist it is attached to the anterior annular ligament, and receives the insertion of the flattened tendon of the palmaris longus. As it

approaches the heads of the metacarpal bones it expands, and finally divides into four slips, which separate slightly from each other, and pass to the roots of the four inner digits. It gives no slip to the thumb. For the most part it is composed of longitudinal fibres, but, where it divides, a series of strong and very evident transverse fibres pass across it in relation to its deep surface, and bind together its diverging slips.

In the three intervals between the digital slips of the palmar fascia, the digital arteries and nerves, together with the corresponding lumbrical muscles, make their appearance.

The connections of the four digital slips of the palmar fascia must be closely examined. Each lies in front of the two flexor tendons proceeding to the finger with which it is connected, and each will be observed to divide into two portions, so as to form an arch under which these tendons pass. This arch is connected with the flexor sheaths, which bind the tendons to the front of the finger, and the two portions which form it are carried backwards, to obtain attachment to the transverse metacarpal ligament, which stretches transversely across the front of the heads of the metacarpal bones. These relations can only be satisfactorily made out by dividing the arch, and slitting the slip of fascia in an upward direction.

Fascial Compartments of the Palm.—Two weak septa proceed into the palm from the margins of the strong central portion of the palmar fascia. They join a layer of fascia, which is spread out over the interosseous muscles and the deep palmar arch, and they thus subdivide the palm into three fascial compartments, viz., a *central*, containing the flexor tendons, the lumbrical muscles, the superficial palmar arch, and the terminal branches of the median nerve; an *inner*, enclosing the short muscles of the little finger; and an *outer*, enclosing the short muscles of the thumb.

Dissection.—Raise the central part of the palmar fascia. Divide its narrow upper part, throw it downwards, and finally remove it completely. The *superficial palmar arch* is the most superficial of the structures now exposed. Trace the ulnar artery into it, and follow the digital branches which it gives off. The slip of fascia which binds the ulnar artery to the front of the annular ligament may now be removed. The median and ulnar nerves must also be dissected. The muscular branches, which the median gives to the muscles of the thenar eminence, are especially liable to injury. They come off in a short, stout stem, almost in a line with the lower margin of the anterior annular ligament, and at once turn outwards

to reach the short muscles of the thumb, to some of which they are distributed. The nerve twigs to the two outer lumbricals must also be looked for. They spring from the digital branches of the median, which go to the radial side of the index and to the cleft between the index and middle fingers.

In order that the digital vessels and nerves may be traced to their distribution, the skin must be reflected from the fingers. This can be done by making an incision along the middle of each digit, and turning the integument outwards and inwards. As the skin is raised from the lateral aspects of the different digits the *cutaneous ligaments of the phalanges* (Cleland) will come into view. These are fibrous bands, which spring from the edges of the phalanges behind the digital vessels and nerves. They are inserted into the skin so as to form a strong fibrous septum on each side of each finger. They retain the integument in proper position during the different movements of the digits.

Superficial Palmar Arch (*arcus volaris superficialis*).—The ulnar artery, when traced into the palm, is found to form the superficial palmar arch—an arterial arcade, which lies immediately subjacent to the deep fascia.

The *ulnar artery* enters the palm by passing downwards in front of the annular ligament, close to the outer side of the pisiform bone. A short distance below this it curves outwards, across the palm, and, near the middle of the thenar eminence, it is joined by the *superficialis volæ* branch of the radial, or, more frequently, by a twig from the *arteria radialis indicis* or *arteria princeps pollicis*. The convexity of the arch is directed downwards towards the fingers, and its lowest point corresponds with a line drawn across the palm from the lower border of the outstretched thumb.

Throughout its entire extent the superficial palmar arch lies very near the surface. Its inner part is covered by the *palmaris brevis* muscle; beyond this it is placed immediately behind the central part of the palmar fascia. As it is followed from the inner to the outer side of the hand it will be seen to rest upon—(a) the anterior annular ligament; (b) the short muscles of the little finger; (c) the flexor tendons, and the digital branches of the median nerve.

Branches of the Superficial Palmar Arch.—Small branches proceed from the superficial palmar arch for the supply of the integument and adjoining short muscles of the palm. As the ulnar artery leaves the surface of the anterior annular ligament it gives off its *profunda branch*; whilst from the convexity of the arch proceed four *digital branches*.

The *profunda artery* is a small vessel, which at once

disappears from view by passing backwards in the interval between the abductor minimi digiti and the flexor brevis minimi digiti. It will be traced to its termination in the deep dissection of the palm.

The *four digital arteries* form the palmar collateral branches for both sides of each of the three inner fingers and for the ulnar side of the index finger. The *first digital artery* runs downwards upon the short muscles of the little finger, to which it gives twigs, and then it is carried along the ulnar side of the little finger. The *second digital artery* proceeds towards the interval between the roots of the little and ring fingers, and divides into two branches (*collateral arteries*), which run along the contiguous sides of these digits. The *third digital artery* supplies in like manner the adjacent sides of the ring and middle fingers; whilst the *fourth digital artery* deals similarly with the contiguous margins of the middle and index fingers.

There are certain points in connection with these digital arteries, during their course in the palm and along the sides of the fingers, which must be noted. In the *palm* the undivided trunks lie in the intervals between the flexor tendons and in front of the digital nerves and the lumbrical muscles. Along the sides of the *fingers* they show a different relation to the nerves: the nerves are now in front, and the arteries behind. Upon the terminal phalanx the two collateral branches join to form an arch, from which proceed great numbers of fine twigs, to supply the pulp of the finger, and the bed upon which the nail rests.

Each digital artery at the point at which it divides is joined by the corresponding interosseous branch of the deep palmar arch. The collateral branches give a liberal supply of twigs to the integument, sheaths of the tendons, and joints of the fingers.

Median Nerve.—The median nerve enters the palm by passing *behind* the anterior annular ligament with the flexor tendons. In this part of its course it is enveloped by the synovial sheath which is wrapped around the tendons. Further, before it emerges it assumes a flattened form, and divides into two portions. Of these, the *external division* is slightly the smaller of the two, and gives off—(1) a stout short branch to some of the intrinsic muscles of the thumb;

(2) three digital branches which go to the two sides of the thumb and the radial side of the index finger.

The *muscular branch* takes origin at the lower border of the annular ligament, and at once turns outwards to supply the abductor pollicis, the superficial head of the flexor brevis pollicis, and the opponens pollicis.

The *digital nerves* which run along the ulnar side of the thumb, and the radial side of the index, give several branches to the fold of integument which stretches between the roots of these digits; whilst the long digital branch to the radial border of the index gives a minute twig to the first or outermost lumbrical muscle.

The larger *internal division* of the median nerve divides into two branches. Of these one runs towards the cleft between the index and middle fingers, and splits into the collateral branches for the adjacent sides of these digits. From this nerve a twig to the second lumbrical muscle is given off. The second branch of the internal division of the median proceeds towards the cleft between the middle and ring fingers, and divides into the collateral branches for their contiguous margins. In some instances the latter nerve supplies a twig to the third lumbrical muscle.

In the palm the digital branches of the median proceed downwards behind the superficial palmar arch, but as they approach the fingers they come to lie in front of the digital arteries which, in many cases, may be observed to pass through, or perforate, the nerves. As the digital nerves lie upon the sides of the fingers, numerous branches are given to the integument; and if the dissector exercises sufficient patience and care in the dissection, he will notice attached to the nerve twigs numerous minute, oval, seed-like bodies. These are the *Pacinian bodies*. At the extremity of the fingers the digital nerves divide into two terminal branches. Of these, one ramifies in the pulp, whilst the other inclines backwards to reach the bed upon which the nail rests. Several twigs pass to the back of the fingers, and these are chiefly responsible for the supply of the integument on the posterior aspect of the second and third phalanges.

Ulnar Nerve.—The ulnar nerve enters the palm by passing *in front of* the anterior annular ligament. It lies secure from the effects of pressure under the shelter of the

pisiform bone, and upon the inner side of the ulnar artery. At this level it divides into two terminal branches—a superficial and a deep.

The *deep branch* of the ulnar is continued downwards upon the annular ligament, and associates itself with the profunda branch of the ulnar artery. It leaves the present dissection by passing backwards between the abductor and the flexor brevis muscles of the little finger.

The *superficial branch* of the ulnar nerve runs downwards under cover of the palmaris brevis, to which it gives a branch of supply, and then divides into two digital branches. One of these proceeds obliquely over the short muscles of the little finger to gain the inner side of that digit; the other descends to the cleft between the little and ring fingers, and divides into the collateral branches for the adjacent sides of these digits. A branch of communication passes from the second digital branch of the ulnar nerve to the adjoining digital branch of the median nerve.

The digital branches of the ulnar nerve are distributed on the sides of the fingers in precisely the same manner as those derived from the median.

Anterior Annular Ligament.—This is a thick, dense, fibrous band, which stretches across the front of the carpal arch, so as to convert it into an osteo-fibrous tunnel for the passage of the flexor tendons into the palm. On each side it is attached to the two piers of the carpal arch, viz., on the *outer side* to the tubercle of the scaphoid and the ridge of the trapezium, and on the *inner side* to the pisiform bone and the hook of the unciform. Its upper margin is in a measure continuous with the deep fascia of the forearm, of which it may be considered to be a thickened part; whilst below, it is connected with the palmar fascia.

Upon the anterior surface of the annular ligament the expanded tendon of the palmaris longus is prolonged downwards to the central part of the palmar fascia, whilst on each side several of the short muscles of the thumb and little finger take origin from it. Close to its inner attachment the ulnar artery and nerve find their way into the palm by passing in front of the ligament, and a strong slip of fascia which bridges over these may be looked upon as an accessory attachment of the ligament, seeing that it springs from the

time line the walls of the canal, and thus greatly facilitate the free play of the tendons behind the anterior annular ligament. As we have stated, these sheaths are two in number. One is wrapped around the tendon of the flexor longus pollicis; the other invests the tendons of the flexor profundus and flexor sublimis. Both are prolonged upwards into the forearm for an inch or more, and both are carried downwards into the palm in the form of diverticula upon the diverging tendons. The diverticula in relation to the tendons which go to the index, middle, and ring fingers, end near the middle of the palm. Those upon the tendons of the thumb and little finger, however, are prolonged downwards into these digits, and line the flexor sheaths which confine the tendons upon the palmar aspects of the phalanges.

It is not likely that these synovial sheaths have been preserved intact throughout the previous dissection of forearm and palm; but should they turn out to be uninjured, a very striking demonstration may be obtained by inflating them with air by means of the blow-pipe. The apertures through which the air is introduced should be made at the upper margin of the annular ligament.

It is said that the synovial sac which invests the tendons of the flexor sublimis and flexor profundus is divided by a vertical partition into two compartments, and that the outer of these communicates, by means of a small aperture near the upper border of the annular ligament, with the synovial sheath of the tendon of the flexor longus pollicis.

Flexor Tendons.—Open the carpal tunnel by making a vertical incision through the anterior annular ligament at its middle. The arrangement of the flexor tendons can now be studied, and the synovial sheath dissected from the surface of each. The tendon of the *flexor longus pollicis* occupies the outer part of the canal, and gaining the palm turns outwards to reach the phalanges of the thumb. The four tendons of the *flexor sublimis* are arranged in pairs behind the annular ligament; those for the little and index fingers lying behind those for the ring and middle fingers. Of the tendons of the *flexor profundus*, only that for the index finger is distinct and separate; the other three as a rule remain united until they emerge from under cover of the annular ligament.

In the central compartment of the palm the flexor tendons diverge from each other, and two, viz., one from the flexor

sublimis, and one from the flexor profundus, go to each of the four fingers. From the tendons of the flexor profundus, the lumbrical muscles take origin, and these, with the digital nerves and arteries, will be seen occupying the intervals between the tendons as they approach the roots of the fingers.

In the *fingers* the two flexor tendons run downwards upon the palmar aspect of the phalanges, and are held in position by the flexor sheaths. These, therefore, must be studied before the insertions of the tendons can be examined.



FIG. 37.—Diagram to illustrate the arrangement of the Synovial Sheaths around the Flexor Tendons.

Flexor Sheaths. — The flexor sheaths of the fingers lie immediately subjacent to the skin and superficial fascia, and the digital vessels and nerves run downwards upon each side of them. Each of these sheaths, with the phalanges of the fingers, forms an osteo-fibrous canal or tube. The posterior wall of the tube is formed by the flat palmar surfaces of the phalanges; the front wall is composed of the fibrous sheath which bridges over the tendons, and is attached on each side to the sharp lateral margins of the phalanges. The strength of this sheath differs very much at different points. Opposite the centre of each of the two proximal

phalanges it is composed of transverse fibres, and it acquires a great thickness and density, forming a distinct arch, called the *vaginal ligament*. Such an arrangement over the joints, however, would seriously interfere with the free flexion of the fingers, and therefore in front of the articulations between the phalanges the sheath is exceedingly thin, and is strengthened by oblique interlacing fibres.

The flexor tubes in front of one or more of the fingers may now be opened. They will be seen to be lined by a

synovial sheath, which is reflected over the enclosed tendons so as to give each a separate investment. The synovial sheath of the little finger has been seen to be a direct prolongation from the carpal synovial sheath; the other three are distinct from this, and are carried upwards into the palm. They envelop the tendons of the ring, index, and middle fingers, as far as a line drawn across the palm immediately above the heads of the metacarpal bones.

If the flexor tendons be raised from the phalanges certain synovial folds will be noticed connecting them to the bones. These are termed the *vincula accessoria*. Of these we distinguish two kinds, viz., *ligamenta brevia* and *longa*. In the accompanying illustration (Fig. 38) the connections of these may be seen. The *ligamenta brevia* are triangular folds, which connect the tendons near their insertions to the




FIG. 38.—Flexor Tendons of the Finger with Vincula Accessoria.

anterior face of the phalanx. The *ligamenta longa* are not invariably present. They are placed higher up, and are narrow, weak folds which pass between the tendons and the bones.

Insertions of the Flexor Tendons.—The insertions of the two tendons can now be studied. In front of the first phalanx the tendon of the flexor sublimis becomes flattened and folded round the subjacent cylindrical tendon of the flexor profundus. It then splits into two parts, which pass behind the tendon of the flexor profundus, and allow the latter to proceed onwards between them. Behind the deep tendon, the two portions of the tendon of the flexor sublimis become united by their margins, and then they diverge, to be inserted into the borders of the shaft of the second phalanx.¹

¹ Where the margins of the two slips of the tendon of the flexor sublimis are united behind the tendon of the flexor profundus, a decussation of fibres takes place between the two slips.

By this arrangement the flattened tendon of the flexor sublimis forms a ring, or short tubular passage, through which the tendon of the flexor profundus proceeds onwards to the base of the ungual phalanx, into which it is inserted. In each of the four fingers the same arrangement is found; the tendon of the flexor sublimis is inserted by two slips into the sides of the second phalanx, whilst the tendon of the flexor profundus is inserted into the anterior aspect of the base of the terminal phalanx.

Tendon of the Flexor Longus Pollicis.—This tendon proceeds downwards in the interval between two of the muscles of the thumb (viz., the superficial head of the flexor brevis pollicis, and the adductor obliquus pollicis), and also in the interval between the two sesamoid bones which play upon the head of the metacarpal bone. Reaching the proximal phalanx, it enters a fibrous sheath constructed upon a similar plan to those of the fingers. When this is opened, the tendon will be observed to be inserted into the front of the base of the terminal phalanx of the thumb. The synovial sheath which surrounds the tendon during its passage through the carpal tunnel is continuous with the sheath which invests the tendon in front of the phalanges.

Dissection.—Throw forwards the superficial palmar arch. Divide it on the inside below the origin of the profunda artery, and on the outside at the point where it is joined by the superficial volar artery. The median nerve may also be severed and its branches turned aside, but care should be taken to preserve the two branches which it gives to the lumbrical muscles, and also the stout branch which enters the muscles of the thenar eminence. Lastly, cut through the fleshy belly of the flexor sublimis in the forearm, and, raising its tendons from the carpal hollow, throw them as far down as possible. The tendons of the flexor profundus and the attached lumbrical muscles are now fully displayed.

Lumbrical Muscles.—These are four slender fleshy bellies which arise from the tendons of the flexor profundus digitorum as they traverse the palm. The *first lumbrical* arises from the outer side of the tendon for the index finger; the *second lumbrical* springs from the radial border of the tendon for the middle finger; whilst the *third* and *fourth lumbricals* take origin from the adjacent sides of the tendons between which they lie (viz., the tendons for the medius, annularis, and minimus). The little muscles pass downwards

and end in delicate tendons on the radial sides of the fingers. Each is inserted into the outer margin of the dorsal expansion of the extensor tendon, which lies upon the posterior aspect of the proximal phalanx.

Dissection.—The flexor profundus may be divided in the forearm and thrown downwards. Great care must be taken in raising the tendons and lumbrical muscles from the palm, because slender twigs from the deep branch of the ulnar nerve enter the two inner lumbrical muscles on their deep aspect. These can easily be secured if ordinary caution be observed. The deep palmar arch and the deep branch of the ulnar nerve are now exposed, and a favourable opportunity is given for studying the short muscles of the thumb and little finger.

Short Muscles of the Thumb.—The *abductor pollicis* forms the most prominent and external part of the ball of the thumb. The *superficial head* of the *flexor brevis pollicis* lies immediately to the inner side of the abductor; and by separating the one from the other, the *opponens pollicis* will be exposed. These three muscles lie to the outer side of the tendon of the flexor longus pollicis. To the inner side of this tendon, and placed deeply in the palm, is a fan-shaped muscular sheet imperfectly separated into an upper and lower part by the radial artery as it enters the palm. The upper muscle is the *adductor obliquus pollicis*, the lower muscle is the *adductor transversus pollicis*.

In dissecting these muscles the muscular branch of the median nerve must be traced to those which lie upon the outer side of the long flexor tendon of the thumb, and the deep branch of the ulnar must be followed, and its branches to the two adductors of the thumb secured.

The *abductor pollicis* arises from the front of the annular ligament and the trapezium. It is inserted into the radial side of the base of the first phalanx of the thumb, and slightly into the extensor tendon on the dorsum of the first phalanx. Its nerve of supply comes from the *median*.

The *superficial head* of the *flexor brevis pollicis*¹ takes origin from the annular ligament, and is inserted into the outer side of the base of the proximal phalanx of the thumb. It is supplied by the *median nerve*.

The *opponens pollicis* springs from the annular ligament and the ridge on the front of the trapezium. Its fibres

¹ The term *superficial head*, applied to this muscle, suggests the presence of a *deep head*. Such a head is present. It is the *interosseus primus volaris* of Henle (v. p. 135).

spread out, and are inserted into the entire length of the radial border of the metacarpal bone of the thumb. Its nerve of supply is derived from the *median*.

The *adductor obliquus pollicis* arises from the bases of the second and third metacarpal bones, and likewise from the os magnum, the trapezoid, the trapezium, and the sheath of the flexor carpi radialis. From this origin the muscle proceeds downwards along the inner side of the tendon of the flexor longus pollicis, and is inserted into the ulnar side of the base




FIG. 39.—Palmar aspect of Bones of Carpus and Metacarpus with Muscular Attachments mapped out.

of the proximal phalanx of the thumb. A strong slip will generally be seen to deviate outwards from the outer border of the muscle. This passes under cover of the long flexor tendon, and joins the superficial head of the flexor brevis pollicis. The adductor obliquus is supplied by the *deep* branch of the *ulnar nerve*.

The *adductor transversus pollicis* has a wide origin from the anterior face of the lower two-thirds of the shaft of the middle metacarpal bone, and from the fascia covering the interosseous muscles. Its fibres converge as they pass out-

wards, and are inserted along with the adductor obliquus into the ulnar side of the base of the first phalanx of the thumb. It is supplied by the *deep branch* of the *ulnar nerve*.

Two sesamoid bones are developed in connection with the tendons of the short muscles of the thumb as they are inserted on either side of the base of the proximal phalanx.

Short Muscles of the Little Finger.—The *abductor minimi digiti* lies on the inner and superficial aspect of the hypothenar eminence, and the *flexor brevis minimi digiti* upon its outer side. On separating these from each other, the *opponens minimi digiti* is seen on a deeper plane, and in the interval between them.

The *abductor minimi digiti* (abductor quinti digiti) arises from the pisiform bone, and is inserted into the ulnar side of the base of the proximal phalanx of the little finger. It is supplied by the *deep branch* of the *ulnar nerve*.

The *flexor brevis minimi digiti* (flexor digiti quinti brevis) is composed of a single fleshy belly which springs from the hook of the unciform bone and the annular ligament, and is inserted into the ulnar side of the proximal phalanx of the little finger, in common with the abductor. This muscle is sometimes much reduced in size, and frequently more or less completely incorporated with the opponens. Its nerve supply comes from the *deep branch* of the *ulnar nerve*.

The *opponens minimi digiti* (opponens digiti quinti) arises from the annular ligament, and the hook of the unciform bone and its fibres spread out to obtain insertion into the entire length of the ulnar margin of the metacarpal bone of the little finger. The *deep branch* of the *ulnar* gives it its nerve of supply.

Deep Branch of the Ulnar Nerve.—This nerve springs from the parent trunk on the anterior aspect of the annular ligament, and gives off a branch which supplies the three short muscles of the little finger. Accompanied by the deep branch of the ulnar artery, it then sinks into the interval between the abductor and flexor brevis minimi digiti, and turns outwards across the palm under cover of the flexor tendons. Near the radial border of the palm the deep branch of the ulnar nerve breaks up into terminal twigs which supply the adductor transversus pollicis, the adductor obliquus pollicis, and the first dorsal interosseous muscle.

In its course across the palm it lies along the concavity or upper border of the deep palmar arch, and sends three fine branches downwards in front of the three interosseous spaces. These supply the interosseous muscles in those spaces, while the two inner also give branches to the deep surfaces of the two inner lumbrical muscles. The third lumbrical has frequently a double nerve supply, as it is not uncommon to find a second twig from the median entering its superficial aspect.

The deep branch of the ulnar may, therefore, be said to supply all the muscles of the palm which lie to the inner side of the tendon of the flexor longus pollicis, whilst the median supplies the three muscles which lie to the outer side of that tendon. There are two exceptions to this generalisation, viz., the two outer lumbrical muscles, which lie upon the inner side of the tendon, and are yet supplied by the median nerve.

Deep Palmar Arch (*arcus volaris profundus*).—The artery which takes the chief part in the formation of this arch is the radial. This vessel enters the palm, by coming forwards through the upper part of the first interosseous space between the two heads of the first dorsal interosseous muscle. In the present state of the dissection it makes its appearance between the contiguous margins of the adductor obliquus and adductor transversus pollicis. It runs inwards upon the interossei muscles and the metacarpal bones immediately below their bases. As it approaches the fifth metacarpal bone it is joined by the deep branch of the ulnar artery, and in this manner the deep palmar arch is completed.

The deep palmar arch does not show so strong a curve as the superficial arch, and it is placed at a higher level in the palm. It is closely accompanied by the deep branch of the ulnar nerve; and is separated from the superficial palmar arch by the group of flexor tendons, the lumbrical muscles, the branches of the median nerve which occupy the middle compartment of the palm, and also at its inner part by the flexor brevis minimi digiti, under which the deep branch of the ulnar artery passes to join the radial.

The *branches* which spring from the deep palmar arch are: (1) the *recurrent*—a few small twigs which run upwards in front of the carpus to anastomose with branches of the anterior

carpal arch; (2) *superior perforating*, which pass backwards in the upper parts of the interosseous spaces to anastomose with the dorsal interosseous arteries; and (3) the *palmar interosseous*—three in number—which pass forwards in front of the interosseous spaces and unite, near the roots of the fingers, with the corresponding digital arteries from the superficial palmar arch. Sometimes one or more of these branches enlarge and take the place of the corresponding digital arteries.

Dissection.—To bring the *arteria radialis indicis* and the *arteria princeps pollicis* into view, the adductor transversus, and the adductor obliquus pollicis, must be detached from their origins and turned outwards. The radial artery is now seen coming forwards between the two heads of the first dorsal interosseous muscle.

Arteria Radialis Indicis, and Arteria Princeps Pollicis.—These arteries spring from the radial as it proceeds forwards between the first and second metacarpal bones.

The *arteria radialis indicis* runs downwards between the adductor transversus pollicis and the first dorsal interosseous muscle to the radial border of the index, along which it proceeds as its outer collateral branch.

The *arteria princeps pollicis* takes a course downwards and outwards under cover of the adductor obliquus pollicis, and gains the front of the metacarpal bone of the thumb. Here it lies behind the tendon of the flexor longus pollicis, and divides into the two collateral branches of the thumb. These branches make their appearance in the interval between the adductor obliquus and the superficial head of the flexor brevis pollicis, and are carried forward on either side of the tendon of the long flexor.

Surgical Anatomy of the Palm and Fingers.—When an abscess forms in the middle compartment of the palm early surgical interference is urgently called for. The dense palmar fascia effectually prevents the passage of the pus forwards, whilst an easy route upwards into the forearm is offered to it by the open carpal tunnel, through which the flexor tendons enter the palm. It is absolutely necessary, therefore, that before this can occur the surgeon should make an opening in the palm by means of which the pus can escape.

In making such an incision it is important to bear in mind the position of the various vessels which occupy the middle compartment of the palm. As we have stated, the level to which the superficial palmar arch descends can be indicated by drawing a line transversely across the palm from the lower margin of the outstretched thumb. The deep palmar arch lies half an inch higher. The digital arteries, which spring from the convexity of

the superficial arch, run in a line with the clefts between the fingers. An incision, therefore, which is made below the superficial arch, and in a direction corresponding to the central line of one of the fingers, may be considered free from danger in so far as the vessels are concerned.

The loose synovial sheath which envelops the flexor tendons as they pass behind the anterior annular ligament has been noticed to extend upwards into the lower part of the forearm, and downwards into the palm. When this is attacked by inflammatory action it is apt to become distended with fluid (thecal ganglion), and the anatomical arrangement of parts at once offers an explanation of the appearance which is presented. There is a bulging in the palm, and a bulging in the lower part of the forearm, but no swelling at all at the wrist. Here the dense annular ligament resists the expansion of the synovial sheath, and an hour-glass constriction is evident at this level.

The fingers are subject to an inflammatory process, termed *whitlow*, and, in connection with this, it is essential to remember that the flexor fibrous sheath ends on the base of the distal phalanx in each digit. When the whitlow occurs below this, in the pulp of the finger, the vitality of the distal part of the ungual phalanx is endangered, but the flexor tendons may be regarded as being tolerably safe. When the inflammation occurs above this, and involves the flexor sheath, as it generally does, sloughing of the tendons is to be apprehended, unless an immediate opening is made. And no slight superficial incision will suffice. The knife must be carried backwards in the centre of the finger, so as to freely lay open the sheath containing the tendons. Early interference in cases of whitlow of the thumb and little finger is even more urgently required than in the case of the other three digits, because, as we have seen, the digital synovial sheaths of the former are, as a rule, offshoots from the great carpal bursa, and offer a ready means for the upward extension of the inflammatory action.

Every amputation of the fingers above the insertion of the tendons of the flexor profundus involves the opening of the flexor sheaths, and this no doubt explains the occasional occurrence of palmar trouble after operations of this kind. The open tubes offer a ready passage, by means of which septic material may travel upwards into the palm, and, in the case of the thumb and little finger, into the carpal tunnel and lower part of the forearm.

BACK AND OUTER BORDER OF THE FOREARM.

The cutaneous nerves and vessels in this region have already been studied. The parts which still require to be examined are :—

1. The deep fascia.
2. The supinator and extensor muscles.
3. The posterior interosseous artery.
4. The perforating or terminal branch of the anterior interosseous artery.
5. The posterior interosseous nerve.

Deep Fascia.—The deep fascia on the posterior aspect of

the forearm is stronger than that which clothes it in front. At the elbow it is firmly attached to the condyles of the humerus and the olecranon process, and it receives a reinforcement of fibres from the tendon of the triceps muscle. Here also it affords origin to the extensor muscles, and sends strong septa between them. At the wrist a thickened band—the *posterior annular ligament*—is developed in connection with it. This can readily be distinguished from the thinner portions of the fascia with which it is continuous above and below, and it will be observed to stretch obliquely from the styloid process of the radius inwards and downwards across the wrist to the inner side of the carpus.

Dissection.—The deep fascia should now be removed, but that portion of it near the elbow, which gives origin to the subjacent muscles, should be left in place. The posterior annular ligament should also be artificially separated from it, and retained *in situ*.

Superficial Muscles.—The muscles in this region consist of a superficial and a deep group. The *superficial muscles*, as we proceed from the outer to the inner border of the forearm, are:—(1) the supinator longus; (2) the extensor carpi radialis longior; (3) the extensor carpi radialis brevior; (4) the extensor communis digitorum; (5) the extensor minimi digiti; (6) the extensor carpi ulnaris; and (7) the anconeus. This group therefore comprises one supinator, three extensors of the wrist, two extensors of the fingers, and a feeble extensor of the forearm at the elbow-joint, viz., the anconeus. In the lower part of the forearm the extensor communis digitorum is separated from the extensor carpi radialis brevior by a narrow interval, and in this appear two muscles belonging to the deep group. These turn round the outer border of the forearm upon the surface of the radial extensors of the wrist, and end in tendons which go to the thumb. The upper muscle is the extensor ossis metacarpi pollicis, and the lower muscle the extensor primi internodii pollicis. They are placed in close contact, and so intimately are their tendons connected that in many cases they appear at first sight to be blended together by their margins.

Four of the superficial muscles arise by a common origin from the front of the external condyle of the humerus, and at the same time derive fibres from the investing fascia and the septa it sends in between them. These are the

extensor carpi radialis brevis, the extensor communis digitorum, the extensor minimi digiti, and the extensor carpi ulnaris. The superficial muscles should be cleaned, and isolated as far as possible from each other.

Supinator Longus (brachio-radialis).— This muscle lies more on the front than on the back of the forearm. It takes origin in the upper arm from the upper two-thirds of the external supracondyloid ridge of the humerus and from the external intermuscular septum. Near the middle of the




FIG. 40.—Dorsal aspect of Bones of Carpus and Metacarpus with Muscular Attachments mapped out.

forearm a flat tendon emerges from its fleshy belly, and this proceeds downwards to gain insertion into the outer aspect of the expanded lower extremity of the radius close to the base of the styloid process. The nerve of supply to this muscle comes from the *musculo-spiral nerve*.

Extensor Carpi Radialis Longior.— The long radial extensor of the carpus is placed behind the supinator longus. It arises from the lower third of the external supracondyloid ridge of the humerus, and from the external intermuscular septum. From the fleshy portion of the muscle a long

tendon proceeds which passes under cover of the posterior annular ligament, and is inserted into the radial side of the base of the metacarpal bone of the index finger. This muscle is supplied by the *musculo-spiral nerve*.

Extensor Carpi Radialis Brevior.—The extensor carpi radialis brevior is closely associated with the preceding muscle. It arises by the common extensor tendon from the external condyle of the humerus; it also derives fibres from the external lateral ligament of the elbow-joint, from the investing deep fascia, and the fibrous septa in connection with it. The tendon of the muscle accompanies that of the long radial extensor under cover of the posterior annular ligament, and is inserted into the radial side of the base of the third metacarpal bone immediately beyond the root of its styloid process. This muscle is supplied by the *posterior interosseous nerve*.

Extensor Communis Digitorum.—The extensor communis digitorum takes origin by the common tendon from the outer condyle of the humerus. The deep fascia and the intermuscular septa in relation to it also contribute fibres. Its fleshy belly in the lower part of the forearm sends out four tendons, which pass under cover of the posterior annular ligament. On the dorsum of the hand they diverge and proceed onwards to the four fingers. Their arrangement and attachments on the dorsum of the hand and fingers will be afterwards considered. This muscle is supplied by the *posterior interosseous nerve*.

Extensor Minimi Digiti.—The extensor minimi digiti is a slender fleshy belly which at first sight appears a part of the preceding muscle, but its tendon passes through a special compartment in the posterior annular ligament. It arises in common with the extensor communis digitorum. This muscle is supplied by the *posterior interosseous nerve*.

Extensor Carpi Ulnaris.—The extensor carpi ulnaris arises, by means of the common extensor tendon, from the outer condyle of the humerus, from the fascia of the forearm, and from the intermuscular septum between it and the extensor minimi digiti. In the middle third of the forearm it may also receive some fibres from the strong fascial layer which binds it to the posterior border of the ulna. The tendon does not become free from the fleshy fibres until it approaches close to the wrist. It occupies the groove on the posterior

aspect of the lower end of the ulna, between the head and styloid process, and passing under cover of the annular ligament is inserted into the tubercle on the base of the metacarpal bone of the little finger. This muscle is supplied by the *posterior interosseous nerve*.

Anconeus.—The anconeus is a short triangular muscle placed on the posterior aspect of the elbow-joint. It presents a narrow origin from the posterior aspect of the external condyle of the humerus. From this its fibres spread out—the upper fibres passing transversely inwards, whilst the others proceed inwards and downwards, with an increasing degree of obliquity towards its lower border. It is inserted into the outer surface of the olecranon process, and into the upper third of the posterior surface of the shaft of the ulna.

The anconeus is frequently more or less directly continuous with the triceps, and this, together with the fact that it gets a special branch of supply from the musculo-spiral nerve, has led some anatomists to regard it as a piece of the triceps muscle. This is not the case, however; it belongs to, and is therefore properly classified with, the group of muscles on the extensor aspect of the forearm.

The nerve of supply to the anconeus has already been dissected. It is a long slender branch from the *musculo-spiral*, which descends to its destination in the substance of the internal head of the triceps. In addition to this, the lower part of the muscle usually receives a twig from the *posterior interosseous nerve*.

Dissection.—Reflect the extensor communis digitorum and the extensor minimi digiti. Divide the fleshy belly of each about its middle, and throw them upwards and downwards. In doing this care must be taken to secure and preserve the nerve twigs from the posterior interosseous nerve which enter these muscles on their deep surface. The posterior interosseous artery and nerve, together with the deep muscles, are now exposed, and may be fully dissected. In the lower part of the forearm the terminal part of the posterior interosseous nerve dips under cover of the extensor secundi internodii pollicis, to reach the interosseous membrane and the back of the carpus. In following this part of the nerve, the terminal or perforating branch of the anterior interosseous artery will be seen appearing on the back of the forearm, under cover of the extensor secundi internodii pollicis.

Deep Muscles.—These are—(1) The supinator brevis; (2) the extensor ossis metacarpi pollicis; (3) the extensor primi internodii pollicis or extensor brevis pollicis; (4) the extensor secundi internodii pollicis or extensor longus pollicis; and (5) the extensor indicis proprius.

The supinator brevis will be recognised from the close




FIG. 41.—Posterior aspect of Bones of Forearm with Attachments of Muscles mapped out.

manner in which it is applied to the upper part of the shaft of the radius. The other muscles take origin from above downwards in the order in which they have been named. The attachments of the supinator brevis cannot be satisfactorily studied at present. They will be described at a later stage of the dissection.

Extensor Ossis Metacarpi Pollicis (abductor longus pollicis).—This muscle arises from both bones of the forearm, and from the interosseous membrane which stretches between them. Its *origin from the radius* corresponds to the middle third of its posterior surface; its *origin from the ulna* is at a higher level from the outer part of the posterior aspect of the shaft immediately below the oblique line which marks the lower limit of the insertion of the anconeus. The muscle proceeds downwards and outwards, and comes to the surface in the interval

between the extensor communis digitorum and the extensor carpi radialis brevior. Closely accompanied by the extensor primi internodii pollicis it crosses the two radial

extensors. The tendon which issues from it at this point is continued downwards over the outer side of the expanded lower end of the radius, and under cover of the posterior annular ligament. It is inserted into the radial side of the base of the metacarpal bone of the thumb. This muscle is supplied by the *posterior interosseous nerve*.

Extensor Primi Internodii Pollicis.—This muscle, frequently called the *extensor brevis pollicis*, is placed along the lower border of the preceding muscle. It arises from a small portion of the posterior aspect of the radius, and also from the interosseous membrane. Its tendon is closely applied to that of the extensor ossis metacarpi pollicis, and accompanies it under the posterior annular ligament. It may be traced on the dorsal aspect of the metacarpal bone of the thumb to the base of the proximal phalanx, into which it is inserted. This muscle is supplied by the *posterior interosseous nerve*.

Extensor Secundi Internodii Pollicis.—The extensor secundi internodii pollicis, or the *extensor longus pollicis*, takes origin from the outer part of the posterior surface of the shaft of the ulna in its middle third, and also from the interosseous membrane. It, to some extent, overlaps the preceding muscle, and it ends in a tendon which passes under cover of the posterior annular ligament. Here it occupies a deep narrow groove on the back of the lower end of the radius. On the carpus it takes an oblique course, and, crossing the tendons of the two radial extensors and the radial artery, reaches the thumb. It is inserted into the base of the distal phalanx of that digit. The extensor longus pollicis is supplied by the *posterior interosseous nerve*.

When the thumb is powerfully extended in the living person the tendons of its three extensors become prominent on the outer aspect of the wrist. The oblique course of the tendon of the extensor secundi internodii is rendered evident, and a distinct depression between it and the other two tendons is seen.

Extensor Indicis Proprius.—The extensor indicis arises below the preceding muscle from a limited area on the posterior surface of the ulna and from the interosseous membrane. Its tendon accompanies those of the extensor communis under cover of the posterior annular ligament, and

will afterwards be traced to its insertion on the index




FIG. 42.—Dissection of the Back of the Forearm and Hand.

finger. This muscle is supplied by the *posterior interosseous nerve*.

Posterior Interosseous Artery (*arteria interossea dorsalis*).—This vessel arises in the front of the forearm, from the common interosseous branch of the ulnar artery. It at once proceeds backwards between the two bones of the forearm, in the interval between the upper border of the interosseous membrane and the oblique ligament. In the present dissection it makes its appearance between the contiguous borders of the supinator brevis and the extensor ossis metacarpi pollicis, and then it extends downwards between the superficial and deep muscles on the back of the forearm. It gives branches to these, and by the time it has reached the lower end of the forearm it is greatly reduced in size. In a well-injected limb it will be seen to end on the back of the carpus by anastomosing with the anterior interosseous and the posterior carpal arteries. In addition to the branches which it supplies to the muscles, it gives off one large branch called the *posterior interosseous recurrent*.

The *posterior interosseous recurrent artery* (*arteria interossea recurrens*) takes origin from the parent trunk as it appears between the supinator brevis and the extensor ossis metacarpi pollicis, and turns upwards, under cover of the anconeus muscle, to reach the posterior aspect of the outer condyle of the humerus. The anconeus should be detached from its origin and thrown inwards, in order that the artery may be traced to its termination. The interosseous recurrent artery will then be seen to end by anastomosing with the posterior terminal branch of the superior profunda artery.

Anastomosis around the Elbow-joint.—The series of inosculation around the elbow should now be reviewed as a whole. A distinct inosculation will be found to take place upon both the anterior and posterior aspect of each condyle of the humerus. Behind the external condyle the *posterior interosseous recurrent* joins the *posterior branch* of the *superior profunda*: in front of the same condyle the *anterior branch* of the *superior profunda* communicates with the *radial recurrent*. On the inner side of the joint the *anterior* and *posterior ulnar recurrent arteries* ascend respectively in front of and behind the internal condyle, and anastomose, the former with the *anterior branch of the anastomotica*, and the latter with the *posterior branch of the anastomotica* and the *inferior profunda*.

In this sketch of the anastomosis around the elbow-joint

only the leading inosculation is mentioned. Rich networks of fine vessels are formed over the olecranon process and the two condyles of the humerus. One very distinct and tolerably constant arch requires special mention. It is formed by a branch which crosses the posterior aspect of the humerus immediately above the olecranon fossa, and connects the posterior branch of the superior profunda with the posterior branch of the anastomotica.

Posterior Interosseous Nerve (*nervus interosseus dorsalis*).—This is one of the two terminal branches of the musculospiral, and it reaches the back of the forearm by traversing the substance of the supinator brevis, and at the same time winding round the outer aspect of the shaft of the radius. It emerges from the supinator brevis a short distance above the artery of the same name, and is carried downwards between the superficial and deep muscles on the back of the forearm. Reaching the upper border of the extensor secundi internodii pollicis, it leaves the posterior interosseous artery, dips under cover of that muscle, and joins the anterior interosseous artery on the posterior aspect of the interosseous membrane. It will afterwards be traced to the back of the carpus, where it ends, under cover of the tendons of the extensor communis digitorum, in a gangliform enlargement.

The *branches* which spring from the posterior interosseous nerve in the forearm are given entirely to muscles. Before it pierces the supinator brevis it gives branches both to it and to the extensor carpi radialis brevior. After it appears on the back of the forearm it supplies the extensor communis digitorum, the extensor minimi digiti, the extensor carpi ulnaris, the three extensors of the thumb, and




FIG. 43.—Diagram of Anastomosis around the Elbow-joint.

the extensor indicis. It therefore supplies all the muscles on the outer and back aspects of the forearm, with the exception of the supinator radii longus and the extensor carpi radialis longior, which derive their nerve-supply directly from the musculo-spiral. The anconeus also derives its main nerve of supply from the musculo-spiral, but it also frequently obtains a second twig from the posterior interosseous nerve.

Terminal Branch of the Anterior Interosseous Artery.—

The terminal or perforating branch of the anterior interosseous artery is a vessel of some size. It appears through the interosseous membrane, about two inches or so above the lower end of the forearm. Accompanied by the posterior interosseous nerve, it runs downwards, under cover of the extensor secundi internodii pollicis, and ends on the back of the carpus by anastomosing with the posterior carpal arch and the posterior interosseous artery.

DORSAL ASPECT OF THE WRIST AND HAND.

Upon the dorsal aspect of the wrist and hand we have still to examine—

1. The radial artery and its branches.
2. The posterior annular ligament.
3. The extensor tendons of the fingers.

Radial Artery.—It is only a small portion of the radial artery that is seen in this dissection. At the lower end of the radius the vessel turns backwards below the styloid process, and upon the external lateral ligament of the radio-carpal joint. Having gained the dorsal aspect of the carpus, it runs downwards upon the scaphoid and trapezium, and finally disappears from view by turning forwards through the upper part of the first interosseous space, and between the heads of origin of the first dorsal interosseous muscle (Fig. 35, p. 102). In the palm it takes the chief share in the formation of the deep palmar arch.

While the radial artery rests on the external lateral ligament, it is deeply placed, and is crossed by the tendons of the extensor ossis metacarpi and the extensor primi internodii pollicis. On the carpus it lies nearer the surface, and is

crossed obliquely by the third extensor tendon of the thumb, viz., the tendon of the extensor secundi internodii pollicis. It is accompanied by two *venæ comites* and some fine filaments from the musculo-cutaneous nerve which twine around it.

The *branches* which spring from the radial artery in this part of its course are of small size. They are—

1. The posterior radial carpal.
2. The first dorsal interosseous.
3. The two arteriæ dorsales pollicis.
4. The arteria dorsalis indicis.

The *posterior radial carpal artery* takes origin on the outer aspect of the wrist, and runs inwards upon the carpus, to join the corresponding carpal branch of the ulnar artery. The arch thus formed is placed under cover of the extensor tendons, and gives off two branches which run downwards in the third and fourth intermetacarpal intervals. They are termed the *second* and *third dorsal interosseous arteries*.

The *first dorsal interosseous artery* arises, as a rule, from the radial trunk, although not infrequently it may be seen to spring from the posterior carpal arch. It extends downwards in the second intermetacarpal interval.

The three dorsal interosseous arteries are brought into connection with the arteries in the palm by communicating branches. They are joined by the three perforating twigs of the deep palmar arch. These make their appearance on the dorsum between the heads of the three inner dorsal interosseous muscles. Further, at the lower ends of the interosseous spaces the dorsal interosseous arteries usually send *inferior perforating branches* to join the corresponding digital arteries in the palm.

The *two dorsal arteries of the thumb* run downwards upon either side of that digit.

The *dorsal artery of the index* is distributed on the radial side of the index.

Posterior Annular Ligament.—This has been seen to be an aponeurotic band which stretches obliquely across the wrist. It is merely a thickened portion of the deep fascia, and its attachments are so arranged that it does not interfere with the free movement of the radius and hand during pronation and supination. On the outer side it is fixed to the outer margin of the lower end of the radius, whilst on the inner side it

is attached to the cuneiform and pisiform bones, and also to the palmar fascia. In the case of the anterior annular ligament one large compartment, or tunnel, is formed for the flexor tendons; not so in the case of the posterior annular ligament. Partitions or processes proceed from its deep surface, and these are attached to the ridges on the dorsal aspect of the lower end of the radius, so as to form a series of six bridges or compartments for the tendons. Each of these is lined by a special synovial sheath, to facilitate the play of the tendons within it. The different compartments may now be successively opened up so that the arrangement of the tendons with reference to the posterior annular ligament may be studied.




FIG. 44.—Transverse section through Forearm immediately above Wrist-joint to show the arrangement of the Tendons.

The *first compartment* is placed on the outer side of the base of the styloid process of the radius, and corresponds with the broad oblique groove which is present in this part of the bone. It contains two tendons, viz., the tendons of the extensor ossis metacarpi and the extensor primi internodii pollicis. The *second compartment* corresponds with the outermost groove on the dorsal aspect of the radius. This is broad and shallow, and it holds the tendons of the extensor carpi radialis longior, and of the extensor carpi radialis brevis. The *third compartment* is formed over the narrow deep intermediate groove on the back of the lower end of the radius, and through it the tendon of the extensor secundi internodii pollicis passes obliquely. The *fourth compartment* is placed over the wide

shallow groove which marks the inner part of the dorsal aspect of the lower end of the radius. It is traversed by five tendons, viz., the four tendons of the common extensor and the tendon of the extensor indicis. The *fifth compartment* is situated over the interval between the lower ends of the radius and ulna. It contains the slender tendon of the extensor minimi digiti. The *sixth and innermost compartment*, which corresponds with the groove on the back of the lower end of the ulna, encloses the tendon of the extensor carpi ulnaris.

Extensor Tendons of the Fingers.—The four tendons of the *extensor communis digitorum*, when they emerge from their compartment in the posterior annular ligament, diverge on




FIG. 45. (From Luschka.)

- | | |
|--------------------------------|---------------------------------------|
| 1. Middle metacarpal bone. | 4. Second lumbrical muscle. |
| 2. Tendon of flexor sublimis. | 5. Second dorsal interosseous muscle. |
| 3. Tendon of flexor profundus. | 6. Extensor tendon. |
- I., II., and III. The three phalanges.

the dorsum of the hand to reach the four fingers. The tendon of the ring finger will be seen to be connected by a tendinous slip with the tendon on either side of it. This explains the small degree of independent movement in a backward direction which the ring digit possesses. The arrangement of the tendons on the fingers is the same in each case. Upon the dorsal aspect of the first phalanx the tendon expands so as to cover it completely. Into the margins of this "*dorsal expansion*," the delicate tendons of the lumbrical and interosseous muscles are inserted. Near the first interphalangeal joint the expansion becomes marked off into three portions—a central and two lateral. The *central part*, which is the weakest, is inserted into the dorsal aspect of the base of the second phalanx. The *stronger lateral portions* unite into one

piece beyond this, and gain an insertion into the base of the ungual phalanx.

The tendon of the *extensor indicis* joins the expansion of the extensor tendon on the dorsal aspect of the first phalanx of the index finger.

The tendon of the *extensor minimi digiti* splits into two parts. Of these the *outer* joins the tendon of the common extensor which goes to that digit, whilst the *inner* ends in the dorsal expansion.

Posterior Interosseous Nerve.—The terminal filament of this nerve can now be traced downwards to the dorsal aspect of the carpus. It passes under cover of the *extensor indicis*, the tendons of the *extensor communis*, and the posterior annular ligament. On the carpus it ends in a gangliform swelling, from which fine twigs proceed for the supply of the numerous joints in the vicinity.

Dissection.—The limb should now be turned round, so that the transverse metacarpal ligament which stretches across the palmar surface of the heads of the metacarpal bones may be examined previous to the dissection of the interosseous muscles.

Transverse Metacarpal Ligament.—The transverse metacarpal ligament is a strong band composed of transverse fibres, which is placed upon the palmar aspect of the heads of the four metacarpal bones of the fingers. Commencing on the outer side upon the distal extremity of the index metacarpal, it ends at the inner margin of the hand upon the head of the metacarpal bone of the little finger. It is not directly attached to the bones, but is fixed to the powerful anterior ligaments of the four inner metacarpo-phalangeal joints, and it effectually prevents excessive separation of the metacarpal bones from each other.

Dissection.—To obtain a satisfactory view of the interosseous muscles the adductor transversus pollicis, if not previously reflected, should be detached from its origin, and thrown outwards towards its insertion into the thumb. The transverse metacarpal ligament must also be divided in the intervals between the fingers.

Interosseous Muscles.—The interosseous muscles occupy the intervals between the metacarpal bones. They are seven in number; and are arranged in two groups, viz., a dorsal and a palmar.

The *dorsal interossei* (*musculi interossei dorsales*) are four in number, and are more powerful than the palmar muscles.

They are best seen on the dorsal aspect of the hand, but they are also visible in the palm. They act as abductors of the fingers from a line drawn through the middle digit, and their insertions are arranged in accordance with this action. Each muscle arises by two heads from the contiguous surfaces of the two metacarpal bones between which it lies, and the fibres converge in a pennate manner upon a delicate tendon. In the case of the *first* or *outermost dorsal interosseous muscle*, this tendon is inserted into the radial side of the base of the first phalanx, and also into the radial margin of the dorsal expansion of the extensor tendon of the index. The *second* and *third dorsal interosseous muscles* are inserted in a similar manner upon either side of the base of the first phalanx of the middle finger; whilst the *fourth* has a corresponding insertion upon the ulnar aspect of the base of the first phalanx of the ring finger.

The first dorsal interosseous muscle is frequently termed the *abductor indicis*, and between its two heads of origin the radial artery enters the palm. Between the heads of the other three muscles the small posterior perforating arteries pass.

The three *palmar interosseous muscles* (musculi interossei volares) can only be seen on the palmar aspect of the hand. They act as adductors of the index, ring, and little fingers towards the middle digit, and each muscle is placed upon the metacarpal bone of the finger upon which it acts. The *first palmar interosseous muscle* therefore arises from the metacarpal bone of the index finger, and its delicate tendon is inserted upon the ulnar side of that digit, partly into the base of the first phalanx, and partly into the extensor expansion. The *second palmar interosseous muscle* springs from the metacarpal bone of the ring finger, and has a similar insertion into the radial side of that digit. The *third palmar interosseous muscle* takes origin from the metacarpal bone, and presents a corresponding insertion into the radial side of the first phalanx and extensor expansion of the little finger. The interosseous muscles are supplied by the *deep branch* of the *ulnar nerve*.

Deep Head of the Flexor Brevis Pollicis (interosseous primus volaris of Henle).—This minute muscle can best be displayed from the dorsal aspect of the hand by reflecting the radial head of the first dorsal interosseous muscle. It arises from the base of the metacarpal bone of the thumb, and is inserted into the ulnar sesamoid bone of that digit. It is deeply placed, and is entirely covered in front by the adductor obliquus pollicis.

Tendon of the Flexor Carpi Radialis.—The tendon of this

muscle should now be traced through the groove on the front of the trapezium to its insertion into the base of the metacarpal bone of the index. It presents also a minor attachment to the base of the middle metacarpal bone.

Dissection.—All the muscles around the elbow-joint should be removed. In raising the brachialis anticus and the triceps from the front and back of the articulation, some care is required to avoid injury to the anterior and posterior ligaments. It is advisable to remove the supinator brevis last, because it is only when this muscle is completely isolated that a proper idea of its attachments and mode of action can be obtained.

Supinator Radii Brevis.—The supinator brevis envelops the upper part of the shaft and the neck of the radius, covering it completely, except on its inner side (Figs. 35, 41, pp. 99, 125). It arises from the deep depression below the lesser sigmoid cavity of the ulna, and also from the external lateral ligament of the elbow and the orbicular ligament of the radius. From this origin the fibres sweep round the posterior, outer, and anterior surfaces of the radius, and clothe its shaft as far down as the insertion of the pronator radii teres. The posterior interosseous nerve traverses the substance of the muscle, and separates it into two layers.

ARTICULATIONS.

ELBOW-JOINT.

At the elbow-joint (articulatio cubiti) the trochlear




FIG. 46.—Vertical section through Humerus and Ulna at the Elbow-joint.

surface of the humerus is grasped by the greater sigmoid cavity of the ulna. The shallow depression on the upper surface of the head of the radius rests upon the capitellum of the humerus, and its slightly raised rim occupies the groove on the lower end of the humerus between the capitellum and the trochlea.

The *ligaments* of the elbow-joint are arranged in the form

of a capsule which surrounds the articulation on all sides. From the differences which this exhibits in strength and attachments four portions are recognised. These are—

- | | |
|-----------------------------------|----------------------------|
| 1. The external lateral ligament. | 3. The anterior ligament. |
| 2. The internal lateral ligament. | 4. The posterior ligament. |

External Lateral Ligament (*ligamentum collaterale radiale*).—This is a strong but short ligamentous band which is attached above to the lower aspect of the external condyle of the humerus. Below, it is fixed to the orbicular ligament




FIG. 47.—Inner aspect of Elbow-joint.

of the radius, and also to the outer side of the olecranon process of the ulna behind this. The orbicular ligament, as we shall afterwards see, is a strong ligamentous collar which surrounds the head of the radius, and retains it in the lesser sigmoid cavity of the ulna.

Internal Lateral Ligament (*ligamentum collaterale ulnare*).—The internal lateral ligament, taken as a whole, is fan-shaped. By its upper pointed part it is attached to the internal condyle of the humerus. Inferiorly it spreads out to find insertion into the coronoid and olecranon processes of

the ulna. It consists of three very distinct portions, viz., an anterior, a posterior, and a transverse.

The *anterior part* springs from the lower and front part of the humeral condyle, and is attached to the inner margin of the coronoid process of the ulna. The *posterior part* is attached above to the lower and back part of the humeral condyle, whilst below it is fixed to the inner border of the olecranon process. The *transverse part* consists of a band of fibres,




FIG. 48.—Anterior aspect of the Elbow-joint.

which bridges across the notch between the olecranon and the coronoid processes, and is attached to both.

Anterior Ligament.—The anterior ligament is broad, and composed of fibres which take an irregular course over the anterior aspect of the joint. It is attached to the front of the humerus above the coronoid fossa, whilst below it is inserted into the margin of the coronoid process of the ulna, and also into the orbicular ligament of the radius.

Posterior Ligament.—This is weaker than the anterior

ligament. It has a loose attachment to the back of the humerus, above the olecranon fossa, and inferiorly it is fixed to the olecranon and the orbicular ligament of the radius.

Synovial Membrane.—The joint should be opened by making a transverse incision through the anterior ligament. The synovial membrane will be seen lining the deep surface of the ligamentous capsule, and to be reflected from this upon the non-articular parts of the bones which are enclosed within the ligaments. In front of the humerus it lines the radial and coronoid fossæ, and behind it is prolonged upwards in the form of a loose diverticulum into the olecranon fossa. In these fossæ a quantity of soft oily fat is developed between the bone and the synovial membrane. In this way pliable pads are formed which occupy the recesses when the bony processes are withdrawn from them.

Inferiorly the synovial membrane of the elbow-joint is prolonged downwards into the superior radio-ulnar joint, so that both articulations possess a single continuous synovial cavity.

Movements at the Elbow-joint.—The movements at the elbow-joint must not be confounded with those that take place at the superior radio-ulnar joint. At the elbow-joint two movements, viz., *flexion*, or forward movement of the forearm, and *extension*, or backward movement of the forearm, are permitted.

The *muscles* which are chiefly concerned in flexing the forearm upon the upper arm at the elbow-joint are the biceps, the brachialis anticus, the pronator radii teres, and the supinator longus. The muscles which extend the forearm at this articulation are the triceps and anconeus.

Dissection.—It is advisable to study the radio-carpal, or wrist-joint, before the articulations between the two bones of the forearm are examined. The anterior and posterior annular ligaments, together with the extensor and flexor tendons, should be completely removed from the wrist. No attempt, however, should be made to detach the extensor tendons from the back of the fingers and thumb. The short muscles of the thenar and hypothenar eminences must also be taken away.

RADIO-CARPAL JOINT.

In the radio-carpal joint (*articulatio radiocarpea*), the under surface of the radius, with a triangular plate of fibro-cartilage on its inner side, forms a shallow socket for the scaphoid, semilunar, and cuneiform bones. The ulna does not take part in this articulation, as the triangular fibro-cartilage is interposed between its lower end and the carpus.

The ligaments which retain the opposed surfaces in contact with each other are four in number, viz.—

- | | | |
|---------------|--|--------------|
| 1. Anterior. | | 3. Internal. |
| 2. Posterior. | | 4. External. |

Anterior Ligament (*ligamentum radiocarpeum volare*).—The anterior ligament is strong and broad, and it is composed of fibres which run in different directions, although those which pass obliquely downwards and inwards predominate. Above, it is attached to the lower border of the inferior expanded extremity of the radius; and below, it is inserted into the bones which constitute the first row of the carpus, with the exception of the pisiform, viz., into the scaphoid, semilunar, and cuneiform. Some of the fibres may be traced beyond the first carpal row on to the os magnum.

Posterior Ligament (*ligamentum radiocarpeum dorsale*).—This is weak in comparison with the anterior ligament. The direction of its fibres is for the most part downwards and inwards. It arises above from the posterior aspect of the lower end of the radius, and is attached below to the scaphoid, semilunar, and cuneiform bones.

External Lateral Ligament.—The external ligament passes from the tip of the styloid process of the radius to the scaphoid bone.

Internal Lateral Ligament.—The internal ligament is round and cord-like. It stretches from the styloid process of the ulna to the cuneiform and pisiform bones.

The *four ligaments* which we have described in connection with the radio-carpal joint are directly continuous with each other, and in consequence they form a *capsule* around the articulation.

Articular Surfaces.—Divide the anterior and lateral ligaments of the radio-carpal joint by a transverse incision carried across the front of the articulation. The hand can now be bent backwards, so as to expose fully the articular surfaces opposed to each other in this joint.

The *carpal surface* is composed of the superior articular facets of the scaphoid and semilunar bones, and a very small articular facet on the extreme outer part of the upper surface of the cuneiform bone. Two interosseous ligaments stretch across the narrow intervals between these bones—one on either side of the semilunar—and complete the

carpal surface. Formed of these factors, the carpal surface is convex both from before backwards and from without inwards. Further, it should be observed that the articular surface extends downwards to a greater extent behind than in front.

The *upper surface* or *socket* (Fig. 49) is elongated from side to side, and concave in both directions, viz., from before backwards and from without inwards. The greater part of it is formed by the lower end of the radius, but to the inner side of this the triangular fibro-cartilage of the inferior radio-ulnar joint likewise enters into its construction. The lower surface of the radius is divided by a low ridge into an outer triangular and an inner quadrilateral facet. The outer facet, in the




FIG. 49.—Carpal Articular Surfaces of the Radius and of the Triangular Fibro-cartilage of the Wrist.

ordinary position of the hand, is in contact with the greater extent of the superior articular surface of the scaphoid. The inner facet of the radius, with the triangular fibro-cartilage, forms a much larger surface, triangular in outline, which is opposed to the superior articular surface of the semilunar. When the hand is placed in line with the forearm no part of the upper articular surface is allotted to the cuneiform: its small articular facet rests against the inner part of the capsule of the joint. When the hand is moved inwards (*i.e.*, adducted), however, the cuneiform bone travels outwards, and its articular surface comes into contact with the under surface of the triangular fibro-cartilage. The semilunar bone at the same time crosses the bounding ridge on the lower surface of the radius, and encroaches on the territory of the scaphoid, whilst

a considerable part of the scaphoid surface leaves the radius, and comes into contact with the outer part of the capsule.

Synovial Membrane.—The synovial membrane of the radio-carpal joint lines the deep surfaces of the ligaments forming the capsule, and between the carpal bones it covers the upper surfaces of the two interosseous ligaments which complete the carpal surface. Sometimes the triangular fibro-cartilage is imperfect, and in these cases the synovial membrane of the radio-carpal joint becomes continuous with the synovial membrane of the inferior radio-ulnar joint.

Movements at the Radio-carpal Joint.—The hand can be moved in four directions at the radio-carpal joint. Thus we have—(a) forward movement, or *flexion*; (b) backward movement, or *extension*; (c) inward movement, or *adduction*; (d) outward movement, or *abduction*. In estimating the extent of these movements in the living person the student is apt to be misled by the increase of range which is contributed by the carpal joints. Thus, flexion at the radio-carpal joint is in reality more limited than extension, although by the combined action of both carpal and radio-carpal joints the hand can be carried much more freely forwards than backwards. Adduction, or ulnar flexion, can be produced to a greater extent than abduction, or radial flexion. In both cases the extent of movement at the radio-carpal joint proper is very slight, but the range is extended by movements of the carpal bones. The styloid process of the radius interferes with abduction.

The *muscles* which are chiefly concerned in producing these different movements of the hand at this joint are the following:—(a) *flexors*—the flexor carpi radialis, the palmaris longus, and the flexor carpi ulnaris; (b) *extensors*—extensor carpi radialis longior, the extensor carpi radialis brevior, and the extensor carpi ulnaris; (c) *abductors*, or *radial flexors*—flexor carpi radialis, extensor carpi radialis longior, extensor ossis metacarpi pollicis, and the extensor primi internodii pollicis; (d) *adductors*, or *ulnar flexors*—extensor carpi ulnaris and flexor carpi ulnaris.

RADIO-ULNAR JOINTS.

At the radio-ulnar joints the movements of pronation and supination take place. They are two in number, viz., a superior and an inferior. At the *superior radio-ulnar articulation* (articulatio radioulnaris proximalis), the inner part of the head of the radius fits into the lesser sigmoid cavity of the ulna; at the *inferior radio-ulnar joint* the small rounded extremity of the ulna is received into the sigmoid cavity on the inner side of the lower end of the radius. In connection with these joints there are special ligaments which retain the bones in apposition. These are—(1) for the

superior radio-ulnar joint, *the orbicular ligament*; and (2) for the inferior radio-ulnar joint, (a) an *anterior* and *posterior ligament*, and (b) a connecting *triangular fibro-cartilage*.

In addition there are other ligaments which pass between the shafts of the two bones of the forearm, and are therefore common to the two articulations, viz., the *oblique ligament* and the *interosseous membrane*.

To expose these ligaments the muscles on the front and back of the forearm must be completely removed.

Orbicular Ligament (*ligamentum annulare radii*).—This is a strong ligamentous collar which encircles the head of the radius, and retains it in the lesser sigmoid cavity of the ulna. It forms four-fifths of a circle, and is attached by its extremities to the ulna, in front and behind the lesser sigmoid cavity. It is somewhat narrower below than above, so that under no circumstances could the head of the radius be withdrawn from it in a downward direction, and it is braced tightly upwards towards the elbow, and greatly strengthened by certain ligaments of the elbow-joint which become incorporated with it along its upper border. These are, on the outer side, the external lateral ligament of the elbow; in front, a portion of the anterior ligament; and behind, a portion of the posterior ligament of the elbow-joint. Its lower border is free, and protruding downwards below this will be seen a reflection of the synovial membrane.

Anterior and Posterior Inferior Radio-ulnar Ligaments.—

These are weak, imperfect bands which can have little influence in retaining the bones in apposition at the inferior radio-ulnar joint. They pass between the radius and ulna in front and behind the articulation, and close in the synovial membrane upon these aspects of the joint.

Triangular Fibro-cartilage.—The triangular fibro-cartilage is the true bond of union at the inferior radio-ulnar joint. It has already been noticed in connection with the radio-carpal joint, where it extends the radial articular surface in an inward direction, and is interposed between the lower end of the ulna and the semilunar bone. It is a thick, firm plate, attached by its base to the margin on the inner and lower end of the radius which separates the sigmoid cavity for the ulna from the facet on the lower surface for the semi-

lunar bone. The apex of the cartilage is directed inwards, and is fixed to the depression on the lower end of the ulna at the root of the styloid process. It intervenes between the inferior radio-ulnar joint and the radio-carpal joint.

Synovial Membranes.—The synovial membrane of the superior radio-ulnar joint is continuous with that of the elbow-joint. It is prolonged downwards so as to line the orbicular ligament, and it protrudes beyond this for a short distance upon the neck of the radius.

In the inferior radio-ulnar joint the synovial membrane is remarkable for its laxity. It is called the *membrana saciformis*, and extends upwards in the form of a loose sac for some distance between the radius and ulna. The synovial cavity is also prolonged inwards in a horizontal direction between the lower end of the ulna and the triangular fibro-cartilage.

Sometimes the triangular fibro-cartilage is perforated; and when this is the case, the inferior radio-ulnar joint-cavity communicates with the cavity of the radio-carpal joint.

Interosseous Membrane (*membrana interossea antibrachii*).—This is a fibrous membrane which stretches across the interval between the two bones of the forearm, and is attached to the interosseous border of each. Superiorly it is deficient. Its upper border does not reach higher than a point about an inch below the tubercle of the radius. The fibres which compose it run for the most part obliquely downwards and inwards from the radius to the ulna, although several slips may be noticed taking an opposite direction. The posterior interosseous vessels pass backwards between the two bones of the forearm immediately above its upper margin, whilst the terminal branch of the anterior interosseous artery pierces it about one and a half inches above its lower end. This ligament, in addition to bracing the two bones together in such a manner that to some extent forces may be transmitted from the radius to the ulna, extends the surface of origin for the muscles of the forearm. By its anterior surface it gives origin to the flexor profundus and the flexor longus pollicis muscles, whilst by its posterior surface it contributes fibres to the three extensor muscles of the thumb and to the extensor indicis.

Oblique Ligament (*chorda obliqua*).—This is a weak slip

which springs from the outer part of the coronoid process of the ulna, and extends obliquely downwards and outwards to find an attachment to the radius immediately below its bicipital tubercle. It crosses the open space between the bones of the forearm above the upper border of the interosseous membrane. The oblique ligament is often absent, and unless the utmost care be taken in removing the muscles in the preparation of the ligaments it is apt to be injured.

Movements at the Radio-ulnar Joints.—At the radio-ulnar joints the movements of pronation and supination take place. When the limb is in a condition of complete supination the palm of the hand is directed forwards, the thumb outwards, and the two bones of the forearm are parallel, the radius lying along the outer side of the ulna. In the movement of pronation the radius is thrown across the ulna, so that its lower end comes to lie on the inner side and in front of it. Further, the hand follows the radius in this movement, and the dorsal aspect of both is directed to the front, and the thumb is turned inwards.

The dissector should analyse, as far as possible, in the part upon which he is engaged, the movements at the two radio-ulnar joints which produce these effects. At the same time it should be remembered that results obtained from a limb, in which the dissection has proceeded so far, are apt to be deceptive.

In the case of the *superior radio-ulnar joint* the movement is simple enough. The head of the radius merely rotates within the orbicular ligament, and accuracy of motion is obtained by the cup-like depression on the upper end of the radius, resting and moving upon the rounded capitellum of the humerus. But it should be noticed that the head of the radius does not fit accurately upon the capitellum in all positions of the elbow-joint. In extreme extension and extreme flexion of the elbow it is only partially in contact with it. Therefore the semi-flexed condition of the elbow-joint places the radius in the most favourable position for free and precise movement at the superior radio-ulnar joint.

At the *inferior radio-ulnar joint* the lower end of the radius revolves around the lower end of the ulna. It carries the hand with it, and describes the arc of a circle, the centre of which corresponds to the attachment of the triangular fibro-cartilage to the lower end of the ulna. In this movement the triangular fibro-cartilage moves with the radius, and travels backwards on the lower end of the ulna in supination, and forwards in pronation.

But the question may be asked, Does the ulna move during pronation and supination? When the elbow-joint is extended to its fullest extent the ulna remains almost immovable. When, however, pronation and supination are conducted in the semi-flexed limb, the ulna does move. A small degree of lateral movement at the elbow-joint is allowed, and the lower end of the ulna during pronation is carried slightly backwards and outwards, and in the reverse direction during supination.

The *muscles* which are chiefly concerned in producing *supination* of the forearm are—the biceps, the supinator longus, and the supinator brevis. The biceps, from its insertion into the back part of the radial tubercle, is placed in a very favourable position, in so far as its supinating action is concerned. The muscles which act as *pronators* of the limb are—the pronator radii teres, the pronator quadratus, and, to a certain extent, the

flexor carpi radialis. The pronator radii teres, from its insertion into the point of maximum outward curvature of radius, can exercise its pronating action to great advantage. The balance of power is in favour of the supinators, and this is due to the preponderating influence of the biceps.

Dissection.—The ulna should be sawn through at the junction of its middle and lower thirds, and the interosseous membrane where it binds the lower portion of the bone to the radius divided in a downward direction. By drawing the lower fragment of the ulna inwards and opening the membrana sacciformis, the upper surface of the triangular fibro-cartilage of the wrist will be displayed and its attachments more fully appreciated.

CARPAL JOINTS.

In studying the articulations of the carpal bones we recognise—

1. A joint between the pisiform and cuneiform bones.
2. Two joints between the remaining bones of the first row, viz., the scaphoid, semilunar, and cuneiform.
3. Three joints between the bones of the second row, viz., the trapezium, trapezoid, os magnum, and unciform.
4. A transverse carpal joint between the two rows of carpal bones.

The pisiform joint is distinct and separate. All the other joints possess a single joint-cavity. Further, this common cavity is continued into the articulations between the metacarpal bones of the four fingers and the carpus, and also into the intermetacarpal articulations.

Pisiform Joint.—The pisiform bone is fixed to the cuneiform by a capsular ligament which surrounds the joint. There is a separate synovial membrane for this articulation.

The dissector has previously noted that the tendon of the flexor carpi ulnaris is inserted into the upper aspect of the pisiform bone. The capsular ligament by itself would be insufficient to withstand the strain to which this muscle subjects the articulation. Certain accessory ligaments are therefore provided, which anchor the pisiform firmly in its place. These consist of two strong ligamentous bands which pass from its lower surface to the hook of the unciform bone, and to the base of the fifth metacarpal bone. Additional security is frequently given by bands which connect it with the bases of the fourth and third metacarpal bones.

First Row of Carpal Bones.—*Two dorsal, two palmar, and two interosseous* ligaments pass transversely from the semilunar

to the scaphoid and cuneiform bones which lie on either side of it.

The *two interosseous ligaments* are composed of short stout fibres which pass between the non-articular portions of the opposed surfaces of the three bones. They are readily seen from above, where they complete the carpal surface of the radio-carpal joint.

Second Row of Carpal Bones.—*Three palmar, three dorsal,* and *three interosseous* ligaments pass transversely between the adjacent bones.




FIG. 50.—Coronal section through Radio-carpal, Carpal, and Carpo-metacarpal and Inter-metacarpal Joints to show Joint Cavities and Interosseous Ligaments (diagrammatic).

The interosseous ligament between the os magnum and unciform is very powerful and strong; that between the os magnum and trapezoid is weak, and sometimes absent.

At the present moment the interosseous ligaments are hidden from view, but they can be studied when the transverse carpal joint between the two rows of bones is opened.

Transverse Carpal Joint (between the two rows of carpal bones).—*Two lateral ligaments*, which pass between the scaphoid and trapezium on the outer side, and the cuneiform and unciform bones on the inner side, together with a series

of *palmar* and *dorsal bands*, and one *interosseous ligament*, connect the two rows of carpal bones together.

The *palmar ligaments* show a tendency to converge upon the os magnum, whilst the *dorsal ligaments* are very irregular. The *interosseous ligament* is placed between the os magnum and scaphoid bones, but is not always present.

Dissection.—To display the articular surfaces and interosseous ligaments of the second row it is necessary to open the transverse carpal joint. This can be done by dividing the two lateral and the dorsal ligaments. The interosseous ligament between the scaphoid and os magnum, if present, will now come into view, and it must be cut, to allow the thorough separation of the two rows of carpal bones.

Articular Surfaces.—The os magnum and unciform form a high convexity, which fits into the concavity of the upper row, whilst the convex lower surface of the scaphoid is received into a concavity formed by the trapezium and trapezoid. The two opposing surfaces, therefore, are concavo-convex from side to side, and adapted the one to the other.

Movements at the Carpal Joints.—The movements at the carpal joints supplement those at the radio-carpal joint, and tend greatly to increase the range of movement at the wrist. Between the individual bones of each row the movement is of a gliding character, and very limited. At the transverse carpal joint forward and backward movement (flexion and extension) is alone allowed.

By the multiplicity of joints in this part of the limb, strength and elasticity is contributed to the wrist.

Dissection.—The interosseous muscles should now be removed from the metacarpal bones. At the same time the flexor tendons and lumbrical muscles may be detached from the fingers. The extensor tendons, however, should be left in position on the dorsal surface of the metacarpophalangeal and interphalangeal joints. The ligaments which connect the carpus and metacarpus, and those which pass between the bases of the four inner metacarpal bones, should be cleaned and defined.

INTERMETACARPAL JOINTS.

The four metacarpal bones of the fingers articulate with each other by their basal or proximal extremities, and are united together by strong ligaments. The metacarpal bone of the thumb stands aloof from its neighbours, and enjoys a much greater freedom of movement.

The ligaments which bind the four inner metacarpal bones to each other are—

1. A series of *palmar* and *dorsal* bands which pass transversely, and connect their basal extremities.
2. *Three stout interosseous ligaments*, which occupy the intervals between the basal ends of the bones.
3. The *transverse metacarpal ligament*, which connects the heads or distal extremities of the bones (p. 134). This ligament has been removed in the dissection of the interosseous muscles.

The *interosseous ligaments* cannot be seen at present, but can be studied later on by separating the bases of the metacarpal bones from each other.

CARPO-METACARPAL JOINTS.

The *metacarpal bone* of the *thumb* articulates with the trapezium by a joint which is quite distinct from the other carpo-metacarpal articulations. A *capsular ligament* surrounds the joint, and is sufficiently lax to allow a very considerable range of movement. On the dorsal and outer aspects of the articulation it is specially thickened. It encloses a separate synovial membrane.

The *four inner metacarpal bones* are connected to the carpus by *palmar* and *dorsal ligaments*, and by *one interosseous ligament*.

Each of these metacarpal bones, with the exception of the fifth, possesses, as a rule, two dorsal ligaments and one palmar ligament. The articulation of the fifth metacarpal bone is also closed on the inner side by ligamentous fibres.

The *interosseous ligament* springs from the contiguous lower margins of the os magnum and unciform, and passes to the inner side of the base of the third metacarpal bone.

Dissection.—To display this ligament, divide the bands which connect the bases of the third and fourth metacarpal bones, and sever the dorsal ligaments which bind the two inner metacarpal bones to the carpus. The metacarpal bones thus set free can then be forcibly bent forward, when the ligament in question will come into view.

Synovial Membranes of the Carpal, Carpo-metacarpal, and Intermetacarpal Joints.—The pisiform joint, and the carpo-metacarpal joint of the thumb, possess each a separate synovial membrane. The other carpal, and carpo-metacarpal, and also the intermetacarpal articulations present one continuous joint-cavity, and possess a single synovial membrane.

This complicated and extensive synovial membrane may be seen to pass upwards in the intervals between the three bones of the first row (scaphoid, semilunar, and cuneiform) as far as the interosseous ligaments. It lines the under surfaces of these, and is excluded by them from the radio-carpal joint. In a downward direction it may be traced between the four bones of the second row to the carpo-metacarpal joints of the four fingers, and from these it finds its way into the three intermetacarpal articulations.

In some cases the interosseous ligament which connects the base of the third metacarpal to the os magnum and unciform shuts off the articulation of the unciform with the two inner metacarpal bones, and also the innermost intermetacarpal articulation from the general joint-cavity. In such cases a separate synovial membrane is provided for these articulations.

Dissection.—To display the articular surfaces of the carpo-metacarpal articulations, the metacarpus should be detached from the carpus. The interosseous ligaments between the carpal bones of the second row, and also between the bases of the four inner metacarpal bones, can likewise be demonstrated by carrying the knife between the bones, and dividing the ligaments.

Articular Surfaces.—The base of the metacarpal bone of the index will be seen to be hollowed out for the reception of the trapezoid. On the outer side it likewise articulates with the trapezium, and on the inner side with the os magnum. The base of the third metacarpal rests on the os magnum alone. The base of the metacarpal bone of the ring finger rests upon the unciform, but also articulates slightly with the os magnum. The fifth metacarpal bone articulates with the unciform.

Movements of the Metacarpal Bones.—The opposed saddle-shaped surfaces of the trapezium and thumb-metacarpal allow very free movement at this joint. Thus the *metacarpal bone of the thumb* can be moved—(1) backwards and outwards (extension); (2) forwards and inwards (flexion); inwards towards the index finger (adduction); (4) outwards (abduction); (5) inwards across the palm towards the little finger (opposition). The *muscles* which operate upon the thumb are—(1) the three extensors (extensor ossis metacarpi, extensor primi internodii, and the extensor secundi internodii), producing *extension*; (2) the flexor brevis pollicis and the opponens pollicis, producing *flexion* and *opposition*, two movements which are similar in character; (3) the abductor pollicis, which produces *abduction*; (4) and the two adductors (adductor obliquus and the adductor transversus), which give rise to *adduction*.

The *metacarpal bones* of the *middle* and *index fingers* possess very little power of independent movement. The *metacarpal bone* of the *ring finger*, and more especially the *metacarpal bone* of the *little finger*, are not so tightly bound to the carpus. In clenching the fist they both move forwards. The metacarpal bone of the little finger is provided with an *opponens muscle*, and has a feeble power of advancing forwards and outwards to meet the thumb.

METACARPO-PHALANGEAL ARTICULATIONS.

The slightly cupped base of the first phalanx of each digit articulates with the rounded head of the corresponding metacarpal bone, and is held in position by three ligaments, viz., a palmar and two lateral.

The *palmar ligament* is a dense fibrous plate placed on the fore aspect of the joint. It is firmly attached to the base of the phalanx, but only slightly connected with the metacarpal bone. Occupying the interval between the two lateral ligaments, it is united to both by its margins, so that the three ligaments are more or less directly continuous.

The palmar ligament also exhibits a close connection with the transverse metacarpal ligament which stretches transversely across the heads of the metacarpal bones, and its palmar surface is grooved for the flexor tendons as they proceed downwards over the joint. Further, the flexor sheath which bridges over the tendons is fixed to its borders.

The *lateral ligaments* are placed one on either side of the joint. They are strong, thick, and short bands, which are attached on the one hand to the tubercle and depression on the lateral aspect of the head of the metacarpal bone, and on the other to the base of the phalanx.

Dissection.—The extensor tendon should now be raised from the dorsal aspect of the joint. By this proceeding the joint is opened, and a demonstration is afforded of the fact that the metacarpo-phalangeal joints are destitute of dorsal ligaments.

A *synovial membrane* lines the deep surfaces of the ligaments in each joint, and also the deep surface of the extensor tendon, as it passes over the articulation and takes the place of a dorsal ligament.

Movements at the Metacarpo-phalangeal Joints.—The movements of the first phalanx at these joints are—(a) *flexion*, or forward movement; (b) *extension*, or backward movement; (c) *abduction*; and (d) *adduction*.

During flexion of the fingers, the first phalanx travels forwards with the

thick palmar ligament upon the head of the metacarpal bone. The *interosseous* and *lumbrical* muscles are chiefly instrumental in producing this movement.

The first phalanges of the fingers in the movement of extension can only be carried backwards to a very slight degree beyond the line of the metacarpal bones. The *extensor communis* and the *special extensors* of the *index* and *little finger* are the muscles which operate in this case.

Abduction and adduction are movements of the first phalanx away from and towards a line prolonged downwards through the middle finger, and are seen when the fingers are spread out and again drawn together. The *abductor minimi digiti* and the *dorsal interosseous muscles* act as abductors of the fingers at these joints, whilst the *palmar interosseous muscles* operate as adductors of the little, ring, and index fingers. In the case of the middle digit, the *second* and *third dorsal interosseous muscles* act alternately as abductors and as adductors. In connection with the movements of abduction and adduction, it should be noticed that in the extended position of the fingers they are very free; but if flexion be induced, the power of separating the fingers becomes more and more restricted, until it becomes absolutely lost when the hand is closed. An examination of the lateral ligaments will afford the explanation of this. These "are attached far back on the metacarpal bones, so as to be much nearer to their inferior ends than to their palmar aspects" (Cleland). Consequently, while they are comparatively lax in the extended position of the fingers, the further flexion advances the tighter they become, and in this way they interfere with the lateral movements of the first phalanges.

The first phalanx of the thumb has only a limited range of movement at the metacarpo-phalangeal joint.

INTERPHALANGEAL JOINTS.

The ligaments connecting the phalanges are arranged upon a plan identical with that already described in connection with the metacarpo-phalangeal joints. This should not be made an excuse, however, to slur them over.

Movements.—From the manner in which the articular surfaces are adapted to each other, flexion and extension are the only movements which can take place at the interphalangeal joints. Flexion of the second phalanges of the fingers is brought about by the flexor sublimis, and of the ungual phalanges by the flexor profundus. Extension of the phalanges at the interphalangeal joints is largely produced by the interosseous and lumbrical muscles acting through the extensor tendons, into which they are inserted. These muscles, therefore, whilst they flex the first phalanx at the metacarpo-phalangeal joints, extend the second and ungual phalanges at the interphalangeal joints.

In the case of the thumb, the long flexor and the extensor secundi internodii pollicis operate at the interphalangeal joint.

THE LOWER LIMB.

On the morning of the third day after the subject has been brought into the dissecting-room, it is placed upon the table with its face downwards and its chest and pelvis supported by blocks (Fig. 1, p. 3). In this position it is allowed to remain for *four* days, and during this time the dissector of the lower limb has a very extensive dissection to perform. He has to dissect—(1) the gluteal region; (2) the popliteal space; and (3) the back of the thigh. With so much work before him, and being limited as to the time in which it must be done, it is necessary that he should apportion the four days at his disposal so as to complete the dissection before the body is turned. The *first two days* he should devote exclusively to the study of the gluteal region; the *third day* may be given to the popliteal space; and on the *fourth day* he should undertake the dissection of the back of the thigh, and revise the work of the three preceding days.

GLUTEAL REGION.

In this region the following are the parts which will be displayed in the course of the dissection:—

1. Superficial fascia.
2. Cutaneous nerves and blood-vessels.
3. Deep fascia.
4. Muscles, . . .
 - { The gluteus maximus; (and after this has been reflected).
 - { Three synovial bursæ.
 - { Gluteus medius and minimus.
 - { Piriformis.
 - { The two gemelli and the tendon of the obturator internus.
 - { The tendon of the obturator externus.
 - { The quadratus femoris.
 - { Upper border of the adductor magnus.
 - { The origin of the hamstrings from the tuberosity of the ischium.
 - { The upper part of the vastus externus
5. The great sacro-sciatic ligament.

- | | | |
|-------------------|---|---|
| 6. Blood-vessels, | { | Gluteal. |
| | | Sciatic. |
| | | Internal pudic. |
| | | Internal circumflex. |
| | | Superior gluteal. |
| | | Great sciatic. |
| | | Small sciatic. |
| 7. Nerves, | { | Internal pudic. |
| | | Nerve to obturator internus. |
| | | Nerve to quadratus femoris. |
| | | Special branches to gluteus maximus (inferior gluteal nerve). |

Supposing that *two days* are allowed for the above dissection, the **first day's work** should consist—(1) in the dissection of the parts superficial to the gluteus maximus ; (2) in the cleaning and reflecting of this muscle ; (3) in tracing and defining the various nerves and blood-vessels which enter its deep surface. **On the second day** the parts which are exposed by the reflection of the gluteus maximus should be dissected.

Surface Anatomy.—Before the skin is reflected, the surface markings of the gluteal region require examination. On each side, the prominence of the nates is seen to form a round, smooth elevation. Below, the nates are separated, in the middle line, by a deep fissure—the *natal cleft*. This cleft, if traced upwards, almost disappears over the prominence formed by the coccyx and lower part of the sacrum. The crest of the ilium can be felt along its whole length, and, in well-formed individuals, it appears as a groove—the *iliac furrow*. Traced forwards, the crest terminates in the anterior superior spine of the ilium ; traced backwards, it ends in the posterior superior spine of the ilium. The position of the latter is indicated by a faint depression which lies on a level with the second spine of the sacrum, and it corresponds with the middle of the sacro-iliac articulation. The prominence of the nates is chiefly formed by the gluteus maximus muscle, covered by a thick layer of fat. A deep transverse groove, produced by a fold of skin and fascia, limits the gluteal elevation below. This is called “the fold of the nates” (gluteal sulcus), and is sometimes said to correspond with the lower border of the gluteus maximus muscle. It can easily be shown that this is not the case. Its inner end lies below the lower margin of the muscle, but as it proceeds transversely outwards it crosses the muscle-border, and finally comes to lie on the surface of the muscle. In disease of the hip-joint, the buttock loses its prominence, whilst the fold of the nates becomes faint. The

tuberosity of the ischium may be felt below the lower border of the gluteus maximus by placing the fingers in the inner part of the fold of the nates and pressing upwards. A line drawn from the most prominent part of this tuberosity to the anterior superior spine of the ilium is called *Nelaton's line*. This line passes over the top of the great trochanter and crosses the centre of the acetabulum. It is used by the surgeon in the diagnosis of dislocations and other injuries of the hip-joint. The great trochanter of the femur may be felt at a point about six inches below the highest part of the crest of the ilium. It can be seen in thin subjects, but it does not form so projecting a feature of this region as might be expected from an inspection of the skeleton, because the thick tendon of the gluteus medius is inserted into its outer surface, and it is moreover covered by the aponeurotic insertion of the gluteus maximus.

Reflection of Skin.—*Incisions.*—(1) From the posterior superior spine of the ilium in a curved direction along the crest of the ilium, as far forwards as the position of the body will permit; (2) from the posterior extremity of this curved incision obliquely downwards and inwards to the middle line of the sacral region, and then perpendicularly downwards to the tip of the coccyx; (3) from the tip of the coccyx obliquely downwards and outwards over the back of the thigh. When properly carried out, this incision intersects the fold of the nates at about its middle point, and terminates a little below the upper third of the thigh (Fig. 1, p. 3).

A large flap of skin is thus marked out, and this must be raised from the subjacent superficial fascia and thrown outwards. On the right side of the body, the dissector begins at the crest of the ilium and works downwards and forwards; whilst on the left side he commences over the coccyx and works upwards and forwards.

Superficial Fascia.—The superficial fascia is now exposed, and it is seen to partake of the same characters as the corresponding layer of fascia in other parts of the body. It presents, however, certain special peculiarities. It is much more heavily laden with fat—especially in the female; it thickens over the lower and upper margins of the gluteus maximus, and it becomes tough, elastic, and stringy over the ischial tuberosity, so as to form a most efficient cushion upon which this bony prominence rests while the body is in the sitting posture.

Cutaneous Nerves (Fig. 51).—The superficial fascia forms a bed in which the cutaneous nerves ramify before they enter the skin. In this region the cutaneous nerves are very

numerous, and they are derived from a great variety of sources. Some proceed from the *posterior primary divisions* of the spinal nerves, whilst others are branches of the *anterior primary divisions* of the spinal nerves.

From the *posterior primary divisions* there are usually *six*—three from the sacral nerves, and three from the lumbar nerves. The *three sacral nerves* reach the surface by piercing the gluteus maximus muscle close to its origin from the sacrum and coccyx. They are usually of small size and pierce the muscle in a line drawn from the posterior superior iliac spine to the tip of the coccyx. The largest is found opposite the lowest piece of the sacrum, the highest about an inch above this, and the lowest about the same distance below it.

Owing to the coarseness of the muscular fasciculi of the gluteus maximus between which they appear, they are somewhat difficult to find. In looking for them, it is best to cut right down through both superficial and deep fasciæ, so as to secure them as they emerge from the muscle.

The *three lumbar nerves* are easily found. They cross the crest of the ilium at a point corresponding to the outer limit of the attachment of the erector spinæ




FIG. 51.—Cutaneous Nerves on the posterior aspect of the Lower Limb.

to the outer limit of the attachment of the erector spinæ

to the innominate bone. They pass downwards and slightly forwards in the superficial fascia, and run in different planes, the larger trunks being placed deeper than the smaller branches. They communicate with one another and with the sacral nerves. A few twigs may be followed as far as the great trochanter.

The cutaneous twigs which come from the *anterior primary divisions* of the spinal nerves may be classified under three headings—(1) those which pass downwards over the crest of the ilium; (2) those which pass backwards over the insertion of the gluteus maximus into the fascia lata; (3) those which turn upwards around the lower margin of the gluteus maximus.

The nerves which cross the crest of the ilium are—(1) the *iliac branch* of the *ilio-hypogastric nerve*; and (2) the *iliac branch* (i.e., the lateral cutaneous branch) of the *last dorsal nerve*.

The *iliac branch* of the *ilio-hypogastric nerve* pierces the external oblique muscle close to its insertion into the ilium. It usually crosses the iliac crest opposite a tubercle which projects from the outer lip of the crest about two and a half inches from the anterior superior spine, but it may emerge at any point between this tubercle and the anterior border of the iliac origin of the latissimus dorsi. The *iliac branch* of the *last dorsal nerve* pierces the external oblique muscle of the abdominal wall, a short distance in front of the ilio-hypogastric branch, at a point situated from one to two inches above the iliac crest. Both nerves, after crossing the iliac crest, run downwards in the thick superficial fascia over the upper part of the gluteus medius, and spread out into a great number of fine twigs, which ramify over the insertion of the gluteus maximus. Certain of them reach downwards as far as the level of the great trochanter.

The nerves which pass backwards over the insertion of the gluteus maximus are a few small branches of the posterior division of the *external cutaneous nerve* of the thigh. They are found above the level of the great trochanter.

The cutaneous twigs which hook round the lower margin of the gluteus maximus muscle, to reach the skin over this region, are a few offsets from the *small sciatic nerve* and the *perforating cutaneous branch* of the *fourth sacral nerve*. The

former appear external to the tuberosity of the ischium, and are accompanied in some cases by twigs from the sciatic artery. The latter comes into view internal to the ischial tuberosity, and is accompanied by small branches of the inferior hæmorrhoidal artery.

These nerves can most readily be found by everting the lower border of the gluteus maximus ; but in doing this, care must be taken not to injure the trunk of the small sciatic nerve, as it passes from under cover of the gluteus maximus and runs vertically down the thigh.

Deep Fascia.—The deep fascia of the gluteal region is brought into view by removing the remnants of the superficial fascia. The fatty tissue should be cleared away not only from the deep fascia as it is spread over the gluteus maximus, but also from the area in front of this. In the latter situation a dense, opaque, pearly white aponeurosis is by this means exposed. This covers the anterior part of the gluteus medius, and is firmly attached above to the crest of the ilium. It stands in marked contrast with the deep fascia over the gluteus maximus, which is thin and transparent. Subsequent dissection will show that the dense fascia over the anterior part of the gluteus medius, when it reaches the anterior border of the gluteus maximus, splits into two lamellæ which enclose that muscle between them.

Dissection.—Now proceed to clean the gluteus maximus muscle. If it is the right limb, begin at the anterior or upper margin of the muscle ; but if it is the left, commence the dissection at the posterior or lower border. In undertaking this dissection, the dissector must keep clearly before him the rules which have already been laid down regarding the cleaning of a muscle :—(1) render the fibres as tense as possible by rotating the limb *inwards* ; (2) remove the fascia in one continuous layer ; (3) always cut in the direction of the muscular fibres ; (4) define very carefully the borders of the muscle.

The gluteus maximus is a difficult muscle to clean, the fasciculi are so exceedingly coarse. To do it well, it is not sufficient to remove the fascia which covers the muscle, but it is necessary at the same time to follow, for a short distance, the septa which penetrate between the fasciculi, and to remove them also. Do not remove the thick opaque fascia which covers the insertion of the muscle.

The dissector of the left limb, on reaching the anterior margin of the muscle, will observe that the fascia which he holds in his hand is continuous with the strong aponeurosis which covers the gluteus medius ; and further, if he now frees the anterior border of the muscle from subjacent parts, he will notice that the layer of fascia upon which the gluteus maximus rests is also continuous with the same aponeurosis. In other words, he will in this manner be able to satisfy himself that the strong fascia, which covers the

anterior part of the gluteus medius splits into two layers to enclose the gluteus maximus. The small sciatic nerve lies in very close relation to the deep surface of the muscle, and is apt to be injured in the subsequent steps of the dissection, unless it is secured at once by everting the lower border of the muscle.

Gluteus Maximus.—This powerful muscle arises (1) from a




FIG. 52.—Outer aspect of the Innominat Bone with the Attachments of the Muscles mapped out.

narrow, rough area on the dorsum ilii, which is included between the superior curved line and the outer lip of the crest; (2) from the sides of the lower two pieces of the sacrum and the upper three pieces of the coccyx; (3) from the entire posterior surface of the great sacro-sciatic ligament; and (4) slightly from the posterior layer of the lumbar

aponeurosis, at the attachment of the latter to the crest of the ilium.

From this extensive origin the coarse fasciculi of the muscle proceed obliquely downwards and forwards towards the upper portion of the femur, but only a comparatively small proportion of them receive direct insertion into that bone. The greater part of the muscle is inserted into the fascia lata. To be more precise, we may say that the whole of the fibres belonging to the upper half of the muscle, and the superficial stratum of fibres of the lower half of the muscle, are inserted into the fascia lata. The deeper fibres of the lower half of the muscle, however, are directly attached to the "gluteal ridge" on the back of the femur (*i.e.*, the ridge which extends from the great trochanter to the linea aspera). (Fig. 68, p. 223.) The gluteus maximus is supplied by the *inferior gluteal nerve*.

Reflection of the Gluteus Maximus.—This is by no means an easy dissection. It is best to detach the muscle from its origin and throw it downwards towards its insertion. It should be dissected completely away from the various surfaces from which it arises. By this means the general outline of the pelvis becomes more apparent, and the dissector obtains distinct bony landmarks which are most useful in enabling him to localise the various structures he is expected to expose. Let us suppose we are dealing with the left lower limb. As a preliminary step, the two borders of the muscle should be freed and the left hand gently insinuated under the fleshy mass. The muscle must, in the first instance, be detached from the ilium. When the surface on the dorsum ilii from which it springs is cleared, we reach the upper margin of the great sciatic notch. Here the dissector must proceed with caution, because through this pass the gluteal vessels, branches of which enter the deep surface of the gluteus maximus muscle. Having secured these, we next detach the muscle from the side of the sacrum, and the pyriformis muscle emerging from under cover of the sacrum comes into sight. The muscular fibres may now be raised from the surface of the great sacro-sciatic ligament and separated from the side of the coccyx. In doing this, care should be taken to preserve the three sacral cutaneous nerves intact, in order that they may be subsequently traced to their origins. As the surface of the great sacro-sciatic ligament is gradually laid bare, a number of small arteries (the coccygeal branches of the sciatic artery) will be seen piercing it and immediately sinking into the substance of the gluteus maximus. These cannot be retained. It is necessary to sever them in order that the muscle may be freed. The perforating branch of the fourth sacral nerve, which winds round the lower border of the gluteus maximus near the coccyx, must also be remembered and traced to the great sacro-sciatic ligament which it will be seen to pierce.

The gluteus maximus is now completely separated from the parts from which it arises, but it cannot be thrown downwards towards its insertion. It is still tied to its place by the blood-vessels and nerves which enter its deep surface. These are (1) the branches of the *superficial division of the gluteal artery* which we have already seen above the level of the pyriformis ;

(2) branches of the *sciatic artery* and the *inferior gluteal nerve* below the level of the pyriformis. The veins may at once be removed, but the arteries and nerves must be systematically cleaned as they come into view, and traced into the substance of the *gluteus maximus*. Finally, to allow of the complete reflection of the *gluteus maximus*, these vessels and nerves must be cut, and it is advisable to leave in connection with the cut end of each a small portion of muscle-substance in order that they may be readily recognised in the further steps of the dissection. The whole muscle may now be thrown forwards, and after a little dissection an admirable view is obtained of its insertion. Piercing the lower part of this there will be seen a few small twigs of the first perforating artery—a branch of the *profunda femoris*.

In the case of the right limb the procedure adopted in reflecting the *gluteus maximus* is the same as detailed above, with this exception, that we begin by detaching it from the coccyx and great sciatic ligament and work upwards towards the ilium.

Although we have recommended that the *gluteus maximus* should be reflected from above downwards, it is right to mention that an equally instructive view of the subjacent parts may be obtained by detaching it from its insertion and throwing it upwards towards its origin. The senior student would do well to adopt this method.

Bursæ under cover of the Gluteus Maximus.—*Two bursæ* are found in relation to the insertion of the *gluteus maximus*. The *one*—a large loose sac—is interposed between the aponeurosis, into which the upper part of the muscle is inserted and the great trochanter of the femur. It allows the bone to play freely on the deep surface of the muscle. The *second bursa* lies immediately below this and in front of the part of the muscle which is inserted into the gluteal ridge of the femur. A slight touch of the knife is sufficient to open it, and then the glistening tendon of the *vastus externus* comes into view. The bursal sac intervenes between this tendon and the aponeurotic insertion of the *gluteus maximus*.

A *third bursa* is situated between the *gluteus maximus* and the *tuber ischii*. In all probability this has already been explored by the dissector of the perineum. It lies over the inferior aspect of the bony prominence, and is interposed more between the tough superficial fascia and the bone, than between the muscle and the bone.

Dissection.—On the *second day* the dissector undertakes the dissection of the remaining structures which are displayed by the reflection of the *gluteus maximus*. The vessels and nerves which have been partially exposed in the previous day's dissection must now be followed up towards the pelvis, and the remaining vessels and nerves, together with the muscles, must be defined and cleaned by removing the loose areolar tissue which covers and passes between them.

Parts under cover of the Gluteus Maximus.—As we

proceed from the dorsum ilii downwards towards the tuber ischii and the back of the thigh, the following muscles may be recognised:—(1) The gluteus medius lying over the




FIG. 53.—Dissection of the Gluteal Region. The Gluteus Maximus, Gluteus Medius, and the Quadratus Femoris have been reflected.

greater part of the dorsum ilii; (2) the piriformis, issuing from the pelvis through the great sacro-sciatic foramen; (3) the tendon of the obturator internus coming through the small sacro-sciatic foramen, with the gemellus superior attached to its upper border and the gemellus inferior to its lower

border; (4) the quadratus femoris passing from the tuber ischii to the upper end of the femur; (5) the upper border of the adductor magnus. By separating the contiguous margins of the gemellus inferior and quadratus femoris widely from each other, and looking into the interval between them, the tendon of the obturator externus will be revealed as it passes round the neck of the femur to reach the digital fossa. By dealing similarly with the adjacent margins of the quadratus femoris and the adductor magnus, the small trochanter of the femur will be exposed. Lastly, the origin of the hamstring muscles from the tuber ischii and the upper part of the vastus externus arising from the root of the great trochanter of the femur on its outer aspect should be noted.

In each interval formed by the adjacent margins of the muscles exposed, blood-vessels and nerves, or blood-vessels alone, are to be found.

Before proceeding to the dissection of these, however, it is well that the student should renew his acquaintance with the skeletal peculiarities of this region. Let him obtain a dried pelvis with the ligaments *in situ*, and study carefully the position and boundaries of the great and small sciatic notches, and how they are converted into foramina by the small and great sacro-sciatic ligaments. Through these foramina most important structures issue from the interior of the pelvis into the gluteal region.

In the interval between the contiguous margins of the gluteus medius and the pyriformis muscles, the *gluteal artery* and the *superior gluteal nerve* issue from the pelvis through the great sacro-sciatic foramen. In the interval between the pyriformis and the gemellus superior, two arteries and six nerves must be looked for as they emerge through the lower part of the sacro-sciatic foramen, viz. :—

Arteries,	{	1. Sciatic.
	{	2. Internal pudic.
	{	1. Great sciatic.
	{	2. Small sciatic.
Nerves,	{	3. Internal pudic.
	{	4. Inferior gluteal.
	{	5. Nerve to the obturator internus.
	{	6. Nerve to the quadratus femoris.

The huge great sciatic nerve, together with the sciatic artery and small sciatic nerve, proceed downwards in the hollow between the great trochanter of the femur and the tuber ischii.

In the interval between the gemellus inferior and the

quadratus femoris, the small *ascending terminal branch* of the *internal circumflex artery* will be seen, whilst between the contiguous margins of the quadratus femoris and the adductor magnus the larger *transverse terminal branch* of the same artery makes its appearance.

Inferior Gluteal Nerve (nervus glutæus inferior).—This is the nerve of supply to the gluteus maximus. It springs from the sacral plexus, and enters the gluteal region through the lower part of the great sacro-sciatic foramen. During the reflection of the gluteus maximus it has been seen to break up into numerous twigs which enter the deep surface of the muscle.

Sciatic Artery (arteria glutæa inferior).—The sciatic artery, which issues from the pelvis through the great sacro-sciatic foramen below the pyriformis muscle, proceeds downwards with the sciatic nerves under cover of the gluteus maximus. Finally reaching the lower border of that muscle, it is continued as a fine cutaneous twig to the back of the thigh, in company with the small sciatic nerve. It gives off numerous branches in the gluteal region. Of these the large muscular offsets to the gluteus maximus, and the cutaneous twigs that accompany the branches of the lesser sciatic nerve which turn round the lower border of that muscle, have been already studied. The following three branches remain to be examined:—(1) the *coccygeal branch*, which passes inwards between the greater and lesser sacro-sciatic ligaments to reach the integument and fascia in the region of the coccyx; a number of twigs derived from this branch have been previously noticed piercing the greater of the two ligaments and ending in the gluteus maximus; (2) *comes nervi ischiadici*, a minute artery, which runs downwards on the great sciatic nerve and finally penetrates into its substance; (3) the *artery to the quadratus femoris*, which accompanies the nerve to that muscle, and will be found lying on the innominate bone under cover of the great sciatic nerve.

In a well-injected body the anastomosis between the sciatic artery, the two terminal branches of the internal circumflex, and the first perforating artery may be made out.

Small Sciatic Nerve (nervus cutaneus femoris posterior).—This arises from the sacral plexus within the pelvis. After escaping through the great sacro-sciatic foramen it extends downwards with the sciatic artery under cover of the gluteus

maximus. Reaching the lower border of this muscle, it proceeds vertically downwards on the back of the thigh, immediately subjacent to the deep fascia. It will afterwards be traced to the posterior aspect of the calf of the leg.

In the gluteal region it gives off several cutaneous branches, viz.—(1) twigs which wind round the lower border of the gluteus maximus to supply a limited area of the skin of the buttock; (2) a few twigs to the skin on the inner side of the thigh; and (3) the long pudendal nerve of Sæmmerring.

The *long pudendal nerve* turns inwards round the origin of the hamstring muscles to reach the perineum.

Great Sciatic Nerve (*nervus ischiadicus*).—The great sciatic, the largest nerve in the body, comes from the sacral plexus, and enters the gluteal region through the lower part of the great sacro-sciatic foramen. At first it has the form of a flattened band, but soon it becomes oval or round, as seen in section. Covered by the *gluteus maximus*, the *great sciatic nerve* traverses the gluteal region in the interval between the great trochanter of the femur and the *tuber ischii*. From above downwards it lies on the innominate bone (at the lower margin of the great sciatic notch), the tendon of the obturator internus with its two gemelli muscles, the quadratus femoris, and the adductor magnus. In this region it does not, as a rule, give off any branch, but occasionally the nerves to one or more of the hamstring muscles issue from the main trunk as high as the level of the quadratus femoris.

The great sciatic nerve frequently escapes from the pelvis in the form of two trunks (the two divisions into which as a rule it divides lower down, viz., the internal and external popliteal nerves) which enclose between them a portion of the pyriformis muscle.

Dissection.—The student should flex the knee and raise it on a block in order to relax the great sciatic nerve. By pulling this great nerve-trunk outwards, the dissector will expose the nerve to the quadratus femoris lying directly upon the innominate bone. Internal to this he will find the pudic vessels and nerve with the nerve to the obturator internus crossing the spine of the ischium. These structures require to be carefully cleaned. The twig from the nerve to the obturator internus to the gemellus superior is especially liable to injury. The dissection will be improved by scraping off the periosteum from the small area of bone which is in relation to the above-mentioned vessels and nerves.

Pudic Vessels and Nerve, and the Nerve to the Obturator Internus.—These structures emerge from the great sacro-sciatic foramen below the pyriformis, and are only exposed in

the present dissection for a very short part of their course. They pass out of view by entering the lesser sacro-sciatic foramen. The *nerve to the obturator internus* is placed most externally. It lies on the base of the ischial spine, and furnishes a twig to the gemellus superior. The *internal pudic artery* (arteria pudenda interna), with a companion vein on each side, crosses the tip of the spine. The *internal pudic nerve* (nervus pudendus) is placed most internally, and lies on the lesser sacro-sciatic ligament close to its attachment to the spine. In some cases, however, the pudic nerve unites in a plexiform manner with the nerve to the obturator internus, so that the whole, or a part, of it may lie external to the pudic vessels.

External Rotator Muscles of the Thigh.—Under this heading we include the piriformis, the obturator internus, the gemelli, the obturator externus, and the quadratus femoris. They are all inserted into or in the neighbourhood of the great trochanter of the femur, and they are applied to the posterior surface of the capsule of the hip-joint.

The *piriformis* arises within the pelvis from the three middle pieces of the sacrum, and slightly from the upper margin of the great sciatic notch of the innominate bone. The sacral origin cannot be seen at present, but the iliac origin should be made out. After passing through the great sacro-sciatic foramen, the muscle is directed downwards, outwards, and forwards. Its fleshy belly rapidly tapers and ends in a rounded tendon, which crosses the common tendon of the obturator internus and gemelli, and is inserted into a small impression on the highest part of the great trochanter of the femur (Fig. 66, p. 217). It is closely adherent to the subjacent obturator tendon for some distance. The piriformis is supplied by branches from the *third and fourth sacral nerves*.

The *obturator internus* and *gemelli* together constitute a tricipital muscle with one intra-pelvic belly (obturator internus), and two extra-pelvic bellies (gemellus superior and inferior). The common tendon of this tricipital muscle is inserted into an impression on the upper part of the great trochanter of the femur immediately in front of the insertion of the piriformis (Fig. 66, p. 217).

The *gemellus superior* arises from the spine of the ischium at the upper margin of the lesser sciatic notch. Its fibres

pass outwards along the superior border of the tendon of the obturator internus, and are inserted obliquely into that tendon. The *gemellus inferior* arises from the tuberosity of the ischium at the lower margin of the lesser sciatic notch, and is inserted into the inferior border of the obturator tendon, in a similar manner to the *gemellus superior*. Close to their origins the gemelli meet under cover of the obturator tendon, and form a fleshy bed, on which it lies; near the trochanter the fibres of the gemelli overlap the obturator tendon, and tend to cover its superficial surface.

The *tendon of the obturator internus* should be freed from the gemelli for some little distance from its point of exit from the small sacro-sciatic foramen. It may then be divided and raised from the bed in which it lies. Its deep surface will be seen to consist of four or five rounded slips separated by deep grooves or furrows. The surface of the small sciatic notch on which this tendon glides is coated with smooth cartilage, which is raised into ridges corresponding to the grooves on the surface of the tendon. A large synovial bursa is interposed, which still further facilitates the play of the tendon round the notch.

The *quadratus femoris* lies between the *gemellus inferior* and the *adductor magnus*. It is a flat oblong muscle which arises from the outer border of the tuber ischii, and proceeds horizontally outwards to gain insertion into the tubercle of the quadratus and into a line which extends downwards on the back of the femur for two inches below this (Fig. 68, p. 223).

Dissection.—The nerve to the *quadratus femoris* should now be traced to its termination. This can be done by reflecting the two gemelli muscles under which it runs. When followed as far as the inferior gemellus, care should be taken to secure the little twig it gives to that muscle. Lastly, reflect the *quadratus femoris* by detaching it from the femur and throwing it towards the ischial tuberosity. By this dissection not only is the whole length of the nerve to the *quadratus femoris* exposed, but also a considerable portion of the posterior aspect of the capsule of the hip-joint is laid bare, and the obturator externus muscle and the termination of the internal circumflex artery are brought into view.

Nerve to the Quadratus Femoris.—This small nerve runs vertically downwards on the innominate bone and passes successively under cover of the following structures: the great sciatic nerve, the *gemellus superior*, the tendon of the obturator internus, the *gemellus inferior*. It gives the nerve of supply

to the gemellus inferior and a twig to the hip-joint, and ends by sinking into the deep surface of the quadratus femoris.

Obturator Externus.—This muscle can now be observed winding round the neck of the femur and finally ending in a rounded tendon which is implanted into the digital fossa of the femur (Fig. 68, p. 223). Its origin will be seen at another time.

Internal Circumflex Artery (*arteria circumflexa femoris medialis*). This vessel comes to an end at the upper border of the adductor magnus by dividing into its ascending and transverse terminal branches. The *ascending branch* runs obliquely upwards and outwards under cover of the quadratus femoris and upon the surface of the obturator externus. Its terminal branches ramify in the neighbourhood of the digital fossa, where they anastomose with twigs from the sciatic and gluteal arteries. The *transverse branch* passes backwards between the quadratus femoris and the adductor magnus. It anastomoses with the terminal twig of the middle division of the external circumflex artery, which in a well-injected subject will be noticed appearing from midst the fibres of the vastus externus at its upper part. An arterial circle is thus completed around the upper part of the femur which communicates above with the sciatic artery and below with the first perforating artery. This series of inosculation is sometimes spoken of as the *crucial anastomosis* of the thigh.

Dissection.—The dissector has now examined all the structures in the gluteal region which lie below the level of the pyriformis. He should, in the next place, turn his attention to that portion of the dissection which lies above the level of that muscle. Here are found a number of parts in close relation to the dorsum ilii. These are the gluteus medius, the gluteus minimus, and the tensor fasciæ femoris muscles, together with the blood-vessel and nerve which supply them, viz., the gluteal artery and the superior gluteal nerve.

The gluteus medius muscle is only covered in its hinder part by the gluteus maximus. In front it is invested by the dense aponeurotic layer already referred to. This fascia must be removed in order that a satisfactory view of the muscle may be obtained. It will then become evident that numerous fleshy fibres arise from the deep surface of the fascia. Care must be taken not to injure the origin of the tensor fasciæ femoris which overlaps the anterior part of the gluteus medius, and is partially adherent to it.

Gluteus Medius.—The gluteus medius arises from that part of the dorsum ilii which is bounded above by the superior curved line and the anterior four-fifths of the crest of the ilium, and below by the middle curved line (Fig. 52, p. 159); it also

derives fibres from the strong fascia which covers its upper and anterior part. The fibres converge to form a flattened band, partly fleshy and partly tendinous, which is inserted into an oblique line on the outer aspect of the great trochanter of the femur, as well as into the surface immediately above it.

Dissection.—The gluteus medius must now be reflected. This dissection is complicated by the fact that in its upper and anterior part the gluteus medius is partially blended with the subjacent gluteus minimus and the tensor fasciæ femoris. Begin by rotating the limb well outwards. Then seizing the gluteus maximus with left hand, pull it well outwards, and divide the glistening aponeurosis into which it is inserted for two or three inches in a downward direction. This will bring very conspicuously into view the upper part of the vastus externus. Next, grasp the cut edge of the fascia lata from which the gluteus maximus has been separated, and, dragging it forcibly outwards, dissect in the interval between it and the gluteus medius. The tensor fasciæ femoris, which is intimately associated with this portion of the fascia lata, is pulled outwards with it, and the deep surface of that muscle clothed by a strong deep lamella of fascia comes into view. Very little dissection is required to expose its nerve of supply—a branch from the superior gluteal—which emerges from the anterior border of the gluteus minimus, and sinks into its deep surface. An artery will also be noticed ramifying on the deep surface of the tensor fasciæ femoris; this is the ascending branch of the external circumflex. Seeing that the anterior borders of the gluteus medius and gluteus minimus are adherent, it is well to separate them from behind forward by introducing the fingers between their posterior borders. When the gluteus medius is completely isolated, it may be divided about two inches above the great trochanter of the femur, and the two portions thrown respectively upwards and downwards. A small bursa between the muscle and the upper part of the great trochanter will thus be brought into view, and the exact insertion of the tendon will be rendered evident. As the upper part of the muscle is raised, a number of vessels and nerves between it and the gluteus minimus will be exposed. These must be carefully cleaned and followed to their destinations. They are derived from the gluteal artery and the superior gluteal nerve.

Gluteal Artery (arteria glutæa superior).—This is a large vessel which escapes from the pelvis through the upper part of the great sacro-sciatic foramen above the level of the pyriformis.

Immediately after its exit, it divides into a superficial and a deep division. The *superficial division* has been already seen during the reflection of the gluteus maximus. It is distributed to the deep surface of that muscle, and is placed between it and the gluteus medius.

The *deep division* bifurcates close to its origin into a superior and an inferior branch; both of these lie between the gluteus medius and minimus. The *superior branch* follows

accurately the middle curved line on the dorsum ilii, and at the anterior superior spine terminates by anastomosing with the superficial and deep circumflex iliac arteries, and with the ascending branch of the external circumflex. The latter has already been noticed passing upwards under cover of the tensor fasciæ femoris. The *inferior branch* runs downwards and forwards towards the great trochanter. It gives twigs to the two gluteal muscles between which it lies, and some terminal offsets to the hip-joint.

Superior Gluteal Nerve (nervus glutæus superior).—The superior gluteal nerve emerges from the pelvis in company with the gluteal artery, and passing forwards between the gluteus medius and minimus, gives branches to both these muscles. Its terminal branch pierces the anterior fibres of the gluteus minimus, and ends in the tensor fasciæ femoris.

Gluteus Minimus.—This muscle arises from the broad area on the dorsum ilii, which is included between the middle and inferior curved lines (Fig. 52, p. 159). The muscular fibres pass gradually into an aponeurotic tendon, which covers the superficial surface of the lower part of the muscle. This tendon as it descends narrows into a flattened band, which is inserted into a special impression on the anterior aspect of the great trochanter of the femur (Fig. 66, p. 217). It is intimately connected at its insertion with the capsule of the hip-joint.

Parts under cover of the Gluteus Minimus.—The last step in the dissection of the gluteal region consists in the reflection of the gluteus minimus muscle. It must be detached from its origin and thrown downwards. Three objects are revealed by this dissection—(1) the capsular ligament of the hip-joint; (2) a bursa which intervenes between the tendon of the muscle and the great trochanter; (3) the reflected tendon of the rectus femoris.

The *capsular ligament* will be seen to be only loosely attached to the posterior aspect of the neck of the femur, but very firmly to the acetabular brim. The *synovial bursa* should be opened and examined. The *reflected tendon* of the *rectus femoris* occupies a groove situated just above the upper margin of the acetabulum. It is partially concealed by some fibres of the capsular ligament, which are prolonged upwards over it. It should be cleaned by repeatedly drawing the point of the knife over it in a direction parallel to its fibres.

POPLITEAL SPACE.

Before the muscles on the back of the thigh are disturbed, it is well to dissect the popliteal space. In this way the boundaries of the space are maintained in position during the examination of the structures which lie within it.

During the dissection of the popliteal space the following structures are brought into view :—

1. Superficial fascia.
2. External saphenous vein.
3. Small sciatic nerve.
4. Popliteal fascia.
5. Muscles which bound the space.

{	Biceps. Semitendinosus. Semimembranosus. Gastrocnemius. Plantaris.
---	--
6. The internal and external popliteal nerves and their branches.
7. The popliteal artery and vein and their branches.
8. A few lymphatic glands.
9. A slender branch from the obturator nerve.
10. The popliteus muscle.

Surface Anatomy.—The space which lies immediately above the knee-joint, and between the hamstring muscles, is termed the ham. It is depressed when the knee is flexed, but forms a slight prominence when the joint is fully extended. By flexing the knee and pressing deeply into the interval between the hamstrings, the (injected) popliteal artery may be distinguished, and its pulsations can usually be distinguished in this situation in the living subject. With the limb in the same position, the tendon of the biceps on the outer side of the space is distinctly seen as it passes down to its insertion into the head of the fibula. This bony prominence lies behind and a little below the most projecting part of the outer tuberosity of the tibia, and by pressing deeply between the fibula and the external condyle of the femur, the cord-like external lateral ligament can be distinguished. By slightly flexing the knee-joint and abducting the limb, the rounded tendon of the adductor magnus may be detected on the inner side of the limb and traced downwards to the adductor tubercle. This bony projection is placed on the femur at the point where the internal supracondylar ridge

joins the upper and back part of the inner tuberosity, and is an important landmark, inasmuch as it indicates the level or the plane of junction between the lower epiphysis and the shaft of the femur. The external popliteal nerve may be felt as it crosses the outer side of the neck of the fibula, just before it pierces the peroneus longus muscle. In muscular subjects, on the upper part of the back of the leg, the two heads of the gastrocnemius form prominent objects.

The back of the thigh presents a smooth, rounded surface. In thin subjects indications of the bellies of the hamstring muscles may be seen.

Reflection of Skin.—Before beginning the dissection a good-sized block should be placed under the knee so as to support the limb and render the muscles which bound the space tense. *Incisions*—(1) a vertical incision along the middle line of the limb, beginning about five inches above, and terminating about four inches below, the bend of the knee; (2) a transverse incision at the upper end of the mesial incision; (3) a transverse incision at the lower extremity of the mesial incision. The two transverse incisions should extend almost half-way round the limb.

Two flaps of skin are thus mapped out, and these must be raised and thrown, the one inwards and the other outwards.

Superficial Fascia—External Saphenous Vein—Branches of Small Sciatic Nerve.—The fatty layer upon which the skin rests is now brought into view, and the cutaneous nerves and vessels must be secured. First look for a small nerve—a *branch of the small sciatic*—which passes downwards over the space near the middle line, and, when this is found, dissect out the *external saphenous vein*. This vessel ascends in the middle line of the leg, and on tracing it upwards it will be found to disappear from view by piercing the deep fascia, and entering the lower part of the popliteal space. The *terminal branch* of the *small sciatic nerve* pierces the popliteal fascia at the lower part of the space, and here it will be seen lying close to the external saphenous vein.

In removing the superficial fascia care must be taken of the deep popliteal fascia, which is somewhat thin.

Popliteal Fascia.—Although thin, the deep fascia possesses considerable strength, owing to the transverse fibres which are interwoven amidst its proper aponeurotic fibres. In removing this fascia the dissector will notice that it is firmly attached on each side to the tendons of the muscles which bound the popliteal space. Above, it is continuous with the fascia lata of the thigh.

Before opening up the popliteal space the dissector is recommended to read the two following paragraphs, which deal generally with its contents and boundaries.

Contents of the Space.—The principal objects within the popliteal space are the *popliteal artery* and *vein* with their branches. They are placed deeply in the space, and in close contact with each other—the vein being superficial to the artery throughout. The *two popliteal nerves*—external and internal—also traverse the space. With the exception of the small sciatic nerve which descends immediately subjacent to the deep fascia, the *internal popliteal nerve* is the most superficial structure in the popliteal space. It lies over the popliteal vessels, and is readily found by separating the adipose tissue in the middle line of the space. The *external popliteal nerve* will be exposed by dissecting along the upper and outer boundary of the space. It lies under shelter of the biceps muscle. Both of these large nerves give off branches. The majority of these are easily secured and readily followed. The articular twigs, however, are very delicate, and great care is required in their dissection.

In intimate relation to the popliteal artery is the *geniculate branch of the obturator nerve*. It descends in close apposition with the coats of the artery. As the fat is being cleared out from the space the dissector will not fail to observe some small *lymphatic glands* in relation to the great vessels.

Boundaries.—The popliteal space is diamond-shaped. Above and to the outside it is bounded by the *biceps muscle*; whilst above and to the inside are the *semitendinosus* and the *semimembranosus muscles*, the former lying upon the surface of the latter. On the inner side of the knee and in front of the semimembranosus, the *gracilis*, *sartorius*, and the tendon of the *adductor magnus*, can be exposed. Below, the space is bounded by the converging heads of the *gastrocnemius*. In the formation of the lower and outer boundary, the outer head of the *gastrocnemius* will be seen to be assisted by the small *plantaris muscle*.

Dissection.—In cleaning the muscles which bound the popliteal space there are certain points to be attended to. In the case of the outer head of the *gastrocnemius*, care must be taken not to remove the *nervus communicans fibularis*, which passes downwards and inwards upon its surface. In the groove between the heads of this muscle will be seen the *nervus communicans tibialis*. Further, the dissector must not overlook

the synovial bursa which intervenes between the tendon of the semi-membranosus and the inner head of the gastrocnemius. This bursa sometimes communicates with a second synovial sac, which will be brought into view by lifting the inner head of the gastrocnemius from the internal condyle of the femur.

The dissection may be carried in a forward direction on the inner aspect of the limb a little beyond the inner boundary of the space, in order to expose the superficial division of the anastomotic artery, the internal saphenous nerve and vein, and the posterior division of the internal cutaneous nerve. The *internal saphenous nerve* accompanied by the

superficial part of the anastomotic artery will be found under cover of the sartorius. They afterwards come to the surface at its posterior border. The *internal saphenous vein* ascends on the surface of that muscle, whilst the *posterior division of the internal cutaneous nerve* courses downwards along the posterior border of the same muscle, and comes to the surface a short distance behind the internal saphenous nerve. Properly speaking, these structures belong to the thigh, but it is convenient to secure them at this stage. They will be afterwards noticed more fully. When the boundaries of the space are thoroughly defined and cleaned, the contents should be dissected by removing the soft fat which surrounds them.




FIG. 54.—Dissection of the Right Popliteal Space.

The dissection of the space should be carried out over the entire area at the same time. The heads of the gastrocnemius muscle, therefore, should be well separated from each other. It is here that the dissection becomes tedious, because the numerous branches of the nerves and vessels to the muscles on the back of the leg require time and care for their dissection.

The floor of the space must now be cleaned. Scrape the fatty tissue from the popliteal surface of the femur with the handle of the knife.

It is during this stage of the dissection that the articular branches of the popliteal artery are liable to injury, as they lie in close contact with the floor. Be especially careful not to injure the azygos articular artery which pierces the posterior ligament of the knee-joint, and the superior

articular arteries which wind round the femur, immediately above the condyles. The fascia covering the popliteus muscle should be left in position.

Popliteal Space as seen in a Section through the Frozen Knee.—The diamond-shaped space on the back of the knee-joint which is brought into view by dissection, differs widely from the condition which is observed when transverse sections are made through this part of the frozen limb (Fig. 55). Before the integuments and fasciæ are removed all the parts are tightly braced together, and the popliteal space is merely represented by a small intermuscular interval between the lower parts of the hamstring muscles, where they are separated from each other by the condyles of the femur. The space in this condition is rather under an inch wide at its broadest part. The popliteal artery, therefore, which traverses the space, is covered by muscles throughout its whole course, with the exception of a very small part immediately above the knee-joint.




FIG. 55.—Transverse section through the Popliteal Space of the Right Lower Limb.

Floor of the Space.—The floor is formed from above downwards by—(1) the popliteal surface of the femur; (2) the posterior ligament of the knee-joint; and (3) by the strong fascia which covers the popliteus muscle.

Small Sciatic Nerve (nervus cutaneus femoris posterior).—The small sciatic nerve enters the popliteal space at its upper angle, and proceeds downwards immediately subjacent to the popliteal fascia. It gives one or two twigs through the fascia to the skin, and finally pierces the fascia in the lower part

of the space. Its terminal twigs are distributed to the skin over the upper part of the calf of the leg.

Internal Popliteal Nerve.—This nerve enters the popliteal space by emerging from under cover of the biceps muscle, and runs vertically downwards so as to bisect the space longitudinally. It is one of the two terminal branches of the great sciatic nerve, and it arises about the middle of the thigh. At the lower border of the popliteus muscle it becomes continuous with the posterior tibial nerve. The superficial position of the internal popliteal nerve has already been referred to. At first upon the outer side of the popliteal vessels it crosses them superficially, and in the lower part of the space it is placed upon their inner side. Its *branches* may be classified into cutaneous, muscular, and articular.

The *nervus communicans tibialis* is its cutaneous branch. It arises about the middle of the space, and proceeds downwards in the furrow between the two heads of the gastrocnemius. It will afterwards be seen to unite with the *nervus communicans fibularis*, a little below the middle of the calf of the leg, to form the external saphenous nerve.

The *muscular branches* supply both heads of the gastrocnemius, the plantaris, the soleus, and the popliteus: they come off in the lower part of the space. The branch to the popliteus requires special notice. It arises lower down than the others, and crosses the superficial surface of the popliteal artery to reach the outer side of that vessel. It then runs downwards on the posterior surface of the popliteus muscle, and gains its deep or anterior surface by winding round its lower border. This will be better seen when the muscle itself is dissected.

The *articular branches* are three in number. They are given off by the internal popliteal nerve in the upper part of the space, and they accompany the azygos and the two internal articular arteries. That which accompanies the internal inferior articular artery is larger than the other two, and can be easily discovered as it runs along the upper border of the popliteus muscle.

External Popliteal Nerve.—This is the smaller of the two terminal branches of the great sciatic, and it ends on the outer side of the neck of the fibula by dividing into the anterior tibial and the musculo-cutaneous. It does not

traverse the entire length of the popliteal space. It runs downwards and outwards along the inner side of the biceps, and leaves the space by following closely the tendon of this muscle. It now lies in the interval between the outer head of the gastrocnemius and the biceps, and finally turning forwards round the neck of the fibula, it ends under cover of the upper part of the peroneus longus. It gives off cutaneous and articular branches.

The *cutaneous branches* are two in number, viz., the *nervus communicans fibularis*, and one to the skin on the anterior and outer aspect of the leg in its upper part. They frequently take origin by a common trunk. The *nervus communicans fibularis* arises from the external popliteal nerve in the popliteal space, and is continued downwards over the outer head of the gastrocnemius. It ultimately unites with the *nervus communicans tibialis*, to form the external saphenous nerve.

The *articular branches* are three in number. They accompany the external articular branches of the popliteal artery, and the anterior recurrent tibial branch of the anterior tibial artery. They are of small size, and difficult to dissect. The *recurrent articular nerve* springs from the termination of the external popliteal nerve, and will be dissected at a later stage.

Popliteal Artery (*arteria poplitea*).—The popliteal artery is the terminal part of the great arterial trunk of the lower limb. It begins at the opening in the adductor magnus, where it is continuous with the femoral artery, and it ends at the lower border of the popliteus muscle by dividing into the anterior and posterior tibial arteries. This division is at present hidden from view by the upper border of the soleus muscle, but it will be exposed in the dissection of the leg.

The course which the popliteal artery takes through the popliteal space is not straight. In the first instance it inclines obliquely downwards and outwards, so as to gain the middle of the space between the two condyles of the femur. From this point to its termination it takes a vertical course downwards. Throughout the greater part of its length it is placed deeply. In the upper part of the space it is covered by the semimembranosus, but when it gains the interval between the two condyles it is simply covered by the integuments and

fasciæ. This superficial part of the vessel is very short, however—not more than about an inch,—because it at once passes onwards between the two heads of the gastrocnemius, is crossed by the plantaris, and finally at its termination sinks under cover of the upper border of the soleus. Throughout its whole course the popliteal artery rests upon the floor of the




FIG. 56.—Popliteal Artery and its Branches.

popliteal space. In its upper part it is separated from the femur by some fatty tissue; then it crosses the posterior ligament of the knee-joint; and lastly it comes into contact with the fascia covering the popliteus muscle.

The *popliteal vein* is placed upon a more superficial plane, and crosses the artery. In the upper part of the space it is placed upon the outer side of the artery, whereas in the lower part it is situated upon its inner side. The two vessels, however, are in close association throughout, and are bound together by a dense fibrous sheath. The *internal popliteal nerve* is superficial to both vessels, and crosses the artery from without inwards; in the upper part of the space it lies a short distance to the

outer side of the artery, but in the lower part it lies on the inner side.

The *branches of the popliteal artery* are:—

1. Muscular.
2. Cutaneous.
3. Articular.

The *muscular branches* consist of an upper and a lower

set. The *upper branches* are distributed to the hamstring muscles near their insertions. The *lower branches*, termed the *sural arteries*, end chiefly in the two heads of the gastrocnemius; but small twigs also go to the soleus and plantaris.

The *cutaneous branch*, called the *superficial sural*, usually arises from one of the sural muscular branches, and supplies the integument over the upper part of the calf of the leg. It lies in the groove between the two heads of the gastrocnemius with the *nervus communicans tibialis*.

The *articular arteries* are five in number, viz., two superior, two inferior, and one median or azygos.

Superior Articular Arteries.—The two superior articular arteries spring from the main trunk as it passes between the condyles of the femur. One proceeds from each side of the popliteal, and they are called *internal* and *external*, according to the direction which they take. They will be found resting directly upon the back of the femur, and will be observed to incline slightly upwards, and then to wind round the bone immediately above the condyles. The external artery is the larger of the two. The student is apt to mistake a muscular branch for one or other of these vessels; but their close apposition to the femur should in all cases be sufficient to distinguish them.

The *superior external articular artery* (*arteria genu superior lateralis*) runs outwards under cover of the biceps, and disappears from the popliteal space by piercing the external intermuscular septum and entering the substance of the crureus muscle. The *superior internal articular* (*arteria genu superior medialis*) proceeds inwards under cover of the semimembranosus, and leaves the popliteal space by passing forwards under cover of the tendon of the adductor magnus to reach the deep surface of the vastus internus muscle.

Inferior Articular Arteries.—The two inferior articular arteries arise from the popliteal as it lies on the lower part of the posterior ligament of the knee-joint. The *inferior external articular artery* (*arteria genu inferior lateralis*) takes a transverse course outwards, under cover of the plantaris and outer head of the gastrocnemius, to gain a point on the outer side of the knee, immediately above the head of the fibula. It proceeds onwards under cover of the external lateral liga-

ment of the knee-joint. The *inferior internal articular artery* (arteria genu inferior medialis) takes an oblique course downwards and inwards, under cover of the inner head of the gastrocnemius, and along the upper border of the popliteus muscle, to gain the inner side of the tibia below the internal tuberosity. Here it turns forwards under cover of the internal lateral ligament of the knee-joint.

Azygos Articular Artery (arteria genu media).—This springs from the popliteal as it lies upon the posterior ligament of the knee-joint. It pierces this ligament to reach the synovial membrane.

Popliteal Vein.—The popliteal vein is formed near the lower border of the popliteus muscle by the union of the venæ comites of the anterior and posterior tibial arteries. It runs upwards through the popliteal space, and, entering Hunter's canal through the opening in the adductor magnus, it becomes the femoral vein. The relations which it presents to the popliteal artery have already been detailed. In addition to tributaries corresponding to branches of the artery, it receives the external saphenous vein, which has been seen piercing the popliteal fascia to join it. By slitting it open with the scissors the dissector will see that it possesses three (sometimes four) valves in its interior.

Obturator Nerve.—This minute nerve will be found lying upon the inner side of the popliteal artery. Trace it upwards, and it will be seen to enter the space by piercing the lower fibres of the adductor magnus; follow it downwards, and it will be observed to enter the knee-joint by penetrating the posterior ligament.

BACK OF THE THIGH.

The dissection of the back of the thigh must be completed on the fourth day. The following are the structures which are brought into view :—

1. Superficial fascia.
2. Cutaneous nerves.
3. Deep fascia.

- | | | |
|--------------|---|-------------------|
| 4. Muscles, | { | Biceps. |
| | | Semitendinosus. |
| | | Semimembranosus. |
| | | Adductor magnus. |
| 5. Nerves, | { | Small sciatic. |
| | | Great sciatic. |
| 6. Arteries, | | Four perforating. |

Reflection of Skin.—A vertical incision must be made in the middle line of the thigh through the belt of skin which still encircles the limb posteriorly. The two flaps can then be reflected, the one outwards and the other inwards.

Superficial Fascia—Cutaneous Nerves.—In the fatty superficial fascia thus brought into view cutaneous twigs from four sources must be looked for—(1) Along the *middle line* of the limb a few minute branches from the *small sciatic* may be discovered; (2) Towards the *outer side* of the thigh some twigs from the *external cutaneous nerve* may be detected; (3) Lastly, towards the *inner aspect* of the limb endeavour to find some offsets from the *internal cutaneous* and *obturator nerves*.

Deep Fascia.—On removing the superficial fascia the deep fascia will be observed to be exceedingly thin. It must now be turned aside, and in doing this be careful of the trunk of the small sciatic nerve, which passes down in the middle line of the limb immediately subjacent to the fascia.


Hamstring Muscles.—The hamstring muscles are three in number, viz., the biceps, the semitendinosus, and the semimembranosus. They stretch from the tuberosity of the ischium to the upper ends of the tibia and fibula. The *biceps* is recognised from its diverging outwards to form the outer and upper boundary of the popliteal space. The *semitendinosus* and *semimembranosus* extend downwards on the inner side of the posterior aspect of the thigh, the former on the superficial aspect of the latter.

In cleaning these muscles the dissector should proceed cautiously to work, otherwise he is certain to injure the arterial and nerve twigs which enter them. The latter may be easily secured by pulling upwards the upper part of the great sciatic nerve, and at the same time gently separating the muscles with the fingers.

Biceps Flexor Cruris (musculus biceps femoris).—The biceps arises by two heads—a *long*, or *ischial*, and a *short*, or *femoral*,—and is inserted chiefly into the head of the fibula. The *long head* arises from the ischium by a tendon which is common to it and the semitendinosus (Fig. 52, p. 159). This is implanted

into the inner of the two impressions which mark the upper part of the tuber ischii.

Some fibres from the great sacro-sciatic ligament are continued into it. The *short head* arises from the back of the femur below the insertion of the gluteus maximus, viz., from the outer lip of the linea aspera, from the upper half of the external supracondyloid ridge, and from the external intermuscular septum. Its parallel



fibres run obliquely downwards and outwards, and join the anterior and inner surface of the tendon of insertion. This tendon, on the outer aspect of the knee-joint, is split into an anterior and a posterior part by the external lateral ligament. Both are inserted into the head of the fibula in front of the styloid process, but the posterior slip gives an aponeurotic extension to the fascia of the leg, whilst the anterior part gives off a slip

FIG. 57.—Dissection of the Back of the Left Thigh.

(in some cases strong, but generally feeble) to the adjacent part of the outer tuberosity of the tibia.

Semitendinosus.—This muscle arises from the inner impression on the upper part of the tuberosity of the ischium by a tendon common to it and the long head of the biceps, and also by fleshy fibres directly from the bone (Fig. 52, p. 159). A narrow tendinous intersection appears on the posterior surface of the muscle about the middle of the thigh, and is directed obliquely downwards and outwards. The muscular belly ends in the lower third of the thigh, in a long cylindrical tendon




FIG. 58.—Front aspect of Upper Portions of Bones of Leg with Attachments of Muscles mapped out.

which passes downwards on the semimembranosus muscle. On the inner side of the knee the tendon bends forwards, crosses the internal lateral ligament of the knee-joint, and, becoming flattened, is inserted into the upper part of the internal surface of the shaft of the tibia, near the anterior border of that bone, and immediately below the tendon of the gracilis. From its lower border aponeurotic fibres pass into the deep fascia of the leg; its upper border is adherent to the gracilis for about half an inch from its insertion, and both tendons are concealed by the expanded insertion of the sartorius. A synovial bursa lies between the three tendons and the internal lateral ligament of the knee-joint.

Semimembranosus.—The semimembranosus muscle arises from the outer impression on the upper part of the tuberosity of the ischium (Fig. 52, p. 159). The tendon of origin is broad at its attachment to the bone, and narrows as it passes inwards beneath the origin of the biceps; it then expands again, and, passing downwards and inwards under cover of the semitendinosus, is folded in such a manner as to form a groove, in which the latter muscle lies. The tendon of insertion is chiefly inserted into the groove on the back of the internal tuberosity of the tibia, under cover of the internal lateral ligament of the knee-joint. Three additional attachments, however, require to be noted. These are effected by aponeurotic extensions from the tendon of insertion—(1) to the back of the knee-joint, forming a considerable part of the posterior ligament; (2) to the surface of the popliteus muscle, which is covered by the expansion; and (3) to the internal lateral ligament of the knee-joint.

Great Sciatic Nerve (nervus ischiadicus).—This large nerve commences at the lower border of the great sacro-sciatic foramen, and usually terminates about the middle of the thigh by dividing into the internal and external popliteal nerves. Its relations in the gluteal region have already been studied. In the thigh it lies on the posterior surface of the adductor magnus muscle, and is covered by the long head of the biceps. It gives branches to both heads of the biceps, to the semitendinosus, to the semimembranosus, and to the adductor magnus; the branches to the two last-named muscles arise by a common trunk. In a few cases it may be observed to give off a long articular twig, which enters the popliteal space and takes the place of the superior external articular nerve which, as a rule, comes from the external popliteal nerve.

Perforating Arteries (arteriæ perforantes).—Four perforating arteries, branches of the profunda femoris, will be found emerging from the surface of the adductor magnus muscle close to the linea aspera of the femur. They are called *first*, *second*, *third*, and *fourth*, according to the level at which they appear from above downwards. The *fourth*, is the terminal branch of the profunda artery of the thigh, and it makes its appearance about an inch above the opening in the adductor magnus muscle through which the popliteal artery enters the

popliteal space. The perforating arteries and their branches must be thoroughly cleaned, together with the apertures in the adductor magnus through which they pass. It will then be seen that they do not pierce the fleshy substance of the muscle. Prepared for each is a tendinous archway, and they reach the back of the thigh by passing between these and the *linea aspera*, to which the piers of the various arches are attached.

These openings lie in the same line, and are in all respects analogous to the large opening in the adductor magnus muscle for the popliteal artery. The result obtained is the same in each case. When the muscle contracts, the vessels are protected from pressure.

Emerging from the tendinous arches the perforating arteries wind round the back of the femur so as to gain its outer aspect, and reach the vastus externus in which they end. In this part of their course they pierce the short head of the biceps. The highest member of the series, which lies above the level of the femoral attachment of the biceps, pierces, as we have already seen, the insertion of the gluteus maximus.

Dissection.—To bring the adductor magnus muscle more fully into view, and at the same time to facilitate the process of cleaning its radiating fibres, it is well to reflect the hamstring muscles from their origins. First divide the conjoined tendon of the biceps and semitendinosus. This displays the precise origin of the semimembranosus, and when the dissector has again examined this under the present more advantageous circumstances, he should divide it also.

Anastomosis on the Posterior Aspect of the Limb.—In a well-injected subject a chain of anastomoses, in which every link is complete, can be traced from the gluteal region down the back of the thigh to the popliteal space. The present is the best time to study this. Commencing above, we find the gluteal artery anastomosing with the sciatic, and the sciatic with the internal circumflex. In the back of the thigh this chain is carried downwards by the internal and external circumflex arteries anastomosing with the first perforating, each perforating artery inosculating with the one below it, and lastly the lower perforating arteries effecting junctions with the muscular branches which the popliteal artery gives to the hamstrings.

FRONT OF THE THIGH.

The body is now turned round so as to lie on its back. The pelvis is supported by two blocks, and the lower limbs are stretched out at full length upon the table (Fig. 5, p. 16).

Surface Anatomy.—The anterior superior spine of the ilium should in the first place be recognised, and the crest of the ilium traced as it proceeds outwards and backwards from this. The boundary line between the front of the thigh and the region of the abdomen is formed by Poupart's ligament, which stretches from the anterior superior spine of the ilium to the spine of the pubis. Its course and position are marked on the surface by a faint groove. By running the finger along this when the thigh is fully extended the ligament may be felt. At its inner end the spine of the pubis should be determined, and then the finger may be carried inwards on the crest of the pubis to the symphysis pubis. The rami of the pubis and ischium, leading downwards and backwards to the tuberosity of the ischium, constitute the upper boundary of the thigh on its internal aspect, and their relation to the surface must therefore be ascertained. Below Poupart's ligament in the extended position of the thigh, there is a faint depression corresponding in position to Scarpa's triangle.

In the dissection of the front of the thigh, the skin is also reflected from the anterior aspect of the knee. The dissector should therefore take the present opportunity of studying the surface anatomy of this articulation. The patella forms a marked prominence in front of the joint. When the limb is extended and the extensor muscles on the front of the thigh are relaxed, the patella will be found to be freely movable when grasped between the finger and thumb. Note its change of position when the leg is flexed on the thigh at the knee-joint. It passes downwards, and comes to lie in front of the interval between the femur and tibia. The patellar surface of the femur can now be felt. The powerful ligamentum patellæ which passes vertically downwards from the patella to the anterior tuberosity of the tibia can be easily distinguished. The massive condyles of the femur should next be studied and compared. The internal condyle is the

more prominent of the two, and immediately above its tuberosity the adductor tubercle can be recognised. The articular interval between the condyles of the femur and the head of the tibia is not visible on the surface, but it can readily be felt by the finger. The three tuberosities of the tibia should likewise be studied, and the position of the head of the fibula on the posterior and lower aspect of the external tuberosity ascertained.

SUPERFICIAL DISSECTION.

This dissection comprises the examination of the following parts:—

1. Superficial fascia.
2. Internal saphenous vein, and its several tributaries.
3. Arteries, {
 - Superficial pudic.
 - Superficial epigastric.
 - Superficial circumflex iliac.
4. Lymphatic glands and vessels.
5. The saphenous opening.
6. Cutaneous nerves.
7. The fascia lata.
8. The bursa patellæ.

Reflection of Skin.—*Incisions.*—(1) From the anterior superior spine of the ilium along the line of Poupart's ligament to the symphysis pubis; (2) from the inner extremity of this line downwards, round the scrotum, and along the inner aspect of the thigh for four inches; (3) from the lower extremity of this vertical incision transversely outwards, across the front of the thigh, to the outer aspect of the limb (Fig. 5, p. 16).

The quadrilateral flap of skin thus traced out must be raised carefully from the subjacent superficial fascia and turned outwards.

Superficial Fascia.—The fatty superficial fascia which is now exposed is continuous with the corresponding layer on the front of the abdomen, and it is regarded by some anatomists as being composed of two layers. This subdivision we consider needless and artificial. In the lower part of the abdominal wall, above Poupart's ligament, it is true the superficial fascia presents two distinct strata—one a fatty layer continuous over Poupart's ligament, with the superficial fascia on the front of the thigh, and sometimes termed the *fascia of Camper*; the other, a deeper layer, firm and membranous and devoid of fat, called the *fascia of Scarpa*. As this latter fascial stratum is attached to the fascia lata

(deep fascia of the thigh), immediately below Poupart's ligament, it is necessary that it should receive some attention.

To demonstrate the fascia of Scarpa the dissectors of the lower limb and abdomen should work in conjunction with each other. A transverse incision should be made through the entire thickness of the superficial fascia on the front of the abdomen, from the anterior superior spine of the ilium to the middle line of the body. On raising the lower edge of the divided fascia the two layers can be easily distinguished. Insinuate the fingers between the fascia of Scarpa and the pearly-looking tendon of the external oblique muscle. Little resistance will be encountered, as it is only bound down by some lax areolar tissue. The fingers can be readily carried downwards behind the fascia of Scarpa as far as Poupart's ligament. Here it will be found that they can force their way no farther. The passage of the hand into the thigh is barred by the blending of the fascia of Scarpa with the fascia lata along an oblique line immediately below Poupart's ligament. At this level therefore it ceases to exist. The fatty superficial layer of Camper, however, as we have said, is continued onwards as the superficial fascia of the thigh.

When urine is effused under the superficial fascia of the anterior abdominal wall, the attachment of the fascia of Scarpa to the fascia lata prevents its passage downwards in front of the thigh.

Dissection.—In the superficial fascia blood-vessels, glands, lymphatic vessels, and nerves are embedded, and these must now be dissected out. First look for the large internal saphenous vein. It will be found extending up the thigh a little way internal to the middle line of the limb. Trace it upwards till it reaches a point about two inches from Poupart's ligament. At this point it dips through the deep fascia, and joins the femoral vein. It is not desirable to define the opening in the fascia lata through which it passes until a later stage of the dissection. Several tributaries join the internal saphenous vein at this point, and these should be dissected along with the small superficial arteries of the groin which accompany them.

The large lymphatic glands of the groin must also be dissected out from the fatty tissue in which they lie. In doing this care must be taken to preserve as many as possible of the minute thread-like lymphatic vessels which enter and leave the glands. A small artery and vein should also be traced to each gland.

Superficial Inguinal Vessels.—Three minute arteries, termed the superficial epigastric, the superficial external pudic, and the superficial circumflex iliac, pierce the deep fascia below Poupart's ligament, and radiate from each other for

the supply of the glands and integument of the groin. They all spring from the femoral artery immediately after it enters the thigh.

The *superficial external pudic* comes forward through the cribriform fascia (a thin fascial layer, which is spread over the saphenous opening), and runs inwards and upwards across the spermatic cord. It supplies the skin of the scrotum and penis.

The *superficial epigastric* turns upwards and leaves the thigh by crossing Poupart's ligament about its middle. It is distributed chiefly to the skin on the front of the abdomen.

The *superficial circumflex iliac* is very minute, and courses upwards and outwards along Poupart's ligament towards the anterior superior spine of the ilium.

The *veins* which accompany these arteries converge towards the saphenous opening and join the internal saphenous vein near its termination.

Lymphatic Glands and Vessels.—The disposition of the lymphatic glands into two groups will now be evident—an upper *inguinal group* along the line of Poupart's ligament, immediately below the attachment of Scarpa's fascia to the fascia lata, and a lower *femoral group*, which extends for a short way down the thigh along the line of the internal saphenous vein.

In a spare subject, or, better still, in a dropsical subject, the general arrangement of the lymphatic vessels may also be made out. To the femoral group of glands proceed the vessels of the lower limb; to the inguinal glands go the lymphatic vessels from the genitals, perineum, and the surface of the abdomen. These are termed the *afferent vessels*. In addition to these, numerous vessels pass between the various glands and connect them with each other. The lymphatic vessels which lead the lymph away from the glands are called the *efferent vessels*. A large number of these pass through the saphenous opening, others pierce the deep fascia. They join the glands which lie in relation to the femoral and external iliac arteries.

Dissection.—It requires an experienced dissector to display in a satisfactory manner the saphenous opening, or, in other words, the aperture in the deep fascia through which the saphenous vein passes to join the femoral vein. Begin by removing the lymphatic glands. In doing this bear in mind that the *crural branch* of the genito-crural nerve pierces the fascia lata in the middle line of the thigh about an inch or so below Poupart's ligament.

Take care also of the two divisions of the *middle cutaneous nerve*, which make their appearance in the same line about three inches below Poupart's ligament.

To define the saphenous opening, the dissector should commence by cautiously removing the superficial fascia from the fascia lata over the upper parts of the adductor longus and pectineus muscles. The deep fascia at this point is called the *pubic portion of the fascia lata*, and as it is cleaned, from within outwards, it will be observed to recede gradually from the surface and to be continued behind the femoral vessels. The clearly defined inferior cornu of the saphenous opening will now be brought into view, curving under the internal saphenous vein, and blending with the pubic portion of the fascia lata. The *cribriform fascia*, a thin and imperfect layer which is spread over the aperture, must be removed so as to display the outer boundary of the opening. In doing this take care not to injure the subjacent sheath of the femoral vessels to which it is more or less firmly attached. This dissection is artificial, seeing that the cribriform fascia is merely a continuation inwards of the outer lip of the opening. The outer boundary is usually very much broken up by the superficial branches of the femoral artery which pierce it, and its definition is a matter of some difficulty. In a spare subject, however, the line of demarcation between the *cribriform fascia* and the *iliac portion of the fascia lata* may be distinguished. The name "iliac portion" is given to that part of the fascia lata which lies external to the opening.

Saphenous Opening.—This is the aperture in the deep fascia through which the saphenous vein passes to effect its junction with the femoral vein. A thin fascia, called the *cribriform fascia*, is spread over the opening. This fascia has received the name of "cribriform," because it is pierced by the saphenous vein and by numerous lymphatic vessels. Some difference of opinion exists as to what this fascia really is. It is regarded by some as being a part of the superficial fascia, but it is more correct to look upon it as being a thin layer of fascia lata carried over the opening, or, in other words, a prolongation inwards of the outer margin of the opening.

The importance of the saphenous opening consists in the fact that it is through it that a femoral hernia makes its way to the surface. It is oval in shape and not more than half an inch in width; but it is at least one and a half inches long. Its inner boundary is formed by the receding *pubic portion* of the fascia lata, and lies on a deeper plane than the outer boundary. The outer boundary is crescentic, and is known as the *falciform edge* of the opening. It is formed by the *iliac portion* of the fascia lata. The *inferior cornu* of the falciform edge curves inwards under the saphenous vein, in the form of a very distinct process which joins the pubic part

of the fascia lata. The *superior cornu* (sometimes called Hey's ligament), not so well defined, sweeps inwards in front of the upper part of the subjacent femoral sheath, and joins the front of Gimbernat's ligament.

Reflection of Skin.—The next step in the dissection consists in reflecting the skin from the lower two-thirds of the front of the thigh, and also from the anterior aspect of the knee. This is effected by extending the vertical incision, which has already been made upon the inner aspect of the thigh downwards to the internal tuberosity of the tibia, and then carrying a transverse incision from the lower end of the vertical cut outwards over the front of the leg to its outer aspect. In raising the skin from the front of the knee take care not to injure the patellar plexus of nerves and the patellar bursa. In reflecting the integument from this extensive area, we have two objects in view—Firstly, the dissection of the cutaneous nerves and vessels of the thigh; and secondly, the examination of the entire extent of the fascia lata.

Internal Saphenous Vein (*vena saphena magna*).—The internal saphenous vein should be dissected in the superficial fascia to the lower limit of the area from which the skin has been reflected. It is the largest superficial vein of the lower limb. Taking origin on the dorsum of the foot, it extends upwards on the leg. On the inner side of the knee it will be seen to be placed very far back. As it reaches the thigh it inclines somewhat forwards, and runs upwards on the front and inner aspect of the limb to the saphenous opening in the fascia lata. Through this aperture it passes to join the femoral vein.

In its course along the thigh it receives several tributaries. Two of these are of large size, viz., an *anterior branch*, which collects the blood from the front and outer aspects of the limb, and a *posterior branch*, which performs a similar office for the posterior and inner aspects of the thigh. They both enter the internal saphenous vein near its termination. In addition to these, the *three small veins* corresponding to the superficial inguinal arteries converge towards the saphenous opening, and join the saphenous trunk as it disappears through it.

Cutaneous Nerves.—The cutaneous nerves are now to be looked for in the superficial fascia. The main stems are six in number, and are derived from two sources. *Three* come directly from the *lumbar plexus*, and *three* are branches of the *anterior crural nerve*:—

From lumbar plexus,	{	Ilio-inguinal.
		Crural branch of genito-crural.
		External cutaneous.

From anterior crural, { Middle cutaneous.
Internal cutaneous.
Long saphenous.

The *ilio-inguinal nerve* will be found as it escapes from the external abdominal ring in company with the spermatic cord. Its branches go for the most part to the scrotum, but some are distributed to the skin on the upper and inner side of the thigh.

The *crural branch* of the genito-crural nerve pierces the fascia a little way below Poupart's ligament, and to the outer side of the femoral artery. With a little care a communication between this nerve and the middle cutaneous may be made out. It supplies a limited area of skin on the upper part of the front of the thigh.

The *external cutaneous nerve* is distributed on the outer aspect of the thigh. It pierces the deep fascia in two parts. Of these, one—the *posterior division*—appears about two inches below the anterior superior iliac spine, and proceeds backwards and downwards. Some twigs of this nerve may be followed to the lower part of the gluteal region. The *anterior division* comes to the surface about two inches lower down. It is the larger of the two, and has a wide area of distribution. It extends as low as the knee-joint. Previous to its division the external cutaneous nerve lies in a prominent ridge of the fascia lata, which descends vertically from the anterior superior spine of the ilium. This may be split up to expose it.

The *middle cutaneous nerve* pierces the fascia lata in the middle line of the thigh about three or four inches below Poupart's ligament. It usually appears as two nerves which perforate the fascia at two points a short distance apart from each other. Both branches extend downwards as low as the knee, which they reach on its inner aspect.

The *internal cutaneous nerve*, following the example of the external cutaneous and the middle cutaneous, divides into two portions—an anterior and a posterior—which perforate the deep fascia on the inner aspect of the limb, and at some distance apart from each other. The *anterior division* makes its appearance through the fascia lata in the lower third of the thigh, in front of the internal saphenous vein. It descends towards the knee, and its terminal branches turn forwards and outwards in front of the patella. The *posterior*

division reaches the surface on the inner side of the knee, behind the long saphenous nerve, and proceeds downwards to supply the integument on the inner side of the upper part of the leg. But the main stem of the internal cutaneous nerve, before it divides, likewise sends a few twigs through the fascia lata to reach the skin on the upper and inner aspect of the thigh. These make their appearance along the line of the internal saphenous vein.

The *long saphenous nerve* becomes cutaneous on the inner side of the knee by perforating the fascia between the tendons of the sartorius and gracilis muscles. The guide to it is the superficial branch of the *anastomotic artery* which descends alongside of it. It follows the course of the internal saphenous vein into the leg. Before it pierces the fascia it gives off a patellar branch.

The *patellar branch* of the long saphenous nerve pierces the sartorius muscle and the fascia lata on the inner side of the knee, and turns outwards and forwards in front of the joint, below the level of the patella.

Four of the cutaneous nerves of the thigh have been noticed to send twigs to the skin over the knee-joint, viz., the anterior division of the external




FIG. 59.—Cutaneous Nerves on the Front of the Lower Limb.

cutaneous, the middle cutaneous, the anterior division of the internal cutaneous, and the long saphenous. These nerves communicate with each other and form an interlacement which is situated over the patella, the ligamentum patellæ, and upper part of the tibia. It is termed the *patellar plexus*.

On the inner side of the thigh two minute cutaneous nerve twigs sometimes make their appearance which do not belong to any of the above main cutaneous trunks. One appears below the ilio-inguinal nerve, and is a twig from the long pudendal branch of the small sciatic; the other pierces the deep fascia half-way down the inner side of the thigh, and comes from the obturator nerve.

Fascia Lata.—This is the name which is given to that portion of the general aponeurotic investment of the lower limb which clothes, and preserves the figure of, the thigh. It should be carefully cleaned by removing the remains of the superficial fascia. This being done, the dissector will be struck with the marked difference in strength which it shows on the outer and inner aspects of the thigh. Externally it is so dense and strong that it appears to be more tendinous than aponeurotic in its character. The reason of this is, that the tensor fasciæ femoris muscle and the greater portion of the gluteus maximus are inserted into it upon this side of the limb. The strong band thus formed goes under the name of the *ilio-tibial band*, from its being attached above to the crest of the ilium, and below, to the outer tuberosity of the tibia and to the head of the fibula. It acts as a powerful brace on the outer aspect of the limb, which in the erect posture helps to steady the pelvis, and at the same time keep the knee-joint firmly extended. Internally, the fascia lata is so exceedingly delicate and thin that the subjacent muscular fibres shine through it, and it is very apt to be removed with the superficial fascia unless care be exercised in the dissection.

Superiorly, around the root of the limb, the fascia lata is attached to Poupart's ligament and the bones of the pelvis. *Behind*, it is continuous with the gluteal aponeurosis, and through this it is fixed to the coccyx, sacrum, and crest of the ilium. On the *outer side*, it is attached to the crest of the ilium; and on the *inner side*, to the body of the pubis, the side of the pubic arch, and to the tuberosity of the ischium. *In front*, its upper attachment is complicated by the presence

of the saphenous opening. This aperture separates the fascia lata into an outer or iliac portion and an inner or pubic portion. This subdivision only extends downwards to the lower border of the saphenous opening. The *iliac portion* is attached along the whole length of Poupart's ligament. Its inner crescentic margin bounds the saphenous opening externally and forms its falciform edge. The superior cornu of this edge blends with Gimbernat's ligament, whilst its inferior cornu joins the pubic portion of the fascia lata. The *pubic portion* clothes the upper portions of the adductor longus and pectineus muscles. It recedes from the surface as it is traced outwards and passes behind the femoral vessels. In this situation it forms the posterior wall of the femoral sheath and is continuous above with the *fascia iliaca*¹ which covers the ilio-psoas muscle in the iliac fossa. To the inner side of the femoral vessels the pubic portion of the fascia lata is attached above to the ilio-pectineal line of the pubic bone. The *cribriform fascia*, as previously stated, is to be regarded as a thin piece of the fascia lata, stretched across the saphenous opening. Externally, it is continuous with the falciform edge of the iliac portion of the fascia; internally, it blends with the front of the pubic portion.




FIG. 60.—Diagram to show the arrangement of the three intermuscular septa and the three osteo-fascial compartments of the thigh. (After Turner.)

- a. Internal intermuscular septum.
- b. Posterior intermuscular septum.
- c. External intermuscular septum.

In the neighbourhood of the knee the fascia lata is continuous behind with the popliteal fascia, whilst on the lateral and front aspects of the joint it is attached to the various bony prominences and to the different tendons in this locality. Here it helps to strengthen and support the capsular ligament of the knee-joint.

Intermuscular Septa.—But the fascia lata has other offices

¹ The dissector must keep clearly before him the distinction between the *fascia iliaca* and the *iliac portion of the fascia lata*. The former is a part of the general aponeurotic lining of the abdominal cavity; the latter is a part of the aponeurotic investment of the thigh.

to perform besides that of forming a continuous investment for the thigh. From every part of its deep surface processes pass off which penetrate the limb and constitute sheaths for the muscles and other structures which compose it. Three of these are especially strong, and form distinct septa or partitions which reach the femur and are attached to the linea aspera on its posterior aspect. These partitions are termed the intermuscular septa, and are so disposed that they intervene between the three great groups of muscles in this region. The *external intermuscular septum* is placed between the extensor muscles in the front of the thigh and the hamstring muscles on the posterior aspect of the thigh; the *internal intermuscular septum* intervenes between the extensor muscles and the adductor muscles on the inner aspect of the limb; whilst the *posterior intermuscular septum*, weak and inconspicuous in comparison with the other two, is interposed between the adductor and the hamstring muscles. These partitions will be disclosed in the subsequent dissection. In the meantime, merely observe that the internal and the external septa show on the surface of the fascia in the lower part of the thigh as white lines. The thigh is in this manner divided into three osteo-fascial compartments, viz., an *anterior*, containing the extensor muscles and the anterior crural nerve; a *posterior*, holding the hamstrings and the great sciatic nerve; and an *internal*, for the adductors with the obturator nerve (Fig. 60).

Patellar Bursa.—This is situated upon the superficial aspect of the patella. Pinch up the fascia lata as it passes over this bone with the forceps, and make a transverse incision through the wall of the sac large enough to admit the finger. The bursa will then be seen to extend downwards for a short distance upon the ligamentum patellæ. It is usually intersected by fibrous bands and cords.

DEEP DISSECTION.

In this dissection, the following parts require to be examined:—

1. The femoral sheath.
2. Crural branch of genito-crural nerve.
3. External cutaneous nerve.

4. Sartorius muscle.
5. Anterior crural nerve and its branches.
6. Femoral vessels and their branches.
7. Ilio-psoas muscle.
8. Quadriceps extensor,

{	Rectus femoris.
	Vastus internus.
	Crureus and subcrureus.
	Vastus externus.
9. Tensor fasciæ femoris muscle.
10. Deep layer of the ilio-tibial band of fascia lata.
11. The external and internal intermuscular septa.

Poupart's Ligament—Gimbernat's Ligament.—Although, properly speaking, both of these ligaments belong more to the abdominal wall than the thigh, it is essential that the dissector should obtain some knowledge of their connections before he proceeds further with the dissection. *Poupart's ligament* is merely the thickened lower border of the aponeurosis of the external oblique muscle of the abdominal wall folded backwards upon itself. It thus presents a rounded surface towards the thigh, and a grooved surface towards the abdomen. By its outer extremity it is fixed to the anterior superior spine of the ilium. Internally, it has a double attachment, viz.—(1) to the spine of the pubis; (2) through the medium of Gimbernat's ligament to the inner part of the ilio-pectineal line. Poupart's ligament pursues an oblique course between its iliac and pubic attachments, and at the same time describes a gentle curve, the convexity of which is turned downwards. By its lower border it affords attachment to the fascia lata, and when this is divided it loses its curved direction.

Gimbernat's ligament is a small triangular piece of aponeurotic fascia which occupies the interval between the inner part of Poupart's ligament and the inner inch of the ilio-pectineal line—being attached by its margins to both. Its base, which looks outwards, is sharp, crescentic, and free, and abuts against the femoral sheath. Gimbernat's ligament occupies a very oblique plane; its femoral surface looks downwards and outwards, whilst its abdominal surface is directed upwards and inwards.

Dissection.—The exposure of the femoral sheath is the next step in the dissection of the thigh. To attain this object the *iliac portion* of the fascia lata must be partially reflected. Divide the superior horn of the outer crescentic margin of the saphenous opening, and then carry the knife outwards along the lower border of Poupart's ligament, so as to sever the

attachment of the fascia lata to this thickened band. This incision should extend to within an inch of the anterior superior spine of the ilium. The piece of fascia marked out by the incision above, and by the outer free margin of the saphenous opening internally, must be carefully raised from the subjacent femoral sheath and thrown downwards and outwards. On the removal of a little loose fat, the *femoral sheath* will be brought into view as it enters the thigh under Poupart's ligament. Isolate it carefully from adjacent and surrounding parts, by carrying the handle of the knife gently round it—insinuating it first between the sheath and *Poupart's ligament*, then between the sheath and *Gimbernat's ligament*, which lies internal to it.

Femoral Sheath.—The funnel-shaped appearance of the femoral sheath will now be apparent—the wide mouth of the membranous tube being directed upwards into the abdomen, and the narrow inferior part gradually closing upon the vessels, and fusing with their coats about the level of the lower limit of the saphenous opening. Whilst it presents this appearance, however, it should be noticed that its sides do not slope equally towards each other. The outer side of the sheath indeed is nearly vertical in its direction, whilst the inner wall proceeds very obliquely from above downwards and outwards. If the dissection has been successfully performed, the crural branch of the genito-crural nerve should be seen piercing the outer wall of the sheath, whilst the internal saphenous vein, and some lymphatic vessels, perforate its anterior and inner walls. Further, if the subject be spare, and the fasciæ well marked, the dissector will in all probability notice that the anterior wall of the sheath in its upper part is strengthened by some transverse fibres which pursue an arched course across it. To these fibres the name of *deep crural arch* is given, in contradistinction to the term *superficial crural arch*, which is frequently applied to Poupart's ligament. In favourable circumstances the deep crural arch may be observed to spring from the under surface of Poupart's ligament about its middle. After traversing the front of the sheath the band expands somewhat, and is attached by its inner extremity to the ilio-pectineal line of the pubic bone behind Gimbernat's ligament.

Constitution of the Femoral Sheath.—The source from which the femoral sheath is derived, and the manner in which it is formed, must next be considered. This entails the study of some of the structures concerned in the construction of the abdominal wall. Unfortunately it is not likely that at this period the dissection of the abdomen is in a

sufficiently advanced state for their examination. A small portion of the inner part of the interval between Poupart's ligament and the portion of the innominate bone over which it stretches is filled up by Gimbernat's ligament. Immediately to the outer side of this the femoral vessels, enclosed within the femoral sheath, enter the thigh from the abdominal cavity, whilst to the outer side of these the interval is occupied by the ilio-psoas muscle. Three nerves also find their way into the thigh through this interval, viz., the crural branch of the genito-crural, which passes downwards in the femoral sheath; the anterior crural nerve, which occupies the interval between the psoas and iliacus muscles; and the external cutaneous nerve, which runs behind Poupart's ligament close to its iliac attachment.

The arrangement of the aponeurotic lining of the abdominal cavity with reference to this interval of communication between abdomen and thigh also requires attention. The lower part of the posterior wall of the abdomen, immediately above the thigh, is formed by the iliacus and psoas muscles. These are covered by that part of the aponeurotic lining of the abdomen which receives the name of the *fascia iliaca*. The anterior wall of the abdomen is lined in like manner by a portion of the general lining, termed the *fascia transversalis*. To the outer side of the femoral vessels these two fascial layers become continuous with each other, and at the same time are attached to the back of Poupart's ligament. It is behind this that the ilio-psoas, the anterior crural nerve, and the external cutaneous nerve, are carried downwards into the thigh. But the external iliac vessels (the femoral vessels in the thigh) with the genito-crural nerve lie in front of the fascia iliaca, or, in other words, within the fascial lining of the abdomen, and, as they proceed downwards behind Poupart's ligament, they carry with them a funnel-shaped prolongation of the lining. This, then, is the femoral sheath, and the dissector will now readily understand that the *front wall* of the sheath is formed of *fascia transversalis* from the anterior wall of the abdomen above Poupart's ligament, while the *posterior wall* is formed of *fascia iliaca*, prolonged downwards from the posterior abdominal wall.

Posterior Wall of the Femoral Sheath.—There are still some additional facts relating to the posterior wall of the

femoral sheath which require to be mentioned. It is formed, as stated above, by the fascia iliaca; but as this enters the thigh it becomes continuous with the pubic layer of the fascia lata, and further, it is firmly fixed in position by certain connections which it establishes in the thigh. Thus beyond the femoral sheath it is prolonged in an outward direction over the ilio-psoas muscle, whilst from its posterior aspect a




FIG. 61.—Dissection to show the Femoral Sheath and the other Structures which pass between Poupart's Ligament and the Innominate Bone.

lamina is given off which passes behind that muscle and joins the capsule of the hip-joint.

Dissection.—The femoral sheath should be opened, in order that the arrangement of parts inside may be displayed. Make three vertical and parallel incisions through the anterior wall—one over the femoral artery which occupies the outer part of the sheath, another over the femoral vein, and the third about half an inch internal to the second. The first two should begin at the level of Poupart's ligament, and should extend downwards for an inch and a half. The most internal of the three incisions should commence at the same point, but should only be carried downwards for half an inch or less.

Interior of the Femoral Sheath.—A little dissection will show that the sheath is subdivided by two vertical partitions into three compartments. The femoral artery and crural branch of the genito-crural nerve occupy the *outermost compartment*; the femoral vein fills up the *middle compartment*; whilst in the *innermost compartment* is lodged a little loose areolar tissue, a small lymphatic gland, and some lymphatic vessels. This last compartment, from its relation to femoral hernia, has the special name of *crural canal* applied to it.

Crural Canal.—The boundaries and extent of this canal must be very thoroughly studied. The best way to do this is to introduce the little finger into it and gently push it upwards. Its length is not nearly so great as that of the other two compartments. Indeed it is not more than half an inch long. Inferiorly it is closed, and it rapidly diminishes in width from above downwards. Its superior aperture lies on the outer side of the base of Gimbernat's ligament, and is called the crural ring. It is closed by the closely applied extra-peritoneal fatty tissue of the abdominal wall. The parts which immediately surround this opening can be readily detected with the finger: externally the *femoral vein*, internally the sharp crescentic base of *Gimbernat's ligament*, anteriorly *Poupart's ligament*, and posteriorly the *pubic bone* covered by the *pectineus muscle*. The portion of the extra-peritoneal fatty tissue which closes the ring is called the septum crurale. On the abdominal surface of the septum crurale is the peritoneal lining of the abdominal cavity, and when examined from above both are seen to be slightly depressed into the opening so as to produce the appearance of a dimple.

Femoral Hernia.—Femoral hernia is the name applied to a pathological condition which consists in the protrusion of a viscus or part of a viscus from the abdominal cavity into the region of the thigh. In its descent it passes behind Poupart's ligament within the *crural canal* or *innermost compartment* of the femoral sheath. The arrangement of the parts which occupy the interval between the innominate bone and Poupart's ligament has been carefully considered, and the dissector should therefore be in a position to understand how the occurrence of such a protrusion is rendered possible. To the inner side of the femoral sheath the interval is closed by Gimbernat's ligament, which, by its strength and firm connections, constitutes an impassable barrier in this locality. To the outer side of the femoral sheath a hernial protrusion is equally impossible. Here the fascia transversalis on the anterior wall of the abdomen becomes continuous with the fascia iliaca on the posterior wall of the abdomen, and along the line of union both are firmly attached to Poupart's ligament.

It is in the region of the femoral sheath, then, that femoral hernia takes place. Its three compartments open above into the abdominal cavity, but there is an essential difference between these three openings. The outer two, which hold the artery and the vein, are completely filled up by their contents. The crural canal, or innermost compartment, is not; it is much wider than is necessary for the passage of the fine lymphatic vessels which traverse it. Further, its widest part is the upper opening or *crural ring*. It has been noted that this is wide enough to admit the point of the little finger. Here then is a weak point in the parietes of the abdomen, and a source of weakness which is greater in the female than in the male, seeing that in the former the distance between the iliac and pubic spines is proportionally greater, and in consequence the crural ring wider. Femoral hernia, therefore, is more common in the female.

When attempts are made to reduce a femoral hernia, it is absolutely necessary that the course which the protrusion has taken should be kept constantly before the mind of the operator. In the first instance it descends for a short distance in a perpendicular direction. It then turns forward and bulges through the saphenous opening. Should it still continue to enlarge, it bends upwards over Poupart's ligament, and pushes its way outwards towards the anterior superior spine of the ilium. The protrusion is thus bent upon itself: if reduction is to be carried out successfully it must be made to retrace its steps. In other words, it must be drawn downwards, and then pushed gently backwards and upwards. The position of the limb during this procedure must be attended to. When the thigh is fully extended and rotated outwards, all the fascial structures in the neighbourhood of the crural canal are rendered tight and tense. When the limb is flexed at the hip-joint and rotated inwards, on the other hand, the superior cornu of the falciform edge of the saphenous opening, and even Gimbernat's ligament, are relaxed. This, then, is the position in which the limb should be placed during the reduction of the hernia.

As the hernia descends it carries before it the various layers which it meets in the form of coverings. First it pushes before it the peritoneum, and this forms the *hernial sac*. The other coverings from within outwards are—(1) the septum crurale; (2) the wall of the femoral sheath (if it does not burst through one of the apertures in this); (3) the cribriform fascia; (4) and lastly, the superficial fascia and skin.

The crural canal, as we have noted, is surrounded by very unyielding structures. Stricture in cases of femoral hernia is therefore a matter of very common occurrence. The sharp base of Gimbernat's ligament and the superior cornu of the falciform edge of the saphenous opening are especially apt to bring about this condition.

Abnormal Obturator Artery.—But the account of the surgical anatomy of femoral hernia would not be complete if we omitted to mention the relation which the obturator artery frequently bears to the crural ring. In two out of every five subjects the obturator artery, on one or on both sides, takes origin from the deep epigastric. In these cases it passes backwards to gain the obturator canal in the upper part of the thyroid foramen. According to the point at which it arises from the epigastric trunk, it presents different relations to the femoral ring. In the majority of cases it proceeds backwards in close contact with the external iliac vein and on the outer side of the femoral ring. In this position it is in no danger of being wounded in operations undertaken for the relief of a strictured femoral hernia. In about thirty-seven per cent, however, of the cases in which it exists, the artery is placed less favourably. In these, it either proceeds backwards across the septum crurale which closes the opening

into the crural canal, or it arches over it and turns backwards on the inner side of the ring upon the deep aspect of the base of Gimbernat's ligament. In the latter situation it is in a position of great danger, seeing that it is the base of Gimbernat's ligament against which the surgeon's knife is generally directed for the relief of strictured femoral hernia.

Dissection.—Scarpa's triangle may now be dissected. To bring its boundaries into view the deep fascia must be removed from the anterior aspect of the upper third of the thigh. In the lower two-thirds of the thigh, the fascia lata should be left undisturbed, so as to maintain as far as possible the natural position of parts.

Scarpa's Triangle.—This is the name which is given to the triangular hollow which lies in the upper part of the thigh below Poupart's ligament.

The *outer boundary* is formed by the *sartorius muscle* as it runs downwards and inwards across the thigh from the anterior superior spine of the ilium; and the *inner boundary* is constituted by the prominent internal margin of the *adductor longus muscle*. These muscles meet below to form the *apex* of the triangle. *Poupart's ligament* forms the *base* of the triangle.

The *contents* of the space must now be displayed by removing the fatty areolar tissue which surrounds them. The *femoral vessels* should first be cleaned. Remove the remains of the femoral sheath and define the various branches which proceed from the vessels in so far as they are seen within the limits of the triangular space. Be careful not to injure the small twig which springs from the anterior crural nerve, and passes inwards behind the vessels a short distance below Poupart's ligament, to supply the pectineus muscle. In this part of its course the femoral artery gives off—(1) the *three superficial inguinal vessels*, which have already been observed ramifying in the superficial fascia of the groin; (2) the *deep external pudic*, which runs inwards over the pectineus; (3) the large *profunda femoris*.

The *profunda femoris* comes off from the outer side of the femoral artery about one and a half inches below Poupart's ligament. It inclines downwards and inwards behind the femoral trunk, and soon leaves the space by passing under cover of the adductor longus. The *external* and *internal circumflex arteries* will be seen to arise from the profunda femoris within Scarpa's triangle.

The *external circumflex* should be traced outwards as it passes amongst the branches of the anterior crural nerve, to

disappear under cover of the outer boundary of the space. The *internal circumflex* is lost to view shortly after its origin by sinking backwards through the floor of the space between the pectineus and psoas muscles. The veins corresponding to these arteries must be cleaned at the same time.

Certain nerves are also to be found in this space, viz.—(1) the *crural branch* of the *genito-crural*; (2) the *external cutaneous*;




FIG. 62.—Dissection of Scarpa's Triangle.

and (3) the *anterior crural*. The *crural branch* of the *genito-crural* descends in the outermost compartment of the femoral sheath on the outer side of the femoral artery. It pierces the external wall of the sheath and the fascia lata a short distance below Poupart's ligament, and has already been traced to its distribution (p. 192). The *external cutaneous nerve* passes into the thigh behind Poupart's ligament, close to the anterior superior spine of the ilium. It soon leaves

the triangle by crossing the sartorius and piercing the fascia lata. It has already been traced in its ramifications in the superficial fascia on the outer aspect of the thigh. The *anterior crural nerve* will be detected lying deeply in the interval between the psoas and iliacus muscles, about a quarter of an inch to the outer side of the femoral artery. Insinuate the handle of a knife under the main trunk, so as to raise it above the level of the muscles between which it lies, and render it tense, and then follow the numerous branches into which it breaks up as far as the limits of the space will allow. The minute twig to the pectineus muscle must be looked for. It passes inwards behind the femoral vessels.

The *floor* of Scarpa's triangle slopes backwards both from the inner and the outer boundary of the space. To the inner side of the femoral artery it is formed by the *adductor longus* and the *pectineus*; in some cases a small portion of the *adductor brevis* may be seen in a narrow interval between these two muscles. To the outer side of the artery are the *psoas* and *iliacus*. The adductor longus is placed in an oblique plane, the inner border being nearer the surface than the outer border; and thus it is that this muscle not only forms the inner boundary of the triangle, but also takes part in the formation of the floor. These muscles should be cleaned in so far as they stand in relation to Scarpa's triangle.

When a transverse section is made through the frozen thigh in the region of Scarpa's triangle, the space appears more in the shape of a deep intermuscular furrow, bounded on the inner side by the adductor longus and pectineus, and on the outer side by the sartorius and rectus femoris, whilst behind it is separated from the bone by the ilio-psoas. The femoral vessels and the anterior crural nerve pass downwards in this groove—the profunda femoris being placed very deeply, whilst the femoral artery lies nearer to the surface.

Femoral Artery (*arteria femoralis*).—The femoral artery, the great arterial trunk of the lower limb, is the direct continuation of the external iliac. It begins at Poupart's ligament, behind which it enters the thigh, and it extends downwards to the opening in the adductor magnus, through which it gains the popliteal space and becomes the popliteal artery. This opening is situated on the inner aspect of the lower third of the thigh, and the course which the vessel pursues may be marked on the surface, when the thigh is slightly abducted and rotated outwards, by an oblique line

drawn from a point midway between the anterior superior iliac spine and the symphysis pubis to the internal condyle of the femur.

The relations which the artery bears to the femur are important. As it enters Scarpa's triangle it passes from the brim of the pelvis and comes to lie in front of the inner part of the head of the femur, from which it is separated by the psoas muscle. Although its relation to the bone is tolerably intimate, this situation should not be chosen for applying compression. On account of the mobility of the head of the bone there is a liability for the vessel to slip from under the fingers. It is much safer to compress it against the brim of the pelvis. Below the head of the femur, during the remainder of its course through Scarpa's triangle, the artery is not in direct relation to the bone. It crosses in front of the angular interval between the neck and shaft of the femur. Towards the apex of the space, however, it comes into relation with the inner side of the shaft of the femur, and this position it holds to its termination.

In the present condition of the dissection it is only that part of the femoral artery which traverses Scarpa's triangle which comes under the notice of the dissector. The length of this part varies with the development of the sartorius muscle, and the degree of obliquity with which this crosses the front of the thigh. It measures from three to four inches in length, and is comparatively superficial throughout its entire course. At the apex of the triangle it disappears under cover of the sartorius and takes up a deeper position in the limb.

In Scarpa's triangle the femoral artery is enveloped in its upper part by the femoral sheath, and is separated from the surface by the skin, superficial fascia, and deep fascia, whilst below it is crossed by the internal cutaneous nerve, which runs along the inner border of the sartorius muscle. *Behind* the vessel is the psoas, and then the pectineus muscle. It rests directly upon the psoas—the femoral sheath and the nerve to the pectineus, as it crosses inwards, alone intervening; but it is separated from the pectineus by an interval occupied by fatty areolar tissue, and here also the profunda artery crosses behind it, and the femoral vein is seen to have a position posterior to it. Upon *the outer side* of the femoral

artery is the anterior crural nerve—but not in apposition with it, as a small portion of the psoas intervenes. The *femoral vein* changes its position with reference to the artery, as it is traced from above downwards. In the upper part of the space it lies on the same plane and to the inner side of the artery, but lower down it becomes more deeply placed and gradually assumes a position posterior to the artery.

The *branches* which the femoral artery gives off in Scarpa's triangle have already been enumerated (p. 203). One of these, viz., the deep external pudic, may now be traced to its destination.

Deep External Pudic Artery.—This is a small twig which arises from the inner side of the femoral, a short distance below Poupart's ligament. It extends inwards upon the pectineus and adductor longus muscles, and, piercing the fascia lata, ends, according to the sex, in the integument of the scrotum or of the labium pudendi.

Dissection.—The fascia lata may now be removed from the lower two-thirds of the thigh. This can best be effected by dividing it along the middle line of the limb, and throwing it outwards and inwards. Preserve undisturbed the thickened band of fascia on the outer side of the thigh.

In cleaning the sartorius muscle several of the nerves of the thigh will be found intimately related to it, and must be carefully dissected. The middle cutaneous nerve frequently pierces its upper border, and then proceeds downwards in front of it; the anterior branch of the internal cutaneous crosses it at a lower level, whilst the posterior branch of the same nerve is carried downwards along its posterior border. Near the knee it lies over the long saphenous nerve, which ultimately comes to the surface between it and the gracilis. A short distance above this the sartorius is pierced by the patellar branch of the long saphenous. Lastly, about the middle of the thigh, there is formed under cover of the sartorius an interlacement of fine nerve twigs derived from the posterior branch of the internal cutaneous, the long saphenous, and the obturator. On raising the sartorius from subjacent parts this must be looked for.

The different portions of the quadriceps extensor muscle must also be cleaned, and the branches which the anterior crural nerve gives to them, as well as the descending branch of the external circumflex artery, traced to their terminations.

Sartorius.—The sartorius is a long slender muscle, which arises from the anterior superior spine of the ilium and the upper part of the notch on the anterior border of the bone immediately below. It crosses the front of the upper third of the thigh obliquely, and gaining the inner side of the limb, it takes a nearly vertical course downwards to a point beyond the inner prominence of the knee. Here it turns forwards,

and ends in a thin, expanded aponeurotic tendon, which is inserted into the inner surface of the shaft of the tibia, behind the anterior tubercle (Fig. 58, p. 183). By its lower border this tendon is connected with the fascia of the leg, whilst by its upper border it is joined to the capsule of the knee-joint.

In its upper oblique part the sartorius muscle forms the outer boundary of Scarpa's triangle, and lies in front of the




FIG. 63.—Dissection of Hunter's Canal in the left lower limb. A portion of the Sartorius has been removed.

iliacus, the rectus femoris, and the adductor longus muscles. Below this, it is placed over the femoral vessels as far as the opening in the adductor magnus. At its insertion its expanded tendon lies in front of, and covers, the tendons of insertion of the gracilis and semitendinosus, but is separated from them by a bursa. The sartorius is supplied by the anterior division of the *anterior crural nerve*.

Hunter's Canal (canalis adductorius Hunteri).—When the

femoral artery leaves Scarpa's triangle it is continued downwards on the inner side of the thigh, in a deep furrow, which is bounded in front by the vastus internus muscle, and behind by the adductor muscles. If this furrow be traced upwards, it will be seen to run into the deeper, wider, and more apparent hollow, which has been described as Scarpa's space. Further, this intermuscular recess is converted into a canal, triangular on transverse section, by a strong fibrous membrane which stretches across it, and upon the surface of which the sartorius muscle is placed (Fig. 64). The tunnel thus formed is called "Hunter's Canal." When the fibrous expansion which closes in the canal is traced upwards, it is seen to




FIG. 64.—Transverse Section through Hunter's Canal.

become thin and ill-defined as it approaches Scarpa's triangle ; when traced in the opposite direction, however, it becomes dense and strong, and opposite the opening in the adductor magnus it presents a thick, sharply defined margin. It stretches from the tendons of the adductor longus and the adductor magnus behind to the vastus internus in front. In its lower part the posterior wall of the canal, where it is formed by the adductor magnus, presents a deficiency or aperture which leads backwards into the popliteal space. The appearance and construction of this aperture will be studied at a later stage. It is called *the opening in the adductor magnus*.

The femoral vessels and the long saphenous nerve traverse

Hunter's canal. In this part of its course the artery gives off some muscular twigs and the anastomotica magna branch. The femoral vessels leave the canal at its lower end by inclining backwards through the opening in the adductor magnus and entering the popliteal space. The long saphenous nerve, accompanied by the superficial branch of the anastomotica magna artery, escape from the canal by passing under cover of the lower thickened margin of the fibrous expansion which closes it in. They can be seen in the present stage of the dissection in this situation.




FIG. 65.—Transverse Section through the Middle of the Thigh. The Relationship of the parts in Hunter's Canal is seen.

Dissection.—The fibrous expansion which is stretched across Hunter's canal under cover of the sartorius muscle should now be divided, in order that the arrangement of the parts within the canal may be studied.

Lower Portion of the Femoral Artery.—The entire length of the femoral artery is now exposed. Below the apex of Scarpa's triangle it enters Hunter's canal, and is separated from the inner surface of the thigh by the fibrous expansion which closes the canal, the sartorius muscle, the fascia lata, and the integument. The long saphenous nerve at first lies to the outer side of this portion of the vessel and then in front of it. From above downwards the artery rests upon the

pectineus, the adductor brevis, the adductor longus, and the adductor magnus. In its upper part, however, it is separated from these muscles by the femoral vein, which lies behind it; lower down, the vein, which inclines outwards, comes to lie on its outer side. The relation of parts in the lower portion of Hunter's canal is seen in Figs. 64 and 65. The two vessels are placed side by side, whilst the long saphenous nerve is in front of the artery.

From the femoral artery, as it traverses Hunter's canal, proceed muscular twigs and the anastomotic branch.

The *muscular branches* are irregular in number and in their mode of origin. They supply the vastus internus, the adductor longus, and the sartorius.

Anastomotic Artery (*arteria genu suprema*).—This branch springs from the femoral trunk a short distance above the point where it enters the popliteal space by passing through the opening in the adductor magnus. It almost immediately divides into a superficial and a deep branch: very frequently, indeed, these branches take separate origin from the femoral artery.

The *superficial branch* accompanies the long saphenous nerve, and leaves Hunter's canal by passing under cover of the lower border of the fibrous expansion which is stretched over the canal. On the inner side of the knee it appears between the gracilis and sartorius, and it ends in branches to the integument on the inner aspect of the upper part of the leg.

The *deep branch* enters the substance of the vastus internus and proceeds downwards in front of the tendon of the adductor magnus. It gives some twigs to the vastus internus and others which spread out over the upper and inner aspect of the knee-joint, and anastomose with branches of the internal articular arteries. One well-marked branch runs outwards above the patella to anastomose with the superior external articular artery.

Femoral Vein (*vena femoralis*).—This is the direct continuation upwards of the popliteal vein. It begins at the opening in the adductor magnus, through which it enters Hunter's canal, whilst above, it passes behind Poupart's ligament and becomes continuous with the external iliac vein. It accompanies the femoral artery, but the relations of the two vessels

to each other differ at different stages of their course. In the lower part of Hunter's canal the vein lies on the outer side of the artery, but it inclines inwards as it ascends, and in the upper part of the thigh it lies on its inner side and on the same plane. The crossing from one side to the other takes place behind the artery and is very gradual, so that for a considerable distance the femoral vein lies directly behind the femoral artery. For a distance of two inches below Poupart's ligament it is enclosed within the femoral sheath, of which it occupies the middle compartment.

In its journey up the thigh the femoral vein receives tributaries which for the most part correspond with the branches of the femoral artery. At the saphenous opening it is joined by the internal saphenous vein. The dissector should slit it open with the scissors. Several valves will then be seen. One is almost invariably found immediately above the entrance of the vein which corresponds to the profunda artery.

Anterior Crural Nerve (*nervus femoralis*).—The anterior crural nerve is a large nerve which arises within the abdomen from the lumbar plexus. It enters the thigh by passing downwards in the interval between the psoas and iliacus muscles and behind Poupart's ligament and the fascia iliaca. In the upper part of the thigh it lies to the outer side of the femoral artery, and is separated from it by a small portion of the psoas muscle and the femoral sheath. A short distance below Poupart's ligament it divides into an anterior and a posterior portion, which at once resolve themselves into a large number of cutaneous and muscular branches. The following is a list of these:—

Anterior division,	Muscular branches,	{ To the pectineus.
	Cutaneous branches,	{ „ sartorius.
Posterior division,		{ Middle cutaneous.
		{ Internal cutaneous.
	Muscular branches,	{ To the rectus femoris.
		{ „ vastus internus.
		{ „ vastus externus.
	Cutaneous branch,	{ „ crureus.
		{ „ subcrureus.
	Articular branches.	Long saphenous.

With the exception of the long saphenous, which is distributed upon the inner side of the leg and foot, the distribution of the

cutaneous branches of the anterior crural has been already examined (p. 192).

The *nerve to the pectineus* arises a short distance below Poupart's ligament and turns inwards behind the femoral vessels to reach its destination. The *branches to the sartorius* are two or three in number. As a rule they take origin by a common trunk with the middle cutaneous nerve.

The *middle cutaneous nerve* sometimes pierces the upper border of the sartorius. It divides into two branches which perforate the fascia lata about three or four inches below Poupart's ligament.

The *internal cutaneous nerve* inclines downwards and inwards, and crosses in front of the femoral artery. It divides into an anterior and a posterior portion, which become superficial at different levels on the inner side of the limb. From the trunk of the nerve a few cutaneous twigs are given to the skin over the upper and inner part of the thigh. The *anterior branch* crosses the sartorius muscle and makes its appearance through the fascia lata in the lower part of the thigh, a short distance in front of the saphenous vein. The *posterior branch* runs downwards along the posterior border of the sartorius, and pierces the deep fascia on the inner side of the knee behind that muscle and the long saphenous nerve.

A short distance below the middle of the thigh the posterior branch of the internal cutaneous nerve forms, with filaments from the obturator nerve and the long saphenous nerve, a plexiform interlacement, the *sartorial plexus*, which is placed under the sartorius muscle, as it lies over Hunter's canal. The twig from the obturator nerve appears at the inner border of the adductor longus.

The *long saphenous nerve* is the largest branch of the anterior crural. It springs from the posterior division of that nerve and extends downwards on the outer side of the femoral artery. Entering Hunter's canal with the femoral vessels it comes to lie in front of the artery. At the lower end of the canal it emerges, by passing under cover of the thickened border of the fibrous expansion which stretches between the vastus internus and the adductor muscles, and, accompanied by the superficial branch of the anastomotic artery, it escapes from under cover of the sartorius and pierces the deep fascia at the inner side of the knee. It gives off the *patellar branch* after it quits Hunter's canal.

This branch pierces the sartorius and appears on the surface of the fascia lata on the inner side of the knee.

Several large branches of the posterior part of the anterior crural nerve enter the four factors which compose the great quadriceps extensor muscle of the thigh. From certain of these, articular filaments are given to the hip and knee-joints.

The *branch to the rectus femoris* sinks into the deep surface of this muscle. It supplies an articular twig to the hip-joint. The large *branch to the vastus internus* accompanies the long saphenous nerve, and enters with it the upper part of Hunter's canal. It can readily be distinguished from its sinking into the inner aspect of the vastus internus about the middle of the thigh. In the substance of this muscle it extends downwards, and near the knee joins the deep branch of the anastomotic artery. It gives an articular nerve to the synovial membrane of the knee-joint. The *nerve to the vastus externus* is associated with the descending branch of the external circumflex artery. Very frequently it gives an articular twig to the knee-joint. The *nerves to the crureus* are two or three in number, and they sink into its anterior surface. The innermost of these is a long slender nerve, which can be traced downwards under the anterior border of the vastus internus to the subcrureus. Its terminal twigs are given to the synovial membrane of the knee-joint.

One filament then from the anterior crural goes to the hip-joint; two, and frequently three, filaments go to the knee-joint.

Ilio-tibial Band of Fascia Lata.—The thick band of fascia lata on the outer side of the thigh which receives this name should now be examined, and its connections ascertained. It has been preserved for this purpose. Inferiorly it is attached to the outer tuberosity of the tibia and to the head of the fibula. On tracing it upwards on the outer surface of the vastus externus it will be observed to split at the junction of the middle and upper thirds of the thigh into two lamellæ—a superficial and a deep. The tensor fasciæ femoris is enclosed between these layers, and when they are disengaged from its surfaces the muscle will be seen to be inserted into the fascia at the angle of splitting. The *superficial lamina* of the ilio-tibial band is attached above to the crest of the ilium, and is continuous posteriorly with the gluteal aponeurosis

where this covers the gluteus medius. The *deep lamina* can be followed upwards on the outer surface of the rectus femoris to the capsule of the hip-joint, with the upper and outer part of which it blends. It is also connected with the reflected tendon of the rectus femoris. This layer is perforated by the ascending twigs of the external circumflex artery.

Tensor Fasciæ Femoris (musculus tensor fasciæ latæ).—This is a small muscle which is placed on the outer and anterior aspect of the upper third of the thigh. It lies between the two lamellæ of the ilio-tibial band of fascia, in the interval between the sartorius muscle in front and the gluteus medius muscle behind. On turning the muscle outwards so as to display its deep surface, a little dissection will bring into view its nerve of supply which comes from the *superior gluteal nerve*. This nerve, however, has in all probability been already exposed in the dissection of the gluteal region. A few arterial twigs from the external circumflex also sink into its deep surface.

The *tensor fasciæ femoris* arises from a small portion of the anterior part of the crest of the ilium; from the upper part of the notch below the anterior superior spine of the ilium; and by some fibres from the aponeurosis covering the gluteus medius. It extends downwards with a slight inclination backwards, and is inserted into the ilio-tibial band of fascia lata at its angle of splitting.

External Circumflex Artery (arteria circumflexa femoris radialis).—This is the largest branch which proceeds from the profunda femoris. It arises near the origin of the latter from the femoral artery, and runs outwards between the divisions of the anterior crural nerve and under cover of the sartorius and rectus femoris muscles. It ends by dividing into ascending, transverse, and descending branches.

The *ascending branch* reaches the dorsum ilii by passing under cover of the tensor fasciæ femoris. Its terminal twigs anastomose with the gluteal artery. The *transverse branch* is of small size and passes to the deep surface of the vastus externus. It reaches the back of the thigh, and inosculates with the internal circumflex and the first perforating arteries. The *descending branch* gives twigs to the crureus and rectus femoris and one long branch, which may be traced downwards amid the fibres of the vastus externus to the knee,

where it anastomoses with the superior external articular artery.

Intermuscular Septa.—Divide the *ilio-tibial band* of fascia lata below the point at which it splits to enclose the tensor fasciæ femoris. This is done so as to obtain a better view of the vastus externus, and in order to demonstrate satisfactorily the external intermuscular septum. Take hold of the lower portion of the ilio-tibial band, and draw it forcibly outwards; at the same time push inwards the vastus externus muscle, and a strong fibrous septum will be seen passing inwards from the fascia lata towards the linea aspera. This is the *external intermuscular septum* of the thigh, a partition interposed between the vastus externus and the short head of the biceps. Follow it upwards and downwards with the finger. The fibres of the vastus externus are seen arising from it, but little difficulty will be experienced in making out its attachment to the linea aspera of the femur. It extends in an upward direction as far as the insertion of the gluteus maximus, whilst below, it reaches the external tuberosity of the lower end of the femur. Immediately above the external condyle of the femur it is pierced by the *superior external articular vessels* and *nerve*. The *internal intermuscular septum* is interposed between the adductors and the vastus internus, and should also be examined. It is thin in comparison with the external septum.

Quadriceps Extensor Cruris (musculus quadriceps femoris).—This muscle is composed of four portions. The rectus femoris, which is placed on the front of the thigh, is quite distinct from the others, except at its insertion; the vastus externus, the crureus, and the vastus internus clothe the shaft of the femur on its outer, anterior, and inner aspects, and are more or less blended with each other.

The **Rectus Femoris** arises by two tendinous heads of origin, which may be exposed by dissecting deeply in the interval between the iliacus and tensor fasciæ femoris. The *anterior* or *straight head* springs from the anterior inferior spine of the ilium (Fig. 52, p. 159); the *posterior* or *reflected head* arises from a marked impression on the outer surface of the ilium, immediately above the upper part of the rim of the acetabulum (Fig. 52, p. 159), and is connected both with the capsule of the hip-joint and the deep lamina

of the ilio-tibial band of fascia lata. The two heads of origin of the rectus femoris join at a right angle immediately beyond the margin of the acetabulum, and form a strong flattened tendon, which gives place to a fusiform, fleshy belly. The tendon of origin spreads out on the anterior surface of the muscle in its upper part in the form of an aponeurosis. About three inches above the knee-joint the rectus femoris ends in a strong tendon of insertion, which is prolonged for some distance upwards on its deep surface in the form of an aponeurosis. As it nears the patella, this tendon is joined by the other tendons of the quadriceps, and through the medium of a common tendon finds insertion into the upper border of that bone. The rectus femoris is supplied by the *anterior crural nerve*.

The **Vastus Externus** (*musculus vastus lateralis*) forms the prominent muscular mass on the outer side of the thigh. Its surface is covered by a glistening aponeurosis. The descending branch of the external circumflex artery constitutes the best guide to its anterior border, and when this margin is raised it will be seen that the muscle lies upon, and is partially blended with, the crureus.

The vastus externus arises—(1) from the upper part of the anterior intertrochanteric line; (2) from the front of the great trochanter, anterior to the insertion of the gluteus minimus; (3) from the root of the great trochanter below the insertion of the gluteus medius; (4) from the outer part of the gluteal ridge in front of the insertion of the gluteus maximus; (5) from the upper part of the linea aspera; and




FIG. 66.—Front Aspect of Upper Portion of Femur with Attachments of Muscles mapped out.

(6) from the external intermuscular septum. The fleshy fibres are for the most part directed downwards and forwards. By means of the common tendon of insertion the muscle gains insertion into the patella, and at the same time gives an expansion to the capsule of the knee-joint. It is supplied by the *anterior crural nerve*.

The **Vastus Internus** (*musculus vastus medialis*) is intimately connected with the crureus, but not to such an extent as might be inferred from a superficial inspection. In its upper part the anterior border, which is fleshy, is either contiguous or blended with the crureus; below, the anterior border is tendinous and overlaps the crureus, but it is not as a rule fused with it.

"A line drawn from the middle of the anterior intertrochanteric line downwards and slightly outwards to the middle of the upper border of the patella will define accurately the thick anterior border of the vastus internus."—(Williams.) Divide the rectus femoris about its middle, and pull the lower part forcibly downwards. The narrow interval between the tendons of the crureus and vastus internus will then become apparent, and may be followed upwards. A still further guide is the long, slender nerve of supply to the subcrureus, which runs along the inner edge of the crureus. When the anterior border of the vastus internus is raised from the crureus, the inner surface of the shaft of the femur will be seen to be perfectly bare. No muscular fibres arise from this bony surface. The fleshy mass of the vastus internus may now, with advantage, be divided transversely about two inches above the patella. The muscle can then be thrown inwards, and its origin studied.

The vastus internus arises—(1) from the lower part of the anterior intertrochanteric line of the femur; (2) from the line leading from this, below the small trochanter, to the linea aspera; (3) from the inner lip of the linea aspera; (4) from the upper part of the internal supracondyloid line as low down as the opening in the adductor magnus; (5) from the rounded tendon of the adductor magnus. The fleshy fibres are directed downwards and forwards, and end in the common tendon of the quadriceps muscle. By this it is inserted into the patella, and becomes connected with the capsule of the knee-joint. It is supplied by the *anterior crural nerve*.

The **Crureus** (*musculus vastus intermedius*) covers the anterior and outer aspects of the shaft of the femur, from both of which, as well as from the lower part of the external intermuscular septum, it takes origin. It is inserted into the patella through the medium of the common tendon. It is supplied by the *anterior crural nerve*.

Common Tendon of the Quadriceps.—It should now be noticed that the common tendon of the quadriceps muscle closes the knee-joint above the patella. It is inserted into the upper border of that bone, and is intimately connected with the capsule of the knee-joint. Some fibres are carried downwards into the ligamentum patellæ upon the surface of the patella. A pouch of synovial membrane is prolonged upwards beyond the level of the patella, between the quadriceps and the bone. Into this some of the lower and deeper fasciculi of the crureus muscle are inserted. They constitute the *subcrureus muscle* (*musculus articularis genu*).

The crureus should be divided in a vertical direction, so as to bring this little muscle into view, and at the same time the long, slender nerve-filament which runs along the inner border of the crureus may be traced to the subcrureus and the synovial membrane of the knee-joint.

The *ligamentum patellæ*, which connects the patella with the anterior tubercle of the tibia, and through which the quadriceps is attached to that bone, will be studied in connection with the knee-joint.

INNER SIDE OF THE THIGH.

The group of adductor muscles on the inner aspect of the thigh, together with the blood-vessels and nerves associated with them, must next be dissected. In this dissection the following are the structures which are displayed:—

Muscles,	{	Pectineus.
		Adductor longus.
		Adductor brevis.
		Adductor magnus.
		Gracilis.
Arteries,	{	Obturator externus.
		Profunda femoris and its branches.
		Obturator.
Nerves,	{	The two divisions of the obturator.
		Occasionally the accessory obturator.

The adductor muscles are disposed in three strata. The *superficial stratum* is formed by the adductor longus and the pectineus, which lie in the same plane. Above they are placed side by side, but below, as they approach their inser-

tions, they are separated from each other by a narrow interval. The *second stratum* is formed by the adductor brevis; and the *third, or deep layer*, by the adductor magnus. The gracilis muscle, also an adductor, extends along the inner aspect of the thigh. It is a long strap-like muscle, applied against the adductor brevis and adductor magnus. Interposed between these muscular layers, are the two divisions of the *obturator nerve*. The *anterior division* is placed between the superficial and middle layers, whilst the *posterior division* lies between the middle and deep layers. In other words, the two divisions of the nerve are separated from each other by the adductor brevis, which intervenes between them. At the lower border of the adductor longus, a fine branch from the anterior division of this nerve makes its appearance to take part in the formation of the sartorial nerve plexus already dissected. The profunda artery and its branches are also to be followed. For a part of its course this vessel is placed between the anterior and middle muscular strata.

Adductor Longus.—This muscle is placed on the inner side of the pectineus. It is somewhat triangular in shape, being narrow at its origin and expanded at its insertion. It arises by a short, but strong, tendon from the front of the body of the pubis, immediately below the pubic crest (Fig. 52, p. 159), and it is inserted into the inner lip of the linea aspera of the femur by a thin, tendinous expansion. It is supplied by the *anterior division* of the *obturator nerve*.

Dissection.—The adductor longus may now be reflected. Divide it close to the round tendon of origin, and throw it outwards. In doing this be careful of the anterior division of the obturator nerve, which lies under cover of it, and gives to it its nerve of supply. On approaching the linea aspera of the femur its aponeurotic tendon will be found intimately connected with the vastus internus in front and with the adductor magnus behind. Separate it from these as far as possible, in order that the profunda femoris vessels may be fully displayed as they proceed behind it.

Arteria Profunda Femoris.—This large vessel is the chief artery of supply to the muscles of the thigh. It arises in Scarpa's triangle from the outer and posterior aspect of the femoral artery, about an inch and a half below Poupart's ligament. At first it is placed on the iliacus, but it inclines inwards as it proceeds downwards, and thus it crosses behind the femoral artery, and comes to lie on the pectineus. Reaching the upper border of the adductor longus, it passes

behind that muscle, and is continued downwards close to the shaft of the femur upon the adductor brevis and adductor magnus. Numerous large branches spring from the profunda femoris, so that it rapidly diminishes in size. Ultimately it is reduced to a fine terminal twig, which turns backwards, through the adductor magnus, and receives the name of the *fourth perforating artery*. The following, then, are the relations of the profunda femoris:—(1) It lies on the iliacus to the outer side of the femoral artery.

(2) It rests on the pectineus, behind the femoral artery, but separated from it by the femoral vein.

(3) It is placed on the adductor brevis, and lower down on the adductor magnus; the adductor longus lies in front of this portion of the vessel and separates it from the femoral artery.

(4) The terminal twig, called the *fourth perforating artery*, pierces the adductor magnus




FIG. 67.—Profunda Femoris Artery and its Branches.

at the junction of the middle and lower thirds of the thigh.

The *branches* which spring from the profunda femoris are:—the two circumflex arteries, the four perforating arteries, and some muscular branches.

The *external circumflex* arises from the outer aspect of the profunda, close to its origin. It has already been followed

to its distribution (p. 215). The *internal circumflex*, which takes origin at the same level, but from the inner and back aspect of the profunda, will be studied when the pectineus muscle is reflected. The *muscular branches* are irregular both in origin and size. They supply the adductor muscles, and give twigs which pierce the adductor magnus to reach the hamstring muscles.

The internal circumflex artery frequently arises from the common femoral trunk.

Perforating Arteries.—These arise in series from the main trunk, and pass backwards through the adductor muscles to the back of the thigh. They may be recognised from the close relation which they bear to the linea aspera of the femur. The *first perforating artery* (arteria perforans prima) comes off at the level of the lower border of the pectineus. It proceeds backwards through the adductor brevis and adductor magnus. The *second perforating artery* (arteria perforans secunda) takes origin a short distance lower down, or perhaps by a common trunk, with the first perforating. It pierces the same muscles, viz., the adductor brevis and adductor magnus. The *third perforating* (arteria perforans tertia) springs from the profunda below the adductor brevis, and passes backwards through the adductor magnus. The *fourth perforating*, as we have noted, is the terminal branch of the profunda femoris, and pierces the adductor magnus.

The *chief nutrient artery* to the femur may come from either the second or the third perforating branch. A *second nutrient twig* is frequently derived from the fourth perforating artery.

When the adductor magnus is more fully exposed, it will be seen that the perforating arteries, as they pierce its tendon, have a series of fibrous arches thrown over them.

Pectineus.—This muscle is placed between the adductor longus and the ilio-psoas. It is flat and somewhat broader at its origin from the brim of the pelvis than at its insertion into the femur. It has a fleshy origin, from the ilio-pectineal line, and from the surface of the innominate bone in front of it (Fig. 52, p. 159). Some fibres are likewise derived from Gimbernat's ligament. It descends obliquely outwards and backwards, and gains insertion into the femur behind the small trochanter, and to a certain extent also into the

line which leads from this prominence down to the linea aspera. It is supplied by the *anterior crural nerve*.

Dissection.—The pectineus may be detached from its origin, and thrown downwards and outwards. In separating the muscle from the pubis the dissector must bear in mind that in some cases an *accessory obturator nerve* descends into the thigh, over the brim of the pelvis, and under cover of its outer margin. Care must also be taken not to injure the anterior division of the obturator nerve which lies behind it, or the internal circumflex artery which passes backwards in contact with its outer border.

The **Accessory Obturator Nerve** when present arises within the abdomen from the obturator trunk near its origin. In the thigh it gives a branch to the hip-joint and joins the anterior division of the obturator nerve. It is very rare to find a twig given to the pectineus either by it or by the trunk of the obturator nerve itself.

Internal Circumflex Artery (*arteria circumflexa femoris medialis*).—This vessel arises from the inner and back aspect of the profunda femoris at the same level as the origin of the external circumflex. It proceeds backwards between the psoas and pectineus, and then between the upper border of the adductor brevis and the obturator externus to gain the back of the limb. Close to the small trochanter of the femur it divides into two terminal branches—a transverse and an ascending. From the main trunk before it divides are given off several *muscular branches* to the adjoining muscles, and an *articular branch*, which enters the hip-joint through the cotyloid notch.

The *terminal branches* of the internal circumflex have already been examined in the dissection of the gluteal region (p. 168).




FIG. 68.—Back aspect of Upper Portion of Femur with the Attachments of Muscles mapped out.

Branches of the Femoral Artery.—In every region of the thigh the dissector has met with branches of the femoral artery. It is well now that he should revert to this vessel and study its branches in the order in which they arise. The following Table may aid him in doing this :—

Femoral.	{	Superficial pudic.	}	Superficial inguinal.
		Superficial epigastric.		
		Superficial circumflex iliac.		
		Deep external pudic.		
	{	Profunda, or deep femoral.	{	Nutrient.
		{	External circumflex.	
			Internal circumflex.	
			First perforating.	
			Second perforating.	
		{	Third perforating.	}
			Fourth perforating, or terminal.	
		Muscular.		
		Anastomotica magna.		

Adductor Brevis.—This muscle lies behind the adductor longus and the pectineus. It arises below the origin of the adductor longus from the anterior aspect of the body and the descending ramus of the pubis (Fig. 52, p. 159). As it descends it inclines backwards and outwards, and it is inserted behind the pectineus into the whole length of the line which extends from the small trochanter to the linea aspera (Fig. 68, p. 223). It is supplied by the *obturator nerve*.

Dissection.—Reflect the adductor brevis by cutting it close to its origin, and throwing it downwards and outwards. The posterior division of the obturator nerve is now exposed, and should be traced upwards to the thyroid foramen, and downwards to its distribution upon the adductor magnus.

Obturator Nerve (nervus obturatorius).—The obturator nerve is a branch of the lumbar plexus, and escapes from the pelvis by passing with its companion vessels through the upper part of the thyroid foramen of the innominate bone. While still within the foramen it divides into an anterior and a posterior division.

The *anterior division* of the obturator nerve enters the thigh over the upper border of the obturator externus muscle, and proceeds downwards upon the anterior surface of the adductor brevis. In front of it are the pectineus and adductor longus muscles. It gives branches to three muscles, viz., the adductor longus, the adductor brevis, and the gracilis. Very rarely it will be observed to supply a twig to the pectineus. In addition to these it supplies an *articular branch* to the hip-joint (Fig. 69, x); a fine twig which appears at the lower border of the

adductor longus to join the sartorial plexus (Fig. 69, 1); and a *terminal twig* which goes to the femoral artery—(Fig. 69, 2)—and breaks up into fine filaments upon its walls.

The *posterior division* of the obturator nerve as it enters the thigh pierces the upper border of the obturator externus. It




FIG. 69.—Diagram to illustrate the distribution of the Obturator Nerve and the general disposition of the Adductor Muscles of the Thigh (Paterson).

extends downwards between the adductor brevis and the adductor magnus, and is chiefly expended in the supply of the latter muscle. It gives also, however, a branch to the obturator externus and an *articular branch* to the knee-joint (Fig. 69, 3). The latter branch pierces the lower part of the adductor magnus close to the linea aspera, and has already

and the tendon of the sartorius. The gracilis is supplied by the *anterior division* of the *obturator nerve*.

Adductor Magnus.—This is one of the most powerful muscles of the thigh. It forms a flat fleshy mass, which springs from the anterior surface of the entire length of the pubic arch, and from the lower part of the tuberosity of the ischium (Fig. 52, p. 159). *The fibres which arise from the pubic arch* spread out as they approach the back of the femur. The upper fibres are nearly horizontal in their direction; below this they descend with increasing degrees of obliquity. They are inserted into the posterior surface of the femur, immediately internal to the gluteal ridge, into the linea aspera, and into a small portion of the upper part of the internal supracondyloid ridge (Fig. 68, p. 223). *The fibres which take origin from the ischial tuberosity* descend almost vertically and form the thick inner border of the muscle. In the lower third of the thigh they end in a strong, rounded tendon, which is inserted into the adductor tubercle on the inner tuberosity of the femur (Fig. 77, p. 255). This tendon is further attached to the femur by the internal intermuscular septum which stretches between it and the internal supracondyloid line. Close to the linea aspera the dissector will notice that fibrous arches are formed in connection with the insertion of the adductor magnus for the passage of the perforating arteries. The opening through which the femoral artery enters the popliteal space lies in series with these. It is a gap between the two portions of the muscle, and is situated in the lower third of the thigh.

The adductor magnus has a double nerve supply. Behind, it is supplied by branches from the *great sciatic*, whilst in front it receives the greater part of the *posterior division* of the *obturator*.

Dissection.—The adductor magnus should now be detached from its origin, in order that the obturator externus muscle and the obturator artery may be more fully examined.

Obturator Externus.—The obturator externus is a flat, fan-shaped muscle, which is placed over the front of the thyroid foramen of the innominate bone. It springs from the inner half of the membrane which closes the foramen, and also from the inner and lower part of its bony margin (Fig. 52, p. 159). It proceeds backwards and outwards below the neck of the

femur and the capsular ligament of the hip-joint, and ends in a stout tendon which obtains insertion into the digital fossa at the root of the great trochanter (Fig. 68, p. 223). This tendon has already been noticed in the dissection of the gluteal region. The obturator externus is supplied by the *posterior division* of the *obturator nerve*.

Obturator Artery (arteria obturatoria).—The obturator artery appears in the thigh through the upper part of the thyroid foramen of the innominate bone. It at once divides into two terminal branches, which diverge from each other, and form an arterial circle upon the thyroid membrane, under cover of the obturator externus. This muscle must therefore be detached in order that these vessels may be followed. Both branches give twigs to the neighbouring muscles, whilst the *outer branch* (i.e. the branch which runs round the outer side of the foramen) sends an *articular twig* through the cotyloid notch of the acetabulum into the hip-joint. When the joint is opened this twig may be followed in a well-injected subject, along the ligamentum teres, into the head of the femur.

Psoas and Iliacus.—These muscles arise within the abdomen and enter the thigh behind Poupart's ligament. A tendon appears on the outer side of the psoas, and into this the fibres of the iliacus are for the most part inserted. The conjoined tendon of the ilio-psoas is implanted into the small trochanter of the femur, but a certain proportion of the fleshy fibres of the iliacus obtain direct insertion into the shaft of the femur below and in front of that prominence (Fig. 68, p. 223).

Dissection.—Divide the femoral vessels, and the anterior crural nerve, about an inch below Poupart's ligament, and having tied them together with twine throw them downwards. Now cut through the sartorius and the rectus femoris about two inches from their origins and turn them aside. The tendon of the ilio-psoas must next be detached from its insertion and the muscle thrown upwards. This will expose the anterior surface of the capsule of the hip-joint. An intervening *bursal sac* will also be displayed. Open this and ascertain its extent by introducing the finger. It facilitates the play of the ilio-psoas upon the front of the hip-joint, and in some rare cases it will be found to be directly continuous with the synovial membrane of this articulation through an aperture in the capsular ligament. The intimate connection which exists between the capsule of the hip-joint and the tendon of the gluteus minimus, the reflected head of the rectus femoris, and the deep layer of the ilio-tibial band, should be noticed. Lastly, reflect the tensor fasciæ femoris, and carefully clean the capsule of the hip-joint.

HIP-JOINT.

It is necessary that the hip-joint (*articulatio coxæ*) be studied at this stage, as the further dissection of the limb can only be satisfactorily carried out after its removal from the trunk.

The hip-joint is the most perfect example of an enarthrodial or ball and socket joint in the body. It does not allow so free a range of movement as that which takes place at the shoulder-joint, but what it loses in this respect it gains in strength and stability. Its great strength and security depend : (1) upon the depth of the cotyloid cavity and the thorough manner in which the head of the femur is received into it ; (2) upon the tension and power of the ligaments ; (3) upon the length and oblique direction of the neck of the femur ; and (4) upon atmospheric pressure.

The *ligaments* in connection with the hip-joint are :—

- | | | |
|----------------------|--|----------------|
| 1. Capsular. | | 3. Cotyloid. |
| 2. Ligamentum teres. | | 4. Transverse. |

The capsular ligament and the ligamentum teres are attached to both bones entering into the construction of the joint. The transverse and the cotyloid ligaments are connected with the acetabular cavity ; the former partially fills up the notch or deficiency in its inferior part, whilst the latter surrounds its circumference in a ring-like fashion, and serves to still further deepen it.

Capsular Ligament (*capsula articularis*).—This is exceedingly strong, and surrounds the joint on all sides. *Superiorly*, it is attached around the acetabulum ; above and behind, directly to the innominate bone, just outside the rim of the cavity ; in front, to the outer aspect of the cotyloid ligament, and below, to the transverse ligament. *Inferiorly*, it clasps the neck of the femur. In front, it is attached to the whole length of the anterior intertrochanteric line, and to the root of the great trochanter. This attachment is very firm and strong. Behind and below, it falls short of the posterior intertrochanteric line by about half an inch, and it presents a weak attachment to the posterior and inferior surfaces of the neck of the femur.

If the capsule of the hip-joint has been carefully cleaned it will be seen that the fibres which compose it run in two different directions. The majority pass in a longitudinal

direction from one bone to the other ; others, however, may be observed to take a more or less transverse or circular course. The latter are only seen to advantage on the posterior aspect of the capsule, whilst the longitudinal fibres are massed on the front of the joint. Certain thickened portions of the capsule, with more or less distinct attach-




FIG. 71.—Dissection of Hip-joint from the front.

ments, are described under special names. These are :—

- | | |
|------------------|----------------------|
| 1. Ilio-femoral. | 3. Ischio-capsular. |
| 2. Pubo-femoral. | 4. The zonular band. |

The *ilio-femoral band* (ligamentum ilio-femorale) is placed over the front of the articulation, and constitutes the thickest and most powerful part of the capsule. It springs from the anterior inferior spine of the ilium, and from a depressed surface on the bone immediately to the outer side of this. As it proceeds downwards in the capsule, it divides into two limbs, which diverge slightly from each other. The outer

portion is implanted into the upper part of the anterior intertrochanteric line, close to the great trochanter; the inner portion, longer and almost vertical in direction, descends to find attachment into the lower end of the anterior intertrochanteric line. The interval between these two diverging parts of this ligament is occupied by a thinner portion of the capsule. The ilio-femoral band is sometimes called the *Y-shaped ligament*, but, in making use of this term, remember that the shape it presents is that of an inverted Y.

The *pubo-femoral band* (ligamentum pubocapsulare) is the name applied to several fasciculi of no great strength, which spring from the pubic bone and the thyroid membrane, and join the lower and anterior aspect of the capsule. In cases where the bursa under the ilio-psoas is continuous with the synovial membrane of the joint, the aperture of communication is placed between this band and the ilio-femoral band.

The *ischio-capsular band* (ligamentum ischio-capsulare) is stronger. It takes origin from the ischium below the acetabulum, and passes into the lower and posterior aspect of the capsule.

The *zonular band* (zona orbicularis) is composed of circular fibres, and will be observed on the posterior aspect of the capsule. It encircles the neck of the femur behind and below, but is lost as it is traced forwards towards the upper part and the front of the capsule.

The dissector has already observed the close connection which is exhibited between the capsule of the hip-joint and the tendons of the gluteus minimus, and the reflected head of the rectus. Reinforcing fibres are contributed to the capsule by both of these tendons.

Movements permitted at the Hip-joint.—Before the capsule of the joint is opened the range of movement which is permitted at the hip-joint should be tested. *Flexion*, or forward movement, is very free, and is only checked by the anterior surface of the thigh coming into contact with the abdominal wall. *Extension*, or backward movement, is limited by the ilio-femoral band. This powerful ligament has a most important part to play in preserving the upright attitude with the least possible expenditure of muscular exertion. In the erect posture the line of gravity falls slightly behind the line joining the central points of the two hip-joints. In the upright attitude the ilio-femoral bands are tight, and prevent the pelvis from rolling backwards on the heads of the femora. *Abduction*, or outward movement of the thigh, is checked by the pubo-femoral band. *Adduction*, or inward movement (*e.g.*, as in crossing one thigh over the other), is limited by the upper portion of the ilio-femoral band and the upper part of the

capsule. *Rotation inwards* tightens the ischio-capsular band, and is therefore in a measure restrained by it. *Rotation outwards* is limited by the outer portion of the ilio-femoral band. In *circumduction*, which is combination of the movements of flexion, abduction, extension, and adduction, different parts of the capsular ligament are tightened at different stages of the movement.

The *flexor muscles*, which operate on the femur at the hip-joint, are chiefly—(1) the ilio-psoas, and (2) the pectineus; the *extensors* are—(1) the gluteus maximus, and (2) the gluteus medius; the *abductors*—(1) the upper part of the gluteus maximus, (2) the gluteus medius, (3) the gluteus minimus; the *adductors*—(1) the three adductors, (2) the pectineus, (3) the lower part of the gluteus maximus, and (4) the obturator externus; the *inward rotators*—(1) the anterior part of the gluteus medius, (2) the anterior part of the gluteus minimus, (3) the tensor fasciæ femoris, and (4) the ilio-psoas; the *outward rotators*—(1) the two obturator muscles, (2) the gemelli, (3) the pyramidalis, (4) the quadratus femoris, and (5) the gluteus maximus.

Dissection.—The hip-joint may now be opened, and in doing this it is advisable to remove in the first instance the whole capsule, with the exception of the ilio-femoral band. The enormous strength of this portion of the capsule can in this way be appreciated. It is fully a quarter of an inch thick, and a strain varying from 250 lbs. to 750 lbs. is required for its rupture (Bigelow). It is very rarely torn asunder in dislocations, and consequently the surgeon is enabled in most cases to reduce the displacement by manipulation. The ilio-femoral band may now be removed.

Cotyloid Ligament (labrum glenoidale).—This is a firm fibro-cartilaginous ring, which is fixed to the brim or margin of the acetabulum. It bridges across the notch, and thus completes the circumference of the cavity, deepens it, and at the same time narrows slightly its mouth. The cotyloid ligament fits closely upon the head of the femur, and, acting like a sucker, exercises an important influence in retaining it in place. Both surfaces are covered by synovial membrane; its free margin is thin, but it is much thicker at its attachment to the acetabular brim.

Transverse Ligament (ligamentum transversum acetabuli).—This ligament is composed of some transverse fibres which bridge across the notch in the inferior part of the acetabulum, and are attached to its margins. The more superficial of these fibres are more or less directly connected with the deep surface of the cotyloid ligament as it stretches across the notch, but they do not fill up the entire gap; a narrow interval is left between the transverse ligament and the bone for the entrance of blood-vessels and nerves into the joint.

Ligamentum Teres (ligamentum teres femoris).—The ligamentum teres is not round, as its name might lead one to expect, but somewhat flattened and triangular in shape. Its

narrow femoral extremity is implanted into the upper margin of the pit which marks the head of the femur, whilst its flattened acetabular end is bifid, and is fixed to the margins of the notch in the lower part of the acetabulum, and also to the transverse ligament. This attachment can be defined by removing the




FIG. 72.—Dissection of Hip-joint from behind. The bottom of the Acetabulum has been removed to show the Ligamentum Teres.

synovial membrane and some areolar tissue. The ligamentum teres is completely surrounded by synovial membrane, and a small artery runs along it to the head of the femur. It is difficult to understand the part which the ligamentum teres plays in the mechanism of the hip-joint. It presents very different degrees of strength in different individuals. It

becomes very tense when the thigh is slightly flexed and then adducted.

Synovial Membrane and Interior of the Joint.—A mass of soft fat occupies the non-articular bottom of the acetabular cavity. Upon this the ligamentum teres is placed, and blood-vessels and nerves enter it by passing through the notch under cover of the transverse ligament. The vessels come from the internal circumflex and the obturator arteries, and the nerves come from the anterior division of the obturator nerve and from the accessory obturator, when it is present. A nerve-twig is also supplied to the back of the joint by the nerve to the quadratus femoris.

The *synovial membrane* lines the interior of the capsule. From this it is reflected on to the neck of the femur, and it clothes the bone as far as the margin of the articular cartilage which covers the head. Along the line of reflection some fibres of the capsular ligament proceed upwards on the neck of the femur and raise the synovial membrane in the form of ridges. These fibres are termed the *retinacula* or *cervical ligaments*.

These *cervical ligaments* are of some surgical importance. In intra-capsular fracture of the neck of the femur they may escape rupture, and they may then to some extent help to retain the fragments in apposition. Hence examinations of this class of fracture must be conducted gently, lest by rupturing this ligamentous connection the fragments be permanently displaced.

At the acetabular attachment of the capsular ligament the synovial membrane is reflected on to the cotyloid ligament and invests both its surfaces. It also covers the articular surface of the transverse ligament and the cushion of fat which occupies the bottom of the cavity. Lastly, it gives a tubular investment to the ligamentum teres.

Removal of the Limb.—The limb may now be removed from the trunk by dividing the ligamentum teres. It should then be taken to one of the tables set aside for the dissection of separate parts. Before proceeding to the dissection of the leg it is advisable to study the attachments of the various muscles to the femur. The bulk of these may be removed, but a small portion of each should be left, so that their connections may again be revised, should it be found necessary to do so at a later period.

THE LEG.

Surface Anatomy.—The relation of the tibia and fibula to the surface should be carefully investigated. The sharp anterior border of the tibia or shin does not form a projection visible to the eye, but nevertheless it is subcutaneous, and can be very distinctly felt when the finger is passed along it. It pursues a slightly sinuous course, and in its lower part becomes rounded-off and indistinct. The broad, flat, internal surface of the shaft of the tibia is also subcutaneous below the level of the insertion of the sartorius, and the inner border of the bone can be followed by the finger throughout its entire length. The fibula is more deeply placed, and the upper half of its shaft cannot be felt from the surface owing to the manner in which it is surrounded by muscles. The head of the bone, however, is very evident where it articulates with the outer and back part of the tuberosity of the tibia; and for a short distance above the external malleolus the shaft of the fibula is subcutaneous over a triangular area which is interposed between the peroneus tertius muscle in front and the peroneus longus and peroneus brevis muscles behind.

The two malleoli form marked projections in the region of the ankle. The internal malleolus is the broader and more prominent of the two; it does not descend so low down, however, and when viewed from the front it is observed to reach further forwards. This latter appearance is due to its greater breadth, because when examined from behind the posterior borders of the two projections are seen to occupy very nearly the same plane.

On the posterior aspect of the leg the prominence known as the "calf of the leg" is visible. This is largely due to the fleshy bellies of the gastrocnemius muscle. Below the calf and immediately above the heel the powerful tendo Achillis can be felt. In front of this tendon a slight hollow is apparent on either side of the limb.

As the skin is reflected from the dorsum of the foot during the dissection of the leg, the present opportunity should be seized for studying the surface anatomy of the foot. The individual tarsal bones cannot be recognised through the

integument which covers the dorsum of the foot ; but if the foot be powerfully extended the head of the astragalus will be brought into view in the shape of a slight prominence. The margins of the foot require very careful study, because it is by the recognition of certain bony projections in these that the surgeon is enabled to determine the point at which to enter the knife when he is called upon to perform partial amputation of the foot. Examine the *inner margin* first. Begin behind at the projection formed by the internal tuberosity of the os calcis, and proceed forwards. About one inch below the internal malleolus the inner edge of the sustentaculum tali may be recognised, and about one inch or a little more in front of this we recognise the tubercle of the scaphoid. Then comes the internal cuneiform bone, and this is succeeded by the first metatarsal bone. None of these bony points can be said to form distinct prominences on the surface of a well-developed foot. In order to distinguish them the inner margin of the foot must be judiciously manipulated by the fingers. On the *outer margin* of the foot the tubercle on the base of the fifth metatarsal bone stands out as a distinct landmark. Behind this is the cuboid, and still further back the outer surface of the os calcis, which is almost completely subcutaneous. When present in a well-developed form the peroneal tubercle on this surface may be distinguished about one inch below and a little in front of the external malleolus. If the foot be strongly inverted the anterior end of the os calcis will be seen to project on the surface.

Subdivision of the Leg into Regions.—In the dissection of the leg four distinct regions may be recognised, viz. :—

1. An *anterior tibio-fibular region*, in which are placed those structures which lie in front of the interosseous membrane, and between the two bones of the leg.
2. A *tibial region*, corresponding to the subcutaneous or inner surface of the shaft of the tibia.
3. A *peroneal region*, which includes the parts in relation to the outer surface of the fibula.
4. A *posterior tibio-fibular region*, in which are placed the parts on the back of the leg which lie behind the interosseous membrane and the two bones of the leg.

ANTERIOR TIBIO-FIBULAR REGION—DORSUM OF FOOT.

The anterior tibio-fibular region should be dissected first, and it is usual to conjoin with this the dissection of the dorsum of the foot. The following parts are exposed in this region :—

- | | |
|---|---|
| 1. Superficial veins. | 8. Anterior tibial vessels. |
| 2. Cutaneous nerves. | 9. Anterior peroneal artery. |
| 3. Deep fascia, with its inter-muscular septa, and annular ligaments. | 10. Anterior tibial nerve. |
| 4. Tibialis anticus. | 11. Recurrent articular branch from the external popliteal nerve. |
| 5. Extensor longus digitorum. | 12. Extensor brevis digitorum. |
| 6. Peroneus tertius. | 13. Dorsalis pedis artery. |
| 7. Extensor longus hallucis. | |

Reflection of Skin.—To place the limb in a convenient position for the dissection of this region, a block should be introduced beneath the knee, and the foot should be extended and fastened firmly to the table by means of hooks. The skin should be reflected from the *tibial* and *peroneal* regions at the same time. **Incisions** :—(1) a vertical cut along the middle line of the leg and dorsum of the foot to the base of the middle toe ; (2) a transverse incision across the ankle-joint ; (3) a transverse incision across the dorsum of the foot at the roots of the toes.

The four flaps of skin thus mapped out must now be raised from the subjacent fatty tissue, and the superficial veins and nerves dissected out.

Superficial Veins.—The *venous arch* on the dorsum of the foot, which receives the digital veins, should in the first place be dissected. From the inner extremity of this arch the *internal saphenous vein* will be seen to take origin, whilst from its outer end the *external saphenous vein* proceeds. Trace these vessels upwards. The former will be found to pass *in front* of the internal malleolus, whilst the latter ascends *behind* the external malleolus. Each is associated with the nerve which bears its own name.

Cutaneous Nerves.—The following are the cutaneous nerves which must be secured in this dissection :—

1. A branch from the external popliteal.
2. External saphenous.
3. Internal saphenous.
4. Musculo-cutaneous.
5. Anterior tibial.

The branch from the *external popliteal* frequently arises in common with the *ramus communicans fibularis*. It turns forwards, and is distributed upon the outer and anterior

aspect of the leg in its upper part. The *external saphenous nerve* can be readily found. It reaches the outer margin of the foot by passing behind the external malleolus in company with the vein of the same name. Trace it forwards, and it will be found to end upon the fibular side of the little toe. On the dorsum of the foot a connecting twig passes between the external saphenous and the outer division of the musculo-cutaneous nerve. The *internal* or *long saphenous nerve* should be looked for in front of the inner malleolus. It descends in company with the internal saphenous vein. It can with care be followed half-way along the inner margin of the foot, but there it ends. Above the ankle-joint several minute twigs from this nerve may be found passing forwards to reach the front of the leg.

The *cutaneous portion* of the *musculo-cutaneous nerve* appears in the lower third of the leg. It pierces the deep fascia a short way to the outside of the middle line of the limb. Almost immediately it splits into an inner and an outer part. The *inner division* extends forwards on the dorsum of the foot, and sends one branch to the inner side of the great toe, and a second to supply the adjacent sides of the second and third toes. It likewise gives a number of twigs to the skin upon the inner margin of the foot, and effects junctions with the anterior tibial and internal saphenous nerves. The *outer division* is smaller than the inner part. It gives several twigs to the skin on the dorsum of the foot, communicates with the external saphenous nerve, and then divides into two branches, which supply the contiguous margins of the third, fourth, and fifth toes. Therefore, with the exception of the adjacent sides of the great toe and the second toe, which are supplied by the anterior tibial nerve, and the outer side of the little toe, which is supplied by the external saphenous nerve, the musculo-cutaneous nerve furnishes twigs to the two margins of each of the toes (Fig. 59, p. 193).

Very frequently the distribution of the musculo-cutaneous nerve is more restricted, and in these cases the external saphenous nerve will, in all probability, be found to supply the outer two and a half toes.

The *anterior tibial nerve*, or rather its *internal terminal branch*, pierces the deep fascia on the dorsum of the foot in the interval between the first and second metatarsal bones.

It receives a communicating branch from the inner part of the musculo-cutaneous, and ends by dividing into two twigs, which go to supply the adjacent margins of the great toe and the second toe.

Deep Fascia.—The fatty superficial fascia should be removed in order that the deep fascia may be displayed. This aponeurosis does not form a complete investment for the leg. It is absent over the internal subcutaneous surface of the tibia, and is attached to the anterior and internal borders of that bone. It is also absent over the triangular subcutaneous surface on the lower part of the fibula, being attached to the ridges which limit this area in front and behind. It is not equally dense throughout. In the upper part of the front of the leg it is thick and strong, but it thins as it is traced downwards, and on the dorsum of the foot it becomes exceedingly fine. Its great strength in the upper part of the front of the leg is due to the fact that here it gives origin to subjacent muscles. In the neighbourhood of the ankle-joint it forms the thickened bands or annular ligaments which retain the tendons in position during the action of the muscles. Two of these may be examined at this stage, viz., the anterior and the external annular ligaments.

The *anterior annular ligament* consists of two portions—an upper and a lower. The *upper part* is a strong, broad band which stretches across the front of the leg immediately above the ankle-joint. By one extremity it is attached to the fibula, and by the other to the tibia. The *lower part* is placed over the ankle-joint. Externally it presents the appearance of a narrow, well-defined band, which is fixed firmly to the anterior part of the os calcis. As this is traced inwards it will be observed to divide into two diverging limbs. Of these the upper is attached to the inner malleolus, whilst the lower passes to the inner margin of the foot, and becomes connected with the plantar fascia. The different parts of the anterior annular ligament are continuous with the deep fascia, but can readily be distinguished on account of their greater density and thickness.

The *external annular ligament* is short and narrow, and bridges over the hollow between the external malleolus and the posterior prominence of the os calcis.

Intermuscular Septa.—As the deep fascia of the leg passes

backwards over the fibular region, two strong inter-muscular septa are given off from its deep surface. These are distinguished as the anterior and posterior peroneal septa. The *anterior peroneal septum* intervenes between the peroneal muscles and the extensor muscles, and is attached to the anterior border of the fibula. The *posterior peroneal septum* is interposed between the peroneal muscles and the muscles on the back of the leg, and is attached to the external border of the fibula. The leg is thus subdivided into three osteo-




FIG. 73.—Diagrammatic representation of the Fascia of the Leg. The fascia of the tibialis posticus is more a muscular aponeurosis than a true fascial septum; but it is convenient for descriptive purposes to regard it as one of the partitions.

fascial compartments, corresponding to the anterior tibio-fibular, peroneal, and posterior tibio-fibular regions. The *anterior compartment* is bounded by the investing deep fascia, the anterior peroneal septum, the anterior part of the inner surface of the fibula (that part which lies in front of the interosseous line), the interosseous membrane, and the external surface of the tibia. The *outer compartment* is bounded by the external surface of the fibula, the investing fascia, and the two peroneal septa. The

posterior compartment is much the largest, and its walls are formed by the posterior surface of the tibia, the hinder part of the internal surface and the whole of the posterior surface of the fibula, the interosseous membrane, the posterior peroneal septum, and the investing deep fascia. This compartment is still further subdivided by two partitions; but these will be studied later on.

Dissection.—The anterior compartment of the leg should now be opened by removing the deep fascia. The two portions of the anterior annular ligament, however, must be retained, and their borders should be separated artificially by the knife from the deep fascia, with which they are continuous. In the upper part of the leg it will be found impossible to raise the fascia from the subjacent muscles without lacerating their surfaces. It

should therefore be left in position. At a lower level it can readily be separated. Divide it in a longitudinal direction midway between the tibia and fibula. On throwing the inner piece inwards, its firm attachment to the anterior border of the tibia will become evident; and as the outer piece is turned outwards, the anterior peroneal septum will come into view.

Contents of the Anterior Tibio-fibular Compartment.—

Four muscles are brought into view by the above dissection, viz., the *tibialis anticus*, the *extensor longus digitorum*, the *extensor longus hallucis*, and the *peroneus tertius*. The *tibialis anticus* lies in relation to the tibia; the *extensor longus digitorum* is placed along the fibula; and on separating these muscles from each other, the *extensor longus hallucis* will be observed in the interval between them. The *peroneus tertius* lies upon the lower portion of the fibula, and in most cases is incorporated with the *extensor longus digitorum*. The *anterior tibial vessels and nerve* proceed downwards in this compartment. At first they are deeply placed, but as they approach the ankle they come nearer to the surface.

Dissection.—To expose the anterior tibial vessels and nerve in their entire course on the front of the leg, the *tibialis anticus* and the *extensor longus digitorum* must be separated from each other along the line of a strong intermuscular septum, which dips backwards between them, and affords a surface of origin to each. The knife should be carried upwards along the plane of this septum. By drawing aside the *peroneus tertius* muscle, the *anterior peroneal artery* will be seen piercing the interosseous membrane. It is a small artery which descends upon the lower end of the fibula. As the structures in the anterior tibio-fibular compartment are being exposed and cleaned, the dissector should at the same time carry on the dissection of the dorsum of the foot. Here the tendons of the muscles on the front of the leg must be followed to their insertions, and the *extensor brevis digitorum muscle* defined. The *dorsalis pedis artery* and the *anterior tibial nerve* should also be followed, and their branches traced to their various destinations.

Tibialis Anticus (*musculus tibialis anterior*).—The *tibialis anticus* is a powerful muscle, which takes origin from the lower part of the external tuberosity of the tibia, and from the upper half of the external surface of its shaft (Fig. 58, p. 183). It likewise derives many fibres from the deep fascia which covers it, from the fascial septum between it and the *extensor longus digitorum* and the portion of the interosseous membrane on which it rests. In other words, it springs from the structures which form the walls of the inner portion of the osteo-fascial compartment in which it lies.¹ A strong tendon issues from

¹ To understand the attachments of the muscles of the leg, it is necessary to bear in mind that the interosseous membrane, which stretches across the

its fleshy belly in the lower third of the leg, and this reaches the dorsum of the foot by passing through both portions of the anterior annular ligament. Here it inclines inwards, and, turning round the inner margin of the foot, gains insertion by two slips into the inner and lower part of the internal cuneiform bone, and into the adjoining part of the base of the first metatarsal bone. The tibialis anticus is supplied by the *anterior tibial nerve*.

Extensor Longus Digitorum.—This muscle arises, for the




FIG. 74.—Transverse section through the Calf of the Leg.

most part, from the structures which form the outer portion of the wall of the anterior tibio-fibular compartment. Thus it springs from the upper part of the outer tuberosity of the tibia, from the head of the fibula, and from the anterior part of the inner surface of the shaft of the fibula in its upper three-fourths (Fig.

interval between the two bones of the leg, and thus extends the surface of origin for these muscles, is attached to the *outer* border of the tibia (*i.e.*, between its outer and posterior surfaces) and to the interosseous line of the fibula. This interosseous line traverses the inner surface of the fibula, so as to divide it into an anterior and a posterior part. The anterior part gives origin to the extensor muscles and the posterior part to the flexor muscles.

58, p. 183). It also takes origin from a small portion of the upper part of the interosseous membrane, the deep investing fascia of the leg, the anterior peroneal septum, and the intermuscular septum, which dips backwards between it and the tibialis anticus. The tendon of the extensor longus digitorum descends in front of the ankle-joint, and, passing through the anterior annular ligament (p. 249), divides into four pieces, which diverge from each other on the dorsum of the foot to reach the four outer toes. On the dorsum of the first phalanx each of the inner three slips is joined on the outer side by a tendon from the extensor brevis digitorum.

The manner in which the four tendons of the extensor longus digitorum are inserted on the dorsal surfaces of the four outer toes is so similar to that in which the corresponding tendons of the fingers are attached, that a very brief description will suffice. An expansion is formed on the dorsal surface of the first phalanx; this is joined by the slender tendons of the lumbrical and interosseous muscles, and divides into a central and two lateral slips. The central slip is inserted into the base of the second phalanx, whilst the stronger lateral slips are prolonged onwards, and, uniting with each other, gain insertion into the base of the ungual phalanx. The extensor longus digitorum is supplied by the *anterior tibial nerve*.

Extensor Longus Hallucis.—The extensor longus hallucis is placed in the interval between the tibialis anticus and the extensor longus digitorum. In its upper part it is hidden from view by these muscles, but near the ankle it comes to the surface. It takes origin behind the extensor longus digitorum, from an extremely narrow strip of the anterior part of the inner surface of the shaft of the fibula in its middle two-fourths, and also from the adjoining part of the interosseous membrane. Its tendon crosses the lower part of the anterior tibial artery, and reaches the dorsum of the foot by passing downwards in front of the ankle-joint and through the anterior annular ligament (p. 249). It is inserted into the dorsal aspect of the base of the ungual phalanx of the great toe.¹ It is *not joined* by the innermost tendon of the extensor brevis digitorum. The extensor longus hallucis is supplied by the *anterior tibial nerve*.

¹ In most cases it likewise gives a slip to the base of the proximal phalanx.

Peroneus Tertius.—This is a small muscle which is continuous at its origin with the extensor longus digitorum. It arises from the lower fourth of the anterior part of the inner surface of the fibula, and from a corresponding extent of the interosseous membrane. It also receives fibres from the lower part of the anterior peroneal septum which intervenes between it and the peroneus brevis. Its slender tendon is inserted into the dorsal surface of the expanded base of the fifth metatarsal bone. It is supplied by the *anterior tibial nerve*.

Anterior Tibial Artery (*arteria tibialis anterior*).—The anterior tibial artery is the smaller of the two terminal branches of the popliteal. It takes origin on the back of the leg, at the lower border of the popliteus muscle, and it gains the anterior tibio-fibular compartment by passing forwards through the opening in the upper part of the interosseous membrane. In this part of its course it lies close to the inner side of the neck of the fibula, and appears in the present dissection immediately below the outer tuberosity of the tibia. On the front of the leg it takes a straight course downwards to the ankle-joint. Here it reaches the dorsum of the foot, and receives the name of *dorsalis pedis*.

In the upper two-thirds of the leg the anterior tibial artery is very deeply placed. It lies upon the interosseous membrane in the interval between the tibialis anticus on the inner side, and the extensor longus digitorum and the extensor longus hallucis on the outer side. In the lower third of the leg where the muscles give place to their tendons the artery comes nearer to the surface. In this part of its course it rests upon the tibia and is overlapped on the outer side by the extensor longus hallucis. Immediately above the ankle-joint the tendon of that muscle crosses the artery and comes to lie on its inner side.

Two *venæ comites* closely accompany the anterior tibial artery, and send short communicating branches both in front of it and behind it. The *anterior tibial nerve* is also intimately related to it. It joins the artery a short distance below the knee and soon takes up a position in front of the vessel. Near the ankle-joint the nerve as a rule assumes a place on the outer side of the artery.

On the front of the leg the anterior tibial artery gives off the following *branches*.—

- | | |
|-------------------------------|------------------------|
| 1. Muscular. | 3. External malleolar. |
| 2. Anterior recurrent tibial. | 4. Internal malleolar. |

The *muscular branches* are numerous and come off at irregular points along the whole length of the artery. They supply the muscles on the front of the leg.

Anterior Recurrent Tibial Artery (*arteria recurrens tibialis anterior*).—This small vessel springs from the anterior tibial immediately after it reaches the front of the leg. It turns upwards on the external tuberosity of the tibia in the fibres of the tibialis anticus muscle. Its terminal twigs reach the front of the knee-joint, and anastomose with the inferior articular branches from the popliteal artery.

Malleolar Arteries.—These arteries take origin immediately above the ankle-joint. The *external malleolar* (*arteria malleolaris anterior lateralis*) is the larger of the two, and passes outwards under cover of the tendons of the extensor longus digitorum and peroneus tertius, to reach the outer surface of the external malleolus. It anastomoses with the anterior peroneal and tarsal arteries. The *internal malleolar* (*arteria malleolaris anterior medialis*) runs inwards under cover of the tendons of the extensor longus hallucis and tibialis anticus. It inosculates with branches from the posterior tibial artery.

Arteria Dorsalis Pedis.—The dorsal artery of the foot is the continuation of the anterior tibial. It begins in front of the ankle-joint at a point midway between the two malleoli, and it extends forwards upon the forepart of the astragalus, the scaphoid, and the middle cuneiform bones to the posterior part of the interosseous space between the metatarsal bones of the great toe and the second toe. Here it leaves the dorsum of the foot by dipping downwards between the two heads of the first dorsal interosseous muscle to reach the sole and unite with the external plantar artery in the formation of the plantar arch. Its relations on the dorsum of the foot are very simple. (1) It lies in the interval between the tendon of the extensor longus hallucis on the inner side and the innermost tendon of the extensor longus digitorum on the outer side. (2) At its commencement it is crossed by the lower part of the anterior annular ligament, whilst near its termination it is crossed by the innermost tendon of the extensor brevis digitorum; with these exceptions the vessel is simply covered by the integument and fascia. (3) The

internal terminal branch of the anterior tibial nerve lies along its outer side, and two *venæ comites* accompany it.

As the dorsalis pedis artery traverses the dorsum of the foot it gives off several twigs to the inner margin of the foot, and also three named branches:—

1. The tarsal.
2. The metatarsal.
3. The first dorsal interosseous.




FIG. 75.—Dissection of the Dorsum of the Foot. The 2nd, 3rd, and 4th Metatarsal Bones have been removed to show the Plantar Arterial Arch in the sole of the foot.

Tarsal and Metatarsal Arteries.—The *tarsal artery* arises opposite the scaphoid bone, and the *metatarsal artery* near the bases of the metatarsal bones. They both run outwards under cover of the extensor brevis digitorum to reach the outer margin of the foot. There they anastomose with branches of the external plantar artery. The tarsal artery

also anastomoses with the external malleolar and peroneal arteries.

From the arch which is formed by the metatarsal artery *three dorsal interosseous arteries* proceed, one to each of the three outer interosseous spaces. At the clefts between the toes these divide and supply dorsal digital twigs to the adjacent sides of the second, third, fourth, and fifth toes. From the outermost interosseous artery a twig is also given to the outer side of the little toe.

First Dorsal Interosseous Artery.—This small vessel takes origin from the *dorsalis pedis* at the point where it turns downwards to reach the sole of the foot. It continues forwards upon the first dorsal interosseous muscle, and divides into dorsal digital branches for the inner side of the great toe and the adjacent sides of the great toe and second toe.

Anterior Peroneal Artery.—This is one of the two terminal branches of the peroneal branch of the posterior tibial. It reaches the front of the leg by piercing the interosseous membrane about one and a half or two inches above the outer malleolus, and it descends upon the lower part of the fibula under cover of the *peroneus tertius*. It is distributed on the outer side of the tarsus, where it anastomoses with the external malleolar and the tarsal arteries.

Extensor Brevis Digitorum.—The *extensor brevis digitorum* may now be examined. It arises from the anterior part of the *os calcis*, and also from the lower part of the anterior annular ligament. It splits into four fleshy bellies, which extend forwards and inwards on the dorsum of the foot, and end in four slender tendons for the four inner toes. The *innermost tendon* crosses the *dorsalis pedis* artery near its termination, and is inserted into the dorsal aspect of the base of the first phalanx of the great toe; the remaining three tendons join the long *extensor* tendons which go to the second, third, and fourth toes. The *extensor brevis digitorum* is supplied by the *external branch* of the *anterior tibial nerve*.

Anterior Tibial Nerve (*nervus peroneus profundus*).—The anterior tibial nerve is one of the terminal branches of the external popliteal. It arises on the outer side of the neck of the fibula, and, piercing the upper part of the *extensor longus digitorum* obliquely, joins the anterior tibial vessels a short distance below the external tuberosity of the tibia. These it

accompanies for the remainder of its course. In the first instance it is placed in front of them, but near the ankle-joint it lies on their outer side. Passing behind the anterior annular ligament, it ends by dividing into an internal and an external branch.

In its course through the leg the anterior tibial nerve gives *muscular branches* to the extensor longus digitorum, tibialis




FIG. 76.—Coronal section through the Left Ankle-joint, Astragalus, and Calcaneum (Paterson).

anticus, the extensor longus hallucis, and the peroneus tertius ; likewise a fine *articular twig* to the ankle-joint.

The *internal terminal branch* of the anterior tibial nerve is continued forwards upon the dorsum of the foot along the outer side of the dorsalis pedis artery. Reaching the first interosseous space it pierces the deep fascia, and divides to supply the contiguous margins of the great toe and the second toe (p. 238). Before it reaches the surface, it furnishes *articular twigs* to the tarso-metatarsal and metatarso-phalangeal

joints of the great toe, and frequently also a fine *muscular twig* to the dorsal surface of the first dorsal interosseous muscle.

The *external terminal branch* of the anterior tibial nerve turns abruptly outwards under cover of the extensor brevis digitorum, and ends on the dorsum of the foot in a gangliform enlargement. From this branches proceed for the supply of the extensor brevis digitorum, and the numerous articulations in the neighbourhood. One fine filament can, in most cases, be traced to the second dorsal interosseous muscle. The terminal swelling resembles closely the corresponding enlargement in which the posterior interosseous nerve of the upper limb ends.

Anterior Annular Ligament.—The dissector should again examine this ligament, and the arrangement of the structures which pass under it. The *upper portion* is attached to the fibula by its outer end, and to the tibia by its inner extremity. By dividing its fibular attachment, and throwing it inwards, it will be seen to give a separate and distinct sheath to the tibialis anticus.

The *lower portion* is the more important of the two. Its attachments have already been noted (p. 239). Examine the manner in which it holds the tendons in position. It consists of two layers, and these, by separating at certain points and becoming re-united at others, form three distinct compartments. Through the *innermost* passes the tendon of the tibialis anticus; through the *middle* one passes the tendon of the extensor longus hallucis; and through the *outermost* are transmitted the tendons of the extensor longus digitorum and peroneus tertius. On opening up these sheaths each will be seen to be lined by a synovial membrane. Lastly, note the position of the anterior tibial vessels and nerve as they pass under cover of the ligament. They lie between the extensor longus hallucis and the extensor longus digitorum (Fig. 76).

PERONEAL REGION.

The peroneal or outer compartment of the leg should now be opened by dividing, in a longitudinal direction, the fascia which covers it. Enclosed within it are :—

1. The peroneus longus.
2. The peroneus brevis.

3. The termination of the external popliteal nerve.
4. The musculo-cutaneous nerve.

Peroneus Longus.—The peroneus longus muscle arises from the head and from the outer surface of the shaft of the fibula in its upper two-thirds. A surface of origin is also afforded to it by the fascia which covers it, and by the two peroneal inter-muscular septa. It ends a short distance above the ankle in a long tendon, which is continued downwards behind the external malleolus. Gaining the outer margin of the foot, it proceeds forwards on the outer surface of the os calcis to the groove on the under surface of the cuboid, which conducts it transversely into the sole. Its insertion will be examined at a later period. It is supplied by the *musculo-cutaneous nerve*.

Peroneus Brevis.—This muscle arises from the lower two-thirds of the outer surface of the shaft of the fibula, below and in front of the peroneus longus, and from the peroneal inter-muscular septum on either side of it. Its tendon descends behind the external malleolus, and then turns forwards on the outer surface of the os calcis to gain an insertion into the projecting base of the metatarsal bone of the little toe.¹ On the back of the external malleolus the tendon of the peroneus brevis lies directly under cover of the tendon of the peroneus longus, and therefore in contact with the bone. On the outer surface of the os calcis the tendon of the peroneus brevis is placed at a higher level than that of its fellow muscle.

As the tendons of the two peronei muscles proceed downwards in the hollow between the external malleolus and the posterior prominence of the os calcis they are held in place by the *external annular ligament*, and their movements are facilitated by the presence of a common synovial sheath. On the outer surface of the os calcis each tendon is retained in position by a separate fibrous sheath, into which the common synovial membrane is prolonged. The peroneal tubercle of the os calcis intervenes between these two sheaths. The peroneus brevis is supplied by the *musculo-cutaneous nerve*.

External Popliteal Nerve (*nervus peronæus communis*).—This nerve has previously been traced as far as the neck of the fibula. At this point it disappears from view by passing

¹ A small tendinous slip will, as a general rule, be observed to proceed forwards from the tendon of the peroneus brevis to join the tendon of the long extensor on the dorsum of the little toe. This is the *peroneus quinti digiti*.

forwards between the peroneus longus muscle and the bone. The muscle must therefore be carefully turned aside from its origin in order that the nerve may be followed out. It will be found to give off a small *recurrent articular nerve* to the knee-joint, and then to divide into the *anterior tibial* and *musculo-cutaneous nerves*.

The *recurrent branch* accompanies the anterior recurrent tibial artery. It turns upwards in the fibres of the tibialis anticus. To the upper part of this muscle it gives several twigs, whilst its terminal filaments gain the front of the knee-joint.

The *anterior tibial nerve* pierces the upper part of the extensor longus digitorum to reach the front of the leg, where it has already been dissected.

Musculo-cutaneous Nerve (*nervus peronæus superficialis*).—This nerve proceeds downwards in the substance of the peroneus longus. It reaches the interval between the two peronei muscles, gives branches to both, and lastly comes to lie between the peroneus brevis and the extensor longus digitorum. In the lower third of the leg it pierces the fascia, and becomes cutaneous.

TIBIAL REGION.

This region corresponds to the subcutaneous or inner surface of the tibia. The deep fascia blends with the periosteum of the bone, and the only structures which have to be examined are:—

1. The internal saphenous vein.
2. The internal saphenous nerve.
3. The expanded tendons of insertion of the sartorius, semitendinosus, and gracilis.
4. Internal lateral ligament of the knee-joint.
5. Inferior internal articular artery and nerve.

The *internal saphenous nerve and vein*, as they pass from the anterior to the posterior tibio-fibular region, cross obliquely over the lower third of the inner surface of the tibia.

The insertion of the *sartorius*, *gracilis*, and *semitendinosus* into the upper part of the inner surface of the tibia should again be examined. Observe how the sartorius overlaps the tendons of the other two, and how the tendon of the gracilis

overlaps the upper part of the tendon of the semitendinosus. A synovial bursa separates these tendons from each other.

The *internal lateral ligament* of the knee-joint will be seen extending downwards for a short distance upon the inner aspect of the shaft of the tibia. Passing forwards under cover of this ligament, so as to gain the anterior aspect of the knee, are the *inferior internal articular vessels and nerve*.

POSTERIOR TIBIO-FIBULAR REGION.

The following is a list of the structures which are met with in this dissection:—

1. Superficial veins, { Internal saphenous.
External saphenous.
2. Cutaneous nerves.
3. Deep fascia.
4. Superficial muscles of the calf, { Gastrocnemius.
Plantaris.
Soleus.
5. Tendo Achillis and its bursa.
6. Posterior tibial vessels.
7. Posterior tibial nerve.
8. Deep muscles, { Popliteus.
Flexor longus hallucis.
Tibialis posticus.
Flexor longus digitorum.
9. Internal annular ligament.

Reflection of Skin.—The limb must now be placed on its anterior aspect, and the muscles of the calf rendered tense by flexing the foot at the ankle-joint. This position should be maintained by the aid of hooks, fastened to the toes and to the under surface of the table. *Incisions.*—(1) A longitudinal incision along the middle line of the leg on its posterior aspect to the extremity of the heel. (2) A transverse incision at the lower end of this, extending along the inner and outer margins of the foot for about two inches on either side.

The two flaps of skin thus marked out must be raised and turned outwards and inwards.

Superficial Veins.—The *internal* and *external saphenous veins* must be traced in the substance of the fatty superficial fascia. Both of these vessels have been seen in previous steps of the dissection. The *internal saphenous vein* has been observed to arise from the inner extremity of the venous arch on the dorsum of the foot, and it has been followed upwards for a short distance in front of the inner malleolus, and then upon the inner aspect of the lower part of the tibia. It has

also been dissected upon the inner aspect of the thigh and knee. It can now be exposed in its course along the inner side of the calf of the leg. It lies a short distance behind the internal border of the tibia. The *external saphenous vein* has been seen to arise from the outer end of the dorsal arch and to pass upwards behind the outer malleolus. It may now be followed as it ascends along the outer side of the tendo Achillis to the back of the leg, where it lies over the interval between the two heads of the gastrocnemius muscle. When it gains the lower part of the popliteal space it pierces the deep fascia and joins the popliteal vein.

Associated with each of these veins are certain cutaneous nerves, which must be displayed at the same time. The *small sciatic* is closely related to the external saphenous vein in its upper part, and the *external saphenous nerve* accompanies it in the lower half of the leg. In company with the *internal saphenous vein* we find the *internal or long saphenous nerve*.

Cutaneous Nerves.—These are very numerous. On the *inner side* of the leg are—(1) the *internal or long saphenous*; (2) the *posterior branch* of the *internal cutaneous*; and (3) the *internal calcanean* (Fig. 51, p. 156).

The guide to the *internal saphenous nerve* is the vein of the same name. It may now be exposed in its entire course along the inner side of the leg (Fig. 59, p. 193). The *posterior branch* of the *internal cutaneous* proceeds downwards a short distance behind the preceding nerve. It usually ends about the middle of the leg. The *internal calcanean* is a branch of the posterior tibial nerve. Dissect for it in the interval between the prominence of the heel and internal malleolus. It pierces the internal annular ligament nearer the former than the latter. Its branches of distribution to the skin of the heel and sole will be seen in a future dissection.

In the *middle line* of the leg two nerves will be found, viz. —(1) the *small sciatic*, and (2) the *nervus communicans tibialis*. They have both been previously seen in the dissection of the popliteal space. The *nervus communicans tibialis*, a branch of the internal popliteal, descends in the interval between the two heads of the gastrocnemius and pierces the deep fascia midway between the knee and ankle. A short distance below this it is joined by the *nervus communicans fibularis*, and then acquires the name of *external saphenous*.

On the *outer side* of the posterior aspect of the leg is the *nervus communicans fibularis*, a branch of the external popliteal. It descends upon the outer head of the gastrocnemius, and, perforating the deep fascia, unites with the *nervus communicans tibialis* a short distance below the middle of the leg, to form the *external saphenous nerve*. The latter has already been traced behind the external malleolus to the outer margin of the foot and little toe.

Deep Fascia.—A continuous view of the deep fascia on the back of the leg can now be obtained by removing the remains of the superficial fat. Observe how thin and transparent it is in the upper part of the leg, and how it thickens as it is followed downwards towards the heel. At no point, however, is it very dense. As it passes over the interval between the heel and the internal malleolus it forms the *internal annular ligament*. It is continuous above with the popliteal fascia, and a short distance below the knee, on the inner side, it receives a reinforcement of fibres from the tendons of the sartorius, the gracilis, and the semitendinosus.

Osteo-fascial Compartments on the back of the leg.—Divide the fascia along the middle line and turn it outwards and inwards. Leave the internal annular ligament intact. On raising the inner part of the fascia it will be seen to be attached to the internal border of the tibia. In fact, it blends with the periosteum covering the inner subcutaneous surface of this bone. On turning the outer portion of fascia outwards it will be observed to be directly continuous with the fascia on the front of the leg: further, the strong intermuscular septum (posterior peroneal septum) which passes in to join the external border of the fibula between the peroneal muscles and the muscles on the posterior aspect of the leg will be demonstrated. In this manner, then, the large posterior osteo-fascial compartment is formed, and, as the dissection goes on, two partitions will be noticed to stretch across it so as to subdivide it into three portions. The most superficial of these holds the superficial muscles of the calf; the intermediate portion contains the flexor muscles with the posterior tibial vessels and nerve: whilst the deepest part encloses the tibialis posticus muscle (Fig. 73, p. 240).

One of these partitions may be exposed at the present moment by removing the fat which is usually accumulated under cover of the tendo Achillis. Subjacent to this tendon is the layer of fascia in question. It stretches between the tibia and fibula, and separates the superficial from the deep group of muscles. In this locality it will be seen to be very dense, and to be strengthened by numerous transverse fibres. It becomes continuous on the inner side of the ankle with the internal annular ligament—indeed, the dissector will not fail to observe that it takes a more prominent part in the formation of this ligament than the investing aponeurosis of the limb. In the upper part of the leg it becomes very thin.

Superficial Muscles.—The superficial muscles of the calf

of the leg are three in number, viz., the gastrocnemius, the plantaris, and the soleus. The gastrocnemius is the most superficial; the soleus is placed under cover of the gastrocnemius; whilst the slender plantaris extends downwards and inwards between them. The tendons of insertion of the gastrocnemius and soleus unite to form the tendo Achillis.

Gastrocnemius.—This strong muscle arises by two heads from the posterior aspect of the lower end of the femur. These heads have been already studied in connection with the popliteal space, which they bound in its lower part. The *outer head* springs from an impression on the outer surface of the external condyle of the femur, and also from a small portion of the posterior surface of the bone immediately above the condyle. The *inner head* takes origin from the upper part of the internal condyle, and likewise from the inferior portion of the internal supracondyloid ridge of the femur. The two fleshy bellies swell out as they descend, and end near the middle of the leg in a thin aponeurotic tendon. They do not blend with each other. They are usually separated by a furrow, at the bottom of which the flattened tendon, to which the fasciculi of both heads are attached, may be seen. The internal head is the more bulky of the two, and it extends lower down than the external head. The flattened tendon in which they terminate narrows slightly as it descends, and a short distance below the middle of the leg it blends with the stouter tendon of the soleus to form the tendo Achillis.

The gastrocnemius is supplied by the *internal popliteal nerve*.

Dissection.—The aponeurotic tendon of the gastrocnemius may be divided in the middle of the leg, and the two heads of origin thrown upwards towards the back of the femur. The sural arteries from the




FIG. 77.—Posterior aspect of lower portion of Femur with Attachments of Muscles mapped out.

popliteal trunk, and the branches of supply from the internal popliteal nerve which enter the heads of the gastrocnemius, can thus be preserved. On raising the upper portion of the inner head, a bursa which intervenes between it and the condyle of the femur will be brought into view. On opening this with the knife it will, in all probability, be found to communicate with the interior of the knee-joint. The smooth and tendinous opposed surfaces of the gastrocnemius and the soleus, and the narrow tendon of the plantaris, which passes downwards and inwards between them, are now displayed.

Plantaris.—The small fleshy belly of the plantaris is not more than three or four inches long. It lies along the inner side, and partly under cover of the outer head of the gastrocnemius, and it arises from the posterior surface of the femur immediately above its external condyle. It ends in a slender tendon which is remarkable for its great length. This proceeds downwards and inwards between the gastrocnemius and soleus, and then runs along the inner side of the tendo Achillis to gain insertion into the posterior aspect of the os calcis. It is frequently closely connected with the tendo Achillis, and sometimes becomes blended with it or with the fascia of the leg before it reaches the os calcis.

The plantaris is supplied by a branch from the *internal popliteal nerve*.

Dissection.—The plantaris may now be reflected.

Soleus.—This is a flat, thick, and powerful muscle which arises from both bones of the leg, as well as from a strong fibrous arch which is thrown across the posterior tibial vessels. Its *fibular origin* is from the posterior surface of the head and the upper third of the posterior surface of the shaft of the bone; by its *tibial origin* it is attached to the oblique line of the tibia below the popliteal surface, and to the internal border of the bone below this as far down as the middle of the leg (Fig. 78, p. 260). The soleus ends in a strong stout tendon which joins with the tendon of the gastrocnemius to form the tendo Achillis. Branches from the *internal popliteal nerve* supply the soleus.

Tendo Achillis (tendocalcaneus).—This is the most powerful tendon in the body. It narrows as it descends, but near the heel it again expands slightly. It is inserted into the middle portion of the posterior surface of the os calcis. The fleshy fibres of the soleus are continued downwards on its deep surface to within a short distance of the heel. A synovial

bursa intervenes between the tendo Achillis and the upper part of the posterior surface of the os calcis.

Dissection.—Divide the soleus muscle transversely at the level at which it is joined by the gastrocnemius tendon, and turn downwards the tendo Achillis. Next make a vertical incision through the substance of the soleus in the middle line, so as to divide it into two lateral portions. By this dissection the tendinous arch which is thrown across the blood-vessels is exposed in the upper part, and both the tibial and fibular origins with the blood-vessels and nerves which enter them are preserved. The two portions of the fleshy belly of the muscle may now be turned outwards and inwards, and the branches which the muscle receives from the peroneal and posterior tibial arteries may be cleaned.

The deep fascial septum which stretches across from the tibia to the fibula between the superficial and deep muscles on the back of the leg may now be removed. In doing this note the manner in which it becomes continuous below with the internal annular ligament. On no account interfere with this ligament. The posterior tibial vessels and nerve, with their branches, should be dissected with as little disturbance to the deep muscles as possible. The muscle which lies on the fibula is the flexor longus hallucis; the muscle on the tibia is the flexor longus digitorum; whilst the third muscle between and on a deeper plane than the other two is the tibialis posticus.

Termination of the Popliteal Artery.—The termination of the popliteal artery lies under cover of the upper border of the soleus. It should now be cleaned, and it will be seen to end at the lower margin of the popliteus muscle by dividing into the *anterior* and *posterior tibial arteries*. Further, the venæ comites which accompany these vessels will be observed to join at this point to form the large popliteal vein.

Anterior Tibial Artery (arteria tibialis anterior).—The anterior tibial artery passes forwards between the two heads of the tibialis posticus muscle to the front of the leg, where it has already been dissected. In this part of its course the anterior tibial artery gives off the posterior recurrent tibial and the superior fibular branch. The *posterior recurrent tibial* is a small twig which is not always present. It runs upwards under cover of the popliteus muscle to the back of the knee-joint. The *superior fibular* runs outwards on the neck of the fibula, and is distributed to the muscles and integument in the neighbourhood.

Posterior Tibial Artery (arteria tibialis posterior).—The posterior tibial artery is the larger of the two terminal branches of the popliteal trunk. It takes origin at the lower border of the popliteus muscle and ends in the hollow on the inner side of the os calcis, under cover of the abductor hallucis, and at

the level of the lower border of the internal annular ligament, by dividing into the external and internal plantar arteries. In the first instance the artery is placed between the two bones of the leg upon the tibialis posticus muscle ; but as it descends it inclines gradually inwards, and at its termination it lies midway between the prominence of the os calcis and the internal malleolus.

In its upper two-thirds the posterior tibial artery is situated very deeply, being covered by the superficial muscles of the calf. In the lower third of the leg it appears between the tendo Achillis and the inner border of the tibia, and is merely covered by the integument, two layers of fascia, and lower down by the internal annular ligament. From above downwards it rests upon the tibialis posticus, the flexor longus digitorum, the tibia, and the posterior aspect of the ankle-joint.

Throughout its entire course the posterior tibial artery is closely accompanied by two *venæ comites*. The *posterior tibial nerve* is at first on its inner side, but it soon crosses the vessel, and then proceeds down on its outer side.

The following are the branches which issue from the posterior tibial artery :—

- | | |
|--------------|------------------------|
| 1. Muscular. | 4. Cutaneous. |
| 2. Nutrient. | 5. Internal calcanean. |
| 3. Peroneal. | 6. Communicating. |

The *muscular branches* supply the deep muscles on the back of the leg, and one or two of large size enter the soleus.

The *cutaneous branches* are given to the skin on the inner aspect of the leg.

The *nutrient artery* (arteria nutritia tibiæ) springs from the posterior tibial close to its origin, and after giving some twigs to muscles enters the nutrient foramen of the tibia. It is remarkable on account of its large size.

The *communicating branch* (ramus communicans) is given off about an inch above the lower end of the tibia. It passes transversely outwards under cover of the flexor longus hallucis, and joins the peroneal artery.

The *internal calcanean branch* (rami calcanei mediales) pierces the internal annular ligament, and accompanies the nerve of the same name to the skin of the heel and the sole.

The *peroneal artery* (*arteria peronæa*) is a large branch which proceeds from the posterior tibial about one inch or so below its origin. In the present stage of the dissection it is seen running obliquely downwards and outwards upon the *tibialis posticus* to reach the fibula. It is covered by the soleus, and is accompanied by the nerve to the *flexor longus hallucis*. It cannot be traced further at present, as it sinks into the substance of that muscle.

Posterior Tibial Nerve (*nervus tibialis*).—This is the continuation into the back of the leg of the internal popliteal nerve. It begins at the lower border of the *popliteus* muscle and ends in the hollow between the heel and the internal malleolus by dividing into the external and internal plantar nerves. It accompanies the posterior tibial vessels, and presents the same relations. For a short distance in the upper part of the leg it lies on the inner side of the posterior tibial artery, but it soon crosses it, and is then continued downwards for the remainder of its course on the outer side of the vessel.

It supplies—(a) *muscular branches* to the *tibialis posticus*, *flexor longus hallucis*, and *flexor longus digitorum*; (b) a *cutaneous twig*, the *internal calcanean*, which springs from it close to its termination, and pierces the internal annular ligament to reach the integument of the heel and sole of the foot; and (c) *articular filaments* to the ankle-joint.

Deep Muscles.—The *popliteus* muscle will be seen lying upon the posterior aspect of the knee-joint and upon the posterior surface of the tibia above the oblique line. Its tendon of origin lies within the capsule of the knee-joint, and can only be properly studied when this articulation is dissected.

Note the strong fascia which covers the posterior surface of the *popliteus*, and trace it upwards and inwards to the inner side of the knee. Here it will be observed to be continuous with the tendon of the *semimembranosus*, and through it, therefore, the *semimembranosus* may be regarded as having an insertion into the oblique line of the tibia.

The *flexor longus hallucis* is placed upon the posterior aspect of the fibula, and its tendon will be noticed to groove deeply the posterior border of the astragalus as it passes forwards to gain the sole of the foot. The *flexor longus digitorum* lies upon the tibia. The *tibialis posticus* rests upon



FIG. 78. — Posterior aspect of Bones of Leg with Attachments of Muscles mapped out.

the interosseous membrane upon a deeper plane and between the fleshy bellies of the two flexors.

Aponeurosis covering the Tibialis Posticus.—This constitutes the second partition which crosses the posterior osteo-fascial compartment of the leg. It is a strong aponeurosis, which is attached on the one hand to the internal border of the fibula, and on the other to the vertical ridge which descends from the oblique line on the posterior surface of the tibia. To demonstrate these attachments, the flexor muscle of the toes must be pushed inwards and some of its fibres divided. The flexor longus hallucis must in like manner be pushed outwards. The aponeurosis will then be seen to serve as a surface of origin for both of these muscles; and, on its removal, it will also be observed to give fibres by its deep surface to the subjacent tibialis posticus.

Popliteus.—The popliteus muscle arises by a stout narrow tendon, within the capsule of the knee-joint, from the front of the popliteal groove on the outer surface of the external condyle of the femur. The fleshy fibres are directed inwards and downwards, and spread out to obtain insertion into the posterior surface of the tibia above the oblique line, and also into the aponeurosis which covers the muscle.

The nerve to the popliteus has already been seen to arise from

the *internal popliteal trunk*. It can now be seen hooking round the lower margin of the muscle to reach its deep surface.

Flexor Longus Hallucis.—The flexor longus hallucis is a powerful muscle which arises from the posterior surface of the fibula below the origin of the soleus, from the posterior peroneal septum, and from the surface of the aponeurosis covering the tibialis posticus. Its tendon occupies a deep groove on the posterior border of the astragalus, and turns forwards under cover of the internal annular ligament to gain the sole of the foot. The flexor longus hallucis is supplied by the *posterior tibial nerve*.

Flexor Longus Digitorum.—The flexor longus digitorum arises from the posterior surface of the shaft of the tibia below the popliteus, and internal to the vertical ridge, which descends from the oblique line. It also derives fibres from the surface of the aponeurosis which covers the tibialis posticus. Crossing the lower part of the tibialis posticus, its tendon grooves the back of the internal malleolus on the outer side of the tendon of that muscle. It is continued under cover of the internal annular ligament into the sole of the foot. The flexor longus digitorum is supplied by the *posterior tibial nerve*.

Tibialis Posticus.—This muscle takes origin from the posterior surface of the interosseous membrane, from the posterior part of the inner surface of the shaft of the fibula, from the posterior surface of the shaft of the tibia on the outer side of the flexor longus digitorum, and from the aponeurosis which covers it. In Fig. 73, p. 240, the compartment which it occupies is shown in a diagrammatic manner, and the surfaces from which it takes origin are indicated. Towards the lower part of the leg the tibialis posticus inclines inwards under cover of the flexor longus digitorum, and its strong flattened tendon grooves the back of the internal malleolus to the inner side of the tendon of that muscle. Proceeding under cover of the internal annular ligament, its tendon is inserted into the tubercle of the scaphoid, and also by a number of slips into certain of the tarsal and metatarsal bones. These will be dissected later on. The tibialis posticus is supplied by the *posterior tibial nerve*.

Peroneal Artery (arteria peronea).—This vessel may now be traced downwards as it runs along the fibula under cover

of the flexor longus hallucis. It is accompanied by two *venæ comites*. About an inch or an inch and a half above the ankle-joint it ends by dividing into its two terminal branches—the anterior and the posterior peroneal arteries.

In addition to these it gives off—

1. Muscular branches.
2. The nutrient artery to the fibula.
3. The communicating artery.

The *muscular branches* supply the muscles around it. The




FIG. 79.—Dissection of the Inner Ankle.

nutrient artery (arteria nutritia fibulæ) enters the nutrient foramen on the posterior surface of the fibula. The *communicating artery* (ramus communicans) arises a short distance above the ankle-joint, and runs transversely inwards under cover of the flexor longus hallucis to join the posterior tibial artery.

The *anterior peroneal artery* (ramus perforans) passes forwards through the interosseous membrane, and has already been dissected on the front of the leg.

The *posterior peroneal artery* is continued downwards behind the external malleolus, and ends on the outer surface of the

os calcis, where it anastomoses with the external malleolar, tarsal, and anterior peroneal vessels.

Internal Annular Ligament.—The connections of this thickened band of deep fascia should be carefully studied, and also the arrangement of the structures which pass under cover of it into the sole of the foot. It bridges across the hollow between the prominence of the os calcis and the internal malleolus, and it is attached to both. Above, it is chiefly connected with that layer of the deep fascia which intervenes between the superficial and deep muscles on the back of the leg, but it is also continuous with the general aponeurotic investment of the limb. Inferiorly, its lower margin gives origin to the abductor hallucis, and is connected with the inner portion of the plantar fascia.

Passing under cover of this ligament the dissector will observe—(a) the posterior tibial vessels and nerve; (b) to the outer side of these, the tendon of the flexor longus hallucis; (c) to their inner side, the tendons of the flexor longus digitorum and tibialis posticus. From within outwards these structures lie in the following order:—

1. Tendon of tibialis posticus.
2. Tendon of flexor longus digitorum.
3. Posterior tibial vessels.
4. Posterior tibial nerve.
5. Tendon of flexor longus hallucis.

The tendons are isolated from each other and from the vessels and nerve by septa, which pass from the deep surface of the ligament to ridges on the bones. These septa can be demonstrated by slitting up the ligament, for a short distance, in the line of each of the tendons: each of the three sheaths will then be seen to be lined by a glistening synovial membrane.

Anastomosis around the Ankle-joint.—The dissector should next satisfy himself with regard to the anastomosis of arteries which takes place around the ankle-joint. On the *outer aspect* of the joint he will observe inosculation taking place between branches of the following arteries:—(a) external malleolar; (b) anterior peroneal; (c) posterior peroneal; and (d) tarsal.

On the *inner aspect* of the joint the internal malleolar branch of the anterior tibial anastomoses with small twigs from the internal calcanean branch of the posterior tibial.

SOLE OF THE FOOT.

In this dissection the dissector will meet with the following structures :—

1. Superficial fascia and cutaneous vessels and nerves.
2. Deep plantar fascia.
3. Superficial muscles,

{	Abductor hallucis.
	Flexor brevis digitorum.
	Abductor minimi digiti.
4. External and internal plantar vessels.
5. External and internal plantar nerves.
6. Tendons of flexor longus hallucis and flexor longus digitorum.
7. Musculus accessorius and lumbrical muscles.
8. Flexor brevis hallucis, adductor obliquus hallucis, and adductor transversus hallucis.
9. Flexor brevis minimi digiti.
10. Plantar arterial arch.
11. Arteria magna hallucis.
12. Tendons of peroneus longus and tibialis posticus.
13. Interosseous muscles.

Reflection of Skin.—The limb should be placed upon the table, with the sole of the foot facing the dissector, and the ankle supported by a good-sized block. Two incisions are required—(1) a longitudinal incision along the middle line of the sole, from the heel to the root of the middle toe; (2) a transverse cut, at the digital extremity of the mesial incision, across the sole at the roots of the toes. The skin should also be reflected from the plantar surface of each of the toes. This can be done by means of a longitudinal incision along its middle line.

Superficial Fascia.—When the flaps of skin which are mapped out by the above incisions are reflected, the peculiar character of the thick layer of superficial fascia becomes apparent. It is tough and granular, and in some respects resembles the superficial fascia which covers the tuber ischii. Traversing it are tough fibrous bands, which subdivide the fatty tissue into small lobules, and connect the thick skin of the sole with the plantar fascia.

Dissection.—The *internal calcanean nerve*, which has already been found piercing the internal annular ligament, should be traced to its distribution. It supplies the skin of the sole in the neighbourhood of the heel.

The superficial fascia may now be removed. Divide it along the middle line of the sole, and turn it outwards and inwards, cleaning at the same time the deep fascia. As the dissector approaches the outer and inner margins of the foot respectively, he will observe two furrows to extend forwards on each side of the central part of the deep fascia. Along the line of these a number of blood-vessels and some nerves will be seen piercing the deep fascia in order to reach the skin. Towards the heads of the

metatarsal bones the digital vessels and nerves are unprotected by the deep fascia, and here the dissector must proceed cautiously. The nerves and vessels which go to the tibial side of the hallux and to the fibular side of the little toe are especially liable to injury, as they perforate the fascia further back than the others. A band of transverse fibres, which crosses the roots of the toes and lies over the digital vessels and nerves, should be noticed. It is the *superficial transverse ligament* of the toes. It is closely connected with the skin, where it forms the cutaneous webs between the




FIG. 80.—Plantar Fascia and Plantar Cutaneous Nerves. (Paterson.)

toes. By forcibly separating the toes its connections will become evident. When the relations of this ligament have been studied it may be removed.

Plantar Fascia.—The plantar fascia, which is now brought into view, will be noticed to consist of three portions—(a) a central, and (b) two lateral parts. This subdivision is indicated by a difference in the density of the three parts and by two shallow furrows which traverse the foot in a longitudinal direction, one upon either side of the strong central portion of fascia. Each of the three portions

of fascia is in relation to a subjacent muscle. The *central portion* covers the flexor brevis digitorum; the *external lateral part* clothes the abductor minimi digiti; and the *internal lateral part* covers the abductor hallucis.

The *central portion* of the plantar fascia stands out in marked contrast to the lateral portions in point of strength and density. Behind, where it is attached to the internal tuberosity of the os calcis, it is narrow, but it expands as it passes forwards, and, near the heads of the metatarsal bones, splits into five processes, which are bound together by transverse fibres. In the intervals between the digital slips the digital vessels and nerves and the lumbrical muscles appear. Trace these processes forwards. One goes to the root of each toe, and there divides into two slips, which embrace the flexor tendons and become fixed to the flexor sheaths and to the transverse metatarsal ligament on either side of the toe. In its arrangement, therefore, this portion of the plantar fascia closely resembles the central part of the palmar fascia.

The *lateral parts* of the plantar fascia are weak in comparison with the central portion. They simply constitute aponeurotic coverings for the muscles which lie subjacent. A strong band is to be noted in connection with the *outer part*. It stretches between the prominence formed by the base of the fifth metatarsal bone and the external tuberosity of the os calcis.

In connection with the plantar fascia two *intermuscular septa* have also to be studied. These pass upwards into the sole, along the lines of the longitudinal furrows which mark off the central portion of the fascia from the lateral parts. They consequently lie one upon either side of the flexor brevis digitorum, and form partitions which separate it from the abductor hallucis on the one side, and the abductor minimi digiti on the other.

Dissection.—To demonstrate these septa, make a transverse incision through the central portion of the plantar fascia about an inch in front of the internal tuberosity of the os calcis, and also a longitudinal cut through the same piece of fascia, extending from the first incision along the middle line of the foot. Now raise the divided fascia and throw it outwards and inwards. Some difficulty will be experienced in effecting this, owing to its affording a surface of origin in its posterior part to the subjacent flexor brevis digitorum. As we approach the margins of this muscle the septa are brought into view.

Muscles and Tendons of the Sole.—It is customary to look upon the muscles and tendons which we find in the dissection of the sole as being disposed in four strata, viz. :—

First layer.	{ Abductor hallucis. Flexor brevis digitorum. Abductor minimi digiti.
Second layer.	{ Tendon of flexor longus digitorum. Musculus accessorius. Lumbrical muscles. Tendon of flexor longus hallucis.
Third layer.	{ Flexor brevis hallucis. Adductor obliquus hallucis. Adductor transversus hallucis. Flexor brevis minimi digiti.
Fourth layer.	{ Interosseous muscles. Tendon of the peroneus longus, Tendon of the tibialis posticus.

Dissection.—The lateral portions of the plantar fascia should be raised from the subjacent muscles. The three superficial muscles of the sole are then exposed to view and their connections can be studied. The *flexor brevis digitorum* is placed in the middle, the *abductor minimi digiti* extends along the outer margin of the sole, and the *abductor hallucis* along the inner margin of the sole. In the interval between the abductor hallucis and flexor brevis digitorum the *internal plantar nerve* and *artery* will be found. Follow the nerve toward the toes and dissect out its four digital branches. In doing so, care must be taken of the muscular twigs which are given to the flexor brevis hallucis and the innermost lumbrical muscle. Slender branches of the internal plantar artery accompany the digital nerves. Now trace the trunk of the *internal plantar nerve* backwards, by carefully separating the flexor brevis digitorum and the abductor hallucis along the line of the internal intermuscular septum. It will be found to give a branch of supply to each of these muscles. In the next place, separate the contiguous borders of the flexor brevis digitorum and abductor minimi digiti. The *external plantar artery* and *nerve* lie for a short portion of their course in the interval between these muscles. Approaching the prominent base of the fifth metatarsal bone, the artery disappears from view by turning inwards under cover of the flexor tendons. At the same point the external plantar nerve divides into its superficial and deep divisions. The *deep division* of the external plantar nerve cannot be dissected at present, as it accompanies the external plantar artery. The *superficial division*, however, should be traced to its distribution.

Flexor Brevis Digitorum.—This muscle arises from the internal tubercle of the os calcis, from the deep surface of the central part of the plantar fascia, and from the intermuscular septum on either side of it. About the middle of the sole the fleshy belly divides into four slips, which end in slender tendons for the four outer toes. These enter the fibrous flexor sheaths of the toes, and will be afterwards studied. The

External Plantar Artery (*arteria plantaris lateralis*).—This vessel is much larger than the internal plantar. It is accompanied by the external plantar nerve and two *vena comites*. From its origin in the hollow of the os calcis it proceeds outwards across the sole to reach the interval between the flexor brevis digitorum and the abductor minimi digiti. In this interval it is continued forwards for a short distance, and then at the base of the fifth metatarsal bone it turns suddenly inwards, and crosses the sole a second time, under cover of the flexor tendons, to form the plantar arch. In the present stage of the dissection it is only displayed as far as the base of the fifth metatarsal bone. Between its origin and this point its relations are as follows:—(1) it is placed between the abductor hallucis and the hollow of the os calcis; (2) it lies between the flexor brevis digitorum and the musculus accessorius; (3) it occupies the interval between the flexor brevis digitorum and the abductor minimi digiti. In this latter situation it is near the surface and is merely covered by the integument and fasciæ.

The *branches* which proceed from this part of the vessel are—(1) twigs to the neighbouring muscles; (2) *internal calcanean* branches which arise near its origin, and gain the heel by piercing the origin of the abductor hallucis; (3) cutaneous branches which appear through the deep fascia along the line of the external intermuscular septum; (4) twigs to the outer margin of the foot which anastomose with the tarsal and metatarsal branches of the *dorsalis pedis*.

Internal Plantar Nerve (*nervus plantaris medialis*).—The internal plantar nerve is the larger of the two terminal branches of the posterior tibial, and it takes origin in the hollow of the os calcis under cover of the internal annular ligament. It accompanies the internal plantar artery, and presents the same relations. After it emerges from under cover of the abductor hallucis, it gives off the digital branch to the inner side of the hallux, and then ends in the interval between the abductor hallucis and the flexor brevis digitorum by dividing into three digital branches.

The *branches* of the internal plantar nerve are:—

1. Cutaneous twigs to the skin of the sole.
2. Muscular branches.
3. Four digital branches.

The *cutaneous twigs* to the integument of the sole spring from the trunk of the nerve, and pierce the deep fascia in the line of the internal intermuscular septum.

The *four digital branches* supply both sides of the hallux and of the second and third toes, and also the tibial side of the fourth toe. The *first* or *innermost digital nerve* goes to the inner side of the great toe. The *second* divides to supply the contiguous margins of the great toe and the second toe. The *third* deals similarly with the second and third toes; whilst the *fourth* supplies the adjacent sides of the third and the fourth toes. In its digital distribution, therefore, the internal plantar nerve closely resembles the median nerve in the hand. To the *fourth* or *outermost digital branch* a twig of communication is given by the superficial division of the external plantar nerve.

The digital nerves should be traced along the toes. They are arranged in a manner very similar to that of the corresponding nerves of the fingers.

The *muscular branches* go to four muscles of the sole, viz., the abductor hallucis, the flexor brevis digitorum, the flexor brevis hallucis, and the innermost or first lumbrical muscle. The branches which supply the abductor hallucis and the flexor brevis digitorum arise from the trunk of the internal plantar nerve a short distance from its origin. The other two spring from the inner two digital nerves: thus, from the first digital nerve proceeds the branch to the flexor brevis hallucis; from the second, the branch to the first lumbrical.

External Plantar Nerve (*nervus plantaris lateralis*).—The external plantar nerve corresponds to the ulnar nerve in the palm of the hand. It accompanies the external plantar artery and presents the same relations. In the interval between the abductor minimi digiti and the flexor brevis digitorum, opposite the base of the fifth metatarsal bone, it divides into a deep and a superficial part. The *deep division* follows the plantar arch under cover of the flexor tendons. The *superficial division* divides into two digital branches.

From the trunk of the external plantar nerve proceed *two muscular branches*, viz., to the musculus accessorius and to the abductor minimi digiti.

The *first* or *outer digital branch* of the superficial part of the external plantar nerve goes to the outer side of the little

toe. It also gives muscular twigs to the flexor brevis minimi digiti and the interosseous muscles in the fourth intermetatarsal space.

The *second digital branch* divides to supply the adjacent sides of the fourth toe and little toe. It likewise sends a twig of communication to the fourth digital branch of the internal plantar nerve.

Dissection.—The abductor minimi digiti should be completely detached from its origin, and turned forwards in order that a good display may be obtained of the structures composing the second stratum of the sole.

Second Layer of Muscles and Tendons.—As the tendon of the *flexor longus hallucis* enters the sole it grooves the under surface of the sustentaculum tali and inclines inwards towards the great toe. The tendon of the *flexor longus digitorum*, on the other hand, inclines outwards to reach the middle of the foot, where it divides into four tendons for the four outer toes. Moreover, the tendons of these two muscles cross each other in the sole—the tendon of the flexor digitorum lying upon the plantar or superficial surface of the tendon of the flexor longus hallucis, and receiving from it a strong tendinous slip.

Sir William Turner has called attention to the fact that this slip, which passes from the tendon of the flexor longus hallucis to the tendon of the flexor longus digitorum, varies greatly in magnitude and in the manner in which it is connected with the flexor tendons of the toes. In the majority of cases it goes to the tendons of the second and third toes; in some cases, however, only to the tendon of the second toe, or to the tendons of the second, third, and fourth toes. Very rarely does it divide so as to bring all the tendons of the flexor longus digitorum into connection with the tendon of the flexor longus hallucis.

The *musculus accessorius*, which is inserted into the tendon of the long flexor of the toes, and also the four *lumbrical muscles* which arise from the flexor tendons, can now be distinguished. Note the position of the long plantar ligament between the two heads of origin of the accessorius.

Fibrous Flexor Sheaths.—Before tracing the flexor tendons forwards on the toes, it is necessary to examine the sheaths which retain them upon the plantar aspect of the phalanges. In their construction these fibrous sheaths are precisely similar to the corresponding sheaths of the fingers. They are not so strongly marked, but they present the same

thickenings over the shafts of the phalanges and the same want of strength opposite the interphalangeal joints. They may now be opened in order that the enclosed tendons may be examined. A synovial sheath is present in each to facilitate the play of the flexor tendons within them.

Insertions of the Flexor Tendons.—Two tendons, one from the flexor brevis digitorum, and one from the flexor longus digitorum, enter the flexor sheath of each of the four outer toes. Of these, the tendon of the former muscle corresponds with a tendon of the flexor sublimis in the hand, whilst the tendon of the flexor longus digitorum corresponds with a tendon of the flexor profundus. Further, they are inserted in exactly the same manner. The tendon of the flexor brevis, which is the more superficial, divides into two slips, and between these the tendon of the flexor longus proceeds forwards to its insertion into the plantar aspect of the base of the ungual phalanx. The two slips of the tendon of the flexor brevis are joined by their margins on the deep surface of the long flexor tendon, and then separate again to obtain insertion into the sides of the shaft of the second phalanx about its middle.




FIG. 82. — Second layer of Muscles and Tendons in the Sole of the Foot.

Tendon of the Flexor Longus Hallucis.—After giving its slip to the tendon of the flexor longus digitorum, the tendon of the flexor longus hallucis is prolonged forwards to the great toe. On the plantar aspect of the hallux it is retained in place by a flexor sheath, and finally it is inserted into the base of the terminal phalanx.

Musculus Accessorius (musculus quadratus plantæ).—This muscle takes a course straight forwards from the heel, and acts as a direct flexor of the toes. It also tends to bring the tendons of the long flexor muscle into a line with the toes

upon which they operate. It arises by two heads which embrace the os calcis and the long plantar ligament. The *inner head*, wide and fleshy, springs from the inner concave surface of the os calcis; the *outer head*, narrow, pointed, and tendinous, takes origin from the outer surface of that bone, and also from the long plantar ligament. The musculus accessorius is inserted into the tendon of the flexor longus digitorum in the middle of the sole. It is supplied by a branch from the *external plantar nerve*.

Lumbrical Muscles.—The lumbrical muscles of the foot are not so strong as the corresponding muscles in the palm of the hand. They are four in number, and arise from the tendons of the flexor longus digitorum. The outer three lumbricals spring from the adjacent sides of the tendons between which they lie; the first or innermost muscle takes origin from the tibial side of the tendon of the long flexor which goes to the second toe. The slender tendons of the lumbrical muscles proceed to the tibial side of the four outer toes, and are inserted into the expansions of the extensor tendon on the dorsal aspect of the proximal phalanges. The *first* or *innermost lumbrical* is supplied by the *internal plantar nerve*: the *others* by the *external plantar nerve*.

Dissection.—To bring the third layer of muscles into view we require to make the following dissection:—Divide the two heads of the accessorius and draw the muscle forwards from under the external plantar vessels and nerve. Sever also the tendons of the flexor longus digitorum and the flexor longus hallucis at the point where they emerge from under cover of the internal annular ligament. Upon cutting the branch which is given by the external plantar nerve to the accessorius these structures can be thrown forwards towards the toes. On raising the lumbrical muscles, the twigs which are furnished to the *second*, *third*, and *fourth* by the deep division of the external plantar nerve must be looked for. That for the second lumbrical muscle will be seen to take a recurrent course around the adductor transversus hallucis muscle. Lastly, cut the internal plantar nerve close to its origin and turn it aside.

Third Layer of Muscles.—The *flexor brevis hallucis* lies along the outer side of the abductor hallucis.

The *adductor obliquus hallucis* has a very oblique position in the sole, and hides to a great extent the interosseous muscles. It lies to the outer side of the flexor brevis hallucis.

The *transversus pedis*, or *adductor transversus hallucis*, is placed transversely across the heads of the metatarsal bones.

The *flexor brevis minimi digiti* may be recognised from its lying upon the fifth metatarsal bone.

The deep division of the external plantar nerve and the




FIG. 83.—The Muscles in the Sole of the Right Foot after removal of the Second Layer. (Paterson.)

plantar arterial arch are partially exposed, but they will be more fully displayed at a later stage.

Flexor Brevis Hallucis.—This muscle arises from the cuboid bone and from the slip from the tendon of the tibialis posticus

muscle, which goes to the middle and outer cuneiform bones. It is narrow and tendinous at its origin, but it soon divides into two separate fleshy bellies, which are ultimately inserted upon either side of the base of the proximal phalanx of the great toe. In the tendons of insertion two large sesamoid bones are developed. The inner head of the flexor brevis hallucis is closely connected with the tendon of the abductor hallucis, and is inserted in common with it. The flexor brevis hallucis is supplied by the *internal plantar nerve*.

Adductor Obliquus Hallucis.—The adductor obliquus hallucis arises from the sheath of the peroneus longus muscle and from the bases of the second, third, and fourth metatarsal bones. It tapers as it approaches the root of the hallux, and is inserted, with the outer head of the flexor brevis hallucis, into the fibular aspect of the base of the proximal phalanx of the great toe. It is supplied by the *deep division of the external plantar nerve*.

Adductor Transversus Hallucis.—The transverse adductor is a second special adductor of the great toe. It springs by a series of slips from the inferior metatarso-phalangeal ligaments of the third, fourth, and fifth toes, and proceeds transversely inwards under cover of the flexor tendons to find insertion into the fibular side of the base of the proximal phalanx of the great toe in common with the adductor obliquus hallucis. Its nerve of supply comes from the *deep division of the external plantar*.

Flexor Brevis Minimi Digiti.—The flexor brevis minimi digiti is a single fleshy slip, which springs from the base of the fifth metatarsal bone and the sheath of the peroneus longus tendon. It is inserted into the fibular side of the base of the proximal phalanx of the little toe. Its nerve of supply comes from the *superficial division of the external plantar nerve*.

Dissection.—The adductor obliquus hallucis and the flexor brevis hallucis must now be detached from their origins and thrown forwards, in order that the entire length of the plantar arterial arch, and the deep division of the external plantar nerve, may be displayed. In raising the adductor hallucis the branch which is given to it by the deep division of the external plantar nerve must be secured and retained.

Plantar Arterial Arch (arcus plantaris).—This is the continuation of the external plantar artery. It extends across the sole from the base of the fifth metatarsal bone to the

posterior part of the first intermetatarsal interval, where it is joined by the dorsalis pedis artery. The plantar arch is deeply placed, it rests upon the interosseous muscles close to the bases of the metatarsal bones, and it is covered by the flexor tendons, the lumbrical muscles, and the adductor obliquus hallucis. It is accompanied by the deep division of the external plantar nerve and by two *venæ comites*.

The *branches* which proceed from the plantar arch are :—

1. Articular.
2. Posterior perforating.
3. Digital.

The *articular twigs* arise from the concavity of the arch, and run backwards to supply the tarsal joints.

The *posterior perforating branches* are three in number. They proceed upwards in the back parts of the outer three intermetatarsal spaces. Each artery occupies the interval between the heads of the corresponding dorsal interosseous muscle. They end on the dorsum of the foot by joining the three dorsal interosseous branches of the metatarsal artery.

The *digital branches* are four in number, and are arranged in the same manner as the digital branches of the superficial palmar arch in the hand. The *first* or *outermost* goes to the fibular side of the little toe ; the *second* proceeds forwards in the fourth interosseous space, and divides to supply the contiguous sides of the fourth and little toes ; the *third* bifurcates at the cleft between the third and fourth toes, and gives the collateral branches to their adjacent sides ; and the *fourth* is disposed in a similar manner, and furnishes collateral branches to the contiguous margins of the second and third toes.

Each of the inner three digital arteries, at its point of division, sends upwards in the interosseous space a minute *anterior perforating branch*, to join the corresponding dorsal interosseous branch of the metatarsal artery.

Upon the sides of the toes the collateral branches are distributed in exactly the same manner as the corresponding arteries of the fingers.

Arteria Magna Hallucis (the *plantar digital branch* of the dorsal artery of the foot).—This vessel corresponds with the arteria radialis indicis and the arteria princeps pollicis of the hand. It arises from the dorsal artery of the foot in the back

part of the first interosseous space, and proceeds forwards to the cleft between the great toe and the second toe. Having supplied a branch to the inner side of the hallux, it divides into the collateral branches for the adjacent sides of the great toe and the second toe.




FIG. 84.—Arteries and Nerves of the Sole of the Foot. (Diagram.)

The external plantar nerve and its branches are tinted yellow.

Deep Division of the External Plantar Nerve.—This accompanies the plantar arch in its inward course across the sole, and ends in the deep surface of the adductor obliquus hallucis. In addition to this muscle it supplies all the interosseous muscles, with the exception of those in the fourth space, the adductor transversus hallucis, and the *three* outer lumbrical muscles. The twig to the second lumbrical

takes a recurrent course around the anterior border of the adductor transversus hallucis.

Transverse Metatarsal Ligament.—The adductor transversus hallucis should now be detached from its origin, and thrown inwards towards the hallux. This brings into view the transverse metatarsal ligament—a strong fibrous band which stretches across the heads of the five metatarsal bones. It is attached to the inferior ligaments of the metatarso-phalangeal joints. It differs from the corresponding ligament of the hand, inasmuch as it includes within its grasp the metatarsal bone of the hallux.

Dissection.—A satisfactory display of the *interosseous muscles* cannot be obtained unless the transverse metatarsal ligament be divided between the heads of the metatarsal bones. The toes can now be separated more freely from each other, and the interosseous muscles traced to their insertions. It is well also to reflect at this stage the flexor brevis minimi digiti.

Interosseous Muscles.—The *plantar interosseous muscles* are three in number, and are so placed that they adduct the three outer toes towards a line drawn through the second toe. They arise from the plantar aspects of the outer three metatarsal bones, and are inserted one upon the tibial side of each of the corresponding toes. The *dorsal interosseous muscles* are four in number. They occupy the four intermetatarsal spaces, and consequently they must be dissected both upon the plantar and dorsal aspects of the foot. They are arranged so as to abduct the second, third, and fourth toes from a line drawn through the second toe. They are inserted, therefore, as follows: the *first* upon the tibial side of the second toe; the *second* upon the fibular side of the same toe; the *third* upon the fibular side of the third toe; and the *fourth* upon the fibular side of the fourth toe. The slender tendons of the interosseous muscles are only very slightly attached to the bases of the proximal phalanges. They are for the most part inserted into the expansions of the extensor tendons on the dorsal aspect of the toes.

Tendon of the Tibialis Posticus.—Before leaving the sole of the foot the dissector must determine the precise insertions of the tendons of the tibialis posticus and of the peroneus longus. The tendon of the *tibialis posticus* is not merely inserted into the tubercle of the scaphoid. Fibrous slips are seen to spread out from it, and these may be traced to every

part of the first interosseous space, and proceeds forwards to the cleft between the great toe and the second toe. Having supplied a branch to the inner side of the hallux, it divides into the collateral branches for the adjacent sides of the great toe and the second toe.




FIG. 84.—Arteries and Nerves of the Sole of the Foot. (Diagram.)

The external plantar nerve and its branches are tinted yellow.

Deep Division of the External Plantar Nerve.—This accompanies the plantar arch in its inward course across the sole, and ends in the deep surface of the adductor obliquus hallucis. In addition to this muscle it supplies all the interosseous muscles, with the exception of those in the fourth space, the adductor transversus hallucis, and the *three* outer lumbrical muscles. The twig to the second lumbrical

takes a recurrent course around the anterior border of the adductor transversus hallucis.

Transverse Metatarsal Ligament.—The adductor transversus hallucis should now be detached from its origin, and thrown inwards towards the hallux. This brings into view the transverse metatarsal ligament—a strong fibrous band which stretches across the heads of the five metatarsal bones. It is attached to the inferior ligaments of the metatarso-phalangeal joints. It differs from the corresponding ligament of the hand, inasmuch as it includes within its grasp the metatarsal bone of the hallux.

Dissection.—A satisfactory display of the *interosseous muscles* cannot be obtained unless the transverse metatarsal ligament be divided between the heads of the metatarsal bones. The toes can now be separated more freely from each other, and the interosseous muscles traced to their insertions. It is well also to reflect at this stage the flexor brevis minimi digiti.

Interosseous Muscles.—The *plantar interosseous muscles* are three in number, and are so placed that they adduct the three outer toes towards a line drawn through the second toe. They arise from the plantar aspects of the outer three metatarsal bones, and are inserted one upon the tibial side of each of the corresponding toes. The *dorsal interosseous muscles* are four in number. They occupy the four intermetatarsal spaces, and consequently they must be dissected both upon the plantar and dorsal aspects of the foot. They are arranged so as to abduct the second, third, and fourth toes from a line drawn through the second toe. They are inserted, therefore, as follows: the *first* upon the tibial side of the second toe; the *second* upon the fibular side of the same toe; the *third* upon the fibular side of the third toe; and the *fourth* upon the fibular side of the fourth toe. The slender tendons of the interosseous muscles are only very slightly attached to the bases of the proximal phalanges. They are for the most part inserted into the expansions of the extensor tendons on the dorsal aspect of the toes.

Tendon of the Tibialis Posticus.—Before leaving the sole of the foot the dissector must determine the precise insertions of the tendons of the tibialis posticus and of the peroneus longus. The tendon of the *tibialis posticus* is not merely inserted into the tubercle of the scaphoid. Fibrous slips are seen to spread out from it, and these may be traced to every

bone of the tarsus with the exception of the astragalus, and also to the bases of the second, third, and fourth metatarsal bones. As it lies under and gives support to the head of the astragalus, the tendon of the tibialis posticus has developed within it a sesamoid nodule of fibro-cartilage, or perhaps a sesamoid bone.

Tendon of the Peroneus Longus.--The tendon of the




FIG. 85.—The insertions of the Tibialis Posticus and Peroneus Longus Muscles in the Right Foot. (Paterson.)

peroneus longus turns round the outer margin of the foot, and runs inwards in the groove on the under surface of the cuboid bone across the sole, to reach the base of the first metatarsal bone. As it traverses the sole it is enclosed in a fibrous sheath. This sheath is mainly formed by fibres derived from the long plantar ligament. Open the sheath and its smooth, glistening, internal surface will be displayed. This appearance is due to the synovial membrane which lines it. The tendon is inserted into the inferior part of the base of the

first metatarsal bone, and also to a slight degree into the adjacent part of the internal cuneiform bone. It likewise, in some cases, sends a slip to the base of the second metatarsal bone. As the tendon winds round the cuboid bone it is thickened, and contains a nodule of fibro-cartilage, or perhaps a sesamoid bone.

Dissection.—The dissection of the sole of the foot is brought to an end by sawing through the first metatarsal bone close to its base, and removing

its proximal extremity. A good view is thus obtained of the continuity between the dorsalis pedis artery and the plantar arch.

Anastomosis around the Knee-joint.—The most important of the anastomoses around the knee-joint are placed on the anterior aspect of the articulation, and take the form of three transverse arches. The *uppermost* of these *arterial arcades* passes through the superficial fibres of the quadriceps extensor close to the upper border of the patella, and is formed by the union of a branch from the superior external articular artery with another from the deep branch of the anastomotica.




FIG. 86.—Anastomosis on the front of the Right Knee-joint.

The middle and lower transverse arches are both placed under cover of the ligamentum patellæ. The *middle arch* runs across in the fatty tissue close to the lower end of the patella. The inferior external articular artery, with a branch which results from the union of a twig from the anastomotica, and another from the superior internal articular artery, enters into its formation. The *lowest arch* lies on the tibia immediately above its tubercle, and results from the anastomosis of the recurrent tibial and inferior internal articular arteries. The upper and middle of these transverse arches are connected, on each side of the patella, by ascending and descending branches, which anastomose with one another, and thus

enclose the patella in an irregularly quadrilateral arterial framework. From all sides of this arterial enclosure, twigs are given off which enter small foramina on the anterior surface of the patella to supply the osseous substance. Six arteries therefore take part in the formation of this system of anastomoses, on the front and lateral aspects of the joint, viz., the deep branch of the anastomotica, the two superior and the two inferior articular branches of the popliteal, and the anterior recurrent branch of the anterior tibial. In addition to the twigs which proceed from these to form the arterial arches, numerous branches are given which spread over the bones in the form of a close meshwork. During the dissection of the articulation these vessels will become apparent.

The knee-joint is supplied on its posterior aspect by twigs derived from all the articular branches of the popliteal. These twigs are variable in their origin, and the anastomoses which are formed between them are unimportant and inconstant. They are sometimes supplemented by another artery, the *posterior recurrent tibial*. This small vessel is a branch of the anterior tibial before it leaves the back of the leg. It ascends under cover of the popliteus muscle, ramifies over the lower part of the ligamentum posticum Winslowii, and inosculates with the two inferior articular branches of the popliteal.

The *azygos articular artery* is chiefly destined for the supply of the interior of the joint. It pierces the posterior ligament, passes forwards between the crucial ligaments, and ramifies in the fatty tissue in that situation. Its terminal twigs usually anastomose with the intermediate arch in front of the knee-joint. It will be dissected at a later stage in the interior of the joint.

Articular Nerves of the Knee-Joint.—The knee-joint is richly supplied with nerves. No less than ten distinct branches may be traced to it. The anterior crural, the external popliteal, and the internal popliteal trunks, contribute three twigs apiece to this articulation, and the obturator furnishes a filament to its posterior aspect. The *anterior crural* supplies the joint through branches which proceed from the nerves to the vastus externus, vastus internus, and subcrureus. These nerves pierce the fibres of the quadriceps muscle, and are distributed to the upper and anterior part of the articulation. The articular branch from the nerve to the vastus internus is of larger size than the other two, and it accompanies the deep branch of the anastomotic artery. The *external popliteal nerve* gives off—(1) the superior and inferior external articular nerves: these accompany the arteries of the same name, and end in fine

filaments, which pierce the capsule of the joint ; and (2) the recurrent articular nerve which accompanies the anterior recurrent tibial artery. This nerve ends chiefly in the tibialis anticus muscle ; but a fine twig may reach the lower part of the anterior aspect of the knee-joint. The *internal popliteal nerve* furnishes the knee-joint with superior and inferior internal articular and azygos articular nerves, which accompany the arteries of the same name. The branch from the *obturator nerve* descends on the posterior aspect of the popliteal artery as far as the back of the knee-joint. At this point it leaves the artery and, inclining forwards, breaks up into several filaments which separately pierce the posterior ligament.

ARTICULATIONS.

The dissection of the knee-joint, the ankle-joint, the tibio-fibular joints, and the various articulations of the foot, may now be proceeded with. It is possible that the ligaments may have become hard and dry. If this be the case, soak the joints in water for an hour or two.

KNEE-JOINT.

In the knee-joint (*articulatio genu*) three bones are in apposition, viz., the lower end of the femur, the upper end of the tibia, and the patella. It is the largest and most complicated articulation in the body ; and if the bones be examined in the skeleton, the joint presents an apparent insecurity, because the bony surfaces show little adaptation the one to the other. In reality, however, the knee-joint is very strong, and very rarely suffers dislocation on account of the strength of the ligaments which retain the bones in place. The ligaments on the exterior of the joint are :—

1. The capsular ligament.
2. Two lateral ligaments—external and internal.
3. The ligamentum patellæ (or anterior ligament).
4. The posterior ligament.

Dissection.—The popliteal vessels and nerves, and the muscles surrounding the knee-joint, must be removed. Portions of the tendons of

the biceps, semimembranosus, sartorius, semitendinosus, gracilis, and popliteus, together with small pieces of the heads of the gastrocnemius, should be left in place in order that their connection with the ligaments of the joint may be studied. The quadriceps extensor may be divided about three inches above the patella, and the lower part allowed to remain in position. Further, the various articular arteries which surround the joint should be followed to their terminations.




FIG. 87.—Dissection of Knee-joint from the front. The Patella has been thrown down.

Capsule (capsula articularis).—The capsule of the knee-joint, together with the internal and posterior ligaments, forms a complete investment for the articulation. In the upper and front part of the joint it is deficient, but here its place is taken by the common tendon of the quadriceps extensor muscle. The capsule may be regarded as an aponeurotic expansion

on the front of the articulation, which fills up the intervals between the two lateral and the anterior ligaments. The fascia lata and expansions from the surrounding tendons enter into its formation. Thus, on the outer aspect, it is largely composed of the ilio-tibial band of fascia lata as this proceeds downwards to its attachment to the tibia. Traced backwards, the capsule will be seen to be prolonged over, and to hide from view, the external lateral ligament. On the inner side of the limb it receives expansions from the sartorius and semi-membranosus, and fuses with the internal lateral ligament.

Ligamentum Patellæ.—This forms the anterior ligament of the knee-joint, and constitutes, at the same time, the tendon of insertion of the quadriceps extensor muscle. By the removal of the capsular expansion from its surface it may be fully exposed and its margins defined.

The *ligamentum patellæ* is a strong band, about two inches long, which is attached above to the apex and lower border of the patella, and below to the lower part of the anterior tubercle of the tibia. Its superficial fibres are directly continuous over the surface of the patella with the central part of the common tendon of the quadriceps extensor. Its deep surface rests upon the infrapatellar pad of synovial fat, and upon a small bursa which intervenes between it and the upper part of the anterior tubercle of the tibia.

Dissection.—The external lateral ligament may be exposed by removing the part of the capsule which is formed by the ilio-tibial band of fascia lata, and also the prolongation which this gives backwards over the ligament. By this proceeding the inferior external articular artery will be displayed as it extends forwards to the front of the joint.

External Lateral Ligament (*ligamentum collaterale fibulare*).—This is rounded and cord-like. It stands well away from the joint, and is attached above to a tubercle on the outer tuberosity of the femur. Below, it is fixed to a depression




FIG. 88.—The External Lateral Ligament of the Knee-joint.

on the head of the fibula in front of the styloid process. It is closely associated with the tendon of the biceps and the tendon of the popliteus. It splits the tendon of the biceps into two pieces, and extends vertically downwards to its fibular attachment between them. The tendon of the popliteus takes origin from the outer tuberosity of the femur below and in front of the femoral attachment of the external lateral ligament. As the tendon proceeds backwards it is placed under cover of the ligament.

An additional slip is sometimes described as the *posterior part* of the external lateral ligament. When present it is attached to the femur, under cover of the outer head of the gastrocnemius, in connection with the posterior ligament. Below, it is implanted into the styloid process of the fibula.

Internal Lateral Ligament (ligamentum collaterale tibiale).—The internal lateral ligament is a long flat band, broader in the middle than at either extremity, which springs from the inner tuberosity of the femur below the adductor tubercle. As it descends it inclines slightly forwards, and finally it gains attachment to the upper part of the shaft of the tibia below the internal tuberosity. The main part of the tendon of the semimembranosus extends forwards under cover of its posterior border to gain an insertion into the tuberosity of the tibia, whilst lower down the inferior internal articular vessels are carried forwards between it and the bone. The tendons of the sartorius, gracilis, and semitendinosus, lie upon its superficial surface, but are separated from it by an intervening bursa.

Posterior Ligament.—The posterior ligament stretches from the external to the internal lateral ligament. Above, it is fixed to the upper margin of the intercondyloid notch, whilst on either side it becomes incorporated with the corresponding head of the gastrocnemius. Below, it is attached to the posterior border of the upper end of the tibia. A strong slip derived from the tendon of the semimembranosus strengthens the ligament on its posterior aspect. This band passes upwards and outwards towards the external condyle of the femur.

Sometimes the term "posterior ligament" (ligamentum posticum Winslowii) is restricted to this oblique band from the semimembranosus, and the remainder of the ligament as described above is then regarded as a portion of the capsule.

The posterior ligament presents a number of apertures for the entrance of blood-vessels and nerves into the interior of the joint. The *azygos* artery is the most conspicuous of these vessels. An opening may likewise sometimes be observed over the upper part of the internal condyle of the femur. Through this protrudes a pouch of synovial membrane which forms a bursa under the inner head of the *gastrocnemius*. As a rule, however, this bursa is independent of the knee-joint, and the aperture in the ligament is absent. Another opening is situated in the outer part of the ligament, and gives exit to the tendon of the *popliteus*.

Dissection.—A vertical incision should be made into the joint on either side of the patella and *ligamentum patellæ*, in order that the common extensor tendon and the patella may be thrown downwards over the upper end of the tibia. The joint is now opened from the front, and the parts in the interior may be observed.

Interior of the Joint.—First note the great pad of soft fat which is placed on the deep surface of the *ligamentum patellæ*. In vertical section this fatty mass is triangular in form (Fig. 89). It is termed the *infra-patellar pad*, and it fills up the interval between the patella, femur, and tibia, and adapts itself to the varied forms which this recess adopts in the different movements of the joint. It is separated from the interior of the joint by a covering of synovial membrane, and from its surface a band of this membrane extends backwards and upwards to the intercondyloid fossa of the femur, where it is attached. This band is termed the *ligamentum mucosum*. As it approaches the femur it becomes narrow and slender; but, before it fairly rises from the surface of the *infrapatellar pad*, it is broad and triangular, and presents two free margins which extend along the lateral borders of the patella in its lower part, and receive the name of *ligamenta alaria* (*plicæ alares*). It must be clearly understood that these are not ligaments in the ordinary sense of the word, but merely folds of synovial membrane.

Within the joint the dissector is now able to recognise :

1. The two crucial ligaments.
2. The two semilunar cartilages.

Synovial Membrane.—This is the most extensive membrane of the kind in the body. It lines the deep surface of the ligamentous structures which surround the joint, and extends upwards for at least an inch beyond the articular surface of the femur, in the form of a great *cul-de-sac*, under cover of the common tendon of the quadriceps. By its upper part this pouch usually communicates by an orifice of greater or less

width with a large bursa which lies at a higher level upon the front of the femur. The synovial membrane covers both surfaces of the semilunar cartilages, gives a partial investment to the crucial ligaments, and contributes a pouch-like prolongation along the tendon of the popliteus. The synovial investment of the crucial ligaments is not complete, and is carried forwards upon them from the posterior wall of the joint. The prolongation upon the tendon of the popliteus extends downwards between the external semilunar cartilage and the




FIG. 89.—Vertical antero-posterior section through the Knee-joint.

back part of the upper end of the tibia. It facilitates the play of the tendon over that bone, and comes very close to the upper part of the superior tibio-fibular joint. Indeed, the synovial membrane of this joint may, in some cases, be found continuous with it.

Dissection.—Divide the ligamentum mucosum and remove the infra-patellar pad of fat. The bursa between the ligamentum patellæ and the upper part of the anterior tubercle of the tibia may now be opened and examined. Next dissect away the posterior ligament of the joint and trace the azygos articular artery, which pierces it, forwards to the crucial ligaments. It will now be seen that the posterior surface of the posterior crucial ligament is not covered by synovial membrane, and that it is connected by areolar tissue to the deep surface of the posterior ligament. Define the attachments of the crucial ligaments by removing the synovial

membrane which is wrapped round them and the areolar tissue in connection with them. The semilunar cartilages should also receive the attention of the dissector, and the manner in which their fibrous pointed extremities are fixed to the tibia must be studied. At this stage the changes produced in the degree of tension of the crucial ligaments, and the change brought about in the position of the semilunar cartilages by movements of the joint, should be examined.

Movements at the Knee-joint.—The movements of the knee-joint are those of flexion and extension. The leg can be bent back until the prominence of the calf comes into contact with the posterior aspect of the thigh; but in extension the movement is brought to a close when the leg comes into a line with the thigh. In this position the joint is firmly locked, and the anterior crucial, the lateral, and the posterior ligaments being fully stretched, the leg and thigh are converted into a rigid column of support. In flexion, however, the lateral and posterior ligaments are relaxed, and a certain amount of rotation of the tibia upon the femur is allowed.

But the movements of flexion and extension at the knee-joint are by no means so simple as at first sight they might appear to be, and to obtain some appreciation of them it is necessary to subject the opposed articular surfaces to a close scrutiny. Flex the joint acutely, and examine the cartilage-covered surface of the lower end of the femur. It consists of an anterior trochlear portion for the patella, and two condylar surfaces which move on the tibia. The trochlea is separated from the surface of the external condyle by a faintly marked groove, which takes a slightly curved course from the external border of the lower end of the femur inwards and backwards to the fore part of the intercondyloid fossa. At either extremity this groove widens out into a distinct depression. In full extension the outer depression rests upon the anterior part of the external semilunar cartilage, whilst the inner depression rests upon the anterior border of the external tubercle of the spine of the tibia (Bruce Young). The line of demarcation between the trochlea and the lower surface of the internal condyle of the femur is not so distinct. Close to the inner margin of the bone there is a depression which, in full extension, rests upon part of the anterior horn of the internal semilunar cartilage (Bruce Young): but external to this the trochlear surface is prolonged backwards for a certain distance along the anterior and inner margin of the intercondyloid fossa. A portion of the internal condyle is thus included in the trochlear surface, viz., the portion skirting the inner border of the anterior part of the intercondyloid fossa, and this is termed the "crescentic facet" of the internal condyle.

The deep surface of the patella may next be examined (Fig. 87), and its movements in connection with flexion and extension of the knee-joint studied. A high vertical ridge divides its deep surface into a large external and a smaller internal area. Each of these is still further subdivided by faint ridges on the cartilage which coats the surface. A faint line upon the inner area of the patella descends in a vertical direction so as to mark off a narrow strip close to the inner border of the bone. This strip is called the *internal perpendicular facet*. Two horizontal lines extend outwards from the outer border of the internal perpendicular facet to the outer border of the bone, and subdivide the remainder of the inner area and the whole of the outer area into three facets each. In a well-marked patella, therefore, the deep cartilage-covered surface shows seven facets, viz., an upper pair, an intermediate pair, a lower pair, and an internal perpendicular facet (Goodsir).

The faceted appearance of the deep surface of the patella indicates that in the movements of this bone upon the trochlear surface of the femur the

entire articular surface is never in contact with the femur at the same time. In flexion and extension of the knee, the patella moves downwards and upwards in a curved path, the concavity of which looks upwards, backwards, and outwards. The different facets come into contact and break contact with the femur in regular succession. Let us suppose the knee-joint to be acutely flexed: in this condition of the limb the internal perpendicular facet of the patella rests upon the crescentic facet of the internal condyle of the femur, while the outer of the two upper patellar facets is in contact with the outer lip of the trochlear surface of the femur. No part of the patella touches the inner lip of the trochlear surface. As the leg is moved from the fully flexed to the fully extended position, the two upper facets, then the two intermediate facets, and, lastly, the two lower facets, come successively into contact with the trochlear surface of the femur (Goodsir). In Fig. 89 the position of the patella in the fully extended knee is exhibited.

Now examine the condylar surfaces of the femur (Fig. 87). The posterior two-thirds of the internal condyle will be seen to be of equal extent with, and parallel to, the external condyle. The anterior third of the internal condyle, however, turns obliquely outwards to join the trochlear surface. The external condylar surface has no part corresponding with this, and its presence in connection with the internal condyle gives rise to the "screw-home" movement, which is so characteristic of the knee-joint when fully extended. At the commencement of flexion and at the completion of extension there is a screw movement, or a movement of rotation of the tibia and femur on each other. As the leg is moved forwards from the condition of acute flexion, the condyles of the femur roll and glide over the surfaces on the upper end of the tibia until the surface of the external condyle, and the corresponding part of the internal condyle, are exhausted. This movement of the femoral condyles has been compared to that of "a wheel partially restrained by a drag" (Goodsir). Any additional movement beyond this point must necessarily take place in connection with the anterior oblique third of the internal condyle. This produces a rotation or screw-like motion of the femur inwards. The internal condyle travels backwards round the spine of the tibia, and the anterior part of the intercondyloid notch comes into contact with the anterior crucial ligament and the internal tubercle of the tibial spine (Bruce Young). The joint is now "screwed home" or locked. In the initial stage of flexion the reverse movement must be accomplished. The unlocking of the joint can only be brought about by a rotation inwards of the tibia, or a rotation outwards of the femur.

When fully extended, as we have seen, the joint is locked, and the posterior, lateral, and anterior crucial ligaments are tense. The limb is converted into a rigid column, and the upright posture is thereby maintained with the smallest possible degree of muscular exertion.

The **muscles** which operate upon the bones of the leg so as to produce flexion and extension of the limb at the knee-joint are:—(1) *extensors*, the four parts of the quadriceps extensor; (2) *flexors*, the biceps, popliteus, sartorius, gracilis, semitendinosus, and semimembranosus. Of these, only one is inserted on the outer side of the limb, viz., the biceps. The other five are inserted into the tibia on the inner side of the leg.

Dissection.—In order to obtain a proper view of the attachments of the crucial ligaments the following dissection should be made:—The femur must be sawn across about two inches above its lower articular surface. When this is done the saw should be applied to the cut surface of the lower

part of the bone, and a vertical cut made through it so as to divide it into a right and a left lateral portion. The saw-cut should be planned to end inferiorly in the intercondyloid fossa between the condyles and between the upper attachments of the two crucial ligaments. By this procedure the crucial ligaments can be studied singly, or together, and their relation to the lateral ligaments of the joint can be examined. It will be seen that the external lateral ligament and the anterior crucial ligament constitute a pair of ligaments appropriated by the external condyle, to either side of which they are fixed; while the internal lateral and the posterior crucial ligaments belong to the internal condyle of the femur, and are attached on either side of it. When this relationship is observed, the internal lateral ligament may be divided. This will, in a measure, set free the internal condyle, and give greater space for the study of the crucial ligaments.

Crucial Ligaments (*ligamenta cruciata genu*).—These are well named, because they cross each other like the limbs of the letter X in the interval between the two condyles of the femur. This crucial arrangement is seen whether they are viewed from the side, by the removal of the lower part of one condyle, or from the front or the back of the joint. The anterior crucial ligament is attached to the external condyle, whilst the posterior is fixed to the internal condyle of the femur. They are consequently sometimes termed *external* and *internal*.

The *anterior crucial ligament* springs from the intermediate rough area on the upper surface of the tibia, immediately in front of the inner tubercle which surmounts the tibial spine. From this it proceeds upwards, backwards, and outwards, to gain attachment to the posterior part of the inner surface of the external condyle of the femur (Fig. 77, p. 255).

The *posterior crucial ligament* springs from the posterior sloping part of the intermediate rough area on the upper surface of the tibia, behind the tibial spine, and behind also the attachments of the posterior horns of both semilunar cartilages. It proceeds upwards, forwards, and somewhat inwards, and, crossing the anterior crucial ligament, is attached in the fore part of the intercondyloid fossa to the outer surface of the anterior oblique portion of the internal condyle. It receives one, or sometimes two, strong slips from the posterior horn of the external semilunar cartilage (Fig. 77, p. 255).

The anterior crucial ligament is tight *in extension*, and the posterior crucial ligament is tight *in flexion* of the knee-joint.

Semilunar Cartilages.—These are two crescentic plates of fibro-cartilage which are placed on the condylar surfaces of the

tibia. They deepen the surfaces upon which the condyles of the femur roll, and, being movable, they fill up the gaps which would otherwise arise during the movements of the joint. Each cartilage presents two fibrous extremities, or horns, which are attached to the rough intermediate surface on the upper end of the tibia. They are thick towards the circumference of the joint, but thin away to a fine free concave edge in the opposite direction. Both surfaces are smooth and covered with synovial membrane. They do not cover the entire extent of the condylar surfaces of the tibia. The central parts of the latter, as well as the sloping surfaces of the tubercles of the tibial spine, are free. On raising the cartilages from the surface upon which they rest, distinct impressions similar in shape and extent are seen on the subjacent encrusting cartilage of the tibia.

Dissection.—Carefully define the attachments of the fibrous horns of the semilunar cartilages.

The *external semilunar cartilage* (meniscus lateralis) is usually somewhat thicker around its circumference than the internal cartilage. It forms the segment of a smaller circle, and its horns being fixed to the tibia close together, a very nearly complete circle is formed. The anterior fibrous horn is attached, immediately in front of the tibial spine, to the outer side of and partly under cover of the attachment of the anterior crucial ligament. The posterior horn is fixed to the summit of the tibial spine in the interval between the two tubercles. It likewise gives a strong slip to the posterior crucial ligament. The external lateral ligament is not in contact with the external semilunar cartilage. It is separated from it by the tendon of the popliteus, and the impress of the tendon is left on the cartilage in the form of a faint smooth groove on its outer and posterior border. Behind, its circumference is attached to the posterior ligament.

The *internal semilunar cartilage* (meniscus medialis) is semi-circular in form, and forms the segment of a much larger circle than the external cartilage. Its anterior fibrous horn is fixed to the fore part of the intermediate rough area of the tibia in front of the attachment of the anterior crucial ligament; its posterior horn is attached to the back part of the intermediate rough area of the tibia, behind the tibial spine,

and in front of the attachment of the posterior crucial ligament. The circumference of this cartilage is closely connected with the deep surface of the internal lateral ligament.

Transverse Ligament (*ligamentum transversum genu*).—This is a fibrous band which stretches across from the fore-part of one semilunar cartilage to the corresponding part of the other, constituting thereby a bond of union between them.

Dissection.—The condyles of the femur should now be detached by dividing the external lateral ligament and the crucial ligaments close to their femoral attachments.




FIG. 90.—Parts attached to the upper end of the Right Tibia.

- | | |
|---|--|
| 1. Transverse ligament. | 8. Fasciculus from external semilunar cartilage to posterior crucial ligament. |
| 2. Anterior cornu of internal semilunar cartilage. | 9. Posterior cornu of external semilunar cartilage. |
| 3. Anterior crucial ligament. | 10. External tubercle of spine of tibia. |
| 4. Internal tubercle of spine of tibia. | 11. External semilunar cartilage. |
| 5. Internal semilunar cartilage. | 12. Anterior cornu of external semilunar cartilage. |
| 6. Posterior cornu of internal semilunar cartilage. | |
| 7. Posterior crucial ligament. | |

Attachment of Parts to Upper Surface of the Tibia.—

The ligamentous structures are attached to the intermediate area on the upper surface of the tibia in the following order from before backwards:—(1) The anterior horn of the internal semilunar cartilage on the inner side of the extreme anterior part of the area. (2) The anterior crucial ligament and the anterior horn of the external semilunar cartilage: these are placed side by side, but the attachment of the former, which lies to the inner side, overlaps that of the external semilunar cartilage. (3) The posterior horn of the

external semilunar cartilage on the summit of the tibial spine between its two tubercles. (4) The posterior horn of the internal semilunar cartilage immediately behind the tibial spine. (5) The posterior crucial ligament at the hinder part of the area.

ANKLE-JOINT.

The ankle-joint (*articulatio talocruralis*) is a diarthrodial articulation of the ginglymus or hinge variety. The articulation takes place between the bones of the leg and the astragalus, and the weight of the body is transferred through it to the foot. It is a joint of great strength; its stability being ensured not only by the powerful ligaments which surround it, but also by the close interlocking of the articulating surfaces.

The bones which enter into the formation of the ankle-joint are the lower ends of the tibia and fibula and the superior surface of the astragalus. The lower ends of the leg bones are very firmly united together by an interosseous and other ligaments which give the joint a certain amount of elasticity or spring. They form a deep hollow resembling a mortice. The upper surface of the astragalus is received into this cavity.

The ligaments of the ankle-joint are:—

- | | |
|--------------------------|--------------------------|
| 1. The anterior. | 2. The posterior. |
| 3. The external lateral. | 4. The internal lateral. |

Dissection.—The remains of the annular ligaments, together with the tendons which are in relation to the joint, should be removed and the ligaments defined. The anterior and posterior ligaments should be first dissected. They may then be removed in order to bring the powerful external and internal lateral ligaments more fully into relief, and at the same time display the articulating surfaces, and thus permit the play of these surfaces to be seen when the joint is flexed and extended.

Anterior and Posterior Ligaments.—These are feeble bands which are placed in front of and behind the joint. They are attached to the margins of the articulating surfaces, except in front and below, where the anterior ligament is fixed to the neck of the astragalus. The fibres of these ligaments have for the most part a transverse direction.

External Lateral Ligament.—This is a composite ligament and consists of three distinct bands—an anterior, a middle, and a posterior. The *anterior fasciculus* (*ligamentum talo-fibulare anterius*) is a flattened band which passes from the

anterior border of the lower end of the fibula to the outer and back part of the neck of the astragalus. The *middle fasciculus* (ligamentum calcaneo-fibulare), round and cord-like, passes from a point a little in front of the tip of the external malleolus to the external surface of the calcaneum. The *posterior fasciculus* (ligamentum talofibulare posterius), the strongest of the three, is a powerful band of fibres which proceeds almost horizontally inwards from the deep pit behind the lower articular surface of the fibula to a prominent tubercle on the back of the astragalus.

This tubercle is sometimes detached, and forms a supernumerary tarsal bone which may represent the *os trigonum* found in some mammals. In such cases it has been mistaken for a fracture.




FIG. 91.—Articular Surfaces of Tibia and Fibula which articulate with the Astragalus.

Internal Lateral Ligament (ligamentum deltoideum).—This presents a triangular form. Its apex is directed upwards and is attached to a shallow pit on the under border of the inner malleolus. Its fibres diverge as they descend, and are attached in a continuous layer from before backwards to the scaphoid, astragalus, sustentaculum tali, and behind this to the astragalus again.

Synovial Membrane.—The synovial membrane lines the ligaments above described, and sends a small process upwards between the tibia and fibula. It is thrown into a transverse fold in front, when the joint is flexed, and into a similar fold behind when the joint is extended.

Movements.—The movements which take place at the ankle-joint are—(1) flexion (dorsal-flexion); (2) extension (plantar-flexion); and (3) a very limited degree of lateral movement (abduction and adduction) when the foot is fully extended. The two principal movements (flexion and extension) take place around a horizontal axis, which is not transverse, but which is directed outwards and backwards, so that it is inclined to the median plane of the body at an angle of about 60° (Krause). This horizontal axis passes through or near the interosseous canal between the os calcis and astragalus (Henle). As the articular cavity formed by the tibia and fibula, and also the part of the astragalus which plays in it, are broader in front than behind, it follows that the more completely the ankle-joint is flexed, the more tightly will the astragalus be grasped between the two malleoli. In the erect position the astragalus is held firmly in the bony socket, and portions of its articular surface project both in front of and behind the tibia. The centre of gravity is placed in front of the ankle-joint, and in this way the bones are kept firmly locked. When, on the other hand, the ankle-joint is fully extended (as when we rise on tip-toe) the narrower posterior part of the astragalus is brought into the socket, and thus a limited amount of lateral movement is allowed. In *flexion* the middle and posterior fasciculi of the external lateral ligament, the greater part of the internal lateral ligament, and the posterior ligament are put on the stretch. In *extension* the anterior fasciculus of the external lateral ligament, the anterior fibres of the internal lateral ligament, and the anterior ligament are rendered tense.

The **Muscles** principally concerned in producing dorsi-flexion of the foot at the ankle-joint are the tibialis anticus and the peroneus tertius; those which operate as plantar-flexors are the superficial muscles of the calf, the tibialis posticus, and the peroneus longus and brevis.

TIBIO-FIBULAR JOINTS.

The fibula articulates with the tibia by both its upper and lower extremity. Each of these joints is provided with a synovial membrane and possesses its own appropriate ligaments. The interosseous membrane which occupies the interval between the shafts of the bones may be regarded as a ligament common to both joints.

Dissection.—Preparatory to the examination of the tibio-fibular joints the foot must be removed by dividing the internal lateral ligament and the three parts of the external lateral ligament of the ankle-joint. The muscles must also be detached from both aspects of the interosseous membrane and the bones of the leg. The ligaments may now be defined.

Interosseous Membrane (*membrana interossea cruris*)^A—This is a strong membrane which stretches across the interval between the two bones of the leg, and greatly extends the surface for the origin of muscles. It is attached on the one hand to the external border of the tibia, and on the other to the interosseous ridge which descends on the internal

surface of the fibula. It is composed of strong oblique fibres, which take a direction downwards and outwards from the tibia to the fibula. An oval opening in its upper part, immediately under the external tuberosity of the tibia, is present for the passage of the anterior tibial vessels, whilst a small aperture a short distance above the ankle-joint marks the point where the membrane is pierced by the anterior peroneal artery.

Superior Tibio-fibular Joint (*articulatio tibiofibularis*).—At this joint the bones are held in apposition by an *anterior* and a *posterior ligament*, which pass from the outer tuberosity of the tibia downwards and outwards to be attached to the head of the fibula. The posterior ligament is the weaker of the two, and upon its upper part the tendon of the popliteus with its synovial investment rests. This investment is a prolongation from the synovial membrane of the knee-joint, and in some cases it will be found to be directly continuous with the synovial membrane which lines the superior tibio-fibular joint.

The relation of the tendon of the biceps to this joint must not be lost sight of. Attached for the most part to the head of the fibula, its fibres stretch over the front of the joint. Some of its tendinous fibres also obtain insertion into the outer tuberosity of the tibia. Firm support is in this way contributed to the superior tibio-fibular joint.

Inferior Tibio-fibular Joint (*syndesmosis tibiofibularis*).—This articulation is constructed upon a stronger plan, because upon its security the strength of the ankle-joint very largely depends. Only a very narrow strip of the lower part of each of the opposing surfaces of the bones is articular and coated with cartilage. Above this, the surfaces are rough, and are held together by an exceedingly strong *interosseous ligament*, composed of short fibres which pass directly between the bones.

In addition to this interosseous ligament there are :

1. An anterior ligament.
2. A posterior ligament.
3. An inferior transverse ligament.

The *anterior* and *posterior ligaments* are flat strong bands which pass from the tibia to the fibula, in an oblique direction, outwards and downwards.

The *transverse ligament* lies under cover of the lower part of the posterior ligament, and to see it properly the latter

should be divided. It is a strong narrow band of yellowish fibres, which takes a transverse course on the back of the joint and is firmly attached to both tibia and fibula, filling up the interval between them. It forms a part of the tibio-fibular socket for the astragalus at the ankle-joint; and on the upper aspect of the articular surface of the astragalus, the area over which it plays is usually easily distinguished.




FIG. 92.—Vertical section through the Foot, along a line stretching from the centre of the heel behind to the centre of the great toe in front. (From Luschka.)

- | | |
|-----------------------------|---|
| 1. Tibia. | 10. Tendo Achillis. |
| 2. Astragalus. | 11. Bursa between tendo Achillis and os calcis. |
| 3. Os calcis. | 12. Tendon of extensor longus hallucis. |
| 4. Scaphoid. | 13. Tendon of flexor longus hallucis. |
| 5. Internal cuneiform. | 14. Plantar fascia (central part). |
| 6. First metatarsal. | 15. Thick superficial fascia of heel. |
| 7 & 8. Phalanges of hallux. | |
| 9. Sesamoid bone. | |

Dissection.—To see the interosseous ligament of the inferior tibio-fibular joint the bones of the leg may be sawn through about two inches above the lower end of the tibia, and then divided with the saw from above downwards in a vertical-transverse, or coronal direction. This cut should be planned so as to pass through the inferior tibio-fibular joint. The short strong fibres of the interosseous ligament will then be seen, and also the short narrow articular interval between the lower portions of the opposing surfaces of the bones. The synovial membrane which lines this is a continuation upwards of the synovial membrane of the ankle-joint.

ARTICULATIONS OF THE FOOT.

The articulations of the foot are very numerous. They consist of :

1. The tarsal, tarso-metatarsal, and the inter-metatarsal joints.
2. The metatarso-phalangeal joints.
3. The interphalangeal joints.

The bones which enter into these articulations are the seven tarsal bones, the metatarsal bones, and the phalanges. The tarsal and metatarsal bones are bound together by inter-osseous, plantar, and dorsal ligaments, and are disposed in the form of two arches, viz., a longitudinal and a transverse. The integrity of these arches is maintained partly by the tension of the ligaments and partly by the direction of the articulating surfaces of the bones.

The longitudinal arch presents a greater height and a wider span along the inner than along the outer side of the foot. The astragalus is placed on the summit of this arch and forms its keystone. The posterior pillar of the longitudinal plantar arch is short and solid, being formed by the os calcis alone ; the anterior pillar, much longer, is composed of several bones, viz., the scaphoid, the cuboid, the three cuneiforms, and the metatarsus. Further, the anterior pillar may be considered as being formed of an inner column composed of the scaphoid, the three cuneiform, and the three inner metatarsal bones, and an outer column composed of the cuboid and the two outer metatarsal bones. The weight of the body is transmitted to the summit of the arch through the astragalus, and the most important ligaments concerned in the prevention of excessive flattening of the arch are the *inferior calcaneo-scaphoid*, the two *plantar calcaneo-cuboid ligaments*, and the various slips of the *tendon of the tibialis posticus* as they pass to find attachment to the different tarsal and metatarsal bones. The *plantar fascia* also acts powerfully in this way: 'connecting as it does the extremities of the two pillars of the plantar arch, it operates, as Sir George Humphry has pointed out, in the same manner as the "tie-beam" of a roof. The transverse arch of the foot is

seen to best advantage across the line of the tarso-metatarsal articulations.

Dissection.—The muscles and tendons which have hitherto been only partially detached from the bones of the foot should now be completely removed and the ligaments defined.

Astragaloid Articulations.—The astragalus articulates by means of the large posterior facet on the under surface of its



FIG. 93.—Astragalus removed so as to show the socket for its head.

body with the corresponding posterior facet on the upper surface of the os calcis. Its head, on the other hand, is received into a large socket which is formed for it by the sustentaculum tali of the os calcis, the scaphoid, and two ligaments which pass between the os calcis and the scaphoid bone—viz., one below, the inferior calcaneo-scaphoid, and another on the outer side, the external calcaneo-scaphoid ligament. These two astragaloid articulations are quite distinct, and each is provided with a separate synovial membrane.

The ligaments which hold the astragalus in its place are four in number. Three are attached to the os calcis and one to the scaphoid bone. They are :

1. An interosseous astragalo-calcanean.
2. An external lateral astragalo-calcanean.
3. A posterior astragalo-calcanean.
4. A dorsal astragalo-navicular.

The *interosseous ligament* is by far the most powerful. It occupies the tarsal canal, and consists of strong fibres attached below to the groove between the articular facets on the upper surface of the os calcis, and above to the corresponding groove on the under surface of the astragalus.

The *external ligament* is a short band of fibres which proceeds from the outer surface of the astragalus to the outer surface of the os calcis. It is parallel with the middle fasciculus of the external lateral ligament of the ankle-joint, but it is placed on a deeper plane, and lies somewhat in front of it.

The *posterior ligament* passes from the posterior border of the astragalus to the os calcis. It closes the posterior calcaneo-astragaloid articulation behind.

The *dorsal astragalo-navicular ligament* extends on the dorsum of the foot from the head of the astragalus to the scaphoid bone. It is thin and membranous.

The two lateral ligaments of the ankle-joint help to keep the astragalus in its place.

Dissection.—The astragalus should now be removed by dividing the various ligaments which hold it in place. By this proceeding the different parts which form the socket for the head of the astragalus will be brought into view; and the posterior astragalo-calcanean articulation will be seen to be completely cut off from the anterior articulation by the interosseous astragalo-calcanean ligament. The great strength of this ligament can now be appreciated, and the facets on the head of the astragalus studied. These are:—(1) a convex surface which looks forwards and articulates with the scaphoid; (2) an elongated facet on its under aspect (sometimes divided into two), which rests upon the sustentaculum tali; and (3) between these, a triangular facet which corresponds with the upper surface of the inferior calcaneo-scaphoid ligament. In the recent state (and indeed usually also in the macerated condition of the bone) these three facets are very distinctly mapped off from each other by intervening ridges.

Calcaneo-navicular Ligaments.—Although the os calcis does not directly articulate with the scaphoid bone, it is connected with it by two powerful and important ligaments, viz., an inferior and an external.

The *inferior calcaneo-scaphoid ligament* is brought into view by the removal of the astragalus. It fills up the angular gap between the sustentaculum tali and the scaphoid bone, and enters into the formation of the socket for the head of the astragalus (Fig. 93). Its upper surface therefore is smooth and covered with synovial membrane; its lower surface is supported by the tendon of the tibialis posticus. This ligament has an important part to play in maintaining the integrity of the longitudinal arch of the foot. Posteriorly it is attached to the fore border of the sustentaculum tali, whilst in front it is fixed to the under surface of the scaphoid bone.

The *external calcaneo-scaphoid ligament* also forms a small part of the socket for the head of the astragalus. It is placed deeply in the anterior part of the depression between the os calcis and the head of the astragalus. It is composed of short fibres which are attached in front to the outer side of the scaphoid bone, and behind to the upper aspect of the fore part of the os calcis, immediately to the outer side of the facet on the sustentaculum tali (Fig. 93). An elongated narrow facet may sometimes be noticed in correspondence with this ligament, along the posterior and outer margin of the articular surface of the head of the astragalus. In such cases four facets mark the head of the astragalus—one for each factor which enters into the formation of the socket in which it lies.

Calcaneo-cuboid Articulation.—In this joint the concavo-convex surface on the fore aspect of the os calcis articulates with the corresponding surface on the posterior aspect of the cuboid. It is a distinct joint, and is provided with a separate synovial membrane. The *ligaments* which bind the two bones together are :—

1. The inferior or plantar calcaneo-cuboid (long and short).
2. The dorsal calcaneo-cuboid.
3. The internal calcaneo-cuboid.

In the maintenance of the longitudinal arch of the foot the *plantar ligament* has an importance which is surpassed only by the inferior calcaneo-scaphoid ligament. It is disposed in two layers which are respectively termed the long and the short plantar ligaments, and which are separated from each other by some fatty areolar tissue.

The *superficial* or *long plantar ligament* springs from the under surface of the os calcis, in front of the internal and external tuberosities, and extends forwards to the inferior surface of the cuboid. Here it broadens out, and is for the most part attached to the prominent ridge on the under surface of that bone. Numerous strong fibres, however, are prolonged forwards over the tendon of the peroneus longus to find attachment to the bases of the three middle metatarsal bones. The long plantar ligament therefore extends over the greater part of the outer portion of the tarsus, and it constitutes the longest of the tarsal ligaments. Further, it

forms the greater part of the sheath of the tendon of the peroneus longus muscle.

The *short plantar ligament* is placed under cover of the long plantar ligament. Slip the knife in between them, and carry the cutting edge backwards so as to detach the long ligament from the under surface of the os calcis. On throwing the detached band forwards, the short plantar ligament comes into view, and little dissection is required to make its connections apparent. It is composed of short but strong fibres, not more than an inch in length. These spring from the anterior tubercle on the under surface of the os calcis, and are attached in front to the inferior aspect of the cuboid behind its ridge. This ligament is broader than the long plantar ligament, and is apparent along its inner border even before the latter is reflected.

The *dorsal* and *internal ligaments* connect the os calcis and cuboid bones upon the superior and inner aspects of the joint. The internal ligament, sometimes called *interosseous*, is to be sought for in the deep pit between the head of the astragalus and the fore part of the os calcis.

The joint between the astragalus and scaphoid bone, and that between the os calcis and the cuboid bone, are sometimes referred to as the "transverse tarsal joint." It is here that the movements of eversion and inversion of the foot chiefly take place, and it should be noted that all the ligaments which connect these two segments of the tarsus together, with the exception of one, are attached posteriorly to the os calcis. They are—

Inferior calcaneo-scaphoid,	}	Attached behind to the os calcis.
External calcaneo-scaphoid,		
Long plantar,		
Short plantar,		
Dorsal calcaneo-cuboid,		
Internal calcaneo-cuboid,	}	Attached behind to the astragalus.
Dorsal astragalo-scaphoid,		

Inter-cuneiform Articulations.—The three cuneiform bones are held together so firmly that very little individual movement is permitted. The chief uniting structures are *two* strong *interosseous ligaments* which pass between the non-articular portions of their opposed surfaces. These can only be seen when the bones are separated from each other. *Dorsal inter-cuneiform ligaments* are also present. These are short flat transversely-placed bands.

Scapho-cuneiform Articulation.—The three cuneiform

bones articulate with the anterior surface of the scaphoid. They are held in position by *dorsal ligaments*, which pass from the dorsal surface of the scaphoid to the dorsal surface of each of the cuneiform bones, and by *plantar ligaments*, which are similarly disposed. The strength of the plantar ligaments is greater than that of the dorsal ligaments, and they are very largely formed by slips from the tendon of the tibialis posticus.

The dissector may now divide freely all the dorsal, and the innermost of the plantar scapho-cuneiform ligaments. The scaphoid bone can then be drawn backwards so as to expose the interior of the joint. The knife may also be carried round the outer side of the external calcaneo-scapoid ligament. A much better view of this ligament is thus obtained, although this dissection entails the division of the dorsal scapho-cuboid ligament.

The convex anterior articular surface of the scaphoid fits into a transversely concave socket, which is formed for it by the posterior surfaces of the three cuneiform bones, and often by a small facet on the inner surface of the cuboid bone as well. The articular surface of the scaphoid is divided by prominent ridges into areas or facets corresponding with the different parts of the socket in which it lies. The *synovial membrane* which lines this joint is prolonged forwards into the intercuneiform joints.

Scapho-cuboid and Cubo-cuneiform Articulations.—It has been noted that the anterior pillar of the longitudinal arch of the foot consists of an outer and an inner column. The tarsal portions of these are connected together by the scapho-cuboid and the cubo-cuneiform articulations.

It is only occasionally that the scaphoid bone touches and articulates directly with the inner surface of the cuboid bone. When it does so, the facet on the cuboid bone lies in series with the articular surfaces on the hinder ends of the cuneiform bones, and forms with them the socket for the anterior surface of the scaphoid. The *ligaments* which bind the scaphoid to the cuboid bone are disposed transversely, and consist of—(1) a series of short strong *interosseous* fibres which bind the opposed surfaces together; (2) a dorsal band; and (3) a plantar band.

The dorsal band has previously been divided in exposing the interior of the scapho-cuneiform joint and in defining the external calcaneo-scapoid ligament, but the interosseous and plantar ligaments may be readily displayed.

The cuboid, by an oval facet on its inner surface, articulates with the external cuneiform bone, forming thereby the *cubo-cuneiform joint*. The two bones are bound together by *interosseous, dorsal, and plantar ligaments*. By dividing the dorsal ligament and insinuating the knife between the two bones the interosseous ligament may be detected. It is the strongest of the three ligaments.

The *synovial membrane* which lines the scapho-cuneiform articulation is prolonged into the cubo-cuneiform joint and also into the scapho-cuboid joint when this exists.

Tarso-metatarsal Articulations.—The bases of the five metatarsal bones articulate with the three cuneiform bones and the cuboid bone, and are very firmly attached to them by dorsal, plantar, and interosseous ligaments.

The *dorsal ligaments* are flat distinct bands which can readily be defined. *One* such ligament passes to the base of the first metatarsal from the internal cuneiform; *three*, one from each of the cuneiform bones, proceed to the base of the second metatarsal; *one* extends from the external cuneiform to the base of the third metatarsal; *two*, of which one proceeds from the external cuneiform, and the other from the cuboid, go to the base of the fourth metatarsal; and *one* passes from the cuboid to the base of the fifth metatarsal.

The *plantar ligaments* are not so regularly disposed. Those in connection with the first and second metatarsal bones are very strong. Some of the bands have an oblique direction, and those which go to the bases of the three middle metatarsal bones are more or less connected with the sheath of the tendon of the peroneus longus, and therefore with the long plantar ligament.

To bring the *interosseous ligaments* into view, divide freely the dorsal ligaments, and then forcibly bend the metatarsus downwards upon the tarsus. The interosseous ligaments will resist this proceeding, and on looking into the joints they will be seen stretched and tense. If the force be continued they will rupture. The interosseous ligaments are three in number, viz., an internal, a middle, and an external.

The *internal interosseous ligament* is an exceedingly strong band, which passes forwards and outwards from the anterior part of the outer surface of the internal cuneiform bone to the adjacent surface of the base of the second metatarsal bone.

The *middle interosseous ligament* is small, and passes forwards between the anterior part of the inner surface of the external cuneiform and the adjacent surface of the base of the second metatarsal. The *external interosseous ligament* passes from the outer surface of the external cuneiform bone to the outer side of the base of the third metatarsal. One interosseous ligament therefore passes from the internal cuneiform bone and two from the external cuneiform; and of these, two are attached to the base of the second, and the third to the base of the third metatarsal bone.

Tarso-metatarsal Articular Surfaces.—The manner in which the metatarsus is implanted upon the tarsus should now be examined. The *first metatarsal* rests upon the internal cuneiform, and this joint possesses a separate synovial membrane. The *second metatarsal* rests upon the middle cuneiform, but its base is grasped by the projecting anterior ends of the internal and external cuneiform bones, with both of which it articulates, and with both of which it is connected by interosseous ligaments. No wonder then that this metatarsal should possess so little power of independent movement, and present a difficulty to the surgeon when he is called upon to amputate the fore-part of the foot through the tarso-metatarsal articulation. The *third metatarsal* rests upon the external cuneiform. The *synovial membrane* which lines the joints between the tarsus and the second and third metatarsal bones is continuous with that which is present between the internal and middle cuneiform bones, and through this with the scapho-cuneiform synovial membrane. The bases of the *fourth and fifth metatarsal bones* are supported by the cuboid, but that of the fourth, by its inner margin, articulates also with the external cuneiform. A separate *synovial membrane* is present in the articulation between the two outer metatarsal bones and the tarsus.

Intermetatarsal Joints.—The bases of the metatarsal bones, with the exception of the first, articulate with each other, and are very firmly bound together.

The ligaments which connect the bases of the four outer metatarsal bones are *dorsal*, *plantar*, and *interosseous*. To bring the interosseous ligaments into view it is necessary to divide the dorsal ligaments, and then forcibly separate the

bases of the bones from each other. They are strong bands which pass between the non-articular portions of the basal parts of the bones. They constitute the chief bonds of union.

In addition to these basal ligaments, the strong *transverse metatarsal ligament* unites the distal extremities of the metatarsal bones. This ligament has been previously described (p. 279).

Synovial Cavities of the Foot.—There are six separate synovial cavities in connection with the tarsal, tarso-metatarsal, and intermetatarsal articulations, viz.—(1) in the joint between the posterior facets of the astragalus and os calcis; (2) in the calcaneo-cuboid joint; (3) in the joint formed by the head of the astragalus, the scaphoid, the sustentaculum tali, and the two calcaneo-scaphoid ligaments; (4) a complicated synovial membrane which lines the scapho-cuneiform articulations, and is prolonged forwards between the cuneiforms, and also between the cuboid and external cuneiform bones. This synovial membrane, however, is not confined to the tarsus, but reaches forwards into the articulation between the second and third metatarsal bones and the tarsus, as well as into the joints between the bases of the second, third, and fourth metatarsal bones;¹ (5) a separate synovial lining for the joint between the first metatarsal and the internal cuneiform; (6) a distinct synovial membrane for the articulations between the cuboid and the two outer metatarsal bones. This is prolonged forwards into the joint between the bases of these two metatarsals.

Metatarso-phalangeal and Interphalangeal Joints.—These joints are constructed upon a plan almost identical with that of the corresponding joints of the upper extremity. For the detailed description the student is therefore referred to p. 151. In the metatarso-phalangeal joint of the great toe the thick *inferior ligament* or *fibrous plate* holds two large sesamoid bones, which slide upon grooved surfaces on the head of the metatarsal bone.

Movements.—The movements which take place in the tarso-metatarsal, intermetatarsal, and in the majority of the tarsal joints, are of a gliding

¹ The external interosseous tarso-metatarsal ligament, which passes from the external cuneiform bone (frequently from the cuboid bone) to the base of the third metatarsal bone, separates the articulations of the fourth and fifth metatarsal bones from the general tarsal articular cavity.

character. In the joints between the astragalus and scaphoid, and also between the os calcis and the cuboid, movements of a wider range are possible. It is here that the movements of *inversion* and *eversion* of the foot chiefly take place.

The first and the fifth metatarsal bones enjoy a considerable degree of mobility. The second metatarsal is so tightly grasped by the internal and external cuneiform bones, and so firmly bound to the tarsus by its basal ligaments, that only a slight degree of movement is possible.

At the metatarso-phalangeal joints, flexion, extension, abduction, and adduction are allowed; whilst the inter-phalangeal joints only permit of flexion and extension.

In the erect posture the parts of the foot which are chiefly concerned in transmitting the weight of the body to the ground are the heel, the head of the first metatarsal bone, and the shaft of the fifth metatarsal bone. Rather more than the middle third of the inner border of the foot is raised above the ground. The outer border of the foot is more or less in contact with the ground in its entire extent, whilst the tips of the toes rest lightly on the ground. In walking—(1) the heel is brought down; (2) the sole and toes follow; (3) the heel is raised, and the weight of the body is transferred to the heads of the metatarsal bones and the toes. In the second and third parts of this operation the arches of the foot are flattened to a certain extent, but more especially in the third part of the process is the transverse arch spread out. Great elasticity is thus given to the step.

The **muscles** which are chiefly concerned in producing *eversion* of the foot are the three peroneal muscles; those which operate as *invertors* of the foot are the tibialis anticus and the tibialis posticus.

The *extensors of the toes* are the extensor longus hallucis, the extensor brevis digitorum, and the extensor longus digitorum. The lumbrical muscles, and the interosseous muscles, through their insertions into the extensor tendons of the four outer toes, operate as extensors of the second and third phalanges.

The *flexors of the proximal phalanges* are the lumbricales, interossei, flexor brevis hallucis, and flexor brevis minimi digiti. The *flexor of the second phalanges* is the flexor brevis digitorum; whilst the *flexors of the distal phalanges* are the flexor longus digitorum, the musculus accessorius, and the flexor longus hallucis.

Abduction and adduction of the toes at the metatarso-phalangeal joints are produced by the interosseous muscles, the abductor hallucis, the adductor obliquus hallucis, the adductor transversus hallucis, and the abductor minimi digiti. The movements of abduction and adduction take place with reference to a line drawn through the second toe.

ABDOMEN.

WHEN the body is brought into the dissecting-room, it is first placed in the lithotomy position (Fig. 95). The body is retained for two days in this posture, and during this time the dissector of the abdomen is expected to dissect the *perineum*.

MALE PERINEUM.

Boundaries of the Perineum.—The perineal space may be said to correspond to the inferior aperture or outlet of the pelvis. It is absolutely necessary, then, that the student should renew his acquaintance with this part of the skeleton before he begins the dissection. Let him obtain a pelvis with the ligaments *in situ*. He will observe that he has to




FIG. 94.—Outlet of Male Pelvis.

deal with a diamond-shaped space, and that it has the following boundaries: *in front*, the symphysis pubis and the subpubic ligament; *behind*, the coccyx; and *on each side from before backwards*, the rami of the pubis and ischium, the tuberosity of the ischium, and the great sacro-sciatic ligament. If he now turn his attention to the subject before him he can readily identify these limits. The great sacro-sciatic ligament, however, is somewhat obscured, from its being covered by the gluteus maximus muscle, but it can be felt by pressing deeply in a line between the ischial tuberosity and the coccyx.

In the undissected body the superficial area of the perineum is very limited; indeed, when the limbs are extended and

approximated, it merely consists of a narrow groove running forwards between the thighs from the coccyx towards the pubis. In this groove are placed the anus or orifice of the rectum and the roots of the scrotum and penis, whilst in the middle line a cutaneous ridge—the *median raphe*—may be observed. This raphe can be traced from the anus forwards over the scrotum and along the under surface of the penis.

Subdivision of the Space.—The perineal space has, therefore, a diamond-shaped form, and it is customary to subdivide it arbitrarily into two portions by drawing an imaginary transverse line between the anterior parts of the ischial tuberosities immediately in front of the anus. Two triangles are thus mapped out. The anterior of these may be appropriately called the urogenital triangle, because the most important objects which it contains are the urethra and the root of the penis; the posterior may be distinguished as the rectal triangle, from its containing the lower end of the rectum.

Preparation of Part for Dissection.—To prepare the part for dissection, a staff should first be introduced into the bladder. The dissector must stand upon the *left* side of the subject. Having smeared the instrument with oil, hold it lightly in the right hand and guide it gently along the upper and right wall of the urethra. When the point of the instrument reaches the triangular ligament,—a strong aponeurotic structure which is stretched tightly across the pubic arch—depress the handle, but use no force. Should any difficulty be experienced, introduce the forefinger of the left hand into the rectum to guide the point of the instrument along the membranous and prostatic portions of the urethra. The most dependent part of the scrotum should now be stitched to the prepuce of the penis, and dragging both penis and scrotum forwards upon the staff, they should be fixed by means of the twine to its handle. Lastly, fasten the handle of the staff to the cord which passes behind the flexed knee-joints of the subject.

The rectum should then be *moderately* distended with tow, and the orifice of the anus stitched up.

Reflection of Skin.—Two incisions are required:—(Fig. 95) (1) a transverse incision along the line which separates the *rectal* from the urogenital triangle—*i.e.*, in front of the tuberosities of the ischium; (2) an incision at right angles to this in the line of the median raphe. This incision should begin well forwards on the scrotum and be continued back a little beyond the point of the coccyx. At the anus the knife should be carried round it so as to encircle it.

The four triangular flaps which are marked out should now be reflected close to the anal orifice. Some difficulty will be experienced in raising the skin. This is due to the presence of a number of fasciculi of involuntary muscle which radiate outwards from the opening. The term *corrugator cutis ani* is applied to this muscle. The *superficial fascia* and the *external sphincter muscle* are now exposed.

Superficial Fascia.—The student should examine the

superficial fascia as it is spread over the entire extent of the perineal space. It shows great differences in character and texture in different positions. At the side of the anus it is remarkable for the large quantity of fat it holds in its meshes. This fat is soft and lobulated, and passes upwards upon each side of the rectum in the form of a pliable and elastic pad. Over the tuberosities of the ischium the superficial fascia undergoes a striking alteration. Here it becomes tough and




FIG. 95.

stringy; dense fibrous septa separate the lobules of fat from each other and connect the skin with the subjacent bone. Make a deep incision into it with the knife, and a bursa will be displayed intervening between the fascia and bone. This bursal sac is frequently intersected by strong fibrous bands or cords. In this locality the superficial fascia acts as a cushion on which the tuber ischii rests when the body is in the sitting posture.

But, again, if the superficial fascia be now followed forwards

over the urogenital triangle, another change in its character becomes manifest. The further forwards we proceed, the scarcer becomes the fat which it contains in its meshes, and in the scrotum the fat entirely disappears and gives place to a thin layer of involuntary muscular fibres. These constitute the *dartos muscle*, and are recognised by their ruddy colour. The rugosity of the scrotal integument is caused by the contraction of these fibres. *

Over the urogenital triangle the superficial fascia can be shown to consist of two very definite layers. The superficial layer is fatty and is not confined to this region. In fact, it is simply a portion of the general fatty covering of the body. Behind, it is continuous with the plugs of fat which fill up the ischio-rectal fossa; on either side, it leaves the perineum and becomes continuous with the fatty tissue on the inner aspects of the thighs. The deep layer is of an altogether different nature. It is a dense membranaceous stratum, devoid of fat, which is spread over the urogenital triangle. It is called the fascia of Colles. This sheet of fascia forms very definite attachments around the limits of the urogenital triangle. Thus, on either side it is fixed to the anterior lips of the rami of the pubis and ischium, whilst inferiorly it is tucked round the two transverse perineal muscles and blends with the base of the triangular ligament. A pouch is thus formed, which is bounded in front by the fascia of Colles, behind by the triangular ligament, laterally by the attachment of these to the sides of the pubic arch, whilst below, it is closed by the union of the fascia of Colles with the base of the triangular ligament (Fig. 97, p. 317). Within this pouch certain important parts are placed—viz., the superficial perineal muscles, vessels, and nerves, the long pudendal nerves, the bulb and crura of the penis, and the termination of the pudic artery. It is partially divided into two lateral parts by a median septum, which dips backwards from the superficial fascia. This septum is very perfect posteriorly, but becomes incomplete towards the scrotum. Traced forwards, the fascia of Colles passes over the scrotum, penis, and spermatic cords, to the front of the abdomen, where it becomes continuous with the fascia of Scarpa.

How to verify these facts.—The student can verify these facts in two ways, viz.—(1) by inflating the pouch with air, and (2) by dissection,

Make a longitudinal incision, large enough to admit the nozzle of the bellows (or better still an injection pipe fitted to a bicycle-pump) into the superficial fascia towards the back part of the pouch and a little to one side of the middle line. This cut must be carried through the fascia until the fibres of the superficial perineal muscles are exposed. In using the pump the margins of the opening into the pouch must be held tightly around the nozzle of the pipe. The air which is introduced passes forwards, and is first confined to one side of the pouch. Reaching the scrotum, however, where the septum is incomplete, it forces its way across the middle line, and inflates the opposite side of the pouch. The pouch is now rendered prominent, and the attachments of the fascia become very evident. The air cannot pass into the rectal triangle owing to the union of the fascia of Colles to the base of the triangular ligament; it cannot pass down the inner aspect of the thighs from the attachment of the fascia to the sides of the pubic arch; it can only force its way forwards under the superficial fascia and dartos muscle of the scrotum, and from this on to the penis and along the spermatic cords to the anterior aspect of the abdomen. By this means the dissector obtains a very striking view of the course which would be taken by urine escaping from a rupture in the urethra in front of the triangular ligament.

The attachments of the fascia of Colles are so important that the student should also test them by dissection. To do this it is necessary to make two incisions through the superficial fascia. Enter the knife in the middle line at the root of the scrotum, and carry it backwards and outwards to the tuber ischii on each side of the body. A central Δ -shaped flap and two lateral flaps of fascia are thus marked out. By raising and turning backwards the central portion, the septum of the pouch is brought into view, and the attachment of the fascia to the base of the triangular ligament is demonstrated, and by throwing each lateral flap outwards it will be seen to be firmly fixed to the side of the pubic arch. In effecting this dissection the utmost care is demanded on the part of the student. In the areolar tissue immediately subjacent to the superficial fascia are the *superficial perineal vessels and nerves*, which are certain to be injured, or perhaps even reflected with the fascia, unless the greatest caution be exercised.

RECTAL TRIANGLE.

The dissection of this portion of the perineal space will disclose the following parts:—

1. The external sphincter ani muscle.
2. The lower part of the rectum covered by the levator ani muscle and the anal fascia.
3. The parietal or obturator layer of pelvic fascia.
4. The lower border of the gluteus maximus muscle and the great sacro-sciatic ligament.
5. The coccygeus muscle.
6. The inferior hæmorrhoidal vessels and nerve.
7. The perineal branch of the fourth sacral nerve.
8. The commencement of the two superficial perineal nerves.
9. The perforating cutaneous branch of the fourth sacral nerve.

Sphincter Ani Externus.—When this muscle is cleaned it

will be seen to consist of a thick ring of muscular fibres surrounding the orifice of the rectum. *Behind*, it is attached by a pointed tendon to the tip and posterior surface of the terminal part of the coccyx; *in front*, it blends with other perineal muscles in the central point of the perineum. The fibres, in passing between these two points of attachment, encircle the anal orifice and constitute a true sphincter muscle. Some of the superficial fibres, both in front and behind the

anal opening, are directly attached to the skin. It draws its nervous supply from two sources, viz., the fourth sacral nerve and the inferior hemorrhoidal nerve.

Ischio-rectal Fossa.—

Although the rectum is the largest and most important object which is contained within the posterior portion of the perineum, it does not fill up the entire extent of the rectal triangle. An interval or recess is left upon each side of the rectum—between it and the ischium,—and to this recess is given the name of the *ischio-rectal fossa*.




FIG. 96.—Diagram. The arrow is directed upwards into the ischio-rectal fossa. The parietal pelvic fascia is seen upon the inner surface of the obturator internus. Observe also the anal fascia clothing the outer surface of the levator ani and the rectal fascia upon its inner surface.

In shape the ischio-rectal fossa is pyramidal, the apex of the pyramid being directed upwards towards the pelvic cavity, and the base downwards towards the integuments. The inner wall of the space is sloping, whilst the outer wall is steep and perpendicular.

Boundaries.—Whilst the term "*ischio-rectal*" is applied to this fossa, it must be borne in mind that neither the ischium nor the rectum enter directly into the formation of its walls. Both are separated from the space by fascial and muscular layers. Upon the inner aspect of the ischium is the obturator

internus muscle, and this again is covered by the parietal or obturator layer of the pelvic fascia as it is continued down to be attached to the tuberosity of the ischium and the great sacro-sciatic ligament. On the other hand, the rectum is clothed from without inwards by—(1) the anal fascia, a thin aponeurotic membrane which invests the outer surface of the levator ani; (2) by the levator ani muscle; and (3) by the rectal portion of the visceral layer of the pelvic fascia (Fig. 96). Strictly speaking, therefore, the perpendicular *outer* or *ischial wall* of the fossa is formed by the parietal layer of the pelvic fascia, and the sloping inner or rectal wall by the anal fascia. ~~In front, the space is limited by the triangular ligament—whilst behind, it is bounded by the posterior or lower margin of the gluteus maximus and the great sacro-sciatic ligament.~~

Contents.—The ischio-rectal fossa is completely filled up by a mass of fat which is prolonged upwards into it from the superficial fascia. The soft, pliable nature of this fat readily allows of the distension of the rectum. Embedded in its midst are certain blood-vessels and nerves. Crossing the fossa from its outer to its inner wall are the inferior hæmorrhoidal vessels and nerve; entering the fossa at its posterior part is the perineal branch of the fourth sacral nerve; turning round the lower border of the gluteus maximus, not far from the coccyx, is the perforating cutaneous branch of the fourth sacral nerve; whilst in the anterior part of the space will be found the commencement of the two superficial perineal nerves (Fig. 97).

Dissection.—Begin by exposing the posterior margin of the *gluteus maximus muscle*. Take a point a short distance to the outside of the tuber ischii and another in the middle line about an inch above the tip of the coccyx, and cut boldly down through the superficial fascia, in a line between these points, until the fleshy fibres become visible. Winding round the lower margin of the muscle so as to gain its superficial aspect, there are a few small arteries and nerves. The arteries are derived from the *inferior hæmorrhoidal vessels*, or from the *sciatic artery*, whilst the nerves are the *perforating cutaneous branch* from the fourth sacral nerve and some offsets from the *small sciatic nerve*. Both are destined for the supply of the skin on the lower part of the gluteal region. The perforating cutaneous nerve turns round the margin of the gluteus maximus close to the coccyx, whilst the cutaneous branches from the small sciatic nerve appear on the outer side of the tuber ischii. Having secured these vessels and nerves, clean the lower margin of the gluteus maximus, and then proceed to dissect the ischio-rectal fossa. If the subject is obese, a considerable quantity of fat may be removed at once without endangering the inferior hæmorrhoidal vessels and nerve. Take the surface of the gluteus maximus and the margin of the external sphincter as guides, and


transfix the fat with the knife in this plane. The adipose tissue superficial to this plane may be removed *en masse* with safety. The *hæmorrhoidal vessels* and *nerve* may be found by dissecting cautiously in the fat and carrying the knife in a transverse direction from the outer to the inner wall of the space. The branch from the *fourth sacral nerve* appears by the side of the coccyx.

Roof of the Space.—When the contents of the space are secured, continue to remove the fat from the fossa until its walls are fully displayed. On passing the finger upwards, its passage into the pelvis is prevented by the junction of the anal fascia with the parietal or obturator layer of the pelvic fascia (Fig. 96, p. 314). Further, if the anal fascia be removed, its entrance into the pelvis is still resisted by the visceral layer of the pelvic fascia, which at this level passes inwards from the parietal pelvic fascia, and also by the levator ani muscle, which lies on the lower surface of the visceral pelvic fascia and takes origin from the line of union between these two layers of fascia.

Internal Pudic Vessels and Nerve.—The dissector should now pass his finger upwards and downwards over the surface of the parietal or obturator layer of the pelvic fascia, which covers the obturator internus muscle and forms the outer wall of the ischio-rectal fossa. About an inch and a half above the lower border of the ischial tuberosity he will feel very distinctly the pudic vessels and nerve as they pass forwards to gain the urethral triangle. In this position they are enclosed in a tube or sheath formed by the parietal pelvic fascia. This fascial tunnel is called Alcock's canal. The student must for the present be satisfied with this partial view of these structures. To expose them would necessitate the division of the parietal pelvic fascia, and this should be kept entire until the pelvic fascia can be studied as a whole.

Inferior Hæmorrhoidal Vessels (*arteria hæmorrhoidalis inferior*). The inferior hæmorrhoidal arteries are branches of the internal pudic. They are usually two or three in number, and, piercing the inner wall of Alcock's canal, they pass inwards through the fat of the ischio-rectal fossa to supply the lower end of the rectum and the muscles in connection with it, as well as the skin around the anus. They anastomose with the corresponding arteries of the opposite side, and with branches from the middle and superior hæmorrhoidal arteries. They likewise send a few twigs round the lower

border of the gluteus maximus, in company with the perforating cutaneous nerve to supply the skin in the lower part of the buttock.



Inferior hæmorrhoidal nerve

Inferior hæmorrhoidal artery

FIG. 97.—Dissection of the Perineum. The Scrotum and the Penis have been cut transversely across and removed.

Inferior Hæmorrhoidal Nerve.—This nerve accompanies the vessels of the same name. It may proceed directly from the sacral plexus, but more frequently it is a branch of the

internal pudic nerve. Perforating the inner wall of Alcock's canal, it enters the ischio-rectal fossa, and then it breaks up into muscular, cutaneous, and communicating branches. The *muscular twigs* supply the external sphincter: the *cutaneous offsets* are given to the skin which surrounds the anus, while the *communicating filaments* pass forwards to join the long pudendal nerve and the superficial perineal nerves.

Perineal Branch of Fourth Sacral Nerve.—This small nerve enters the ischio-rectal fossa by piercing the coccygeus muscle at the side of the coccyx. It is distributed to the skin between the anus and coccyx, and to the external sphincter muscle.

Ano-coccygeal Body.—An indefinite mass of muscular and fibrous tissue which lies between the tip of the coccyx and the anus receives the name of *ano-coccygeal body*. It is best seen in sections through the pelvis, and it requires notice on account of the support which it gives to the rectum in front of the coccyx. The muscular tissue which enters into its constitution belongs to the levator ani and the external and internal sphincter muscles (Symington).

UROGENITAL TRIANGLE.

The superficial fascia in this locality has already been studied. The following is a list of the structures which still require to be examined:—

1. The superficial perineal vessels and nerves.
2. The long pudendal nerve.
3. The root of the penis; The bulb and the crura.
4. The superficial perineal muscles.

{	<i>a.</i> Transversus perinei.
	<i>b.</i> Ejaculator urinæ.
	<i>c.</i> Erector penis.
5. The triangular ligament.
6. The internal pudic vessels and nerve and their branches.
7. The compressor urethræ muscle.
8. Cowper's glands.
9. The membranous portion of the urethra.
10. The deep layer of the triangular ligament (*i.e.*, the parietal pelvic fascia opposite the pubic arch).

Superficial Perineal Vessels and Nerves.—The superficial perineal vessels and nerves must now be followed out. There are two arteries and three nerves to be looked for:—

- | | | |
|-----------|---|---|
| Arteries. | { | 1. Superficial perineal artery. |
| | { | 2. Transverse perineal artery. |
| Nerves. | { | 1. Posterior or external superficial perineal nerve. |
| | { | 2. Anterior or internal superficial perineal nerve. |
| | { | 3. The long pudendal nerve or the nerve of Soemmerring. |

The *superficial perineal artery*, a branch of the pudic, first pierces the inner wall of Alcock's canal, and then the base of the triangular ligament, so as to gain the-interior of the perineal pouch of fascia. It now crosses the transversus perinei muscle, and is continued forwards in the interval between the ejaculator urinæ and erector penis to the scrotum, to the dartos muscle and integuments of which it is distributed in the form of numerous long, slender branches. Before it reaches the scrotum, it supplies twigs to the superficial perineal muscles. It is accompanied by the superficial perineal nerves.

The *transverse perineal artery* is a small vessel which usually springs from the pudic by a common root of origin with the preceding. It pierces the base of the triangular ligament, and, gaining the surface of the transversus perinei muscle, proceeds transversely inwards to the interval between the rectum and the bulb, where it ends by supplying the parts in this locality, and by anastomosing with the corresponding vessel of the opposite side.

The *posterior superficial perineal nerve*, a branch of the perineal division of the pudic nerve, has already been seen in the anterior part of the ischio-rectal fossa, where it effects a communication with the inferior hæmorrhoidal nerve. It leaves the fossa by piercing the base of the triangular ligament, and is continued forwards with the superficial perineal artery to the scrotum.

The *anterior superficial perineal nerve*, also derived from the perineal part of the pudic nerve, supplies a few twigs to the levator ani, and, piercing the base of the triangular ligament, is prolonged forward with the posterior nerve to the scrotum. In some instances this nerve passes under cover of the transversus perinei muscle.

Dissection.—Instead of searching for the long pudendal nerve at the point where it becomes superficial, and then following it towards its distribution, it is much easier to find it after it has entered the perineal pouch of fascia. Here it will be discovered lying in close relation to the two preceding nerves, but to their outer side. Trace it forwards and

backwards. The long pudendal communicates with the inferior hæmorrhoidal nerve, and also with the posterior superficial perineal nerve.

The *long pudendal nerve* is derived from an altogether different source. It is a branch of the small sciatic nerve, and pierces the deep fascia of the thigh a short distance in front of the tuber ischii, and about an inch and a half to the outer side of the margin of the pubic arch. As it proceeds forwards it inclines inwards, and, piercing the attachment of the superficial fascia to the margin of the pubic arch, it accompanies the other vessels and nerves to the scrotum, the outer and front part of which it supplies.

Dissection.—Divide the superficial perineal vessels and nerves, and throw them aside.

Root of the Penis.—At this stage of the dissection the student should consider the position of the




FIG. 98.—Transverse section through the body of the Penis.

the position of the triangular ligament, and the relation which it bears to the root of the penis. The *triangular ligament* is a strong aponeurotic membrane which stretches across the pubic arch, and subdivides the urogenital portion of the perineum into a superficial and a deep area. The *root of the penis* is placed altogether in front of it, in the superficial area of this

region. With the handle of the knife clear away for a short distance the loose tissue which surrounds the body of the penis. The *body of the penis* is then seen to consist of three cylindrical masses which are chiefly composed of erectile tissue, and are placed in close apposition with each other. These are the two corpora cavernosa and the corpus spongiosum.

The *corpora cavernosa* constitute the chief bulk of the organ. They are placed side by side and form the dorsum and sides of the penis. They are partially blended with each other along the middle line,—indeed, the only surface indication of the double nature of this portion of the penis are two median longitudinal grooves which run one along its upper

and the other along its lower aspect. The *corpus spongiosum* is slender in comparison with the corpora cavernosa, and is lodged in the groove which extends along the lower aspect of these bodies. On account of this, the body of the penis has a somewhat prismatic form. The corpus spongiosum is traversed throughout its whole length by the urethra.

If these three constituents of the body of the penis be traced backwards, the student will observe that opposite the




FIG. 99.—The Root of the Penis and the Triangular Ligament (formalin specimen).

lower part of the symphysis pubis they separate from each other and become attached to parts in the superficial area of the urogenital triangle. The *corpora cavernosa* diverge widely from each other, and now they receive the name of the *crura* of the penis. Each crus is fixed firmly to the corresponding side of the pubic arch by an attachment which extends from the sub-pubic ligament backwards to a point a short distance in front of the tuberosity of the ischium. Close to the point where it becomes continuous with the corresponding corpus cavernosum it shows a slight dilatation or bulging; from this

to its posterior extremity it gradually tapers away. The *corpus spongiosum* is continued backwards in the middle line of the body to within a short distance of the anus, and it expands so as to form a bulbous posterior extremity. The corpus spongiosum, as it lies in the interval between the diverging crura, is therefore termed the *bulb* of the penis. The bulb rests upon the superficial aspect of the triangular ligament,




FIG. 100.—Dorsal or attached aspect of the Penis. The specimen was hardened by formalin injection and removed from the pubic arch and the triangular ligament.

and it is firmly bound down to this by an aponeurotic investment, which is prolonged over it from the ligament. The posterior extremity of the bulb is frequently notched in the middle line—an indication of its originally double constitution.

The bulb and the two crura together constitute *the root of the penis*, and each is provided with a special muscle, which at present hides it from view. Clothing the bulb the student will recognise a bipenniform muscle called the *ejaculator urinæ*, whilst moulded upon the surface of each crus is the

erector penis muscle. These muscles should now be cleaned and their connections examined.

Superficial Perineal Muscles.—Under this heading are included not only the ejaculator urinæ and erector penis muscles, but also the transversus perinei. The superficial perineal muscles have been seen to lie within the pouch formed by the superficial fascia and the triangular ligament. When the superficial fascia is removed each will be found to be invested by its own delicate aponeurotic layer.

Transversus Perinei (musculus transversus perinei superficialis).—This muscle is a narrow slip of muscular fibres which arises from the inner aspect of the ascending ramus of the ischium close to the tuberosity. It passes inwards and unites with the corresponding muscle of the opposite side in the central point of the perineum.

The central point of the perineum is a tendinous septum situated in the middle line of the body close to the posterior end of the bulb and a short distance in front of the anus. Towards this point, a number of the perineal muscles converge to obtain attachment. *On each side*, it gives attachment to the transverse perineal muscles; *behind*, to the sphincter ani; *in front*, to the posterior fibres of the ejaculator urinæ; whilst *from above*, the anterior fibres of the levator ani descend to reach its upper aspect.

Ejaculator Urinæ (musculus bulbo-cavernosus).—This muscle is spread over the bulb and posterior part of the corpus spongiosum. It is composed of two symmetrical halves, and its fibres take origin from the central point of the perineum and from a fibrous median raphe which is prolonged forwards between the two halves of the muscle. The insertion differs according to the point at which the muscle is examined. The *posterior fibres* are simply attached to the superficial aspect of the triangular ligament; the *middle fibres* constituting the greater part of the muscle, sweep around the corpus spongiosum so as to invest it completely, and are inserted into a common aponeurosis upon the upper surface of this portion of the penis; lastly, the *anterior fibres* form two long narrow muscular bands which diverge from each other like the limbs of the letter V, and, passing forwards over the sides of the corpora cavernosa, are inserted into an aponeurosis on the dorsum of the penis. Thus the

posterior fibres partially embrace the bulb; the *middle fibres* embrace the corpus spongiosum; whilst the *anterior fibres* embrace the body of the penis. The ejaculator urinæ supports the urethra during micturition, and by its contraction it ejects the last drops of urine or semen from the passage.

Erector Penis (musculus ischio-cavernosus).—The erector penis lies upon the crus penis. It arises by fleshy fibres from the inner aspect of the tuber ischii, and is inserted by an aponeurotic expansion into the lower and outer surface of the anterior portion of the crus.

Perineal Nerve.—This is one of the two terminal branches of the pudic nerve. It supplies twigs to the skin, to the muscles of the perineum, and to the bulb of the penis. The *cutaneous branches* have already been followed out. They are the posterior and anterior superficial perineal nerves. *Muscular twigs*, occupying a deeper plane, may be traced to each of the three superficial perineal muscles and to the levator ani, whilst a few minute offsets pierce the triangular ligament to supply the compressor urethræ muscle. The *nerve to the bulb* is a small branch which breaks up into filaments which enter the hinder part of the corpus spongiosum.

Perineal Triangle.—If the superficial perineal muscles be now examined in regard to the relations which they hold to each other, the student will observe that they constitute the boundaries of a small triangular space upon each side of the middle line. The *base* of the triangle is formed by the transversus perinei; *externally* it is limited by the erector penis, and *internally* by the ejaculator urinæ. Let the student now place the point of his finger within this space and press upwards and backwards. He will perceive that it rests upon a strong resisting membrane. This is the triangular ligament, which therefore forms the floor of the space.

Dissection.—To bring the triangular ligament of the urethra fully into view, it is necessary in the first place to remove the superficial perineal muscles. When this is done the three divisions of the root of the penis are exposed to view, and their manner of attachment (which has already been described, p. 321) can be studied. Detach in the next place the crura penis from the sides of the pubic arch, and turn them aside. This must be effected with care, so as not to destroy the attachment of the ligament to the sides of the pubic arch, or to injure the pudic artery and dorsal nerve of the penis, which pierce the ligament in its upper part.

Triangular Ligament.—This is now seen to be a strong

aponeurotic membrane which stretches across the pubic arch. It must be regarded as lying in the same morphological plane as the bony and ligamentous wall of the pelvis, and as completing the pelvic wall in front in the same manner as the thyroid membrane fills up the gap formed by the thyroid foramen.

Upon each side the triangular ligament is attached to the margins of the rami of the pubis and ischium. Its base is




FIG. 101.—Deep dissection of the Perineum. The penis has been removed, the urethra cut across, and the superficial layer of the triangular ligament removed on the left side.

somewhat indefinite, and has already been seen to blend along the lower border of the transversus perinei muscle with the fascia of Colles. In addition to this attachment, however, a careful dissection in a good subject will show that the central part of the base projects backwards and downwards in the form of a short process or peak, which joins the central point of the perineum. Near the symphysis pubis some transverse fibres, in association with the triangular ligament, pass from one side of the pubic arch to the other,

and form a more or less distinct band, called the *transverse perineal ligament*. Between the upper border of this band and the sub-pubic ligament an oval gap is left for the passage of the dorsal vein of the penis.

In the erect posture of the body the superficial surface of the triangular ligament looks downwards and forwards, whilst its deep surface looks upwards and backwards towards the cavity of the pelvis. In close contact with its superficial surface are the parts which constitute the root of the penis, viz., the bulb and the two crura and the muscles which are associated with them, also the transversus perinei muscle on each side. The structures which are in relation to its deep surface will be studied when it is reflected.

The triangular ligament is not an unbroken continuous layer of fascia. It is pierced—(1) by the urethra ; (2) by the internal pudic arteries ; (3) by the dorsal nerves of the penis ; (4) by the arteries to the bulb ; (5) and lastly, at its base, where it blends with the superficial fascia, by the superficial perineal vessels and nerves. The *aperture for the urethra* is situated in the middle line, one inch below the symphysis pubis. It is not a clean-cut hole with sharp edges. The margins of the opening are prolonged over the bulb of the penis so as to form for it an aponeurotic capsule. As soon as the urethra gains the superficial aspect of the ligament, it sinks into the bulb, and is carried forwards through the entire length of the corpus spongiosum to its external opening on the glans penis. On either side of the urethral aperture there is a small opening in the ligament which gives passage to the corresponding *artery to the bulb*. Half an inch further forwards the *dorsal nerve of the penis* and the *internal pudic artery* pierce the ligament on either side, close to the margin of the pubic arch, and under cover of the corresponding crus penis.

The term "*inferior or superficial layer*" of the triangular ligament is frequently applied to this membrane, which implies that there is a deeper or superior layer to be studied in connection with it ; and so there is. But whilst these layers are very intimately connected, they must be looked upon as being distinct structures. The superficial or inferior layer or the triangular ligament proper is in the same morphological plane as the bony wall of the pelvis and the thyroid membrane, and, in fact, completes the pelvic wall in front. The *superior or*

deep layer is simply the parietal layer of the pelvic fascia carried round to the front of the pelvis. Consequently the connections of this layer can be examined very much better in conjunction with the pelvic fascia. Suffice it for the present to say that inferiorly it is blended with the base of the triangular ligament, but that it recedes from the surface as it passes upwards, so that a space or interval is left between the two aponeurotic strata. Contained within this interval are the following structures:—

1. The membranous portion of the urethra.
2. The dorsal vein of the penis.
3. The compressor urethræ muscles.
4. Cowper's glands.
5. The internal pudic vessels, the dorsal nerves of the penis, and the artery to the bulb.

Dissection.—To expose these parts, the superficial layer of the triangular ligament must be raised upon one side of the body. It should be carefully preserved upon the opposite side, for in the subsequent dissection of the pelvis it is required as a landmark. On the side selected detach the ligament from the margin of the pubic arch, and, cautiously raising it from the subjacent structures, throw it inwards towards the bulb.

Membranous Portion of the Urethra.—The canal of the urethra is subdivided for descriptive purposes into three parts, according to the structures which are in relation to its walls as it passes from the bladder to its termination on the glans penis. These are—(1) the prostatic portion; (2) the membranous or muscular portion; and (3) the spongy portion. Each of these subdivisions has a very definite relation to the triangular ligament; the prostatic part is placed *behind* this ligament; the membranous part is situated *between* the two layers of the ligament; whilst the spongy portion lies *in front* of the ligament.

Now that the superficial layer of the triangular ligament is removed upon one side, the student can readily feel with the point of the finger the staff as it lies within the membranous portion of the urethra. He should examine also its surroundings. It is the shortest subdivision of the urethra, and is distant about one inch from the symphysis pubis. Throughout its entire extent it is enveloped by the fibres of the compressor urethræ muscle, and on this account it is sometimes called the muscular part of the urethra. On each side, and at a lower level, is Cowper's gland, whilst between it and the symphysis

pubis is the dorsal vein of the penis as it extends backwards between the two layers of the triangular ligament.

Compressor Urethræ (musculus transversus perinei profundus).—This is a fan-shaped muscle. It has a narrow tendinous origin from the pubic arch close to the junction of the pubic and ischial rami. Expanding as it passes inwards towards the urethra, its fibres arrange themselves into two layers, which enclose between them the entire extent of the membranous portion of the urethra. The muscles of opposite sides meet therefore in the middle line, and the muscular fibres which compose the two layers are inserted into a median raphe, both upon the upper and lower aspects of the urethra. This muscle is supplied by one or two delicate twigs from the *perineal division* of the *pudic nerve*.

Cowper's Glands (glandulæ bulbo-urethrales).—As a general rule, these glands can readily be detected by raising the lower fibres of the compressor urethræ. They are small lobulated bodies of a deep yellow colour, and resemble peas both in size and shape. They are placed one on each side of the middle line, immediately below the membranous part of the urethra, and are overlapped by the posterior part of the bulb—separated from it, however, by the triangular ligament. From each a minute duct proceeds, but this duct does not open into the membranous portion of the urethra. It passes forwards between the wall of the urethra and the substance of the bulb for the distance of one inch, and opens on the floor of the spongy part of the urethra.

Internal Pudic Artery (arteria pudenda interna).—The pudic artery is a branch of the internal iliac. It is met with in three different regions of the body—viz. (1) within the cavity of the pelvis; (2) in the gluteal region, where it lies upon the spine of the ischium; and (3) in the perineal space. It is consequently described as consisting of a *pelvic*, a *gluteal*, and a *perineal part*. The *perineal* or *third part* of the pudic artery enters the perineum by passing through the small sacro-sciatic foramen. At first it is placed deeply; but, as it is traced forwards, it is found to become more superficial, and, at the same time, to incline inwards, so that, at its termination, it lies close to the middle line of the body.

In the rectal triangle the pudic artery is contained within a sheath, termed Alcock's canal, which is formed by the

splitting of that part of the parietal pelvic fascia which forms the outer wall of the ischio-rectal fossa. It lies fully an inch and a half above the level of the lowest part of the ischial tuberosity, and is accompanied by two veins and the two divisions of the pudic nerve. Of the latter the dorsal nerve of the penis lies above it and the perineal nerve below it. Reaching the base of the urethral triangle, the pudic artery insinuates itself between the two layers of the triangular ligament, and, gradually emerging from under cover of the




FIG. 102.—Diagram. Vertical section through the pubic arch to show the two perineal compartments and their contents.

bone, proceeds forwards along the edge of the pubic arch to a point about half an inch below the symphysis, where it pierces the superficial layer of the triangular ligament, and immediately ends by dividing into two branches under cover of the crus penis—viz., (1) the artery to the corpus cavernosum, and (2) the dorsal artery of the penis (Fig. 101, p. 325).

Branches of the Pudic Artery.—The pudic has already been seen to give off the *inferior hæmorrhoidal*, the *superficial perineal*, and the *transverse perineal arteries*, and to divide into its two terminal branches—the *dorsal artery of the penis* and

the *artery to the corpus cavernosum*. Between the layers of the triangular ligament it gives origin to the *artery to the bulb*.

The *artery to the bulb* is a short wide vessel which springs from the pudic about a quarter of an inch above the level of the base of the triangular ligament. It passes transversely inwards between the two layers of this ligament, and, giving a small twig to Cowper's gland, it enters the substance of the bulb. It supplies the bulb and corpus spongiosum with blood.

The *artery to the corpus cavernosum* pierces the inner aspect of the crus penis, and is carried forward in the substance of the corpus cavernosum, which it supplies with blood.

The *dorsal artery of the penis* runs forward in the interval between the crura penis, and, passing between the two layers of the suspensory ligament, gains the dorsum of the penis, where it will be afterwards traced.

Pudic Nerve (*nervus pudendus*).—The pudic nerve is a branch of the sacral plexus. Following the internal pudic artery, it enters Alcock's canal, and after giving off the *inferior hæmorrhoidal nerve*, it divides into two terminal divisions—viz., (1) the perineal nerve, and (2) the dorsal nerve of the penis.

The *perineal nerve* has been seen to break up into the following branches:—

- | | | |
|-------------------|---|--|
| <i>Cutaneous.</i> | { | 1. The posterior superficial perineal. |
| | | 2. The anterior superficial perineal. |
| <i>Muscular.</i> | { | 1. The ejaculator urinæ. |
| | | 2. The erector penis. |
| | | 3. The transversus perinei. |
| | | 4. The compressor urethræ. |

It also supplies one or two branches to the bulb and the corpus spongiosum penis.

The *dorsal nerve of the penis* follows the pudic artery between the two layers of the triangular ligament, where it lies more completely under shelter of the side of the pubic arch than the artery. Finally, piercing the superficial layer of the triangular ligament, about half an inch below the symphysis pubis, it accompanies the dorsal artery of the penis. At the root of the penis it supplies one or two twigs to the corpus cavernosum.

The dissection of the perineum is now completed, but whilst the body is in the lithotomy position, and the various parts of the perineum exposed, the student should consider what structures still cover the perineal aspect of the prostate gland. Three layers would still require to be removed to

bring the prostate into view—viz., (1) the compressor urethræ muscle; (2) the parietal pelvic fascia or the deep layer of the triangular ligament; (3) the anterior fibres of the levator ani muscle. Such being the case, it will be apparent that within the limits of the urogenital triangle, and dissecting from the surface towards the prostate gland, we meet with an alternation of *muscular* and *fascial* strata, viz. :—




FIG. 103.—Deep dissection, in which the lower portion of the levatores ani muscles have been removed, and the external sphincter detached from the central point of the perineum, and the rectum turned back.—(From GRAY'S *Anatomy*.)

1. The fascia of Colles.
2. *Superficial perineal muscles*.
3. Triangular ligament.
4. *Compressor urethræ muscle*.
5. Parietal pelvic fascia or deep layer of triangular ligament.
6. *Levator ani muscle*.
7. Capsule of prostate.

Further, the fasciæ of the urogenital triangle are so arranged that they form a superficial and a deep compartment, and within one or other of

these all the structures of this division of the perineum are contained (Fig. 102).

The *superficial compartment* is bounded *in front* by the fascia of Colles, *behind* by the triangular ligament, *laterally* by the attachment of these to the margins of the pubic arch, and *inferiorly* by the blending of the fascia of Colles with the base of the triangular ligament. For the contents of this compartment see p. 312.

The *deep compartment* is the interval between the triangular ligament and the parietal pelvic fascia, and the structures which it contains are enumerated at p. 327 (Fig. 101).

A pad of tow, soaked in a mixture of spirit and carbolic acid, should be placed in the perineum, and the flaps of skin carefully stitched over it. On the *third day* after the body has been brought into the Rooms, it is placed upon its face, and the dissectors of the abdomen stop work until the subject is turned, which is done *four days* later.

THE FEMALE PERINEUM.

The boundaries of the female perineum are identical with those in the male. The region, however, is wider and of greater extent. For purposes of description, it is subdivided by an imaginary transverse line drawn in front of the anus and the tuberosities of the ischium into a *posterior rectal triangle* and an *anterior urogenital triangle*.

External Anatomy.—The rectal triangle presents the same points for consideration as in the male. The external anatomy of the urogenital triangle demands the careful study of the student, because here we find the external organs of generation. They are—

- | | |
|----------------------|--------------------------|
| 1. The mons Veneris. | 4. The clitoris. |
| 2. The labia majora. | 5. The urethral opening. |
| 3. The labia minora. | 6. The vaginal orifice. |

All these parts are included under the common term of *Vulva*.

Mons Veneris.—This is a marked cushion-like eminence situated in front of the pubes. This projection is due to a collection of adipose tissue under the integument. It is covered by hair.

Labia Majora.—These correspond to the scrotum in the

male, cleft along the middle line. They are two rounded folds, which commence in front at the mons Veneris and extend downwards and backwards towards the anus. They diminish in thickness as they proceed backwards, and anteriorly they unite to constitute the *anterior commissure*. Externally, they are covered by skin studded with scattered hairs, whilst internally they are coated with smooth humid integument, the free surface of which is lubricated by a semi-solid secretion, derived from numerous sebaceous glands which open upon it. During parturition, the labia majora are unfolded, and thus give the vagina a greater capability of dilatation.

The labia majora enclose an elliptical fissure, which is termed the *puddendal cleft*, or the *urogenital fissure*, on account of its containing the apertures of the urethra and vagina. Within this fissure a slightly marked crescentic fold of integument stretching between the hinder parts of the labia majora will be observed. This fold receives the name of the "*fourchette*" or "*frenulum pudendi*." It is usually ruptured in first labours.





FIG. 104.—Outlet of Female Pelvis.

Between the fourchette and the entrance to the vagina there is a depression which is known as the *fossa navicularis*.

It may be well for the student to bear in mind that the term "perineum" in the language of the obstetric surgeon is used in a very restricted sense. It is given to the narrow interval which exists between the anus and the fourchette.

Labia Minora or Nymphæ.—These represent the male prepuce. They are two pendulous folds of integument which lie within the labia majora. To display them fully the labia majora must be pulled apart. They are placed one on each side of the vaginal orifice. As they proceed forwards they become more prominent, and at the same time converge so

as to approximate to each other more closely. Reaching the clitoris, each terminates by splitting into two divisions or folds. The smaller and lower fold is attached to the under surface



1. Labium majus.
2. Labium minus or nympha.
3. Clitoris.
4. Vestibule (figure placed immediately above urethral opening).
5. Hymen.
6. Fourchette.
7. Vagina.
9. Opening of the duct of Bartholin's gland.
- A. Anus.
- G.S. Line of great sciatic ligament.
- P.A. Inner border of pubic arch.

FIG. 105. — External Genitalia of the Female. (From Symington.) The outlet of the pelvis is indicated by dotted lines.

of the clitoris, and receives the name of *frenulum clitoridis*. The upper fold arches over the clitoris like a hood, and unites with the corresponding fold of the opposite side to form the *præputium clitoridis*.

Clitoris.—The clitoris is the homologue of the penis, and, notwithstanding its diminutive proportions, it presents a close resemblance to the male organ both in appearance and structure. It is a minute elongated projection placed below the anterior commissure, and surmounted by a sensitive rounded tubercle called the *glans*, but it is not traversed by the urethra. The manner in which its prepuce and frenum are formed has already been described. To obtain a proper view of the clitoris the student must lay hold of the glans with the forceps and draw it out from the prepuce.

Vestibule.—The dissector should next take note of a smooth triangular interval which exists between the clitoris and the entrance to the vagina. The term *vestibule* is given to this area. It is bounded laterally by the nymphæ, and towards its lower part or base is seen the orifice of the urethra.

The triangular outline of the vestibule is only seen when the labia are forcibly drawn apart from each other. In the natural condition of parts the labia are in close apposition, and the vestibule is then a deep recess which represents the bottom of the pudendal cleft, between the clitoris and the vagina.

Urethral Orifice.—This lies close to the opening of the vagina, about one inch below the clitoris. It usually presents the appearance of a vertical slit, and the mucous membrane around it is prominent, pouting and slightly puckered, so that when the tip of the finger is passed over the vestibular area the opening can readily be distinguished by touch.

Vaginal Orifice.—The vaginal opening in the virgin is partially closed by the *hymen*—a semilunar fold of mucous membrane attached to the posterior aspect and sides of the entrance to the vagina, and presenting a free concave margin towards the pubes. The form of the hymen, however, is very variable. Sometimes it is present in the shape of a septum attached around the entire circumference of the vaginal entrance, but pierced in the centre by a circular opening or a vertical slit; again, it may be cribriform or fringed along its free margin. Lastly, it may constitute a complete septum across the opening of the vaginal canal. In this case awkward results ensue from the retention of the menstrual fluid. After it has been ruptured its position is marked by certain rounded elevations which have received the name of *carunculae myrtiformes*.

Close to each side of the vaginal orifice, in the groove between it and the posterior part of the labium minus, is the opening of the duct of *Bartolin's gland*, an orifice just visible to the naked eye.

Passage of Catheter and Examination of Os Uteri.—The dissector should now practise the passing of the female catheter, and afterwards introduce a speculum into the vagina, so as to obtain a view of the os uteri.

In passing the catheter the forefinger of the left hand should be placed in the orifice of the vagina, with its palmar surface directed upwards towards the pubes. If the instrument be now passed along this finger, and the point raised slightly when it reaches the entrance to the vagina, a little manipulation will cause it to enter the urethra.

When the speculum is introduced into the vagina, the points to be noted in connection with the os uteri are:—(1) the small size of the opening; (2) the two rounded and thick lips which bound this aperture. In the virgin the opening is circular, but in women who have borne children it is somewhat transverse and often scarred. Note further that the anterior lip is the thicker and shorter of the two, whilst the posterior lip is the longer.

Reflection of Skin.—The rectum should be moderately filled with tow, and the vulva and anal orifice stitched up.—*Incisions*—(1) A transverse incision should, in the first place, be carried from one ischial tuberosity to the other, in front of the anus. (2) The urogenital fissure and the orifice of the anus should next be closely encircled by incisions, and these joined by a cut along the middle line. (3) Lastly, carry an incision forwards from the second or third piece of the coccyx along the middle line to the cut which surrounds the anus.

Four flaps are thus marked out; the two anterior may be thrown forwards and outwards, and the two posterior backwards and outwards.

Superficial Fascia.—The superficial fascia of the perineum is now laid bare. In the rectal triangle it agrees in every particular with the same portion of fascia in the male. In the anterior or urogenital triangle, however, owing to the difference in the external organs of generation, there is a slight modification. It presents the same two layers. In the superficial fatty layer, where it covers the labia majora, there are *dartos fibres* similar to those in the scrotum of the male. The deeper layer has the same attachments as in the male, viz., to the anterior lips of the pubic arch, and to the base of the triangular

ligament ; but it is not so membranaceous, and consequently does not form so distinct a stratum. The two fascial pouches are also present in the female, and are sometimes spoken of as the *vulvo-scrotal sacs*. Their separation along the middle line is not due to the interposition of a median septum, as in the male, but to the presence of the urogenital fissure.

RECTAL TRIANGLE.

Nothing need be added to what has already been written regarding this portion of the perineal space in the male. In both sexes the steps of the dissection and the parts found are precisely the same (*vide* p. 313).

UROGENITAL TRIANGLE.

Superficial Perineal Vessels and Nerves.—Under this heading we include *two arteries* and *three nerves*, viz. :—

Arteries.	{	The superficial perineal artery.
		The transverse perineal artery.
Nerves.	{	The posterior superficial perineal nerve.
		The anterior superficial perineal nerve.
		The long pudendal nerve.

They have precisely the same disposition as the corresponding vessels and nerves in the male, with this exception, that they are somewhat smaller, and are distributed to the labium majus, instead of to the scrotum. For a detailed description of these structures, the student may refer to p. 319.

Dissection.—The superficial perineal vessels and nerves should now be divided and thrown backwards, and the superficial perineal muscles cleaned. These are three in number, viz., the transversus perinei, the erector clitoridis, and the sphincter vaginæ. The two first have a similar position to the corresponding muscles in the male ; the sphincter vaginæ lies upon the side of the vagina close to its orifice. To obtain a good view of these muscles the superficial fascia and the labia should be dissected away.

In cleaning the muscles the dissector should look for the small nerve twigs which are given to each by the perineal division of the internal pudic nerve.

Superficial Perineal Muscles.—*The transversus perinei* has the same disposition as in the male, but it is rare to find it so well marked in the female. In most subjects its fibres are

pale, and it is very difficult to define. It is a slender fasciculus which takes origin from the inner surface of the ramus of the ischium close to the tuberosity, and passes obliquely forwards and inwards to its insertion into the central point of the perineum.

In the female the central point of the perineum is placed behind the vaginal orifice.

The *erector clitoridis* corresponds with the erector penis in




FIG. 106.—Muscles of the Female Perineum (after Peter Thompson).

the male. It is a small muscle which arises from the inner aspect of the ischial tuberosity, and is inserted by a tendinous expansion on the surface of the crus clitoridis.

The *sphincter vaginæ* is the representative of the ejaculator urinæ of the male. It is a true sphincter muscle, and consists of two halves, which are placed one on each side of the vaginal orifice and vestibule, and are closely adapted to the surfaces of the two halves of the vaginal bulb. Posteriorly the fibres of opposite sides unite behind the vaginal opening, and are attached to the central point of the perineum, some

of the fibres intermixing with those of the sphincter ani. Anteriorly the two portions of the muscle become narrower, and, converging towards the middle line, are attached to the sides of the clitoris. In some cases a small fasciculus on each side may be observed to reach the dorsum of the clitoris, and there gain insertion into a tendinous expansion which lies superficial to the dorsal vein. This fasciculus is comparable with the anterior fibres of the ejaculator urinæ in the male, which embrace the circumference of the body of the penis.

Perineal Triangle.—The dissector should now observe that the three perineal muscles form the sides of a small triangle, the floor of which is constituted by the superficial layer of the triangular ligament.

Perineal Body.—It has been already stated that the term “perineum” is confined by the obstetrician to the narrow interval between the fourchette and the anus. Now that this part has been dissected, it will be seen to consist of an indefinite mass of fibrous and muscular tissue, which occupies the interval between the rectum and the vagina. This is known as the *perineal body*. Muscular tissue belonging to the sphincter ani, levatores ani, and sphincter vaginæ, together with the central point of the perineum, enter into its constitution.

Dissection.—The sphincter vaginæ should now be carefully raised from the surface of the bulb, and the erector muscle from the surface of the crus clitoridis. The transversus perinei muscle may be removed at the same time.

Bulb of the Vestibule.—The bulb of the vestibule is now displayed. It consists of two oblong bodies, composed of erectile tissue, placed one on each side of the vestibule and entrance to the vagina. Somewhat narrow in front, they expand as they pass backwards, and each is invested by a fibrous capsule derived from the triangular ligament, upon the anterior surface of which they rest. Externally they present a rounded convex surface which is coated with the sphincter vaginæ muscle, whilst internally, each erectile mass rests upon the deep surface of the mucous membrane of the vagina. In front of the urethra, between it and the clitoris, the two halves of the bulb are brought into direct communication with each other by a small venous plexus called the *pars intermedia*, which in turn is continuous with the erectile tissue of the glans clitoridis. To obtain a proper idea of these connections,

it is necessary to study specimens which have been specially injected and prepared.

The arrangement of erectile tissue in the female corresponds more or less closely with the condition present in the male. The apparent dissimilarity is due to the presence of the urogenital fissure and orifice of the vagina. Let us suppose for a moment that the latter is obliterated, and that the vestibule is closed in the form of a canal which carries the urethra forwards to the extremity of the clitoris. The two halves of the bulb would then be in contact with each other, and its entire surface would be covered by a muscular stratum, after the manner of the bulb and ejaculator urinæ in the male. Further, the urethra would be surrounded by erectile tissue, and the *pars intermedia* would be seen to correspond to some extent to that portion of the corpus spongiosum which in the male lies in front of the bulb, and becomes continuous with the glans.

Dissection.—If the stitches uniting the lips of the pudendal cleft have not been already removed they should now be taken away. The crura clitoridis have been exposed by the removal of the erector muscles. To obtain a good view of the entire organ, strip the mucous membrane from the body of the clitoris, and clear away the loose tissue which surrounds it. In doing this, however, remember that on its dorsal aspect certain vessels and nerves run forwards to reach the glans, and that suspending it to the front of the pubes there is the suspensory ligament. ~ . .

Clitoris.—The *body of the clitoris* is composed of two cylindrical erectile bodies called the *corpora cavernosa*, which correspond with the structures that bear the same name in the male. Along the middle line they are united by their inner surfaces, and the erectile tissue of the one is separated from that of the other by an imperfect *pectiniform septum*. The body of the clitoris is about an inch and a half long, and is bent in a downward direction on itself at the lower border of the symphysis pubis. Anteriorly it terminates in a small rounded tubercle, which bears the name of the *glans clitoridis*. The glans, however, is not structurally continuous with the corpora cavernosa. It is a little mass of erectile tissue continuous with the *pars intermedia*, and fitting into a slight concavity which is formed for its reception on the extremities of the corpora cavernosa. Posteriorly, opposite the lower part of the symphysis pubis, the corpora cavernosa separate, and diverging widely from each other, form the

crura clitoridis. Each crus is attached by its deep surface to the rami of the pubis and ischium, and is covered by its own erector muscle.

The clitoris, then, consists of three parts:—(1) *a glans* continuous with the *pars intermedia*; (2) *a body* composed of two corpora cavernosa lying side by side and united along the middle line; and (3) *two crura* attached to the sides of the pubic arch. We have seen that the *pars intermedia* corresponds with the *corpus spongiosum* in the male. This




FIG. 107.—Dissection of Female Perineum to show the Clitoris and the Bulb of the Vestibule.

apparatus in the female, therefore, closely resembles the penis in the male, the chief differences being the diminutive size of the clitoris, and the fact that the glans clitoridis is not perforated by the urethra.

Dissection.—Detach the crura clitoridis from the sides of the pubic arch and throw them aside. This dissection requires care, because the pudic arteries, the dorsal nerves of the clitoris, and the small arteries which enter the crura, are very apt to be injured. The pudic vessels and the dorsal nerve will be seen piercing the triangular ligament about half an inch below the symphysis pubis, and a little way external to the middle line.

Triangular Ligament.—A good view is now obtained of the triangular ligament. Owing to the greater width of the pubic arch, it is a more extensive membrane than in the male. It does not possess the same strength, however, and is not so perfect, seeing that it is pierced by the vaginal canal.

In the middle line it is pierced fully an inch below the symphysis pubis by the urethra, and immediately below the urethral opening by the wide vaginal canal. Its base is perforated by the superficial perineal vessels and nerves, whilst the internal pudic artery and the dorsal nerve of the clitoris pierce it about half an inch below the symphysis.

The dorsal vein of the clitoris passes backwards through an oval opening between the transverse perineal ligament and the subpubic ligament.

The so-called *deep layer of the triangular ligament* is really a part of the parietal layer of the pelvic fascia. Opposite the pubic arch the deep layer of the triangular ligament by its lower border fuses with the base of the triangular ligament. As it is traced upwards, however, it recedes from the triangular ligament, and consequently a space or interval is left between them.

Dissection.—The triangular ligament should be reflected upon one side. Detach it from the margin of the pubic arch and throw it inwards. The pudic vessels and the dorsal nerve of the clitoris, together with the compressor urethræ muscle, may now be examined.

Urethra.—The female urethra is a short canal, which extends from the neck of the bladder to its orifice on the vestibule. It measures about one and a half inches in length, and has an oblique and slightly curved course from above downwards and forwards. The concavity of the curve is directed forwards. So close is its relation to the anterior wall of the vagina, that it may almost be said to be embedded in it.

At the present stage of the dissection, the urethral canal is seen to be covered by the fibres of the compressor urethræ muscle.

A leading peculiarity of the female urethra is its great dilatability. Cases are on record in which vesical calculi weighing from two to four ounces have traversed it, and thus escaped from the bladder. It thus happens that in the extraction of foreign substances from the female bladder, it is rarely necessary to have recourse to the knife.

Compressor Urethræ.—This muscle differs somewhat from the corresponding muscle in the male. It has the same origin (*viz.* from the inner aspect of the pubic arch at the junction of the pubic and ischial rami), and it also divides into two bundles; but these have not the same intimate relation to the urethra. The upper or anterior bundle spreads out upon the upper or anterior surface of the urethra, whilst the lower or posterior bundle spreads out upon the wall of the vagina.

The **Vagina** will be fully described in connection with the pelvic viscera.

Bartholin's Glands.—These glands are the representatives in the female of Cowper's glands in the male. They are two round or oblong bodies about the size of a horse-bean, placed one upon each side of the entrance to the vagina immediately behind the rounded end of the bulb, and under cover of the sphincter vaginæ. A long duct proceeds from each gland, and opens in the angle between the nymphæ and the hymen or *carunculæ myrtiformes* (Fig. 105, p. 334).

Internal Pudic Vessels and Nerve.—The internal pudic vessels and nerve have a similar disposition to the corresponding vessels and nerve in the male (p. 329). If anything, they are somewhat smaller.

The student must therefore look for the *artery to the bulb*, a branch of the internal pudic, which in this case is given to the bulb of the vagina, and the two terminal branches of the internal pudic artery, *viz.*, the *dorsal artery of the clitoris*, and the *artery to the corpus cavernosum*.

The internal pudic nerve ends by dividing into the perineal nerve and the dorsal nerve of the clitoris.

The *perineal nerve* gives off—(1) the anterior and posterior superficial perineal branches to the skin covering the labium majus; (2) muscular twigs to all the perineal muscles; and (3) a branch to the bulb of the vagina.

The *dorsal nerve of the clitoris* gives a twig to the corpus cavernosum, and runs forwards with the artery of the same name between the crura to reach the dorsum of the clitoris.

Dorsal Vessels and Nerves of the Clitoris.—On the dorsum of the clitoris a little dissection will display the *dorsal vein* occupying the groove in the middle line, with a *dorsal artery* and *nerve* lying upon each side of it.

The arteries and nerves should be traced forwards to their distribution in the glans.

The *dorsal vein* takes origin in the glans. As it proceeds backwards it receives certain superficial veins and also tributaries from the corpora cavernosa. At the root of the clitoris it dips downwards between the crura, and, passing between the triangular and the subpubic ligaments, is continued backwards into the pelvis to join the plexus of veins around the neck of the bladder.

ABDOMINAL WALL.

On the fifth day, after the dissection of the perineum is completed, the body is placed upon its back, with blocks under the chest and pelvis, and the dissectors of the abdomen begin the dissection of the abdominal wall (Fig. 108).

External Anatomy.—It is well, however, before proceeding to the actual dissection of the part, that some attention should be paid to the general configuration and bony prominences of the region. If the subject is obese the abdomen presents a smooth, rounded, and protuberant appearance; if, on the other hand, it is spare, the abdominal wall is depressed, and the lower margin of the thorax above, and the pubes, crest of the ilium, and Poupart's ligament below, stand out in marked relief. In the middle line, the student will notice a linear depression extending downwards towards the symphysis. This corresponds with the *linea alba* or the interval between the two recti muscles. It is an important line to the surgeon, because here the wall of the abdomen is thin and devoid of blood-vessels. In this line the trocar is introduced into the abdomen in the operation of paracentesis abdominis or tapping.

In this linear depression, rather nearer the pubes than the ensiform cartilage, is the *umbilicus* or *navel*. This is a depressed and puckered cicatrix, the floor of which is raised in the form of a little button-like knob. It results from the closure of an opening in the abdominal wall of the fœtus, through which passed the constituents of the umbilical cord

—viz., the ~~umbilical vein, the two allantoic or hypogastric arteries, and the urachus~~ ↙

In powerful well-developed subjects the rectus muscle stands out on each side of the middle line, and its outer margin gives rise to a curved line, the concavity of which is directed inwards. This line corresponds to the *linea semilunaris*—i.e., the line along which the aponeurotic tendon of the internal oblique muscle splits to enclose the rectus. The *linea semilunaris* is on certain occasions selected by the surgeon as the site for incisions through the abdominal wall.

The student should now place his finger upon the upper part of the symphysis pubis and carry it outwards, over the pubic crest, to the pubic spine; from this he should follow the line of Poupart's ligament to the anterior superior spine of the ilium, and, having identified these parts, let him next endeavour to determine the position of the external abdominal ring. This is easily done in a male subject. Immediately ↙ external to the spine of the os pubis the spermatic cord can be felt as it passes over Poupart's ligament to reach the scrotum. Taking this as a guide, push the loose skin of the scrotum upwards before the finger. The tip of the finger enters the opening, the sharp margins of which can now be felt.

The spermatic cord, as it passes downwards into the scrotum, should be taken between the finger and thumb. On pressure being applied the vas deferens can be easily distinguished at the back of the cord, by the hard whip-cord-like feel that it conveys to the fingers.

The crest of the ilium, as it proceeds upwards and backwards from the anterior superior spine, can be easily felt. Indeed, in most cases it is visible to the eye for a distance of about two and a half inches. At the point where it disappears from view a prominent tubercle is developed on its outer lip, and it is here that the lateral outline of the trunk joins the ilium. It is the highest point of the iliac crest, therefore, that can be seen from the front. As we shall see later on, use is made of this fact in subdividing the abdominal cavity into regions.

In females who have borne children the skin over the lower part of the abdomen is wrinkled and scarred.

Parts to be dissected.—A dissection of the abdominal wall will display the following parts :—

1. Superficial fascia.
2. Cutaneous vessels and nerves.
3. The external oblique muscle.
4. The internal oblique muscle.
5. The lower six intercostal nerves and accompanying vessels ; the ilio-inguinal and ilio-hypogastric nerves.
6. The transversalis muscle.
7. The rectus and pyramidalis muscles and the sheath of the rectus.
8. The transversalis fascia.
9. The deep epigastric and deep circumflex iliac arteries.
10. The superior epigastric and musculo-phrenic arteries.
11. The spermatic cord.
12. The inguinal canal.
13. The extra-peritoneal fat.
14. The parietal peritoneum.




FIG. 108.

Reflection of Skin.—*Incisions*—(1) Along the middle line of the body from the ensiform cartilage to the symphysis pubis. At the navel the knife should be carried round so as to surround it with a circular incision. (2) From the ensiform cartilage transversely outwards around the chest, as far back as the knife can be carried. (3) From the symphysis pubis outwards along the line of Poupart's ligament to the anterior superior spine of the ilium, and then backwards along the crest of the ilium (Fig. 108).

The large flap of skin thus mapped out should be carefully raised from the subjacent superficial fascia and turned outwards. If the abdominal wall is flaccid, the dissection may be facilitated by inflating the abdomen. Make an incision through the umbilicus large enough to admit the nozzle of the bellows or an injection-pipe fixed to a bicycle-pump, and when the walls are quite tense secure the opening with twine, which has previously been *sewn* round the lips of the incision.

Superficial Fascia.—The superficial fascia which is now laid bare is seen to present the same appearance, and possess the same characters, as in other localities. Above, it is thin

and weak, and is directly continuous with the corresponding fascia over the chest; below, it becomes more strongly marked, and acquires a greater density. Towards the lower part of the abdomen it consists of two layers—a fatty superficial stratum called *Camper's fascia*, and a deep membranaceous stratum termed *Scarpa's fascia*. ↙

There is another point, however, in which the superficial fascia differs somewhat from the same fascia in other parts of the body. It is more elastic, and this elasticity is due to the presence of elastic fibres in its deeper membranaceous part. Over the lower part of the linea alba the elastic tissue is generally seen collected in the form of a distinct band which in the region of the symphysis pubis becomes connected with the penis and its suspensory ligament. A reference to comparative anatomy gives interest to this fact. In the human subject this elastic band is the rudimentary representative of a continuous and distinct layer of yellow elastic tissue (*the abdominal tunic*), which is present in the horse and other quadrupeds in which the weight of the viscera is chiefly sustained by the abdominal wall.

But what becomes of the two layers of the superficial fascia if we follow them downwards from the front of the abdomen? The fatty layer of Camper is carried over Poupart's ligament, and becomes directly continuous with the fatty superficial fascia on the front of the thigh. The relations of the fascia of Scarpa are very different. In the region of the pubes it is carried continuously downwards over the spermatic cords, the penis and scrotum, into the perineum, where it becomes continuous with the fascia of Colles. On the outer side of the spermatic cord, in the region of the groin, it proceeds downwards, and ends immediately below Poupart's ligament by blending with the fascia lata of the thigh.

These connections of the fascia of Scarpa are so important that it is necessary to undertake a special dissection, in order that they may be demonstrated. As this encroaches somewhat upon the region of the thigh, it must be done in conjunction with the dissection of the lower limb. A transverse incision should be made through the entire thickness of the superficial fascia on the front of the abdomen from the anterior superior spine of the ilium to the middle line of the abdomen. On raising the lower edge of the divided fascia the two layers can be easily distinguished. Insinuate the fingers between the fascia of Scarpa and the subjacent pearly-looking tendon of the external oblique muscle. Little resistance will be met, as the fascia of Scarpa is only bound down by some lax areolar tissue.

As the superficial fascia is thus raised from the aponeurosis of the external oblique, the hypogastric branch of the ilio-hypogastric nerve will be seen piercing the aponeurosis a little way above the external abdominal ring, and then sinking into the deep surface of the superficial fascia. The fingers can be readily carried downwards behind the fascia of Scarpa as far as Poupart's ligament. Here it will be found that they can force their way no further. The passage of the hand into the thigh is barred by the blending of the fascia of Scarpa with the fascia lata of the thigh. At this level it ceases to exist; it loses its identity by becoming fused with the deep fascia of the thigh along the line of, and immediately below, Poupart's ligament.

Towards the pubes the finger can be pushed downwards behind the fascia of Scarpa and along the spermatic cord into the perineum. No barrier opposes the passage of the finger in this direction. The continuity of the fascia of Scarpa and the fascia of Colles is thus demonstrated.

If the dissector now recall the fact that in the urethral triangle of the perineum the fascia of Colles is attached laterally to the margins of the pubic arch, and posteriorly to the base of the triangular ligament, whilst anteriorly towards the abdomen it is free, he will have little difficulty in understanding the course which urine takes when extravasated from a rupture of the urethra in front of the triangular ligament. The effused fluid is directed upwards over the scrotum and penis, and along the spermatic cords to the front of the abdomen. From the abdomen it cannot pass downwards to the front of the thighs, owing to the attachment of the superficial fascia to the fascia lata. Unless vent be given to it by early and free incisions, it will continue to ascend over the abdomen.

Cutaneous Nerves.—A dissection must now be made of the cutaneous nerves of the abdomen. These are arranged on the same plan as the cutaneous nerves of the chest. We have therefore to look for an *anterior* and a *lateral series*.

- | | | |
|------------------|---|--|
| Anterior series. | { | <ol style="list-style-type: none"> 1. Anterior cutaneous nerves. 2. Hypogastric branch of the ilio-hypogastric nerve. 3. The ilio-inguinal nerve. |
| Lateral series. | { | <ol style="list-style-type: none"> 1. Lateral cutaneous nerves. 2. Lateral or iliac branch of last dorsal nerve. 3. Iliac branch of ilio-hypogastric nerve. |

The *anterior cutaneous nerves* are the small terminal twigs of the lower four or five intercostal nerves, and also of the last dorsal nerve. They pierce the aponeurotic sheath of the rectus muscle at variable points, some close to the middle line, and others a little distance from it. Entering the superficial fascia, they run for a short distance outwards.

To find these nerves, the best plan to adopt is to divide the superficial fascia along the middle line, and reflect it cautiously outwards. The small arteries which accompany the nerves serve as guides.




FIG. 109. —Dissection of Anterior Wall of the Abdomen. The obliquus externus has been reflected on the right side.

The hypogastric nerve is the terminal twig of the ilio-hypogastric, and it lies in series with the preceding. In the dissection of the superficial fascia it has been seen piercing

the aponeurosis of the external oblique immediately above the external abdominal ring.

The *ilio-inguinal nerve* comes out through the external abdominal ring, and is distributed to the integument of the scrotum and the inner aspect of the thigh.

The *lateral cutaneous nerves* are branches of the five lower intercostal nerves. They become superficial between the digitations of the external oblique muscle, and then each divides into an anterior and posterior division. The *posterior divisions* are small, and are directed backwards over the latissimus dorsi. The *anterior divisions* run forward, and a careful dissector may trace them as far as the outer margin of the rectus.

The *iliac branch of the last dorsal* corresponds with the lateral cutaneous branches of the intercostal nerves. It differs from the other members of the series in not dividing into an anterior and a posterior branch, and in being destined for the supply of the integument over the gluteal region. It pierces the external oblique muscle in a line with the other lateral nerves, and is then directed downwards over the crest of the ilium. It crosses the iliac crest from one to two inches behind the anterior superior spine.

The *iliac branch of the ilio-hypogastric nerve* is also distributed to the skin of the gluteal region. It pierces the external oblique immediately above the iliac crest, which it usually crosses opposite the tubercle which projects from the outer lip of the crest, about two and a half inches behind the anterior superior spine of the ilium.

Cutaneous Vessels.—Cutaneous arteries are found accompanying the cutaneous nerves. Those which are associated with the lateral cutaneous nerves are branches of the *aortic intercostal arteries*, whilst those in relation to the anterior cutaneous nerves are derived from the *deep* and *superior epigastric arteries*, and also from the *aortic intercostal arteries*.

In addition to these, *three* small branches of the femoral artery ramify in the superficial fascia of the groin.

These are—

1. The superficial pudic.
2. The superficial epigastric.
3. The superficial circumflex iliac.

They take origin in the thigh, a short distance below

Poupart's ligament, and, piercing the fascia lata, diverge from each other in the superficial fascia.

The *superficial pudic* is directed inwards over the spermatic cord, and gives branches to the skin of the scrotum and under surface of the penis.

The *superficial circumflex iliac* proceeds outwards and upwards along the line of Poupart's ligament, and ends in the skin in the neighbourhood of the anterior superior spine of the ilium.

The *superficial epigastric* takes a vertical course upwards, and, crossing Poupart's ligament, ramifies in the superficial fascia over the lower part of the abdomen. Its branches extend as high as the level of the umbilicus.

The small *veins* which accompany these arteries open into the internal saphenous vein.

Muscles of the Abdominal Wall.—The abdominal wall is formed anteriorly and laterally by *five pairs of muscles*, and by the aponeuroses which constitute their tendons. *In front* are the two recti muscles and the two pyramidales muscles. The recti are placed parallel to the middle line, and extend in a vertical direction from the pubic bones to the lower margin of the thorax. *On each side* three fleshy and aponeurotic strata are met with as we dissect from the surface towards the abdominal cavity. These strata are—(1) the external oblique muscle; (2) the internal oblique muscle; (3) the transversalis muscle. The direction taken by the muscular fibres which compose each of these layers is different. The external oblique corresponds in this respect with the external intercostal muscles; the fibres proceed obliquely downwards and forwards. Again, the internal oblique resembles the internal intercostal muscles in the direction of its fibres; they are directed upwards and forwards, and thus the fibres of the two oblique muscles cross each other like the limbs of the letter X. Lastly, the fibres composing the transversalis muscle pursue a horizontal or transverse course.

This difference of direction in the fibres which compose these three strata is a source of strength to the fleshy part of the abdominal wall, and offers an insurmountable barrier to the protrusion of any of the abdominal contents. The two oblique muscles and the transversalis are prolonged forwards to the middle line in the form of aponeuroses. The union

of these with the corresponding aponeuroses of the opposite side forms the *linea alba*—a strong band which extends in the median line from the symphysis pubis to the ensiform cartilage.

Dissection.—Remove the superficial fascia from the front of the abdomen. This will expose the aponeurosis of the external oblique muscle. Towards the thorax this aponeurosis is very thin, and is liable to injury, unless the dissection be performed with care. Proceed cautiously also at the lower part of the abdomen, above the inner end of Poupart's ligament. Here the aponeurosis is pierced in the male by the spermatic cord. The lips of the opening thus formed are prolonged downwards upon the cord in the form of a thin membrane called the *external spermatic fascia*. In defining this the blade of the knife must not be used. Work entirely with the handle. The thin layer of deep fascia which is spread over the muscular part of the external oblique muscle must also be removed. In doing this it is not necessary to carry the knife in the direction of the fleshy fasciculi. Indeed, the muscle can best be cleaned by carrying the knife at right angles to the general direction of the fibres. In front, the deep fascia will be seen to blend with the aponeurosis of the muscle, along the line of junction between the tendinous and fleshy fibres. The slips of origin of the external oblique muscle from the eight lower ribs must each be carefully defined.

Obliquus Abdominis Externus.—The external oblique muscle arises by *eight* pointed processes or digitations from the outer surfaces and lower borders of the eight lower ribs (Fig. 109). Of these, the *upper five* interdigitate with the digitations of the serratus magnus, and the *lower three* with those of the latissimus dorsi. From this origin the fibres proceed downwards and forwards with varying degrees of obliquity. The *posterior fibres* have a nearly vertical direction, and are inserted into the anterior half of the outer lip of the crest of the ilium. The *superior fibres* are almost horizontal, and the *intermediate fibres* are directed obliquely downwards and forwards, and both end in a strong aponeurosis called the *aponeurosis of the external oblique*.

Superiorly, the aponeurosis of the external oblique is very thin, and is carried forwards to be attached to the ensiform cartilage. It is from this part of it that the pectoralis major derives fibres of origin. *Inferiorly* it is attached to Poupart's ligament, which, indeed, is simply the thickened lower border of the aponeurosis folded back upon itself. *Between these attachments* it proceeds forwards over the rectus, and is inserted into the linea alba and into the front of the os pubis.

In connection with this aponeurosis note that it is broadest

and strongest inferiorly, that it is narrowest about the level of the umbilicus, but that it widens somewhat again towards the ribs. Superiorly it is so thin that the fibres of the rectus muscle shine through it.

External Abdominal Ring (annulus inguinalis subcutaneus) (Figs. 111 and 112).—In the male, the aponeurosis of the external oblique is pierced immediately above the pubes by the spermatic cord; in the female it is pierced, at the same point and in the same manner, by the round ligament of the uterus. The aperture which is thus formed receives the name of the *external abdominal ring*. At the present stage of the dissection this opening is not visible, because a thin fascial covering is carried downwards from its lips upon the spermatic cord or round ligament of the uterus. This is called the *external spermatic* or the *intercolumnar fascia*. If the cord be raised and rendered tense, this covering will be observed to invest it completely, and to be somewhat funnel-shaped—wide above, but closing upon the cord as it is traced downwards.

With the point of the knife divide the external spermatic fascia round the cord, and then, with the handle, define the margins of the external abdominal ring. When this is done, the dissector will observe that the term “ring,” as applied to this opening, is calculated to convey to the mind an erroneous impression. It is not circular, but triangular, in shape. The direction of the opening is very oblique, the base of the triangle being formed by the crest of the pubes, whilst the apex is directed outwards and slightly upwards.

The external abdominal ring, therefore, is merely a small gap or interval left between that portion of the aponeurosis of the external oblique muscle which is inserted into Poupart’s ligament, and that portion which is inserted into the front of



FIG. 110.—Crest of the Ilium as seen from above (semi-diagrammatic), with Attachments of Muscles mapped out.

the pubic bone. The margins of the aperture are termed *the pillars or crura of the ring*. The *internal or superior pillar* (crus superius) is flat and broad, and is attached to the symphysis pubis. Some of its fibres cross the middle line, decussate with the corresponding fibres of the other side, and are inserted into the front of the opposite pubic bone. The *external or inferior pillar* (crus inferius) is simply the inner end of Poupart's ligament. It is, therefore, thick and strong, and is fixed to the pubic spine. The spermatic cord, as it




FIG. 111.—Dissection of the External Abdominal Ring and the parts in its vicinity.

issues from the external abdominal ring, rests upon the external pillar.

The *size* of the external abdominal ring is very variable. In the male the average length may be said to be one inch, and the breadth about half an inch. In the female it is much smaller. In the female the round ligament of the uterus will be found to end in the superficial fascia of the groin.

On a close inspection of the lower part of the external abdominal aponeurosis, the student will observe a number of cross fibres arching over its surface. These are called the

intercolumnar fibres (fibræ intercolumnares), and in some cases they are very strongly marked. They begin at Poupart's ligament close to the iliac spine, and curve upwards and inwards upon the aponeurosis above the external abdominal ring. The function of these fibres is very evident, and the term "*intercolumnar*" is derived from the part which they play. They bind together the two pillars of the ring, and




FIG. 112.—Dissection to show the connections of the lower part of the Aponeurosis of the External Oblique Muscle.

prevent their further separation or divarication. There is a direct continuity between the intercolumnar fibres and the external spermatic fascia which clothes the cord, and consequently, as we have already seen, the term "*intercolumnar*" is frequently applied to the latter.

Reflection of the Obliquus Externus.—The external oblique muscle should now be reflected. Begin by detaching each digitation from the rib to which it is fixed. Between the last rib and the crest of the ilium the posterior border of the muscle will be found free; sometimes it is slightly

overlapped by the latissimus dorsi, but in other cases a small portion of the internal oblique muscle can be observed in a triangular interval between them (trigonum Petiti). These points can only be seen by tilting the body slightly over on its opposite side. Raise the posterior border of the muscle from the subjacent internal oblique, and divide the fleshy fibres which are inserted into the crest of the ilium close to the bone. Next divide the aponeurosis horizontally in a line leading from the anterior superior spine of the ilium to the outer border of the rectus. The entire muscular portion, and the greater part of the aponeurotic portion of the external oblique can now be thrown forward. On approaching the outer border of the rectus, the dissector must proceed with care, because a little beyond this the anterior lamella of the aponeurosis of the internal oblique fuses with the deep surface of the aponeurosis of the external oblique. Define the line of union, and notice that it does not extend beyond the lower margin of the thorax. Above this the rectus is simply covered by the aponeurosis of the external oblique; the outer margin of the muscle in this locality is bare, and the hand can be freely passed between it and the costal cartilages.

On the *left side* of the body, the parts below the horizontal line drawn from the anterior superior iliac spine to the outer border of the rectus, and along which the aponeurosis of the external oblique muscle has been divided, should be preserved intact for the special study of those parts which are related to inguinal hernia. On the *right side* of the body divide the lower part of the aponeurosis along the outer border of the rectus to the pubes. This incision should pass to the inner side of the internal pillar of the external abdominal ring, so that this opening may be preserved. The triangular flap of aponeurosis may now be thrown downwards and outwards. By this proceeding we can study more successfully Poupart's ligament, the entire extent of the internal oblique muscle, and the cremaster muscle.

Poupart's Ligament (ligamentum inguinale). — Poupart's ligament is merely the thickened lower border of the aponeurosis of the external oblique folded backwards upon itself. It thus presents a rounded surface towards the thigh and a grooved surface towards the abdominal cavity. The manner in which it is attached by its outer and inner extremities deserves the close study of the dissector. *Externally* it is fixed to the anterior superior spine of the ilium; *internally* it has a double attachment—viz. (1) to the pubic spine, which may be considered as its attachment proper; (2) through the medium of Gimbernat's ligament to the iliopectineal line.

Poupart's ligament does not pursue a straight course between its iliac and pubic attachments. It describes a curve, the convexity of which is directed downwards and outwards towards the thigh. By its lower border it gives attachment to the fascia lata. When this is divided, Poupart's ligament at once loses its curved direction.

Gimbernat's Ligament (ligamentum lacunare) (Fig. 112). —

This is a triangular process of aponeurotic fascia. Raise the spermatic cord, and place the finger behind the inner end of Poupart's ligament, and press downwards. The structure upon which the finger rests is the ligament in question, and the student should note that at this point it offers a barrier to the passage of the finger into the thigh. With the handle of the knife its shape and connections can be easily defined. Its *apex* is fixed to the pubic spine; by *one margin* it is attached to the inner part of Poupart's ligament; by its *other margin* it is inserted for the distance of an inch into the ilio-pectineal line. Its *base* is sharp, crescentic, and free, and is directed outwards towards the femoral sheath. The dissector should thoroughly realise that Gimbernat's ligament is not an independent structure. It is merely the inner part of the folded-back margin of Poupart's ligament which, in the vicinity of the pubic spine, obtains an attachment to bone.

Gimbernat's ligament occupies an oblique plane, its lower femoral surface looking downwards and slightly forwards and outwards, whilst its upper abdominal surface looks upwards and slightly backwards and inwards. It is of importance that the student should note the precise relation which this ligament bears to the spermatic cord. Taken in conjunction with Poupart's ligament and the aponeurosis of the external oblique, it forms a gutter or groove in which the cord lies.

Triangular Fascia (Fig. 112).—The triangular fascia is a small triangular piece of fascia which springs from the crest of the pubic bone and the inner end of the ilio-pectineal line. It passes upwards and inwards under cover of the internal pillar of the external abdominal ring, and passes into the linea alba. If the fibres which compose it are followed through the linea alba, they will be found to be continuous with the fibres of the aponeurosis of the external oblique muscle of the opposite side. It must, therefore, be considered as an additional insertion of this muscle. It is frequently so poorly developed, that its true relations and connections are demonstrated with difficulty, if indeed they are capable of demonstration at all.

Dissection.—The internal oblique muscle should now be cleaned. Towards its lower part it will be seen to be pierced by certain nerves, and these must be preserved. Close to the iliac crest the *iliac branches* of the ilio-hypogastric and last dorsal nerves will be noticed emerging from the

midst of its fleshy fibres, whilst in front it is pierced by the *hypogastric branch* of the ilio-hypogastric and by the *ilio-inguinal nerve*. The former of these appears near the anterior superior iliac spine, and then proceeds forwards under cover of the external oblique aponeurosis, which it soon pierces. The ilio-inguinal nerve will be found perforating the internal oblique a little way in front of the hypogastric nerve and at a lower level. It becomes superficial by passing through the external abdominal ring.

Care must be taken in defining the lower margin of the muscle to preserve its relations to the spermatic cord, and not to injure the muscular fasciculi which it gives to the cremaster muscle.

Obliquus Abdominis Internus (Fig. 109).—The internal oblique muscle *arises*—(1) from the abdominal grooved surface of Poupart's ligament in its outer half; (2) from the middle lip of the anterior two-thirds of the iliac crest; (3) from the lumbar aponeurosis. From this origin the muscular fibres radiate, but the general direction is from below upwards and forwards. The *posterior fibres* ascend, and are inserted into the lower borders of the cartilages of the lower four ribs. These fibres occupy the same plane as the internal intercostal muscles—indeed, they will be observed to be directly continuous with the fibres of the internal intercostal muscles of the two lower spaces. The *lower fibres*, or those springing from Poupart's ligament, arch downwards and inwards, and join with the lower fibres of the transversalis in a flat tendon, called the *conjoined tendon*, which is inserted into the pubic crest, and into the ilio-pectineal line, behind Gimbernat's ligament and the triangular fascia, for fully half an inch of its extent (Figs. 113 and 118). The *intermediate fibres* proceed upwards and forwards, and end in a strong aponeurosis, which extends from the lower margin of the chest to the pubis. By this aponeurosis they gain insertion into the lower borders of the seventh and eighth ribs and the ensiform cartilage, and into the linea alba throughout its entire length. The manner, however, in which the aponeurosis reaches the middle line requires special description.

At the outer margin of the rectus muscle the aponeurosis of the internal oblique splits into two layers—a superficial and a deep. The *superficial aponeurotic layer* passes in front of the rectus, and has already been seen to fuse with the aponeurosis of the external oblique muscle. The *deep layer* is carried inwards behind the rectus, and becomes incorporated with the subjacent aponeurosis of the transversalis muscle. But this arrangement does not hold good lower down than a point about midway between the umbilicus and the pubes.

Below this point the tendon does not split, but passes entirely in front of the rectus, to join the aponeurosis of the external oblique.

It is important to mark exactly the relation which the lower part of the muscle bears to the spermatic cord. At first the cord lies under cover of the fleshy fibres, but it soon emerges, clothed by the cremaster muscle, and as it is continued downwards and inwards to the external abdominal ring, it lies in front of the conjoined tendon. Especially




FIG. 113.—Dissection of the Inguinal Region. The aponeurosis of the external oblique is turned down.

note the position of the conjoined tendon in relation to the external abdominal ring. It lies immediately behind it, and gives strength to this otherwise weak point in the abdominal parietes.

Cremaster Muscle.—This muscle supports the testicle and spermatic cord, and is consequently peculiar to the male. It *arises* from the inner part of Poupart's ligament, and also derives fibres from the lower border of the internal oblique (rarely from the lower border of the transversalis muscle). The fleshy fibres descend upon the outer and anterior aspects of the cord in the form of loops, the concavities of which are

directed upwards. The depth to which these loops descend varies. Some reach the tunica vaginalis of the testicle, and the scrotum should now be opened up on the right side, in order that they may be traced downwards to this point; the majority of the fibres, however, do not reach so far down, some going no further than the external abdominal ring. Upon the posterior aspect of the cord the loops are directed upwards, and some reaching the os pubis, obtain a tendinous insertion into its spine and crest.

It will be noticed that the cremasteric fleshy loops do not form a complete investment for the cord and testicle. The intervals between the fasciculi are occupied by areolar tissue, and this combination of muscular and areolar tissue is sometimes termed the *cremasteric fascia*.




FIG. 114.—Diagram to illustrate the relation of the lower border of the internal oblique muscle to the cord, the conjoint tendon, and the inguinal canal.

O.I. Internal oblique muscle.

C.T. Conjoint tendon.

The position of the external abdominal ring is indicated by a dotted outline.

depth to which the knife should be carried is indicated by the dense areolar tissue which lies between it and the subjacent transversalis muscle. An ascending branch from the deep circumflex iliac artery will also serve as a guide. This vessel emerges from the fibres of the transversalis close to the fore-part of the iliac crest, and is then directed upwards upon its surface. Although this vessel has not attained the dignity of a name, it is a very constant branch. On the right side the fibres springing from Poupart's ligament should also be severed, but on the left side carry the knife horizontally inwards, from the anterior superior spine of the ilium to the outer margin of the rectus. Now turn to the upper part of the muscle, and make an incision through it along the lower margin of the thorax, from the outer border of the rectus to the last rib. Lastly, carry the knife downwards, from the tip of the last rib to the crest of the ilium.

The muscle freed in this manner can be thrown forwards towards the outer border of the rectus. In doing this the dissector must proceed with

Reflection of Internal Oblique.—On the *right* side of the body the entire muscle may be reflected, but on the left side preserve the lower portion of it (*i.e.*, that part which is still covered by the aponeurosis of the external oblique) *in situ*. Begin below by dividing the muscular fibres along the crest of the ilium. The

caution, because he has reached the plane of the main trunks of the nerves of the abdominal wall and the arteries which accompany them. These pass forwards between the internal oblique and transversalis, and, in raising the former muscle, they are apt to adhere to its deep surface and be cut.

In all probability the student will experience considerable difficulty in separating the lower part of the internal oblique from the corresponding portion of the transversalis. At this level these two muscles are always closely connected, and in some cases they may be even found to be partially blended.

The *cremaster muscle* should also be reflected from the spermatic cord. This can best be done by making a longitudinal incision along it. Entering the deep surface of the cremaster is a small *branch of the deep epigastric artery* and the *genital branch of the genito-crural nerve*. These constitute its vascular and nervous supply, and must, if possible, be secured. Now clean the transversalis muscle, and dissect out the vessels and nerves which lie upon it.

Nerves of the Abdominal Wall.—Running forwards upon the transversalis muscle, the dissector will find the following nerves :—

- | | |
|---|---|
| 1. The anterior portions of the lower six intercostal nerves. | } The anterior primary divisions of the lower seven dorsal nerves.
From the anterior primary division of the first lumbar nerve. |
| 2. The last dorsal nerve. | |
| 3. The ilio-hypogastric nerve. | |
| 4. The ilio-inguinal nerve. | |

The *six lower intercostal nerves* issue from the anterior ends of the six lower intercostal spaces, and then proceed forwards, between the internal oblique and transversalis muscles, to the outer border of the rectus. Here they disappear by piercing and passing within the sheath of this muscle. In a future dissection they will be observed sinking into the substance of the rectus, supplying it with twigs, and then turning forwards to pierce the sheath a second time. They end on the front of the abdomen as the *anterior cutaneous nerves*. Midway between the spine and the linea alba they give off the *lateral cutaneous nerves*. They likewise supply offsets to the transversalis and two oblique muscles. Minute arteries accompany these nerves.

The *last dorsal nerve* has the same relation in the abdominal wall as the preceding nerves. It gives off the same branches, but in addition supplies a branch to the pyramidalis muscle. Its *lateral cutaneous* or *iliac branch*, however, goes to the skin of the buttock.

The *ilio-hypogastric* and *ilio-inguinal* are the two lowest nerves of the series. They are directed forwards between

the internal oblique and the transversalis close to the crest of the ilium.

The ilio-hypogastric is the higher of the two, and gives off an *iliac* or *lateral branch*, which pierces the two oblique muscles and then crosses the crest of the ilium to reach the skin of the gluteal region. The *hypogastric portion* of the nerve perforates the internal oblique a short distance in front of the anterior superior spine of the ilium, and then runs forwards towards the linea alba. It does not enter the sheath of the rectus, and it becomes superficial by piercing the aponeurosis of the external oblique immediately above the external abdominal ring.

The *ilio-inguinal nerve* gives off no lateral branch. It pierces the internal oblique, to which it gives branches, a short distance above Poupart's ligament, and it becomes superficial by passing through the external abdominal ring.

Transversalis Muscle (*musculus transversus abdominis*).—

This is the deepest of the three muscular strata which enter into the formation of the wall of the abdomen. It has a threefold origin—viz., from the pelvis, from the vertebral column, and from the costal cartilages. By its *pelvic origin* it is attached to the outer third of Poupart's ligament and to the anterior two-thirds of the inner lip of the crest of the ilium; by its *costal origin* it arises from the inner surfaces of the costal cartilages of the lower six ribs by a series of slips or digitations which interdigitate with the slips of origin of the diaphragm; by its *vertebral origin* it is attached through the medium of the lumbar fascia to the spinous processes, transverse processes, and bodies of the lumbar vertebræ. In point of fact, the lumbar fascia constitutes the posterior aponeurosis of this muscle. But the manner in which this fascia is attached to the vertebræ requires further explanation. As it approaches the spine it splits into three layers or lamellæ; of these the *posterior lamella* is attached to the tips of the spinous processes, the *anterior lamella* to the bodies of the vertebræ at the roots of the transverse processes, and the *intermediate lamella* to the tips and adjacent sides of the transverse processes. Two aponeurotic compartments are thus formed, the posterior of which is occupied by the erector spinæ, whilst in the anterior is placed the quadratus lumborum. These are points which cannot be demonstrated in

this dissection, but a reference to Fig. 115 will help the student to understand the arrangement.

Anteriorly the fibres of the transversalis muscle end in a strong aponeurosis, which is inserted into the linea alba, the pubic crest, and the ilio-pectineal line. Towards this aponeurosis the fleshy fibres for the most part run in a transverse direction. The lower fibres, however, take a curved course downwards and inwards, so that the muscle presents an arched lower margin.

The dissector has already seen that the lower portions of




FIG. 115.—The dotted line represents the Peritoneum.

the aponeuroses of the internal oblique and the transversalis muscles blend to form the *conjoined tendon*. It is through the medium of this tendon that the transversalis gains its insertion into the pubic crest and into the ilio-pectineal line. The aponeurosis of the transversalis constitutes the greater portion of the conjoined tendon—indeed, whereas the internal oblique aponeurosis has an attachment to the ilio-pectineal line of little more than half an inch, the aponeurosis of the transversalis is fixed to fully an inch of this line.

Above the level of the conjoined tendon the aponeurosis of the transversalis is inserted into the linea alba, but in

passing inwards to this insertion it presents two different relations to the rectus muscle. Down to a point midway




FIG. 116.—Deep dissection of the Anterior Wall of the Abdomen. On the *left side* the external oblique and the internal oblique have for the most part been removed, the sheath of the rectus opened, and the greater part of the contained muscle removed. On the *right side* the external oblique, the upper part of the internal oblique, and the upper part of the anterior wall of the sheath of the rectus have been removed.

between the umbilicus and pubes it passes *behind* the rectus, and blends with the posterior lamella of the aponeurosis of

the internal oblique. Below this point it passes *in front* of the rectus, and blends with the aponeuroses of the internal oblique and external oblique.

Dissection.—The sheath of the rectus should now be opened on both sides of the body by a vertical incision along the middle line of the muscle. The divided anterior lamella should then be carefully raised from the surface of the muscle and turned outwards and inwards. At the *lineæ transversæ* this can only be done with difficulty, so close is the connection between the sheath and the tendinous intersections of the muscle.

Contents of the Sheath of the Rectus.—Within the rectal sheath we find the following structures:—

1. The rectus muscle.
2. The pyramidalis muscle.
3. The terminal portions of the six lower intercostal nerves, and the last dorsal nerve.
4. The deep epigastric artery.
5. The superior epigastric artery.

In cleaning the rectus keep in mind the intercostal nerves and the last dorsal nerve. These will now be seen to enter the sheath and sink into the rectus. After supplying it with twigs, they come forward from its substance as the *anterior cutaneous nerves* of the abdomen.

Rectus Muscle (*musculus rectus abdominis*).—This is a broad band of muscular fibres which stretches between the chest and the pubes, on each side of the *linea alba*. Inferiorly it *arises* by two heads; of these, the external and larger is attached to the pubic crest, whilst the internal and smaller is fixed to the ligaments in front of the symphysis pubis (Fig. 52, p. 159). Towards the chest the muscle widens and becomes thinner, and its *insertion* is effected by three large slips into the anterior aspect of the costal cartilages of the *fifth, sixth, and seventh ribs*.

The rectus muscle is broken up into portions by irregular tendinous intersections—the *inscriptiones tendineæ* or *lineæ transversæ*. These are usually three in number, and are placed, one at the level of the umbilicus, another opposite the ensiform cartilage, and a third midway between. A fourth intersection is sometimes found below the umbilicus. We have seen that these tendinous intersections are closely adherent to the sheath of the rectus in front. Raise the muscle, and it will be apparent that they have no attachment to the sheath behind.

Pyramidalis Muscle.—This is a small triangular muscle—

not always present—which springs from the front of the pubes and the ligaments of the symphysis, and is inserted into the linea alba. It lies upon the lower part of the rectus, and is supposed to act as a tensor of the linea alba.

The nerve of supply to the pyramidalis comes from the last dorsal nerve. To bring it into view the muscle must be carefully detached from the linea alba and turned downwards towards the pubes. The nerve will be exposed entering its deep surface.

Sheath of the Rectus (*vagina recti abdominis*).—The dissector is now in a position to study the manner in which the rectal sheath is formed. An examination of the relations which the aponeuroses of the three flat muscles of the abdomen bear to the rectus, will show that the sheath is incomplete, in so far as the rectus is concerned. It is deficient *posteriorly*, both above and below.

From the lower margin of the thorax to a point midway between the umbilicus and pubes, it encloses the rectus upon all sides. Here the *anterior wall* or *lamella* is formed by the aponeurosis of the external oblique fused with the anterior layer of the aponeurosis of the internal oblique, whilst the *posterior wall* or *lamella* is formed by the fusion of the posterior layer of the aponeurosis of the internal oblique with the aponeurosis of the transversalis (Fig. 115).

Superiorly, the rectus muscle rests directly upon the costal cartilages, and the sheath is merely represented by the aponeurosis of the external oblique, which covers the muscle anteriorly. *Inferiorly*, the posterior wall of the sheath is also absent, and the rectus rests on the transversalis fascia. Here, however, the anterior wall is formed by a blending of all three aponeuroses (Fig. 117).

The lower free margin of the posterior lamella of the sheath can be easily defined by raising the rectus and working with the handle of the knife. It usually presents a sharp lunated edge, the concavity of which is directed downwards to the pubes. It is called the *semilunar fold of Douglas* (*linea semicircularis*). The deep epigastric artery will be observed to enter the sheath by passing upwards in front of this free border (Fig. 116).

The semilunar fold of Douglas is often rendered indistinct by the presence of scattered tendinous bundles crossing behind the lower part of the rectus.

Linea Alba.—The linea alba can now be studied to the best advantage. It is a dense fibrous cord or band which extends perpendicularly between the ensiform cartilage and the symphysis pubis. It is formed by the union and decussation of the fibres composing the aponeuroses of the two oblique and the transversales muscles of opposite sides. Above the umbilicus it is broad and band-like; whilst below this point it becomes narrow and linear. A close examination will show that it is pierced by several small round openings for the transmission of blood-vessels, and from some of these the dissector may even observe minute fatty masses protruding. A little below its middle is the umbilicus, but the foramen, of which this is the remains, is now completely closed; indeed, in the adult the linea alba is stronger at this point than elsewhere.

Fascia Transversalis.—This is a thin layer of fascia which



FIG. 117.—Transverse section through Abdominal Wall a short distance above Pubis.

is spread out upon the deep surface of the transversalis muscle. The fascia of one side is directly continuous with the fascia of the opposite side, and it forms a part of an extensive fascial stratum which lines the entire abdominal wall, and is placed between the abdominal muscles and their aponeuroses on the one hand, and the extra-peritoneal fatty tissue on the other.

Traced upwards, the fascia transversalis becomes thin, and at the margin of the thorax it is directly continuous with the fascia which lines the lower surface of the diaphragm. Towards the inguinal region it plays an important part as a constituent of the abdominal wall.

In the present state of the dissection (on the right side of the body), a small gap or interval is seen to exist between the lower arched border of the transversalis muscle and Poupart's ligament. The membrane which fills up this interval is the *transversalis fascia*. At no part of the abdominal wall is the fascia stronger than here, and this

accession of strength is obviously for the purpose of compensating for the deficiency in the internal oblique and transversalis muscles, which, at this point, do not descend so low as Poupart's ligament. In this interval the transversalis fascia has an important relation to the spermatic cord. Here the fascia is pierced by the cord, but as yet no opening is visible.




FIG. 118.—Deep dissection of the Inguinal Region. The internal oblique has been reflected to show the whole length of the inguinal canal, and the cord enclosed within the infundibuliform fascia is seen cut across.

Take hold of the cord and draw it downwards and inwards. The margins of the aperture through which it passes will be observed to be prolonged downwards upon the cord in a funnel-shaped manner, so as to invest it upon all sides with a tube of fascia. This investment, which is thus seen to come directly from the fascia transversalis, is called the *infundibuliform* or *internal spermatic fascia*.

Dissection.—It must now become the object of the dissector to demonstrate the more important attachments of this fascia. For this purpose divide the fibres of the transversalis muscle along the outer part of Poupart's ligament and along the crest of the ilium, and, raising the muscle from the subjacent fascia, throw it upwards. It is not necessary to reflect the entire muscle.

Attachments of the Fascia Transversalis.—When the fascia is cleaned with the handle of the scalpel, it will be seen to be attached *laterally* to the inner lip of the iliac crest. Along the line of this attachment, which is by no means firm, it becomes continuous with the *fascia iliaca*—that portion of the same fascial stratum which covers the iliacus and psoas muscles in the iliac fossa. Close to the crest of the ilium the fascia transversalis is pierced first by the ascending branch and then by the terminal branches of the deep circumflex iliac artery. *In front*, in the inguinal region, its connections are more complicated, and must be studied at three different points—(1) between the anterior superior iliac spine and the femoral artery, where it will be seen to be attached to Poupart's ligament; along this line also it becomes continuous with the fascia iliaca; (2) opposite the femoral vessels, where it is carried downwards into the thigh behind Poupart's ligament, to form the anterior part of the femoral or crural sheath (*vide* p. 199); (3) internal to the femoral vessels, where it is attached to the ilio-pectineal line and the pubic bone, behind the conjoined tendon, with which it is partially blended.

Internal Abdominal Ring (*annulus inguinalis abdominalis*).—We have seen that the transversalis fascia is pierced by the spermatic cord. The opening through which it passes is called the *internal abdominal ring*. This opening can only be defined from the front by an artificial dissection—viz., by dividing the infundibuliform fascia around the cord, and pushing it upwards with the handle of the knife. The ring thus defined will be observed to lie about half an inch above Poupart's ligament, at a point midway between the symphysis pubis and the anterior superior spine of the ilium. Through the opening the dissector can see the extra-peritoneal fat upon which the transversalis fascia rests, and immediately internal to the opening he will notice the deep epigastric artery, pursuing its oblique course upwards and inwards, and shining through the fascia. If the handle of the knife be now introduced into the ring and carried outwards between the fascia and extra-peritoneal fat, the

attachments of the fascia to Poupart's ligament and to the iliac crest can be very clearly shown.

Canalis inguinalis.—The dissector has observed that the spermatic cord in the male and the round ligament in the female pierces the abdominal wall above Poupart's ligament. The passage which is formed for their transmission receives the name of the *inguinal canal*. Now, as this canal is a source of weakness to the abdominal wall, and as it is in connection with it that inguinal hernia occurs, the student will understand how necessary it is that he should examine it carefully from all points of view.

The *inguinal canal* is a narrow channel of about one inch and a half in length. It begins at the internal abdominal ring, which may be spoken of as its inlet, and ends at the external abdominal ring, which constitutes its outlet. It is, consequently, very oblique, having a direction almost directly inwards, with a slight inclination downwards and forwards. So much for its length and direction; we have still to make out in connection with it (1) a floor; (2) an anterior wall; and (3) a posterior wall.

The *floor* is formed in the first part of the canal by the upper grooved surface of Poupart's ligament. Towards the outlet, however, the floor becomes broader and more definite; here it is formed not only by Poupart's ligament, but also by Gimbernat's ligament. At this point, as the student has already observed, the cord rests directly upon the abdominal surface of the latter ligament. The parts which enter into the formation of the *anterior wall* are—(1) the aponeurosis of the external oblique throughout the entire extent of the canal; and (2) the lower border of the internal oblique in the outer third of the canal. These facts can be readily verified by restoring the structures to their original positions. The parts which compose the *posterior wall* are still *in situ*. Naming them in order, from the inlet to the outlet, they are—(1) the fascia transversalis; (2) the conjoined tendon; and (3) the triangular fascia, when it is strongly developed.

But it may be asked, Does the transversalis muscle take no part in the formation of the inguinal canal? The student can readily satisfy himself as to this point. He will notice that the arched lower border of this muscle does not descend so low as that of the internal oblique, that, in fact, it stops

short immediately above the internal abdominal ring. The canal is closed superiorly by the approximation of the anterior and posterior walls above the cord and by the intervention between these walls of the lower border of the transversalis.

There is still another point to be noted, viz., the relation which the deep epigastric artery bears to the posterior wall of the canal. This vessel can be felt (and, indeed, in most cases seen) extending obliquely upwards and inwards, behind the transversalis fascia, to the outer border of the rectus. A triangular space is thus mapped out by the artery, Poupart's ligament, and the outer border of the rectus. This receives the name of the *triangle of Hesselbach*. The floor of the space is formed by the posterior wall of the inguinal canal, and chiefly by that part of it which is composed of the conjoined tendon.

In the female the inguinal canal is much smaller than in the male. It has the same boundaries, and it is traversed by the round ligament of the uterus.

Arteries of the Abdominal Wall.—In the abdominal wall we find the following arteries:—

1. The intercostal and lumbar arteries.
2. The deep epigastric.
3. The deep circumflex iliac.
4. The superior epigastric.
5. The musculo-phrenic.

The *intercostal arteries* of the three lower spaces are prolonged forwards between the internal oblique and the transversalis. They have already been noted accompanying the corresponding nerves. In front they anastomose with the epigastric arteries, whilst inferiorly they effect communications with the lumbar arteries.

The *abdominal branches* of the *lumbar arteries* ramify between the same two muscles as the preceding vessels, but at a lower level in the abdominal wall. Anteriorly they anastomose with the deep epigastric artery; above with the intercostal arteries; and below with the deep circumflex iliac and the ilio-lumbar.

Deep Epigastric Artery (*arteria epigastrica inferior*).—This, a branch of the external iliac, is a vessel of some size, and takes origin about a quarter of an inch above Poupart's ligament. At present it is seen, shining through the fascia transversalis and forming the outer boundary of Hesselbach's triangle.

Divide the fascia transversalis along its course and it will be observed to be accompanied by two veins. Study the course and relations of this vessel. At first it runs inwards for a short distance between Poupart's ligament and the internal abdominal ring, and then changing its direction it is carried upwards and inwards on the inner side of the ring. Reaching the deep surface of the rectus it enters the rectal sheath, and proceeding vertically upwards, ends near the lower margin of the thorax in branches which sink into the substance of the muscle and anastomose with the superior epigastric and the intercostal arteries.

In the first part of its course, the deep epigastric lies in the extra-peritoneal fat between the peritoneum and the fascia transversalis. It soon, however, pierces the fascia, and, passing in front of the fold of Douglas, ascends between the rectus muscle and the posterior lamella of its sheath. These are its immediate relations, but there are others of equal importance, viz., (1) as it runs upwards it lies close to the inner side of the internal abdominal ring; (2) as the spermatic cord traverses the inguinal canal it lies in front of the artery, only separated from it by transversalis fascia; (3) as the vas deferens passes from the inguinal canal into the abdominal cavity it hooks round the outer side of the artery.

The *branches* which spring from the deep epigastric are—

1. Cremasteric.
2. Pubic.
3. Cutaneous.
4. Muscular.

The *cremasteric* is a small twig which supplies the cremaster muscle and anastomoses with the spermatic artery. The *pubic*, also insignificant in size, goes to the back of the pubes, where it anastomoses with a small branch from the obturator. The importance of this branch arises from the fact that the anastomosis which it establishes sometimes becomes so large as to take the place of the obturator artery. The *muscular branches* are given to the substance of the rectus, and the *cutaneous offsets* pierce the abdominal muscles and anastomose with the superficial epigastric artery.

Deep Circumflex Iliac (arteria circumflexa illi profunda).—This vessel springs from the outer side of the external iliac artery, about the same level as the deep epigastric, and runs

outwards behind Poupart's ligament to the anterior superior spine of the ilium. From this point onwards it takes the crest of the ilium as its guide, and ends by anastomosing with the ilio-lumbar artery. At first it is placed in the extra-peritoneal fat, and consequently it lies between the fascia transversalis and the peritoneum. Its course behind Poupart's ligament is indicated by a whitish line, which marks the union of the fascia transversalis and fascia iliaca; and if the former fascia be now divided along this line, the deep circumflex iliac will be exposed. At the crest of the ilium the vessel pierces the fascia transversalis, and lies between this and the transversalis muscle; and lastly, about the middle point of the iliac crest it pierces the transversalis muscle, and its terminal twigs ramify between it and the internal oblique. In this manner, then, the artery gradually approaches the surface as we trace it from its origin to its termination, and its relations may be expressed thus:—

1. Between fascia transversalis and peritoneum.
2. Between fascia transversalis and transversalis muscle.
3. Between transversalis muscle and internal oblique muscle.

The dissector has already seen the *ascending branch* which it sends upwards between the internal oblique and transversalis muscles.

Superior Epigastric and Musculo-phrenic Arteries.—These are the two terminal branches of the internal mammary. The *superior epigastric* (arteria epigastrica superior) will be found behind the rectus muscle and within the upper part of its sheath. It gives twigs to the rectus, and anastomoses with the deep epigastric.

The *musculo-phrenic* (arteria musculophrenica) can only be seen by reflecting the transversalis from the ribs. It will be found at the level of the eighth rib. From this it proceeds downwards and backwards, along the attachment of the diaphragm, to the last intercostal space. It gives branches to the diaphragm and others (the anterior intercostals), which enter the lower intercostal spaces.

Dissection.—When the transversalis fascia is reflected the only layers which intervene between the dissector and the abdominal cavity are the extra-peritoneal fatty tissue and the parietal peritoneum.

If the subject be a male, now is the best time for the student to examine the constitution of the scrotum, spermatic cord, and testicle. This can

only be done at present on the right side, as the parts on the opposite side must be kept *in situ* for the study of hernia. After this, however, the dissection can be repeated on the left side.

The dissector works at a great disadvantage when he attempts to unfold the coverings of the cord and unravel its constituent parts while they are attached to the body. The cord and testicle of the right side should be removed by dividing the former with its coverings at the level of the external abdominal ring. The specimen should then be placed in a cork-lined tray and dissected under water. Having fastened the cord and testicle with pins to the bottom of the tray, little difficulty will be experienced in displaying and recognising the different layers, and a splendid demonstration will be afforded of the constituent parts of the cord.

Scrotum.—This is a pendulous purse-like arrangement of the skin and superficial fascia for the lodgment of the testicles. The skin composing it is of a dark colour and rugose, and is traversed along the middle line by a *median raphe* or ridge, an indication of its bilateral character.

When the skin is removed the superficial fascia is observed to possess certain characters peculiar to itself. It has a ruddy colour, and is totally devoid of fat. The ruddy tint is due to the presence of involuntary muscular fibres, which take the place of the fat, and constitute what is called the *dartos muscle*. The rugosity of the scrotal skin is maintained by these muscular fibres. But further, the superficial fascia forms in the interior of the scrotum an imperfect septum or partition, which divides it into two chambers—one for each testicle. These points in connection with the construction of the scrotum have all, to a certain degree, been noted in the dissection of the perineum.

But these two scrotal tunics are not the only coverings of the testicle. Each constituent of the abdominal wall has been seen to contribute an investment to the spermatic cord, and these in turn are continued down so as to clothe the testicle. Presuming, then, that the skin and superficial fascia are reflected, the testicle and cord within the scrotum will still be found to be invested by—

1. The external spermatic or intercolumnar fascia from the aponeurosis of the external oblique.
2. The cremasteric fascia—the muscular element of which is partly derived from the internal oblique.
3. The infundibuliform fascia from the fascia transversalis.

The dissector will find it difficult to demonstrate in every case these different investments of the testicle. In cases of large herniæ of old standing, however, they become thickened, and are more readily recognisable.

From the above description the student will understand that there is only *one* tunic common to both testicles—viz., the integument; that the superficial fascia and dartos, and the investments derived from the abdominal wall, constitute special tunics for each testicle.

Spermatic Cord.—The spermatic cord is formed by the association together of certain blood-vessels, nerves, and




FIG. 119. — Diagrams illustrating the descent of the testicle and the derivation of the tunica vaginalis from the peritoneal lining of the abdominal cavity. The inguinal canal is represented by a ring.

P. Peritoneum.
T. Testicle.
S. Scrotum.

P.V. Processus vaginalis.
T.V. Tunica vaginalis.
F.C. Fibrous cord or thread.

lymphatics, along with the vas deferens, all of which are proceeding to or coming from the testicle. These structures come together at the internal abdominal ring, and this may be taken as the point at which the cord begins. It has already been traced in its course through the inguinal canal, and has been observed to issue from it through the external abdominal ring. It is now seen as it lies within the scrotum suspending the testicle.

Before dissecting out the constituent parts of the cord,

examine the extra-peritoneal fatty tissue which lies behind the internal abdominal ring. Note that a process of this tissue is prolonged downwards with the cord. Now with the handle of the knife gently separate the extra-peritoneal fat from the subjacent peritoneum. Behind the internal abdominal ring the peritoneum shows a slight bulging forwards, and a slender fibrous band may be detected passing into the cord from the most prominent part of this bulging. This fibrous cord is the remains of the tube of peritoneum, which in the foetus connected the serous investment of the testicle (the tunica vaginalis) with the general peritoneal lining of the abdomen. In some cases it may be traced as far as the testicle, but more commonly it only extends down the cord for a short distance; indeed it is frequently absent.

To obtain a proper conception of this fibrous thread, it is necessary that the student should understand that the testicle is not developed within the scrotum. Up to a comparatively late period of intra-uterine life the testicle is situated within the cavity of the abdomen. It lies upon the psoas muscle, immediately below the kidney, and is not only invested by peritoneum, but is connected to the posterior wall of the abdomen by a short fold of that membrane, which receives the name of the *mesorchium*.

As development proceeds, the testicle gradually descends on the posterior wall of the abdomen. It retains its peritoneal investment, and in the seventh month it reaches the internal abdominal ring. Prior to its entrance into the inguinal canal, a test-tube-like process of peritoneum, termed the *processus vaginalis*, is carried into the passage (Fig. 119, A.). The testicle with its peritoneal covering enters this tubular recess, and during the eighth month it traverses the inguinal canal. Finally, towards the end of the ninth month, it reaches the bottom of the scrotum (Fig. 119, B.). Throughout the whole journey it is preceded by the *processus vaginalis*, which, as it were, prepares the way for it.

The testicle, therefore, in its descent has a double relation to the peritoneum—viz., (1) it carries with it into the scrotum its own proper investment; (2) it is preceded in its passage into the inguinal canal and the scrotum by a tubular prolongation of the parietal peritoneum, which forms a diverticulum of the general peritoneal sac within the scrotum. In those quadrupeds in which the testicle reaches the scrotum, this diverticulum or *processus vaginalis* remains open, and freely communicates with the abdominal cavity. In man, the lower part of the diverticulum which holds the testicle is alone retained; the upper part is obliterated, and no trace is left, beyond, perhaps, the fibrous cord mentioned above. In this manner, then, the tunica vaginalis of the testicle is formed, the original peritoneal investment remaining as the *visceral* or *testicular* part, and the lower part of the *processus vaginalis* being retained as the *parietal* or *scrotal* part (see description of tunica vaginalis, p. 379).

The orifice by which the abdominal peritoneal cavity communicates with the scrotal peritoneal diverticulum is usually closed before birth (Fig. 119, C.), and the upper part of the *processus vaginalis*, from the

internal abdominal ring to the upper end of the testicle, is generally obliterated in the first month of extra-uterine life (Fig. 119, D.).

The *gubernaculum testis* is the active agent in bringing about the descent of the testicle. This is a band of involuntary muscular fibres which traverses the inguinal canal, and establishes important connections both within and without the abdominal cavity. Below, three main attachments of the gubernaculum may be recognised—viz., (a) to the abdominal wall; (b) to the pubis; (c) to the bottom of the scrotum. Above, the gubernacular fibres are chiefly connected with the testicle; but many of them are also attached to the peritoneum on the posterior wall of the abdomen. By the traction which the gubernaculum exerts on the testicle the descent of that organ is brought about. By the portion attached to the abdominal wall the testicle is pulled down to the internal abdominal ring, the pubic portion drags it through the inguinal canal, whilst the scrotal part finally leads it into the scrotum.

The formation of the processus vaginalis is accounted for in the same way. Some of those gubernacular fibres which are inserted into the peritoneum drag down the peritoneal diverticulum which lines the inguinal canal and scrotum, and prepares the way for the testicle.

It is but right to state that the active part we have ascribed to the gubernaculum in the process of testicular descent is not admitted by all anatomists. There are many who deny that it exerts any active traction upon the testicle. They consider that through the gubernaculum failing to keep pace with the general growth of surrounding parts, it anchors the testicle to a particular level, and by this means finally lands it in the scrotum.

Dissection.—The coverings of the spermatic cord should now be removed, and the parts which enter into its formation isolated from each other.

Constituent Parts of the Spermatic Cord.—The following are the structures which form the spermatic cord:—

1. The vas deferens.
2. Blood-vessels.

{	Arteries.	{	The spermatic.
			The cremasteric.
			The artery to the vas deferens.
	Veins.	{	The spermatic plexus of veins.
3. Lymphatics.
4. Nerves.

{	Genital branch of the genito-crural.
	Sympathetic twigs.

These are all held together by loose areolar tissue which intervenes between them, and also by the investments which are given to the cord by the abdominal wall.

The *cremasteric artery* is a branch of the deep epigastric, and has already been seen entering the cremaster muscle. The *genital branch* of the genito-crural nerve has a similar destination. It has also been displayed in a previous stage of the dissection.

The *spermatic artery* arises within the abdomen from the

front of the aorta, and entering the cord at the internal abdominal ring, proceeds to the testicle, into the posterior border of which it sinks, after dividing into several smaller twigs. The *spermatic veins* issue from the testicle at its posterior border, and as they pass upwards they form in the cord a bulky plexus, which is termed the *spermatic* or *pampiniform plexus*.

A single vessel issues from this, which enters the abdomen through the internal abdominal ring. On the right side it pours its blood into the inferior vena cava; on the left side it joins the left renal vein.

The *vas deferens* (ductus deferens), the duct of the testicle, can always be distinguished by the hard, firm, cord-like sensation which it gives when the spermatic cord is held between the finger and thumb. It ascends along the posterior part of the cord. At the internal abdominal ring, however, it separates from the spermatic vessels, and lies to their inner side, and as it enters the abdomen it hooks round the deep epigastric artery.




FIG. 120.—Dissection of the Left Spermatic Cord to show its constituent parts. (From Waldeyer, modified.)

The *artery to the vas deferens* is a small branch from the superior vesical. It follows the duct to the testicle.

The *sympathetic filaments* extend downwards upon the spermatic artery. They come from the renal and aortic plexuses.

The *spermatic lymphatics* enter the abdomen through the internal abdominal ring, and join the lumbar glands.

Testicle (testis).—The testicle should next be examined. First note its position in the scrotum. It lies somewhat obliquely, with its upper end directed forwards and outwards,

and its lower end backwards and inwards. The left testicle hangs at a lower level than the right.

Each testicle is enveloped by the *tunica vaginalis testis*.

The *tunica vaginalis* is a serous sac, and consequently presents a *parietal* or *scrotal* portion, and a *visceral* or *testicular* portion. Its extent can be demonstrated in a striking manner by making a small aperture in the parietal part, and




FIG. 121.—Transverse section through the left side of the Scrotum and the Left Testicle. The sac of the tunica vaginalis represented in a distended condition.

then introducing a blow-pipe into the serous cavity and inflating it with air. It will be seen to be considerably larger than the gland which it envelops. It ascends for some distance upon the spermatic cord, and it even descends beyond the testicle. When flaccid, the parietal part is simply wrapped loosely over the visceral portion which adheres to the surface of the testicle.

Dissection.—Open into the sac of the tunica vaginalis by running a pair of scissors along the anterior aspect of the parietal part. On folding back

the parietal portion of the tunica vaginalis the form of the testicle may be studied, and also the manner in which it is clothed by the visceral layer.

Body and Epididymis of the Testicle.—The testicle is an oval body, with flattened sides. The posterior border is also somewhat flattened, and here we see the *epididymis*. This is an elongated and arched structure, which is adapted to the upper




FIG. 122.

A. The Right Testis and Epididymis within the tunica vaginalis. (A. F. Dixon.)

s.c. Spermatic cord.
g.m. Globus major.
e. Body of epididymis.
t. Testis.
h. Hydatids of Morgagni.
t.v. Tunica vaginalis.

B. The Right Testis and Epididymis seen from behind, after removal of the parietal part of the tunica vaginalis. (A. F. Dixon.)

t.v'. Cut edge of tunica vaginalis.
v.d. Vas deferens.
g.m'. Globus minor.

end and outer side of the posterior border of the testicle. The upper end of the epididymis is enlarged, and is termed the *globus major* (caput epididymis); its lower end is called the *globus minor* (cauda epididymis); while the intervening portion, which is narrow, receives the name of the *body of the epididymis* (corpus epididymis). The globus major is attached to the upper end of the testicle, which it surmounts like a helmet, not only by the visceral tunica vaginalis which is continued

over it, but also by the *vasa efferentia*, which pass from the one into the other. The *globus minor* is merely fixed to the back of the testicle by the visceral tunica vaginalis and some intervening areolar tissue, whilst the *body of the epididymis* is free, and is separated from the body of the testicle by an involution of the serous covering which forms the *digital fossa*.

If the upper end of the body of the testis be carefully examined, two minute structures will be observed attached to it close to the *globus major*. These are the "*hydatids of Morgagni*," remnants of an embryonic canal called Müller's duct. One of the hydatids is usually pear-shaped and stalked; the other is smaller and generally sessile.

The *vas deferens* emerges from the lower end of the *globus minor*, and then passes upwards upon the posterior border of the testicle on the inner side of the epididymis. By this relation, the side to which a given testicle belongs can be readily detected. The vessels have already been seen entering and emerging from the posterior border of the testicle.

Visceral Layer of the Tunica Vaginalis Testis.—Having learned the foregoing points concerning the testicle, the student is in a position to trace the visceral layer of the tunica vaginalis upon its surface. Observe that it envelops it closely on every side, with the exception of the posterior border, where the vessels enter and emerge. The posterior aspect of the epididymis is also, to a certain extent, left bare. On the outer surface of the organ it forms a little *cul-de-sac* between the body of the epididymis and the body of the testicle. This is called the *digital fossa*. Note particularly that it is along the posterior border of the testicle that the parietal part of the tunica vaginalis becomes continuous with the visceral part.

Dissection.—Some of the main facts relating to the structure of the testicle may be learned by a careful naked-eye examination of its different parts. For this purpose place it in a cork-lined tray and dissect it under water. Having fixed it with pins to the bottom of the tray, begin by tracing the vessels into the gland. In doing this a quantity of involuntary muscular tissue spread over the posterior border of the testicle and the epididymis becomes apparent. This is the *inner muscular tunic of Kölliker*. The intimate manner in which the visceral tunica vaginalis clings to the surface of the testis should next be ascertained by endeavouring to raise it as a distinct layer. Remove now the parietal tunica vaginalis and free the *globus minor* and body of the epididymis from the back of the gland. This can be easily done by cutting the serous covering as it passes

from one to the other, and breaking through the fibrous tissue which intervenes between the globus minor and the lower part of the body of the testis. Do not interfere with the globus major. Turning the epididymis aside, the body of the gland may be divided transversely with a sharp knife about its middle into an upper and a lower portion.

Structure of the Testicle.—The cut surface of the lower part of the body of the testis may now be studied. The dense, tough fibrous coat which envelops it under cover of the visceral tunica vaginalis first attracts attention. It is called the *tunica albuginea*. At the posterior border of the gland it will be seen to be projected into the interior in the form of a thick fibrous elevation. This extends along the whole length of the posterior border, and receives the name of the *mediastinum testis* (corpus Highmori). It is traversed by the vessels that pass into and out from the gland, and it is also tunnelled by a plexus of seminal canals, called the *rete testis*.

From the front and sides of the mediastinum testis radiating fibrous lines will be seen passing into the substance of the testis. These are the cut margins of incomplete fibrous lamellæ or septa which extend towards the deep surface of the tunica albuginea and become connected with it (Fig. 121). By means of these partitions and the mediastinum testis, the space enclosed by the tunica albuginea becomes broken up into a large number of loculi or compartments, the walls of which are imperfect. Such is the fibrous framework of the body of the testicle.

The blood-vessels have a very definite arrangement with reference to this framework. Passing in through the mediastinum they spread out on the deep surface of the tunica albuginea, and upon both surfaces of the fibrous lamellæ which bound the testicular compartments. The vascular mesh-work thus formed is sometimes called the *tunica vasculosa*.

The proper glandular substance of the testis is lodged within the compartments described above. It consists of an enormous number of fine hair-like tubes, termed the *seminiferous tubules*. Two or more occupy each compartment, and constitute what is called a *testicular lobule* (lobulus testis). In this they are closely packed and are coiled and convoluted to an extraordinary degree. The dissector should now

endeavour to unravel some of these tubuli seminiferi under water. It will be impossible to open them out in their whole length, but a sufficiently good demonstration may be obtained to make their general arrangement apparent. The length of these tubes is remarkable. They average two feet in length.

Approaching the mediastinum testis the tubuli seminiferi join each other at acute angles and form a smaller number of tubes, which finally become straight and considerably reduced in diameter. These are called the *tubuli recti*. They enter the mediastinum and join the *rete testis*.

Dissection.—The tubuli seminiferi should now be removed from the lower part of the gland. This can be done with the forceps under a stream of water. A good view is then obtained of the fibrous framework of the testicle. The strength of the tunica albuginea becomes evident, whilst the mediastinum testis and the lamellæ which proceed from it are seen to great advantage.

The dissector must next endeavour to ascertain the manner in which the secretion of the testicle passes from the rete testis into the epididymis. For this purpose the upper part of the testicle with the attached epididymis must be examined. Gently raise the globus major from the surface of the body of the testis by dividing the visceral part of the tunica vaginalis which binds them together, and carefully break down the intervening connective tissue. Under favourable circumstances the *vasa efferentia* may be seen.

Structure of the Epididymis.—The *vasa efferentia* (ductuli efferentes testis) are fifteen to twenty delicate ducts which leave the upper part of the rete testis, pierce the tunica albuginea, and pass into the globus major. In this body the vasa efferentia become coiled and form a series of small conical masses, called the *coni vasculosi*. Ultimately these ducts open into a single convoluted canal, termed the *canal of the epididymis* (ductus epididymis). The globus major is thus composed of the coni vasculosi and the coiled canal of




FIG. 123.—Diagram illustrating the Structure of the Testicle. (A. F. Dixon.)

- v.d. Vas deferens.
- g.m. Globus minor.
- g. Globus major.
- c.v. Coni vasculosi.
- v.e. Vasa efferentia.
- r.r. Tubuli recti.
- r.r. Rete testis.
- s.t. Seminiferous tubule.
- s. Septula testis.

the epididymis. The body and globus minor of the epididymis are formed of the continuation of the same canal coiled and convoluted upon itself to a remarkable degree.

The intricacy of its flexuosities will be better understood by simply stating that if it were completely opened out it would be found to measure twenty feet or more. At the lower end of the globus minor the canal of the epididymis becomes continuous with the vas deferens.

Dissection.—The dissector should endeavour to unravel a part of the canal of the epididymis. The coils are held together by areolar tissue and the dissection is very tedious.

Surgical Anatomy.—To the surgeon the anatomy of the abdominal wall presents a very special interest from the bearing which it has upon **Hernia or Rupture.**

Hernia abdominis may be defined as being the protrusion of any viscus or portion of a viscus, or the protrusion of any portion of a peritoneal fold (e.g., great omentum) through the wall of the abdomen. There are three localities in which, from natural weakness of the parietes, this protrusion is specially liable to occur—(1) through the external abdominal ring, which gives passage to the spermatic cord in the male, and the round ligament of the uterus in the female; (2) through the crural canal or innermost compartment of the femoral sheath, within which certain lymphatic vessels ascend from the thigh into the abdominal cavity; (3) through the umbilicus or the foramen in the linea alba of the foetus, which transmits the constituents of the umbilical cord. These different forms of hernia are distinguished by the terms—*inguinal, femoral, and umbilical.*

There are other situations at which hernial protrusions occur, but so rarely that it would be out of place to take notice of them here.

Inguinal Hernia.—The inguinal canal is not so great a source of weakness to the abdominal wall as might, at first sight, be expected, and this chiefly on account of its obliquity of direction. The inlet or internal abdominal ring is situated a long way (fully an inch and a half) to the outer side of the outlet or external abdominal ring. The canal is therefore distinctly valvular; the greater the force with which the viscera are pressed directly against the inguinal part of the abdominal parietes, the more firmly will the posterior wall of the canal be pressed against the spermatic cord and the anterior wall.

On the *left side* of the body the parts related to inguinal hernia have been retained in position. The student should, therefore, make a dissection of the inguinal region, with special reference to hernia. Begin by reflecting the aponeurosis of the external oblique. Make a vertical incision through it parallel to the outer border of the rectus, and carry it downwards on the inner side of the internal pillar of the external abdominal ring. The aponeurosis can thus be thrown downwards and outwards, and the external ring, at the same time, preserved. The internal oblique, cremaster, and conjoined tendon should now be cleaned, and their precise relations to the spermatic cord studied. Notice that the fleshy lower border of the internal oblique overlaps the upper part of the cord, whilst, towards the outlet of the inguinal canal, the conjoined tendon lies behind the cord. Next replace the aponeurosis of the external oblique, and, introducing the point of the

forefinger into the external abdominal ring, press directly backwards. Observe that it rests upon the conjoined tendon; that, in fact, this tendon and the fascia transversalis alone intervene between the finger and the extra-peritoneal fatty tissue and the peritoneum. The lower part of the internal oblique muscle should now be separated from the transversalis by insinuating the handle of the knife between them. When this is done, divide the internal oblique close to Poupart's ligament, and throw it forwards. At the same time, make a longitudinal incision through the cremaster muscle, and turn it aside from the surface of the cord.

All further dissection must be effected from the inside. Divide the abdominal wall horizontally, from side to side, at the level of the umbilicus. When the lower part of the abdominal wall is raised, the student will observe on its posterior aspect three peritoneal ridges or falciform folds radiating from the umbilicus as from a centre, and proceeding downwards towards the brim of the pelvis. These are caused by the presence of three fibrous cords,—the urachus and the two obliterated hypogastric arteries,—in the extra-peritoneal fatty tissue. The *urachus* occupies the middle line, and extends downwards to the apex of the bladder. The *obliterated hypogastric artery* proceeds downwards and outwards on each side so as to gain the side of the bladder when this is distended, or the lateral wall of the pelvis when it is empty. On the posterior aspect of the anterior wall of the abdomen it lies a short distance to the inner side of the internal abdominal ring.

There is still another peritoneal ridge or fold on this aspect of the abdominal wall. It is formed by the deep epigastric artery as it passes upwards and inwards to reach the deep surface of the rectus abdominis muscle. It is placed a short distance to the outer side of the fold which corresponds to the obliterated hypogastric artery, and runs more or less parallel to it.

By these three peritoneal folds three fossæ, which vary greatly in depth in different subjects, are formed on either side of the middle line close to Poupart's ligament. They are termed the external, middle, and internal inguinal pouches, and are very generally regarded as determining, to a certain extent, hernial protrusions in this region. The *internal inguinal fossa* lies between the folds formed by the urachus and the obliterated hypogastric arteries, and the external abdominal ring or the outlet of the inguinal canal corresponds to its outer and deepest part. The *middle inguinal fossa*, very narrow but frequently very deep, is situated between the peritoneal folds which enclose the obliterated hypogastric artery and the deep epigastric arteries. The bottom of this fossa corresponds to the outer part of the posterior wall of the inguinal canal, or, in other words, to that part of the posterior wall which is formed by the fascia transversalis. The *external inguinal fossa* is placed to the outer side of the deep epigastric artery, and its lower, inner, and deepest part corresponds to the internal abdominal ring.

The student has already seen, in the dissection of the abdominal wall, that the deep epigastric artery, together with Poupart's ligament and the outer border of the rectus, bound a triangular space termed Hesselbach's triangle. Recalling this fact, he will understand that the obliterated hypogastric artery, which lies to the inner side of the deep epigastric, must ascend in relation to the posterior aspect of the floor of the triangle and cut the space into two.

Having determined these points, the dissector can proceed as follows:—Divide the lower part of the abdominal wall in a vertical direction along the

linea alba, from the umbilicus to the pubes. Make this incision a little on one side of the urachus, and, on nearing the pubic symphysis, be careful not to injure the bladder, which may project upwards beyond it. On throwing the left flap downwards and outwards, it may be possible to detect the position of the internal abdominal ring from the fact that in some cases the peritoneum is slightly dimpled into it. This dimple or depression is termed the *digital fossa*. Now strip the peritoneum from the flap as far down as Poupart's ligament. This can be easily done with the fingers, as its connection with the extra-peritoneal fatty tissue is very slight. Next separate the extra-peritoneal fatty tissue from the fascia transversalis with the handle of the knife, proceeding with great care as Poupart's ligament is approached. The *internal abdominal ring*, or the inlet of the inguinal canal, is now seen from within. From this point of view the opening is more like a vertical slit in the fascia transversalis than a ring. Its lower and external margin will be seen to be specially strong and thick. Note the deep epigastric artery passing upwards and inwards close to its inner margin. Further, observe the vas deferens and the spermatic vessels entering it, the former, as it disappears into the canal, hooking round the deep epigastric artery. Introduce the tip of the little finger into the opening and push it gently downwards in the direction of the inguinal canal. On raising the flap of the abdominal wall and looking at its front aspect, a very striking demonstration of the infundibuliform fascia can thus be obtained.

There are *two* forms of *Inguinal Hernia*,—viz., *oblique* and *direct*. *Oblique inguinal hernia* follows the course of the spermatic cord. The protrusion traverses the entire length of the inguinal canal, entering at the inlet or internal abdominal ring, and emerging (when the hernia is complete) at the outlet or external abdominal ring. *Direct inguinal hernia* only traverses the lower part of the inguinal canal. It pushes before it or bursts through that part of the posterior wall of the canal which forms the floor of Hesselbach's triangle, and, having thus gained the interior of the canal by a short cut, it emerges like the oblique variety at the external abdominal ring.

The *deep epigastric artery* bears a different relation to each of these forms of hernia. This vessel lies close to the inner margin of the internal abdominal ring, and it forms the outer boundary of Hesselbach's triangle; consequently, in oblique inguinal hernia, the protrusion, as it enters the inguinal canal, lies *external* to the vessel, whilst, in direct inguinal hernia, it lies *internal* to it. So important are these relations, that the terms *external* and *internal* are frequently employed to denote the two forms of inguinal hernia instead of *oblique* and *direct*.

It is also essential that the student should determine the relation which these forms of hernia hold to the inguinal pouches of peritoneum. In *oblique inguinal hernia* the protrusion invariably leaves the abdominal cavity at the lower and inner part of the *external inguinal pouch*. It is here that the internal abdominal ring is situated.

In the case of *direct inguinal hernia* the protrusion may leave the abdominal cavity either from the *middle* or from the *internal inguinal pouch*, both of which are in relation to the floor of Hesselbach's triangle.

In almost every case a hernial protrusion in passing to the surface carries before it a portion of the parietal peritoneum, which constitutes its immediate covering, and is termed by surgeons the *sac* of the hernia (Fig. 124, left side). In *oblique inguinal hernia* the other coverings which the protrusion acquires are identical with those of the spermatic cord. Entering

the internal abdominal ring, it receives an investment from the infundibuliform fascia; emerging from the lower border of the internal oblique, it acquires a cremasteric covering; and, coming out through the external abdominal ring, it obtains the external spermatic or intercolumnar fascia. From the surface, then, to the peritoneal sac, the following are the coverings of an oblique inguinal hernia:—

1. Skin and superficial fascia.
2. Intercolumnar or external spermatic fascia.
3. Cremasteric fascia.
4. Infundibuliform fascia.
5. Extra-peritoneal fatty tissue.
6. Parietal peritoneum, constituting the hernial sac.

In *direct inguinal hernia* the coverings of the protrusion differ according to the part of Hesselbach's triangle through which it projects. If the




FIG. 124.—Diagram to show the different peritoneal relations in an ordinary inguinal hernia (left side) and a congenital inguinal hernia (right side).

student examine the floor of this triangular area, he will observe that the conjoined tendon does not stretch over its entire extent; that, towards the outer part of the space, the transversalis fascia alone forms the floor. When a direct hernia leaves the abdomen from the middle inguinal pouch, it is through this outer part of Hesselbach's triangle that it protrudes, and, in this case, the coverings are almost identical with those of oblique hernia.

1. Skin and superficial fascia.
2. Intercolumnar or external spermatic fascia.
3. Cremasteric fascia (as a general rule).
4. Transversalis fascia.
5. Extra-peritoneal fatty tissue.
6. Parietal peritoneum or sac.

This form of direct hernia is comparatively rare. The more common form of direct hernia leaves the abdomen from the internal inguinal pouch, and pushes its way through the inner part of Hesselbach's triangle. It

therefore acquires a covering from the conjoined tendon. The following are its investments :—

1. Skin and superficial fascia.
2. Intercolumnar or external spermatic fascia.
3. Conjoined tendon.
4. Transversalis fascia.
5. Extra-peritoneal fatty tissue.
6. Parietal peritoneum or hernial sac.

When the conjoined tendon is feeble, or when a direct hernia takes




FIG. 125.—Diagram to illustrate the four different varieties of infantile hernia. (After Lockwood.)

- | | |
|---|---|
| <p>A. Processus vaginalis closed above.</p> <p>B. Processus vaginalis closed above and below, but open in intermediate part.</p> <p>P.V. Processus vaginalis.</p> <p>T.V. Tunica vaginalis.</p> | <p>C. Processus vaginalis open throughout its entire extent.</p> <p>D. Processus vaginalis closed below, but open above.</p> <p>T. Testis.</p> <p>S. Hernial sac.</p> |
|---|---|

place suddenly, the protrusion may burst through it, in which case it does not obtain a covering from this source.

There are two special varieties of oblique inguinal hernia which it is necessary to mention—viz., *congenital hernia* and *infantile hernia*.

Congenital Hernia.—We have seen that the passage of the testis from the abdomen into the scrotum is accompanied by a protrusion of parietal peritoneum, which lines the inguinal canal and the scrotal sac. This diverticulum is called the processus vaginalis. Under ordinary circumstances the lower part persists as the tunica vaginalis, whilst the upper part becomes obliterated so as to completely shut off the communication

between the general peritoneal cavity and the cavity of the tunica vaginalis. In certain cases this closure fails to take place, and an open pathway from the peritoneal cavity into the processus vaginalis is the result (Fig. 119, B.). Such a condition is favourable to the occurrence of a hernial protrusion into the open processus vaginalis, and a hernia of this nature is distinguished by the term *congenital* (Fig. 124, right side).

Infantile Hernia.—The conditions favourable to the occurrence of an infantile hernia are also due to faults in the developmental process by which the testicle acquires its serous investment. They may be said to owe their origin to an excess of zeal on the part of the gubernaculum. The processus vaginalis remains patent, or is only partially closed. The gubernacular tissue in relation to the parietal peritoneum draws down into the inguinal canal a second test-tube-like diverticulum of the membrane behind the true processus vaginalis (Fig. 125, S.). This is altogether an abnormal peritoneal recess which is thus produced, and it gives rise to a dangerous condition, because at any time an abdominal content may be forced into it. When this takes place an infantile hernia is the result. Four varieties are recognised according to the state of the true processus vaginalis. These are indicated in the diagram (Fig. 125).

Femoral Hernia.—This consists in the protrusion of an abdominal content from the abdominal cavity into the region of the thigh. In its descent it passes *behind* Poupart's ligament along the *crural canal* or *innermost compartment* of the femoral sheath. It is consequently mainly the duty of the student who is engaged in the dissection of the lower limb, and within whose domain the femoral sheath lies, to investigate the anatomical connections of this variety of hernia (p. 201). Still it is essential that the dissector of the abdomen should examine, from its abdominal aspect, the *crural ring* or aperture of communication between the crural canal and the abdominal cavity, and give the dissector of the lower limb an opportunity of doing so likewise.

The *crural ring* is placed immediately behind Poupart's ligament, in the interval between the external iliac vein and the base of Gimbernat's ligament. If the peritoneum is still in position at this point it may exhibit a slight digital depression as it passes over the ring. Strip the peritoneum from the greater part of the iliac fossa. The extra-peritoneal fatty tissue, which stretches over the crural ring, will be observed to be denser, stronger, and more fibrous than elsewhere. A special name is applied to this small portion of the extra-peritoneal fatty tissue. Seeing that it is applied to the ring in such a manner as to close the crural canal at its abdominal end, it is called the *septum crurale*. The extra-peritoneal fatty tissue should now be dissected back with the handle of the knife, to the same extent as the peritoneum. The *fascia iliaca* clothing the iliacus and psoas muscles is thus exposed, and the dissector should note that the external iliac vessels lie *upon* and not *behind* this fascia.

The student is now in a position to study the manner in which the *crural ring* is formed. Let him follow the fascia iliaca and the fascia transversalis towards Poupart's ligament. If the dissection has been carefully performed, he will observe that to the outer side of the external iliac vessels these two fasciæ become directly continuous with each other, and, further, that along the line of union they are both firmly attached to Poupart's ligament. It is evident, then, that no hernial protrusion could leave the abdominal cavity behind Poupart's ligament and external to the iliac vessels.

Opposite the iliac vessels the arrangement of the fascia will be found to be very different. Here the fascia iliaca is carried downwards behind the vessels, whilst the fascia transversalis is prolonged downwards in front of the vessels and behind Poupart's ligament. In the region of the thigh they together constitute a funnel-shaped sheath for the femoral artery and vein, and for some lymphatics ascending to the abdomen. This sheath is divided into three compartments by two vertical partitions. The femoral artery occupies the outermost compartment, and the vein the middle compartment, whilst the innermost compartment, called the *crural canal*, is occupied by the lymphatics, and sometimes by a small lymphatic gland.

An essential difference between these compartments is this—that whilst the two outer are completely filled up by the artery and vein, the crural canal is much wider than is necessary for the passage of its contents. Gauge the width of the crural ring by introducing the point of the little finger. It is readily admitted within the opening. Here, then, is a source of weakness to the abdominal wall, and one which is greater in the female than in the male, seeing that the distance between the iliac and pubic spines is proportionally greater, and, in consequence, the crural ring wider.

When the finger is within the ring, mark the structures which surround it—in *front*, Poupart's ligament, with the spermatic cord or round ligament of the uterus; *behind*, the ramus of the pubis, giving origin to the pectineus muscle, which is covered by the pubic portion of the fascia lata; *internally*, the sharp crescentic free border of Gimbernat's ligament; and *externally*, the external iliac vein.

It is still more necessary to note the relations of the blood-vessels to the crural ring. The *external iliac vein* has been seen to lie to its outer side. The *deep epigastric artery*, as it ascends on the posterior aspect of the abdominal wall, is close to its upper and outer margin, and sends its *pubic branch* inwards in front of it. More important than any of these is the relation of the *obturator artery*, when it takes origin from the deep epigastric. This anomalous vessel may adopt one of three courses:—(1) It may follow the course of the pubic artery, an enlarged form of which it in reality is, and pass inwards *in front* of the ring, and then descend along its *inner* margin. In this case, the ring is surrounded on all sides, except posteriorly, by important vessels. (2) It may pass downwards and backwards across the crural ring. (3) It may run downwards between the ring and the external iliac vein (*vide p. 202*).

Internal to the crural sheath the passage of a hernial protrusion behind Poupart's ligament is effectually prevented by Gimbernat's ligament.

Femoral hernia is more common in females, and inguinal hernia in males; and for the very evident reason, that in the female the crural canal is relatively larger, whilst in the male the passage of the spermatic cord weakens the inguinal region more than the passage of the small round ligament of the uterus.

Umbilical Hernia.—This form of hernia consists in the protrusion of an abdominal content through the umbilical ring in the linea alba. When it occurs in the fetus the hernia passes into the umbilical cord, and the three vessels are separated by it. More than one case has occurred in which the bowel has been cut in dividing the cord at the birth of the child. In the adult the fibrous cords in connection with the umbilicus are related to the lower border of the ring, and the hernia escapes through its upper part (Treves).

Penis.—The penis has already, to a certain extent, been studied in the dissection of the perineum (p. 320). It has been seen to be composed of the *two corpora cavernosa* and the *corpus spongiosum*. Posteriorly, the corpora cavernosa separate from each other, become tapered and are attached to the sides of the pubic arch under the name of the *crura penis*; anteriorly, they together form a blunt rounded extremity, which is covered by the glans penis. The corpus spongiosum, when traced backwards into the perineum, expands into the *bulb of the penis*, which is attached, in the mesial plane, to the anterior aspect of the triangular ligament; traced forwards to the extremity of the penis, it is again found to expand into the *glans penis*, which fits like a cap upon the rounded ends of the corpora cavernosa. The glans penis is somewhat conical in shape, and the projecting margin of its base is termed the *corona glandis*. The urethra opens at the extremity of the glans by a vertical fissure, called the *meatus urinarius*.




FIG. 126.—Median section through the terminal part of the Penis.

The *integument of the penis* is remarkable for its great delicacy and elasticity, and the absence of hairs. It has a brownish tint, and is freely movable over the organ. At the glans the skin leaves the body of the penis, and, passing for a variable distance over the glans, is folded back upon itself so as to form the *prepuce*. The deep layer of the prepuce reaches the penis again behind the corona glandis, and is then reflected forwards over the glans to become continuous with the mucous membrane of the urethra at the meatus urinarius. A slight fold will be observed on the under surface of the glans, extending from the lower angle of the urinary orifice to the prepuce; this is the *frenum preputii*.

Dissection.—Reflect the integument from the surface of the penis by making a longitudinal incision along the middle line of the dorsum.

The superficial fascia will then be seen to be composed of a quantity of loose areolar tissue. We never find fat in the meshes of this tissue. The suspensory ligament and the dorsal vessels and nerves of the penis should now be dissected.

Suspensory Ligament.—The suspensory ligament is a strong fibro-elastic band of a triangular shape. By its posterior border it is attached to the symphysis pubis. Towards the penis it separates into two lamellæ, which join the body of the organ, and between which are placed the dorsal vessels and nerves.

Dorsal Vessels and Nerves.—On the dorsum of the penis, in the groove which extends along the middle line between the two corpora cavernosa, is the *dorsal vein*; on each side of this is the *dorsal artery*, and superficial and external to the artery is the *dorsal nerve*. On the dorsum of the penis, therefore, we find *one* vein, *two* arteries, and *two* nerves.

The *dorsal vein* of the penis begins by several twigs from the glans and prepuce. It extends backwards in the middle line, and disappears between the two layers of the suspensory ligament. It gains the pelvis by passing under the sub-pubic ligament, and ends by joining the prostatic plexus of veins.

The *dorsal arteries* are the terminal twigs of the internal pudic vessels. Piercing the triangular ligament, they pass forward between the two layers of the suspensory ligament, and, continuing their course on the dorsum of the penis, they terminate in branches from the glans penis.

The *dorsal nerves* are branches of the internal pudic. They have a similar course to the arteries, and end in fine twigs to the papillæ of the glans.

ABDOMINAL CAVITY.

The abdominal cavity may now be opened completely by carrying an incision from the umbilicus upwards to the ensiform cartilage. On throwing the two flaps thus formed upwards and outwards over the lower margin of the thorax, a strong fibrous cord, the *obliterated umbilical vein*, will be observed extending from the umbilicus to the under surface of the liver. The obliterated umbilical vein also receives the name of the *round ligament*, or *ligamentum teres*, of the liver.

As it ascends towards that organ, it gradually recedes from the posterior surface of the anterior abdominal wall, taking with it a fold of peritoneum, termed the *falciform ligament* of the liver.

Shape and Boundaries of the Abdominal Cavity.—The abdominal cavity is ovoid in shape, its vertical diameter being the longest. *Superiorly*, it is roofed by the dome-shaped diaphragm, which presents a deep concavity towards the abdomen. *Inferiorly*, it is floored by the pelvic diaphragm, which is also concave towards the abdominal cavity. It is formed by the levatores ani and the coccygei muscles. Neither the roof nor the floor is complete and unbroken. The diaphragm is perforated by certain structures which pass between the thorax and the abdomen. The continuity of the pelvic diaphragm is broken by the passage of certain structures between the pelvic division of the abdominal cavity and the perineum. The upper part of the abdominal cavity extends upwards for a considerable distance under the shelter of the lower ribs and their costal cartilages. The protection which is thus afforded to the viscera in this portion of the cavity is most complete laterally and behind. In front, as the costal cartilages ascend towards the sternum, a wide A-shaped gap is left between those of opposite sides. The level to which the costal arches descend on either side varies greatly in different subjects, but in the great majority of cases a narrow belt of abdominal wall, from one to two inches wide, is left between the lower border of the chest wall and the highest point of the iliac crest, which receives no skeletal support beyond that which is afforded by the vertebral column.

Inferiorly, the expanded iliac bones give support to the abdominal walls posteriorly and laterally, whilst, in its lowest part, the pubic, ischial, sacral, and coccygeal bones form very complete bony boundaries for the cavity.

Whilst the abdominal cavity, therefore, is very fully protected, posteriorly and laterally, by skeletal parts, the front wall is almost entirely formed by the muscles and aponeuroses which have been dissected in this region.

From this it will be seen that the roof, floor, and the greater part of the abdominal wall are composed of muscular structures, the contraction of which would diminish the

capacity of the cavity, and subject the contained viscera to compression.

Subdivision of the Abdominal Cavity.—In dealing with so large a cavity, and one which contains such a diversity of contents, it is absolutely necessary for anatomists to subdivide it into regions, in order that the precise position of each viscus may be accurately defined. In making the first




FIG. 127.—Outline of the Abdominal Cavity as seen in mesial section. The planes of subdivision are indicated by dotted lines.

subdivision, we take advantage of the brim of the true pelvis. That part of the cavity which is situated above this is termed the **abdomen proper**; whilst that part which lies below it is called the **pelvic cavity**. These two portions of the general abdominal cavity do not lie the one directly over the other. The long axis of the abdomen proper is very nearly vertical; that of the pelvic cavity is very oblique, and directed backwards and downwards. Indeed, the pelvic cavity presents the appearance of a recess leading backwards and downwards from the lower and

back part of the abdominal cavity (Fig. 127).

The abdomen proper is still further subdivided by means of four arbitrary planes of section. Two of these are supposed to pass through the body in a horizontal direction, and two in a vertical direction. The former are termed the *subcostal* and the *intertubercular planes* of subdivision, and the position of each is determined as follows:—A horizontal line is drawn around the body at a level corresponding to the most dependent parts of the tenth costal arches. This gives the

position of the subcostal plane. A second line is drawn




FIG. 128.—Planes of subdivision of the Abdominal Cavity.

R.H. Right hypochondrium.
 R.L. Right lumbar region.
 R.I. Right iliac region.
 E. Epigastric region.
 U. Umbilical region.

H. Hypogastric region.
 L.H. Left hypochondrium.
 L.L. Left lumbar region.
 L.I. Left iliac region.

horizontally around the trunk so as to pass through the highest point on the iliac crest on each side that is seen

from the front. This point is always easily determined, as a prominent tubercle juts out from the outer lip of the iliac crest at that spot. It is situated rather more than two inches behind the anterior superior iliac spine, and it marks the point where the outline of the body meets the iliac crest. The line which encircles the body at this level indicates on the surface the position of the intertubercular plane of subdivision.

The two horizontal planes, thus placed, map out the abdomen into three districts or zones, which are termed from above downwards—(1) the *costal*, (2) the *umbilical*, and (3) the *hypogastric zone*.

The two vertical planes of subdivision are called the *right* and *left mid-Poupart planes*, seeing that they correspond on the surface to two perpendicular lines reared from the mid-points of Poupart's ligament.

By these mid-Poupart planes, each of the three zones determined by the horizontal planes of section is subdivided into three.

The costal zone is mapped off into a central *epigastric region* and a *right* and *left hypochondriac region*; the umbilical zone into a central *umbilical region* and a *right* and *left lumbar region*; and the hypogastric zone into a central *hypogastric region* and a *right* and *left iliac region*.

Contents of Abdomen Proper.—Within the abdominal cavity we find the following structures:—

1. Abdominal part of the alimentary canal. {
 - Stomach.
 - Small intestine.
 - Large intestine.
2. Glands situated outside the walls of the alimentary canal and pouring their secretions into it. {
 - Liver with its gall-bladder or reservoir.
 - Pancreas.
3. The spleen.
4. The two kidneys, the ureters, and the two suprarenal bodies.
5. Lymphatic glands, lymphatic vessels, the receptaculum chyli, and the commencement of the thoracic duct.
6. The abdominal aorta, with its various visceral and parietal branches.
7. The inferior vena cava and its tributaries, and the commencements of the venæ azygos major and minor.
8. The vena portæ and its tributaries.
9. The lumbar plexuses of nerves.
10. The abdominal portion of the sympathetic nervous system.
11. The peritoneal membrane which lines the cavity and invests the viscera.

A mere glance is sufficient to distinguish between the three primary parts of the alimentary canal within the abdominal cavity. The *stomach* is the dilated portion which lies in the left part of the costal zone. The *small intestine* succeeds the stomach, and presents a striking contrast to the *large intestine*. The following are the leading points of difference:—(1) The calibre of the small intestine is as a rule smaller than that of the large intestine. Sometimes, however, the large intestine is very much contracted. It is not unusual to see the part termed the descending colon with a diameter not greater than that of the middle finger. (2) The walls of the small intestine are smooth and uniform, whereas the walls of the great intestine are puckered and sacculated. (3) The longitudinal muscular fibres in the wall of the great intestine are not disposed uniformly around the tube as in the small intestine, but are collected into three bands (*tenia coli*), which are separated from each other by intervals, and are distinctly visible to the naked eye. These bands are shorter than the tube itself, and this is the reason of its walls being puckered in the intervals between them. (4) Attached to the great intestine are *appendices epiploicae*. These are small peritoneal pouches or folds, which hang from the gut and contain fat.

On opening the abdominal cavity, a very partial view of the contained viscera is obtained, so long as they are left undisturbed. On the right side of the costal zone the sharp margin of the liver may be observed projecting slightly below the ribs, whilst opposite the ninth costal cartilage the fundus of the gall-bladder is seen peeping out from under cover of this organ, and projecting slightly beyond its anterior border. In the same zone to the left of the liver, a portion of the stomach is visible, whilst extending downwards from the lower border of this viscus is a broad fold of peritoneal membrane, called the *great omentum*. This usually contains a quantity of fat in its meshes, and is spread out like an apron, so as to hide from view the viscera which occupy the two lower zones. Sometimes, however, the great omentum is narrow and short; or it may be turned more or less completely upwards or to the side. In either case some of the coils of the small intestine will be seen, and also, in all probability, those parts of the great intestine which occupy the right and left iliac fossæ. That part lying in the right iliac fossa is

called the *cæcum*, whilst the part situated in the left iliac fossa is the *iliac colon*. It may also chance that the bladder is full, in which case its apex will be observed projecting above the pubes. Lastly, in pregnant females the gravid uterus will be visible, reaching a height in correspondence with the period of gestation.

Raise the great omentum and turn it upwards over the lower margin of the thorax. By this proceeding the coils of the small intestine are exposed, and a part of the great intestine which extends across the cavity of the abdomen will be seen shining through the posterior layer of the great omentum. This is the *transverse colon*.

The position and connections of the various viscera should now be studied.

Liver (hepar).—The liver is the largest gland in the body. It is a solid pliant organ, the chief bulk of which lies in the epigastrium. It also occupies the right hypochondrium, and extends for a variable distance into the left hypochondrium. Further, the lower right margin crosses the subcostal plane, and enters for a short distance into the upper part of the right lumbar region.

The liver has the shape of a right-angled triangular prism (Symington), but its substance is so pliant that its natural configuration can only be preserved when special measures are adopted for this purpose. It presents five surfaces, viz., an inferior, a superior, an anterior, a posterior, and a right lateral surface. The inferior surface looks downwards and to the left and is in relation to other viscera within the abdomen; it may therefore be specially distinguished by the name of *visceral surface*. The other four surfaces are applied to the diaphragm and abdominal parietes, and they pass insensibly into each other by means of rounded borders. They may thus be grouped together under the one term of *parietal* (Birmingham). A sharp attenuated margin separates the inferior or visceral surface from the right lateral, from the anterior, and, at the left extremity of the organ, from the superior surface. This margin constitutes a prominent feature of the liver.

At the present moment, with the organ *in situ*, the connections of the liver are such that the posterior surface cannot be studied at all, and the inferior or visceral surface only

partially. The other three surfaces and the sharp margin can be fully examined. The *right lateral surface* forms an area of some extent, which passes vertically downwards in relation to the lateral portions of the seventh, eighth, ninth,




FIG. 129.—The Abdominal Viscera as seen from the front after removal of jejunum and ileum with their mesentery. The dark lines indicate the subdivision of the abdominal cavity. (Birmingham.)

tenth, and eleventh costal arches. It is separated from these, however, by the diaphragm and the thin basal margin of the right lung. It is convex from before backwards, and is adapted to the curvature of the ribs, under the shelter of which it lies. This surface passes insensibly by means of rounded borders into the superior, anterior, and posterior

surfaces. Inferiorly, however, the sharp margin of the liver marks it off in the most distinct manner from the inferior surface. This portion of the sharp margin constitutes the most dependent part of the liver, and extends for a variable distance below the subcostal plane into the right lumbar region.

The *superior surface* is adapted accurately to the under surface of the diaphragm. Its right portion rises in the form of a high convexity, which occupies the right cupola of the diaphragm. Immediately to the left of this is a depressed slightly concave area (*impressio cardiaca*), which corresponds to the heart and pericardium on the upper surface of the diaphragm; whilst, still further to the left, the superior surface of the liver again shows a convexity, but not so pronounced as that on the right side, which fits into the left cupola of the diaphragm. Full rounded borders separate this surface from the right lateral, from the anterior, and from the posterior surfaces of the liver. At the left extremity of the organ, the superior surface is separated from the inferior surface by the left portion of the sharp margin.

The *anterior surface* of the liver, which looks directly forwards, presents a triangular outline. The base of the triangle is formed by the rounded border which separates this surface from the right lateral surface; the upper limit is formed by the rounded border which intervenes between the superior and anterior surfaces; and the lower limit by the anterior sharp margin of the liver. The apex of this triangular area points to the left, and corresponds with the left extremity of the organ. The greater part of the anterior surface lies against the diaphragm, and under cover of the lower ribs and costal cartilages of the right side. Its left part lies under shelter of the costal arches of the left side; whilst in the Δ -shaped interval between the costal cartilages of opposite sides it lies behind the ensiform cartilage, and, for a variable distance below this, in direct relation to the posterior surface of the anterior abdominal wall.

Attached to the anterior and superior surfaces of the liver will be seen the broad peritoneal *falciform ligament* (ligamentum falciforme hepatis), which maps out the organ into a right and a left lobe. The smooth glossy appearance of the three surfaces we have examined is due to the peritoneal investment of the organ. If the hand be passed backwards

over the upper surface of the liver, it is prevented from reaching the posterior surface by the reflection of the peritoneum from the upper surface of the organ on to the under surface of the diaphragm. This reflection forms the upper layer of the *coronary ligament*.

The *posterior* and *inferior surfaces* of the liver can only be satisfactorily studied after the removal of the organ. Still, there are several important points in connection with the inferior or visceral surface which can be best ascertained




FIG. 130.—Anterior Surface of the Liver.

under the present conditions. This surface is very oblique ; it slopes from the right inferior sharp margin upwards to the left extremity of the organ, so that it looks very nearly as much to the left as downwards. It follows from this that the vertical depth of the liver diminishes rapidly as it extends to the left. In relation to this sloping inferior surface there are a number of viscera, all of which leave their imprint upon the liver in the shape of fossæ of greater or less depth. Thus the left lobe is moulded over the stomach, whilst in contact with the inferior surface of the right lobe are :—(1) the gall-

bladder, which is bound down ~~to it by peritoneum~~; (2) the pyloric end of the stomach and the duodenum or commencement of the small intestine; (3) the hepatic flexure of the colon; and (4) the right kidney. The precise relations of these organs to the liver will be studied more fully at a later stage.

The *sharp margin of the liver* forms a continuous attenuated border, although it is convenient to speak of it as consisting of a *right inferior part* intervening between the right lateral surface and the inferior surface; an *anterior part*, which separates the anterior surface from the inferior surface; and a *left portion*, which turns round the left lobe and forms its left fine edge or extremity. The anterior part of the sharp margin presents a slight deficiency where it is adapted to the fundus of the gall-bladder, and a notch (*incisura umbilicalis*) of varying depth where the falciform ligament meets the *ligamentum teres* or obliterated umbilical vein.

To map out the liver on the anterior surface of the body take three points: (a) half an inch below the right nipple; (b) one inch below the left nipple; (c) on the right side one inch below the extremity of the tenth rib. Join b and c; this will give fairly accurately the lower limit of the organ. Next draw a curved line, convex to the right, between a and c; this marks out the right limit. A line extending from a to b will indicate the upper limit. But this upper line must be drawn with some care. At each extremity it must be curved upwards, whilst the intermediate portion must cross the sternum at the level of the junction of the sixth costal cartilages and be somewhat depressed in correspondence with the depressed area on the upper surface of the liver which lies under the pericardium (Birmingham).

Even in health the position and shape of the liver is subject to considerable variation. From its intimate connection with the diaphragm it is easy to understand how it must rise and fall with every respiratory act. Further, the full or empty condition of the neighbouring hollow viscera affects not only its form, but also its position. Displacement of the liver from artificial causes, such as tight-lacing in females, is by no means uncommon. A gravid uterus, also, as it gradually ascends in the abdominal cavity, exercises a marked influence upon the shape of the liver.

Gall-Bladder (vesica fellea). — The gall-bladder should be examined in connection with the liver. This small pyriform sac lies in the epigastric region close to the right mid-Poupart plane. Its fundus, covered by peritoneum, peeps out from under cover of the anterior margin of the liver, but in the rest of its extent it is bound down by a partial peritoneal investment to the under surface of the right lobe of that organ.

Spleen (lien).—The spleen is a solid organ, which lies deeply in the left part of the costal zone, and is altogether out of sight in the undisturbed condition of the viscera. By drawing the stomach to the right, and thrusting the hand into the left hypochondrium, it can readily be discovered and pulled forwards for inspection. It lies very obliquely in the abdominal cavity, its upper end being much nearer the mesial plane than its lower end. Its long axis is directed from above downwards and outwards, and also to some extent forwards. For the most part it lies in the left hypochondrium, but its upper end extends inwards beyond the left mid-Poupart plane, so that fully a third of the organ is situated in the epigastric region.

The spleen when properly hardened *in situ* has the shape of an irregular tetrahedron with its apex above and its base below. The upper extremity or *apex* is curved to some extent forwards on itself, and approaches close to the left suprarenal capsule.

Of the four surfaces the most extensive is the diaphragmatic (superficies diaphragmatica), which is convex and looks backwards and outwards. It rests upon the back part of the diaphragm, to the curvature of which it is adapted. By the diaphragm it is separated from the ninth, tenth, and eleventh ribs. It is necessary also to remember that the pleura descends between this portion of the chest wall and the diaphragm and comes to lie superficially to the greater part of the diaphragmatic surface of the spleen. The thin basal margin of the lung which occupies the upper part of the pleural recess likewise intervenes between the upper part of the spleen and the surface of the body.

The remaining three surfaces are turned towards the cavity of the abdomen, and are closely applied to the neighbouring viscera. These three surfaces meet at a blunt but usually conspicuous prominence which may be termed the *internal basal angle*. From this as from a centre three ridges radiate. One, a salient and prominent border (*margo intermedius*), ascends to the apex and separates an extensive anterior gastric area from a posterior renal surface; a second short ridge or border passes backwards to the posterior basal angle and intervenes between the renal and the basal surfaces; whilst the third ridge, less distinctly marked, proceeds

forwards to the anterior basal angle and separates the gastric and the basal surfaces from each other. The two last-named ridges, together with the lower border of the organ, map out a triangular area which may be distinguished as the basal surface.

The *gastric surface* (*superficies gastrica*) is the most extensive of the three visceral districts. It is deeply concave and moulded upon the fundus of the stomach. Within its area and about half an inch to the outer side of the *margo inter-*




FIG. 131. —The Spleen (visceral aspect).

medius is situated a longitudinal slit, frequently broken up into two or more pieces, and termed the *hilum*. This gives passage to the vessels and nerves which enter and leave the organ. Behind the hilum and immediately in front of the internal basal angle there is a *pancreatic depression* of variable extent and depth into which the tail of the pancreas is received.

The *renal surface* (*superficies renalis*) is flat and even, and varies somewhat in its extent. It is applied to the anterior surface of the upper part of the kidney close to its outer border.

The peritoneal relations of the spleen are such that the renal surface

cannot be studied unless the posterior border of the organ is pulled forwards, so that we can see behind it.

The *basal surface* (superficies basalis) is smaller than the other two visceral areas. It is triangular in form, and looks downwards and inwards. It is in contact with the splenic flexure of the colon and the costo-colic ligament.

Of the several borders which separate the different surfaces of the spleen from each other, the anterior, the inferior, and the posterior are the most prominent and conspicuous. The *anterior border* (margo crenatus) is notched or crenated, and intervenes between the diaphragmatic surface and the gastric surface. The *inferior border* separates the diaphragmatic surface from the basal surface; whilst the *posterior border* (margo obtusus) intervenes between the renal and diaphragmatic surfaces. The other margins which separate the visceral areas from each other radiate out from the internal basal angle, and have been already noticed.

A very characteristic feature of the typically formed spleen is the great prominence of the anterior basal angle. It forms the most anteriorly placed part of the spleen.

The form of the spleen varies very greatly with the varying degrees of distension of the hollow viscera which are related to its visceral aspect. There is good reason to believe that the tetrahedral form which is described




FIG. 132.—The Esophagus, Stomach, and Duodenum.

above is associated with an empty or slightly distended stomach and a well-distended intestine. When, however, the stomach is distended and the gut more or less empty, the basal surface partially or even entirely disappears, and then the spleen assumes a form similar to that of the segment of an orange (Shepherd).

Peritoneal Connections of the Spleen.—Passing from the fundus of the stomach to the gastric surface of the spleen along the line of the hilum is a fold of peritoneum known as the *gastro-splenic omentum*; whilst tying the visceral aspect of spleen down to the surface of the kidney is another short fold




FIG. 133.—Stomach of a Child, two years of age, hardened *in situ* by formalin injection.

called the *lieno-renal ligament*. It is between the two layers of the lieno-renal ligament that the splenic vessels reach the hilum of the organ.

Stomach (ventriculus).—The stomach is the most dilated part of the alimentary canal, and it constitutes the receptacle for the food after it has been masticated and swallowed. The gullet or œsophagus opens into the stomach above and to the left, whilst below and to the right the stomach becomes continuous with the duodenum or first part of the small intestine. The form and the position of the organ within the abdomen are greatly influenced by the amount of food it contains, and

it is convenient to describe it as it appears when moderately distended. It then assumes a pyriform shape and is strongly curved upon itself. It is customary to recognise in connection with it: (1) a blunt left extremity or fundus; (2) a narrow right extremity or pylorus, in close association with which is the pyloric canal and the antrum pylori; (3) two orifices, a cardiac and a pyloric; (4) two surfaces, a superior and an inferior; and (5) two borders or curvatures, a greater and a lesser.

The *fundus*, or left cardiac end, is full and rounded and forms a marked bulging directed upwards and backwards. It occupies the back part of the left cupola of the diaphragm, from which it is in part separated by the spleen and the liver. To the right of the fundus and about two inches below its summit is the œsophageal or *cardiac orifice*. It is placed on the upper surface of the stomach close to the commencement of the lesser curvature. At this point the organ is joined by the gullet. The *pylorus* or narrow right extremity of the stomach becomes continuous with the duodenum, and the junction is marked on the surface by a slight but distinct constriction. The portion of the stomach immediately adjoining the pyloric constriction (about one inch in extent) is narrow and cylindrical, and it would appear that it undergoes little or no change during distension of the organ. It is termed the *pyloric canal* (Jonnescos), and when the stomach is full it is directed backwards and lies below the lobulus quadratus of the liver.

The two surfaces of the stomach look for the most part upwards and downwards. The *upper surface* is fuller and more convex than the lower surface. To some extent it is directed forwards as well as upwards, and it is largely covered by the left lobe of the liver. Below and to the left of the sharp margin of the liver, however, a considerable portion of this surface of the stomach is in apposition with the diaphragm, and also with the posterior aspect of the anterior abdominal wall.

The *inferior surface* of the stomach is flatter than the superior surface, and is supported by a slightly curved and sloping shelf, which projects forwards from the posterior wall of the abdomen. This has been appropriately called by Birmingham the stomach-bed, and it is formed by the following

structures, all of which are related to the lower surface of the organ: (1) the gastric surface of the spleen; (2) the left suprarenal capsule and a varying amount of the upper part of the left kidney; (3) the upper surface of the pancreas; (4) the transverse meso-colon; and (5) the transverse colon. The lesser sac of the peritoneum alone separates the stomach from the spleen, suprarenal capsule, kidney, pancreas, and colon, whilst the transverse meso-colon intervenes between it and the coils of the small intestine.




FIG. 134.—The stomach has been removed from its bed so as to display the recess in which it lies.

The right or posterior border of the stomach is termed its *lesser curvature*. It extends from the cardiac orifice to the pylorus, and curves round the base of the tuber omentale on the under surface of the liver (*vide* p. 463), and also to a smaller extent round the corresponding prominence of the pancreas (*vide* p. 453). It is therefore concave, and from it proceeds a fold of peritoneum, called the gastro-hepatic omentum, which connects the stomach to the liver and the diaphragm. The left or anterior border of the stomach, called the *greater curvature*, on account of its great length, is convex and is directed to the left and forwards. From this border an extensive peritoneal fold, termed the great omentum, hangs downwards.

The *antrum pylori* is a dilatation or bulging of the stomach wall immediately to the left of the pyloric canal. It is chiefly developed on the greater curvature, and when well marked it is separated by a more or less distinct constriction from the remainder of the organ. As the viscus distends the antrum becomes more and more evident, and in many cases of complete or excessive distension it bulges to the right for a variable distance beyond the pyloric canal.

When the stomach is empty it is questionable if it ever assumes during life the flaccid, relaxed, and flattened form which is so frequently seen in the dissecting-room in subjects which have not been specially hardened. In life it contracts more or less uniformly, and its walls become thick and firm. Although the contracted stomach differs considerably in appearance from the organ when distended, still the different parts which have been described above (with, in certain cases perhaps, the exception of the antrum pylori) can be easily distinguished.

Position of the Stomach.—When empty the stomach lies more or less horizontally within the abdominal cavity. It is placed within the left hypochondrium and the left portion of the epigastrium. The pyloric extremity either occupies the mesial plane or lies at a point about half an inch or so to the right of this plane. Addison's method of indicating the position of the pylorus on the surface of the abdomen is probably the best. Draw a line from the top of the manubrium sterni to the symphysis pubis; bisect by a horizontal line drawn across the front of the body. A point on this latter line half an inch to the right of the mesial plane lies over the pylorus.

As the stomach fills it becomes more oblique, occupies more space within the abdomen, and may even over-step the subcostal plane and enter the left lumbar and the umbilical regions. The *pylorus* moves to the right, but not as a rule more than an inch and a half or at most two inches from the mesial plane. It does not alter in a vertical direction; it thus maintains the same level within the cavity. As already mentioned, however, the *antrum pylori* may protrude downwards, and to the right for some distance beyond the pylorus. The *cardiac opening* is fixed in its position, and is little, if at all, affected by the distension or emptying of the organ. It is placed opposite the tenth dorsal vertebra, and on the surface of the body its situation may be indicated by placing

the finger on the seventh costal cartilage of the left side about one inch from its junction with the sternum.

Œsophagus.—The portion of the gullet which is placed within the abdomen is very short, and occupies a groove on the back aspect of the left lobe of the liver. The œsophagus joins the stomach, when the parts are in their natural position, so as to form a very decided angle with its upper surface. By pulling the left lobe of the liver aside the junction between the gullet and the stomach will be seen.

Relations between Thoracic and Abdominal Organs.—At this stage it is useful to consider the relations which exist between the abdominal and thoracic organs which lie upon the different aspects of the diaphragm. We have seen that the right lobe of the liver occupies the right vault of the diaphragm, whilst the left lobe of the liver, the fundus of the stomach, and the spleen occupy the left vault. The base of the right lung is in relation to the right lobe of the liver. The pericardium, in by far the greater part of its extent, lies above the left lobe of the liver, which therefore intervenes between it and the stomach; only a limited portion of the apex of the heart extends over the region of the stomach. The base of the left lung lies over the left lobe of the liver, the fundus of the stomach, and the spleen.

Small Intestine (intestinum tenue).—The small intestine is that part of the alimentary canal which succeeds the stomach. It begins in the epigastric region at the pylorus, and ends in the lower part of the right lumbar region by joining the great intestine. Its average length is somewhere about twenty-three feet, and as it is traced towards its termination it will be seen to diminish slightly in calibre. It is divided into three portions, viz. :—

1. The duodenum.
2. The jejunum.
3. The ileum.

The *duodenum* is the name which is given to the first part of the small intestine. It is about ten inches long, and extends from the pylorus to the left side of the body of the second lumbar vertebra. As it lies deeply in the greater part of its extent, and as dissection is necessary to bring out its relations, it is better to defer its description for the present.

The *jejunum* and *ileum* constitute the coils of the small

intestine, and are ~~more or less completely covered by the great omentum.~~ The jejunum begins where the duodenum ends, viz., on the left side of the body of the second lumbar vertebra; and the ileum ends in the lower part of the right lumbar region by joining the cæcum or the commencement of the great intestine. The subdivision of the small intestine is of the most arbitrary kind. After mapping off the duodenum it is customary for anatomists to look upon the upper two-fifths of the remainder as being jejunum, and the lower three-fifths as being ileum. There is no hard-and-fast line of demarcation between the lower two divisions—the one passes insensibly into the other; and as the chief distinction is to be found by an examination of the interior of the tube, the student will not in the meantime see much difference between them.


To expose the commencement of the jejunum, the great omentum should be thrown upwards with the enclosed transverse colon over the lower margin of the thoracic wall. The coils of the small intestine should then be drawn over to the right. The junction between the duodenum and the jejunum will now be seen on the left side of the vertebral column, at the level of the second lumbar vertebra. The termination of the duodenum is fixed, and the jejunum bends suddenly forwards and downwards upon it, forming the duodeno-jejunal flexure. To bring the termination of the ileum into view, the coils of the intestine should be turned over to the left. The terminal part of the ileum, which almost invariably lies in the pelvis, has no great latitude of movement. It passes upwards across the iliac vessels and upon the psoas muscle, to join the cæcum at the level of the intertubercular plane, and close to the right Poupart plane.

The coils formed by the jejunum and ileum are suspended from the posterior wall of the abdomen by a wide fold of peritoneum, called the mesentery. They are thus freely movable within the cavity. Owing to the manner in which the mesentery is attached to the posterior wall of the abdomen (Fig. 129), they tend to lie more in the left portion of the cavity than in the right part, and they occupy the umbilical, hypogastric, lumbar, and iliac regions, filling up the greater part of the abdominal cavity below the transverse colon and its mesentery. A variable number of coils extend downwards

into the pelvis, and not uncommonly some coils of the jejunum may be found in the left hypochondrium.

Meckel's Diverticulum.—In about 2 per cent of subjects dissected, a blind, hollow protrusion termed Meckel's diverticulum juts out at a right angle from the wall of the ileum at a point rather less than three feet from the junction of the small intestine with the cæcum. ~~It represents a persistent portion of the vitelline duct of the embryo, and under certain circumstances it may lead to conditions which require surgical interference.~~

Large Intestine (intestinum crassum).—The large intestine, although, in its distended condition, possessing a much wider calibre than the small intestine, is not nearly so long. It extends from the right iliac fossa to the anus, and it rarely measures more than five or six feet in length. Like the small intestine, it is widest at its commencement, and gradually diminishes in diameter as it advances towards its termination. It is subdivided more or less arbitrarily into the following parts:—



Cæcum (caput cæcum coli).—The cæcum is the blind commencement of the great intestine. It lies in the right iliac fossa, on the ilio-psoas muscle, and immediately above the outer half of Poupart's ligament. Except in a very few exceptional cases (6 to 7 per cent) it is completely enveloped by the peritoneum, and is thus allowed some latitude of movement. When distended it is in contact with the anterior abdominal wall, but when it is empty and collapsed it is usual to find some coils of the small intestine intervening. The terminal part of the ileum, which passes upwards on the inner side of the cæcum, opens into it upon its inner and hinder aspect about two and a half inches above its blind end, and marks the point where it becomes continuous with the ascending colon.

On the surface of the anterior abdominal wall the position of the ileo-cæcal orifice may be determined by the fact that it lies subjacent to the point at which the Poupart and the intertubercular lines intersect.

Vermiform Appendix (processus vermiformis).—In connection with the cæcum the dissector will find the vermiform appendix. This is a narrow cæcal tube, which has a diameter slightly greater than that of a goose quill, and a length which varies from three to five or six inches, or even more. It opens into the cæcum upon its inner and back aspect below the termination of the ileum, and is provided with a small peritoneal fold, which constitutes its mesentery. It cannot be said that the appendix has any fixed position. It may occupy any situation consistent with its length and the latitude of movement allowed by its mesentery. Probably the most usual position which it assumes is one behind the cæcum. In many cases, however, it lies behind the terminal part of the ileum and its mesentery, whilst in others it curves over the psoas and dips into the pelvis. The tæniæ coli or three longitudinal muscular bands on the wall of the cæcum meet at the base of the appendix and give it a continuous and uniform coating of fibres. The anterior tænia coli on the cæcum, if followed downwards, affords a sure guide to the appendix.

The orifice of the appendix may be determined on the surface by placing the finger upon the right Poupart line one inch below the inter-tubercular plane.

Ascending Colon (colon ascendens).—The ascending colon extends upwards through the right lumbar region, until it reaches the under surface of the right lobe of the liver. It is continuous below with the cæcum, whilst above it becomes the hepatic flexure. It is usually clothed anteriorly and laterally by peritoneum, whilst posteriorly it is bare; and this bare surface rests upon the fascia covering the upper part of the iliacus muscle, the quadratus lumborum muscle, and upon the lower part of the anterior surface of the right kidney, with each of which it is connected by a little loose areolar tissue. In certain cases the peritoneum may surround the tube, and form behind it a short meso-colon.

The *hepatic flexure* (flexura coli dextra) is the bend which connects the ascending colon with the transverse colon. When the colon reaches the inferior surface of the right lobe of the liver, it bends forwards and then turns suddenly to the left, and this curvature constitutes the flexure. The summit of the curve lies in the right hypochondrium. It

occupies a marked depression on the under surface of the liver to the right of the gall-bladder, and is placed in front of the lower part of the kidney. Like the ascending colon, it is only partially covered by peritoneum. Its posterior surface is more or less bare, and in direct contact with the kidney.

Transverse Colon (colon transversum).—The transverse colon is continuous on the one hand with the hepatic flexure, and on the other with the splenic flexure. It is the longest part of the great intestine (eighteen to twenty inches), and it stretches across the entire width of the abdominal cavity. At first it descends into the umbilical region, and then ascends into the left hypochondrium. It takes an arched course, the summit of the arch being nearer the anterior wall of the abdomen, and at the same time at a lower level in the body, than its extremities. The transverse colon possesses greater freedom of movement than any other part of the great intestine. It is attached to the posterior abdominal wall by a wide peritoneal fold, called the *transverse meso-colon*. Its right extremity lies in front of the duodenum, whilst its left extremity is in close relation to the lower surface of the pancreas and the base of the spleen.

The *splenic flexure* (flexura coli sinistra) is the term applied to the bend which the colon takes in the left hypochondrium, before proceeding downwards as the descending colon. It is placed at a higher level and gains a deeper plane in the abdominal cavity than the hepatic flexure, and it receives its name from the fact that it lies in more or less intimate relation with the basal surface of the spleen. A fold of peritoneum, with a free, crescentic border, binds it to the diaphragm opposite the tenth or eleventh rib. This fold is called the *phrenico-colic ligament* or the *sustentaculum lienis*.

When the stomach is empty and the colon distended with gas, the transverse colon, where it adjoins the splenic flexure, may rise so as to occupy a position against the vault of the diaphragm, beside or in front of the fundus of the stomach. In such a case it intervenes between the stomach and the thoracic wall, and would yield a tympanitic note upon percussion.

Descending Colon (colon descendens).—The descending colon takes a vertical course downwards through the left lumbar region, and, on gaining the crest of the ilium, becomes continuous with the iliac colon. Its calibre is less than that

of the ascending colon, and very frequently it is found in a firmly contracted condition. As it proceeds downwards it first curves round the outer margin of the left kidney and then descends more or less vertically in the angle between the psoas and the quadratus lumborum muscles.

~~Its anterior surface and its sides are covered by peritoneum, but in the great majority of cases its posterior surface is bare, and connected to the lower part of the diaphragm and the quadratus lumborum, on both of which it rests, by loose areolar tissue.~~




FIG. 135.—From a tracing of a transverse section through the abdomen, at the level of the fourth lumbar vertebra.

p. 1 and *p. 2* indicate the points at which the peritoneum is reflected from the descending colon on to the posterior wall of the abdomen.

Iliac Colon (colon iliacum).—The iliac colon is a short portion of the great intestine, not more than five or six inches in length, which takes a slightly curved course downwards and inwards in the left iliac fossa. Above, it begins at the iliac crest, where it is continuous with the descending colon; below, it turns over the inner margin of the psoas muscle, enters the pelvis and becomes the pelvic colon. As a rule the peritoneum is related to it in very much the same manner as in the case of the descending colon; it clothes it anteriorly and laterally, but leaves its posterior surface bare. This surface is connected to the ilio-psoas muscle, on which it lies, by

areolar tissue. In a certain number of cases (10 per cent according to Jonnesco) it receives a complete investment of peritoneum and is provided with a mesentery.

Pelvic Colon (colon pelvicum).—Next to the transverse colon this is, as a rule, the longest section of the great intestine, and indeed it not infrequently exceeds the transverse colon in length; on the other hand, it should be remembered that it is sometimes greatly reduced in length. It forms a long loop, freely movable owing to its being provided with an extensive mesentery, termed the *pelvic meso-colon*, but its two extremities are fixed and are placed in close proximity to each other. The upper end, which is continuous with the iliac colon, is placed on the inner margin of the left psoas; the opposite extremity is fixed by the shortening and disappearance of the mesentery to the front of the third piece of the sacrum, and here it becomes continuous with the rectum.

The pelvic colon is thus ~~completely invested with peritoneum~~, and as a rule it is stowed within the cavity of the pelvis in intimate relation to the rectum and bladder and also to the uterus in the female. It is subject to much variation, however, both in length and in position, and in certain cases, either through its own distension or through the distension of the bladder and rectum, or through both causes acting together, it comes to occupy a place in the abdominal cavity.

In the above account of the iliac and the pelvic portions of the colon the old conventional description of the sigmoid flexure and the first part of the rectum has been abandoned and the subdivision of the great intestine recommended by Jonnesco followed. It should be noted that the iliac colon corresponds to the upper part of the sigmoid flexure as formerly described, and that the pelvic colon includes the remainder of the sigmoid flexure with the first part of the rectum of most English text-books.

The *rectum* and the *anal canal* will be described with the pelvic viscera.

Adaptation of the Abdominal Walls to the Viscera, and of the Viscera to each other.—The abdomen is an air-tight cavity, and the atmospheric pressure acts upon its mobile walls so as to keep them constantly in accurate apposition with the viscera, and also the viscera in accurate contact with each other. During life, and in the undissected subject, no space of any kind is left vacant. The external configuration of the solid organs within the abdomen is

determined by this close adaptation of walls to contents, and of viscus to viscus. The liver is the best example of this—every structure with which it is in contact by its visceral surface leaves its mark upon it in the form of a depression, whilst its parietal surface presents an exact mould of the under surface of the diaphragm and other parts of the abdominal parietes with which it is in apposition. During life the hollow viscera are constantly undergoing changes of form, and they react upon the pliable solid organs and model them in such a manner that they also undergo striking alterations in form.

Peritoneum.—The peritoneum is the serous membrane which lines the walls of the abdominal cavity, and gives more or less complete coverings to all the viscera within it. In the male it is a closed sac like other serous membranes. In the female, however, there is a small opening at the extremity of the Fallopian tube, by means of which the lumen of this tube communicates with the interior of the sac. It differs from other serous sacs in its great size, and also in its many complications. Take, for example, the pleura or the serous pericardium, or the tunica vaginalis; in these cases the serous membrane lines a cavity which holds a single viscus, and the reflection of the membrane from the walls of the cavity on to the viscus, and from the viscus again on to the walls, can be followed with the greatest ease. The peritoneal sac, on the other hand, belongs to a cavity which contains numerous viscera, the majority of which have undergone striking changes in form and in position during development, and this is the reason why it is so very complicated.

In opening the cavity of the abdomen, the peritoneal sac has been laid open, and the inner surface of the membrane is observed to present the usual smooth, polished, and glistening appearance. The part which lines the walls of the abdomen is termed the parietal peritoneum; that which is reflected on to viscera is called the visceral peritoneum.

Before tracing the peritoneum through its many foldings, it is well that some terms which are applied to certain of its folds should be explained. The term omentum is employed to denote a fold of peritoneum which connects the stomach with neighbouring viscera. Thus we have the great or gastrocolic omentum connecting it with the transverse colon; the small

or gastro-hepatic omentum connecting it with the liver ; and the gastro-splenic omentum connecting it with the spleen. The term mesentery is applied to any fold of peritoneum which attaches a part of the intestinal tube to the posterior wall




FIG. 136.—Diagram to illustrate the continuity of the Peritoneum in the vertical direction in the Female. (Birmingham.)

of the abdomen, and conveys to it its blood-vessels, as, for example, the mesentery proper in connection with the small intestine, the transverse meso-colon, the pelvic meso-colon, the mesentery of the vermiform appendix, and the mesenteries occasionally found in connection with the ascending and descending portions of the colon. The term ligament is

given to folds which connect viscera which are not parts of the intestinal canal to the walls of the abdomen, or which bind viscera of any kind to the diaphragm. Examples of these are to be found in the peritoneal ligaments of the liver, bladder, and uterus, and also in the lienorenal, the phrenicocolic, and the gastrophrenic ligaments.

Let us now endeavour to follow the peritoneal membrane in the vertical direction (Fig. 136). The best point to start from is the great omentum, or large apron-like fold which hangs down from the stomach, and is spread out over the coils of the small intestine. This omentum is composed of four layers—two anterior layers and two posterior layers, and these are continuous with each other at the lower free margin of the fold. Trace the two anterior layers upwards. They lead to the greater curvature of the stomach, and here they separate from each other so as to enclose this viscus between them—one passing in front and the other passing behind it. The smooth glistening appearance presented by the surface of the stomach is due to the peritoneal coating which it thus acquires. At the lesser curvature of the stomach the two layers come together, and are prolonged upwards to the liver as a distinct fold, which receives the name of the gastro-hepatic or lesser omentum. Reaching the transverse fissure of the liver the two layers again separate, this time to enclose the liver. The one layer is directed forwards over the under surface of the organ, round its anterior border, and then onwards over its anterior and superior surfaces. On reaching the point where the liver and diaphragm are in contact, it is reflected on to the diaphragm, and proceeds forwards upon its under surface to reach the anterior wall of the abdomen. The other layer turns backwards, and, clothing the lobus Spigelii on the posterior surface of the liver, is reflected on to the back part of the diaphragm, and turns downwards on the posterior wall of the abdomen. We shall now leave these layers for a little and trace the two posterior layers of the omentum. For this purpose it is necessary to turn up the great omentum over the ribs. Its two posterior layers in proceeding upwards come to the transverse colon. This they enclose, the one passing in front and the other behind, and coming in contact with each other again on the other side of the gut, they are prolonged backwards to the

posterior wall of the abdomen, as the *transverse meso-colon*. They reach the back wall of the abdomen along the anterior border of the pancreas, and here they separate. The one layer is carried backwards and upwards over the upper surface of the pancreas to become continuous with the layer which we left upon the posterior wall of the abdomen. The other turns downwards over the third part of the duodenum, and is almost immediately led away from the posterior wall of the abdomen by the superior mesenteric vessels, which, spreading out in a fan-like manner, conduct it to the small intestine. Turning round the gut so as to invest it, the peritoneum proceeds upwards upon the posterior aspect of the superior mesenteric vessels to the spine. In this manner the *mesentery proper* is formed. The peritoneum is now carried downwards over the posterior abdominal wall into the pelvis, where it may be traced over the pelvic colon, rectum, and bladder,¹ to which it gives coverings, and then on to the anterior abdominal wall, where it becomes continuous with the layer which we left there.

The *two anterior layers* of the great omentum, therefore, proceed upwards to the under surface of the diaphragm, and there separate, the one passing forwards over the anterior portion of its under surface to reach the anterior wall of the abdomen, whilst the other is directed backwards over the posterior part of its under surface to reach the posterior wall of the abdomen. On their way up to the diaphragm these layers enclose the stomach, form the gastro-hepatic omentum, and partially enclose the liver. On the other hand, the *two posterior layers* are directed backwards to the spine, and there separate. In passing back, they enclose the transverse colon, form the transverse meso-colon, and partially enclose the pancreas. The one layer then ascends to become continuous with the layer on the posterior abdominal wall. The other layer passes downwards, doubles upon itself to enclose the small intestine and form the mesentery proper, enters the pelvis, and then reaches the anterior abdominal wall.

A reference to Fig. 136 will show that the peritoneal cavity is arranged in two sacs,—a *large sac* in front and a *smaller sac*

¹ In the female it also gives a covering to the uterus, but the disposition of the peritoneum in the pelvis, both male and female, will be fully described in connection with the pelvic viscera.

situated behind it. The large pouch is the one into which we have opened in opening the cavity of the abdomen. Now it must be clearly understood that these are simply compartments of *one* serous sac, and that they communicate with each other through a narrow channel called the **Foramen of Winslow** (foramen epiploicum). The best way to find the foramen of Winslow is to lay hold of the fundus of the gall-




FIG. 137.—Section through the Peritoneal Cavity at the level of the Foramen of Winslow.

- | | |
|-------------------------|-----------------------------|
| 1. Stomach. | 8. Foramen of Winslow. |
| 2. Aorta. | 9. Portal vein. |
| 3. Parietal peritoneum. | 10. Common bile duct. |
| 4. Spleen. | 11. Hepatic artery. |
| 5. Twelfth D.V. | 12. Ligamentum teres. |
| 6. Right kidney. | 13. Gastro-hepatic omentum. |
| 7. Vena cava. | |

bladder with the left hand, and then pass the forefinger of the right hand backwards along it towards its neck. The finger will slip behind the gastro-hepatic omentum into the foramen.

The foramen of Winslow has the following boundaries:—*in front*, the right free margin of the gastro-hepatic omentum, between the two layers of which are the hepatic artery, the portal vein, the common bile duct, and some nerves; *behind*,

the vena cava inferior, and the right crus of the diaphragm, covered by peritoneum; *below*, the duodenum and hepatic artery; and *above*, the lobus caudatus of the liver.

The lesser bag of the peritoneum extends *downwards* into the omentum, *upwards* to the posterior surface of the Spigelian lobe of the liver and back part of the diaphragm, and *to the left* as far as the spleen. It is closed in the




FIG. 138.—Section at the level of the Umbilicus through the Intervertebral Disc between the third and fourth lumbar vertebræ.

- 1. Small intestine.
- 2. Aorta.
- 3. Ureter.
- 4. Descending colon.

- 5. Spinous process of third L.V.
- 6. Ascending colon.
- 7. Vena cava.
- 8. Mesentery.

following manner:—*in front*, by the two anterior layers of the great omentum, by the stomach, by the gastro-hepatic omentum, and the lobus Spigelii of the liver; *behind*, by the two posterior layers of the great omentum, by the transverse colon, by the transverse meso-colon, and by the layer which ascends on the posterior wall of the abdomen over the pancreas, left kidney, left suprarenal capsule, and diaphragm: on *the left side*, by the spleen and gastro-splenic omentum.

In a favourable subject these points can be made out by dividing the

two anterior layers of the great omentum along the greater curvature of the stomach, and introducing the hand into the lesser sac. The entire extent of the pouch can thus be explored, and its continuity with the greater bag demonstrated, by turning the forefinger to the right and bringing it out through the foramen of Winslow, or by passing the forefinger of the other hand into the foramen of Winslow, and making the two fingers meet behind the gastro-hepatic omentum.

The peritoneal lining of the abdomen must also be traced in the transverse direction at different levels. Fig. 137 gives a diagrammatic view of the manner in which it is arranged at the level of the foramen of Winslow or the twelfth dorsal vertebra. Taking the gastro-hepatic omentum as the starting-point, follow the two layers of which this is composed to the right. They become continuous around the hepatic artery and common bile duct and the portal vein forming the right free border of this omentum and the anterior boundary of the foramen of Winslow. Following them to the left, they separate to enclose the stomach, and then, coming in contact again, they are prolonged to the spleen in the form of the *gastro-splenic omentum*. Here they separate, and the posterior of the two layers is reflected backwards to the anterior surface of the left kidney, so as to form the *right layer* of a fold called the *lienorenal ligament*. Upon the kidney it turns to the right, and is continued over the posterior wall of the abdomen until it reaches the foramen of Winslow, of which it forms the posterior boundary. Here it covers the vena cava inferior, and is then carried onwards over the right kidney on to the lateral and the anterior wall of the abdomen. The anterior layer of the gastro-splenic omentum, which we left at the spleen, turns round this organ so as to give it its serous covering, and, reaching again its inner aspect, it is reflected backwards to the left kidney, forming the *left layer* of the *lienorenal ligament*. Upon the anterior surface of the kidney it turns to the left, and, reaching the wall of the abdomen, is continued round this to become continuous with the layer which we left there. Observe that at this level the peritoneum is borne off the anterior wall of the abdomen by the obliterated umbilical vein, so as to form a distinct fold, called the *falciform ligament* of the liver.

In the diagram which is given to illustrate the continuity of the peritoneum at this level (Fig. 137), the continuity of the lesser and greater bags of the peritoneum through the

foramen of Winslow is seen. The gastro-splenic and the lieno-renal folds which connect the spleen to the stomach and to the left kidney are also exhibited.

Opposite the umbilicus, at the level of the intervertebral disc, between the third and fourth lumbar vertebræ, the peritoneum may be followed in the transverse direction with the greatest ease (Fig. 138). Turn the great omentum with the enclosed transverse colon upwards over the ribs, and, taking the *mesentery proper* as the starting-point, trace its two layers towards the small intestine. They will be observed to be continuous around it. Now follow them backwards to the spine, and here they will be observed to separate—the one turning to the right, and the other to the left over the posterior wall of the abdomen. In the lumbar regions they meet the ascending and descending portions of the colon. These they clothe anteriorly and laterally, as we have already seen, and then they are carried on to the anterior wall of the abdomen, where they become continuous.¹

Peritoneal Ligaments.—In the abdomen proper, the student must specially examine—(1) the gastro-phrenic ligament; (2) the lieno-renal ligament; (3) the phrenico-colic ligament; and (4) the hepatic ligaments.

The *gastro-phrenic ligament* is an insignificant fold which connects the fundus of the stomach with the under surface of the diaphragm. It is placed close to the œsophageal opening, on its left side, and is formed by that layer which ascends over the anterior surface of the fundus of the stomach to reach the diaphragm. It is simply a reduplication of this layer.

It is interesting to note that the stomach is not completely covered by peritoneum. There is a small triangular area situated on its posterior surface immediately below the œsophagus, which is bare, and rests directly upon the left crus of the diaphragm.

The *lieno-renal ligament*, formed of two layers of peritoneum, passes from the visceral face of the spleen to the front surface

¹ As we have previously observed, the ascending and descending portions of the colon may be completely enveloped by peritoneum, and even connected by mesenteries to the posterior wall of the abdomen. Symington states, with good reason, that the frequency of these mesenteries has been much exaggerated by recent writers.

of the left kidney. It is a short fold, and between its two layers the branches of the splenic artery reach the hilum of the spleen (Fig. 137).

The *phrenico-colic ligament* has been already noticed (p. 414).

The *ligaments of the liver* are *five* in number—viz., (1) the ligamentum teres; (2) the falciform ligament; (3) the coronary ligament; (4) the right lateral; and (5) the left lateral ligaments.

The *ligamentum teres* is not a peritoneal ligament, but it is convenient to describe it at the present stage. It is a fibrous cord, in fact the obliterated umbilical vein of the foetus, which extends from the umbilicus upwards and backwards to the anterior part of the longitudinal fissure on the under surface of the liver. It ends by joining the wall of the left terminal branch of the portal vein.

The *falciform ligament* (ligamentum falciforme hepatis) is a double layer of peritoneum of a triangular shape. By its *anterior border* it is attached to the anterior wall of the abdomen, and to the under surface of the diaphragm, whilst by its *posterior border* it is fixed to the upper and anterior surfaces of the liver, so as to mark it off into a right and left lobe. Its *lower border* or *base* is free, and contains between its two peritoneal layers the ligamentum teres. Along the line of its attachment to the liver the two layers of peritoneum which compose it separate—the one spreading over the left lobe and the other over the right lobe. When followed backwards these leave the liver as upper layers of the coronary and lateral ligaments (Fig. 130).

To understand the *coronary ligament* (ligamentum coronarium hepatis) aright, it must be borne in mind that an irregular area on the posterior surface of the right lobe of the liver is devoid of peritoneum, and that this area is in direct apposition with the diaphragm, to which it is connected by some loose areolar tissue. The peritoneum covering the upper surface of the liver is reflected at the upper limit of this bare area directly on to the diaphragm; this reflection constitutes the *upper layer* of the coronary ligament. The *lower layer* of the ligament is formed at the lower limit of the bare area by the reflection of the peritoneum from the under surface of the liver on to the upper part of the right kidney and the vena cava inferior. The two layers, therefore, of the coronary ligament are not in contact with each other, but are separated by a

distance equal to the breadth of the bare surface of the liver (Figs. 152 and 153, pp. 465 and 466).

The *right lateral ligament* (ligamentum triangulare dextrum) will be brought into view by dragging the right lobe of the liver to the left and looking into the interval between the back part of its right surface and the diaphragm. It is a very small free fold, formed by the apposition of the two layers of the coronary ligament at the right extremity of the bare area of the liver (Fig. 152, p. 465).

The *left lateral ligament* (ligamentum triangulare sinistrum) is a much more extensive fold, which passes from the under surface of the diaphragm to the posterior part of the upper surface of the left lobe of the liver. It is triangular in form, and its basal margin is crescentic and free and directed to the left. When the ligament is traced to the right its upper layer is seen to become continuous with the left layer of the falciform ligament, whilst the lower layer becomes continuous with the front layer of the gastro-hepatic omentum (Figs. 152 and 153, pp. 465 and 466).

Peritoneal Omenta.—These are three in number—viz., the great omentum, the small omentum, and the gastro-splenic omentum.

The *great omentum* (omentum majus) is as a rule by far the largest free fold of peritoneum in the abdomen. It is formed by the two layers which invest the stomach and first part of the duodenum passing downwards for a variable distance and then being folded backwards upon themselves to gain the transverse colon. In the adult, especially towards its lower free margin, the four layers have become blended, so that it is impossible to separate them. The cavity of the lesser peritoneal bag is carried downwards into it. In obese people the whole structure becomes loaded with fat.

The *small or gastro-hepatic omentum* (omentum minus), formed of two layers, leaves the lesser curvature of the stomach and the first part of the duodenum, and proceeds upwards as a free fold towards the liver. Above it is attached along the transverse fissure of the liver, the posterior part of the longitudinal fissure of the liver (*i.e.*, that part which contains the obliterated ductus venosus) (Fig. 152), and also to the diaphragm in the immediate vicinity of the oesophagus. It presents a right free margin, which extends from the trans-

verse fissure of the liver to the duodenum, and forms the anterior boundary of the foramen of Winslow. Over the greater part of its extent it is very thin; the two layers are fused, and often it is fenestrated. The two layers, however, become evident along its lines of attachment, and also in the portion adjoining its right free edge.

The *gastro-splenic omentum*, composed of two peritoneal layers continuous with the two anterior layers of the great omentum, forms a short fold, which connects the fundus of the stomach with the gastric surface of the spleen immediately in front of its hilum. Between its two layers the *vasa brevia* of the splenic artery gain access to the stomach.

Mesenteries of the Great Intestine.—Under ordinary circumstances these are three in number—viz., the meso-appendix, the transverse meso-colon, the pelvic meso-colon.

The *transverse meso-colon* (*mesocolon transversum*) stretches from the transverse colon to the posterior wall of the abdomen, to which it is attached along the anterior border of the pancreas (Fig. 134, p. 408). It is an extensive fold, formed by the two posterior layers of the great omentum after they have enclosed the colon, and containing between them the blood-vessels which go to this portion of the gut. It is longest in the mesial plane of the body, and shortens as it is traced to the right and to the left, until finally at the two flexures which mark the limits of the transverse colon it ceases to exist as a free fold.

The *pelvic meso-colon* varies considerably in different subjects not only in its length and extent, but also in the manner in which its root is attached to the pelvic wall. It is composed of two layers, between which the sigmoid arteries run towards the portion of the colon which they enclose. The root of the pelvic meso-colon is as a rule fixed to the pelvic wall along a line which is bent sharply on itself. This attachment begins on the inner aspect of the left psoas muscle and runs upwards and inwards in the direction of the pelvic brim and along the inner aspect of the external iliac vessels. Having gained a point on the inner side of the left common iliac artery, it turns abruptly downwards over the promontory of the sacrum and along the middle of the anterior surface of that bone as far as the third sacral vertebra. Here the mesentery ends by its two layers separating from each other in such a way as to leave the

posterior surface of the rectum bare. The superior hæmorrhoidal artery runs downwards in the vertical part of the root of the pelvic meso-colon, while the lower sigmoid arteries enter the mesentery through the upper oblique part of the root.

The pelvic meso-colon includes both the sigmoid meso-colon and the meso-rectum of the older descriptions. It should be noted that when the pelvic colon with its mesentery is drawn out from the pelvis and extended



FIG. 139.—The Mesentery in a subject which was hardened by formalin injection. The jejunum and ileum have been removed, and the foldings of the mesentery are displayed.

to its full length, it presents a somewhat pedunculated appearance, and cases of intestinal obstruction through twisting of this loop of colon around its own root or base are not unknown.

Mesentery of the Small Intestine.—The mesentery proper is an extensive fold of peritoneum by which the jejunum and ileum are suspended from the posterior wall of the abdomen.

To obtain a proper view of this fold it is necessary to throw up the great omentum and the transverse colon over the lower margin of the chest. It is attached along an oblique line, which extends from the left side of the body of the second lumbar vertebra downwards, and to the right into the right iliac fossa (Fig. 129, p. 399). The portion of the mesentery immediately adjoining this attachment is very thick and is called the "root" of the mesentery. As this is traced downwards it will be seen to cross obliquely the third part of the duodenum, the aorta, the vena cava, and the right psoas muscle. The "root" of the mesentery is thus, comparatively speaking, narrow (about six inches), but, as the fold approaches the coils of the small intestine, it widens out enormously, so that when it reaches the gut its width equals the length of the jejunum and ileum. This great width is not at first apparent, because the mesentery is thrown into folds like a goffered frill (Fig. 139). The coiled condition of the gut is due to this arrangement. The mesentery is thus markedly fan-shaped, and its length at its longest part is about six inches.

The two layers of the mesentery are not in apposition with each other. They are separated by a variable amount of fat, and also certain important structures which lie between them. These are (1) the superior mesenteric vessels and their branches to the jejunum and ileum; (2) the superior mesenteric nerves; (3) great numbers of lymphatic glands and lacteal vessels; (4) the gut itself.

Occasional Peritoneal Fossæ.—It is necessary to take notice at this stage of certain peritoneal pockets or blind recesses which are occasionally present in different positions on the posterior wall of the abdomen. There are three localities in which these fossæ may be found: (1) in the neighbourhood of the cæcum; (2) in relation to the duodeno-jejunal flexure; and (3) in the root of the pelvic meso-colon.

There are several forms of fossæ in the region of the cæcum. By raising up the cæcum a fossa may sometimes be seen to ascend either behind the inner or outer part of the lower portion of the ascending colon. Peritoneal pouches of this kind are termed *retrocolic fossa*, and within such recesses when they exist the vermiform appendix frequently lies. Another form of fossa in this neighbourhood is where a small peritoneal recess is found on the inner side of the great intestine immediately above or immediately below the ileo-cæcal junction. The term *ileo-colic* is applied to the former, and *ileo-cæcal* to the latter.

The region immediately to the left of the duodeno-jejunal flexure must also be explored for occasional peritoneal fossæ. One in relation to the summit of the flexure, which looks downwards and is termed the *superior duodenal fossa*, was present in 50 per cent of the subjects examined by Jonnesco;

another, a little lower down and with its mouth directed upwards, lies on the left side of the terminal part of the duodenum, and is called the *inferior duodenal fossa*. It is found in 75 per cent of subjects dissected (Jonnescos).

A third peritoneal pouch in this neighbourhood, termed the *para-duodenal fossa*, is sometimes formed by a small fold of peritoneum being raised from the back wall of the abdomen by the inferior mesenteric vein. It lies a little to the left of the terminal part of the duodenum.

Other varieties of peritoneal fossæ in this region are described.

The *fossa intersigmoidea* is not often seen in the adult. When present it will be found by raising the pelvic loop of the great intestine. Its mouth lies about the middle of the under surface of the root of the pelvic meso-colon.

Dissection.—The structures which are included between the two layers of the mesentery proper and between the two layers of the transverse meso-colon must now be dissected. The great omentum being thrown well up over the lower margin of the chest, remove the entire anterior layer of the mesentery from its root down to where it is attached to the gut. Begin at the upper end of the jejunum at the left side of the second lumbar vertebra, and gradually travel downwards to the lower end of the ileum, stripping off the peritoneum and cleaning the structures exposed. To display all the branches of the superior mesenteric artery it is necessary to remove also the inferior layer of the transverse meso-colon and the peritoneum which proceeds on the posterior wall of the abdomen towards the cæcum and ascending colon. Follow the main trunk of the superior mesenteric artery upwards to its origin from the aorta, by raising the lower border of the pancreas.

Superior Mesenteric Artery (arteria mesenterica superior).

→ The superior mesenteric artery springs from the front of the abdominal aorta about a quarter of an inch below the coeliac axis. At its origin it is covered by the neck of the pancreas, and crossed by the splenic vein. Emerging from under cover of the pancreatic neck it proceeds downwards in front of a portion of the head of the pancreas, crosses the third part of the duodenum, close to the duodeno-jejunal flexure, and then enters the mesentery proper. Between the two layers of the mesentery the artery is placed at a short distance from the mesenteric root, and pursues a slightly curved course towards the right iliac fossa, where it ends by anastomosing with one of its own branches. The convexity of the curve which it describes is directed to the left, and the concavity to the right. It is accompanied by the superior mesenteric vein, which lies upon its right side, and by the superior mesenteric plexus of nerves which surrounds it closely.

The following branches proceed from the superior mesenteric artery :—

1. Inferior pancreatico-duodenal.
2. Branches to the jejunum
and ileum. } Rami intestini tenuis.

3. Branches to the great intestine. $\left\{ \begin{array}{l} \text{Ileo-colic.} \\ \text{Right colic.} \\ \text{Middle colic.} \end{array} \right.$

The *inferior pancreatico-duodenal* (arteria pancreatico-




FIG. 140.—Dissection of the Superior Mesenteric Artery.

duodenalis inferior) takes origin from the upper part of the superior mesenteric artery and passes upwards and to the right behind the head of the pancreas. It gives branches both to the duodenum and the pancreas and anastomoses with the superior pancreatico-duodenal artery.

The *rami intestini tenuis* (arteriæ intestinales) spring from the convexity or left side of the superior mesenteric, and proceed obliquely downwards and to the left, between the layers of the mesentery, to supply the jejunum and ileum. They are very numerous, from twelve to fifteen, or even more, in number, and, by their mutual inosculations, they form a very remarkable series of arches before they finally reach the bowel. At first they run parallel to one another, but soon they divide into two branches, each of which joins its neighbour, and in this way a succession of arterial arcades is formed. From these smaller vessels proceed, which divide and unite in a similar manner to form a second series of arches, and so on, until three, four, or perhaps even five tiers of arterial arcades are produced. From the lowest arches a multitude of small branches pass directly to the wall of the intestine. Here, along the line of mesenteric attachment, they divide, and the minute twigs thus derived pass transversely round the gut so as to encircle it. At first they lie subjacent to the peritoneal coat, but soon they seek a deeper plane in the wall of the intestine, and ultimately reach the submucous coat.

The *colic branches* (arteriæ colicæ) spring from the concavity or right side of the superior mesenteric artery.

The *ileo-colic artery* (arteria ileo-colica), the lowest of the three branches which go to the great intestine, proceeds downwards and outwards towards the right iliac fossa. It is placed behind the parietal peritoneum, and divides into an ascending and a descending or ileo-cæcal branch. The *ascending branch* turns upwards, inosculates with a branch of the right colic, and from the arterial arch thus formed branches are given to the ascending colon. The *descending branch*, sometimes called the *ileo-cæcal artery*, proceeds to the upper part of the ileo-cæcal junction and sends branches in different directions. Two, termed the *anterior* and *posterior cæcal arteries*, pass respectively to the front and back of the cæcum; one, a long slender vessel, the *artery to the appendix*, runs downwards behind the terminal part of the ileum and enters the meso-appendix for the supply of the vermiform appendix; whilst a fourth, the *ileal artery*, turns to the left along the ileum, and forms a loop with the termination of the superior mesenteric trunk.

The *right colic artery* (arteria colica dextra) frequently arises in common with the ileo-colic. Escaping from the root of the mesentery it takes a horizontal course to the right, behind the parietal peritoneum on the back wall of the abdomen, and divides into two branches, a superior and an inferior. The *superior branch* ascends between the two layers of the transverse meso-colon to inosculate with the *middle colic*; whilst the *inferior branch* joins the ascending part of the ileo-colic. From the convexity of these arches twigs proceed to the colon.

The *middle colic artery* (arteria colica media) is the highest of the three branches which spring from the concavity of the superior mesenteric. It passes between the two layers of the transverse meso-colon, and divides into a right and a left branch. The *right branch* joins the superior part of the right colic, whilst the *left branch* inosculates with the ascending part of the *left colic artery*, which is derived from the inferior mesenteric. Arterial arcades are thus formed in the transverse meso-colon, from which branches proceed for the supply of the transverse colon.

Superior Mesenteric Vein (vena mesenterica superior).—

This large vein lies to the right of the superior mesenteric artery, and receives tributaries, which come from those parts of the intestinal canal which are supplied by branches from the superior mesenteric artery, and also the right gastro-epiploic vein from the great curvature of the stomach. Leaving the mesentery, it passes upwards in front of the duodenum, and then disappears under cover of the neck of the pancreas. Here it unites with the splenic vein to form the vena portæ.

Superior Mesenteric Nervous Plexus (plexus mesentericus superior).—This is a dense plexus of sympathetic twigs, which surrounds the superior mesenteric artery like a sheath. From it filaments are prolonged to the gut along the various branches of the artery. As the nerves approach the bowel, some of the twigs leave the vessels and effect a series of communications with each other in the intervals between the arteries.

The superior mesenteric plexus is an offshoot from the *solar plexus*, and it distributes twigs to the jejunum, ileum, and to the right half of the great intestine.

Mesenteric Lymphatic Glands (lymphoglandulæ mesen-

tericæ).—These are very numerous, indeed considerably over a hundred in number. In health they rarely attain a size greater than that of a small bean or a pea, and they are scattered between the two layers of the mesentery. The larger glands lie along the superior mesenteric artery, whilst the others are placed in the intervals between its branches. It should be noted that they are most numerous opposite the jejunum, and that the mesentery in the immediate vicinity of the gut is free from them.

A few lymphatic glands will also be noticed in connection with the great intestine.

The *lacteal vessels* enter the mesentery from the walls of the intestine in enormous numbers. As they proceed upwards they pass through the succession of glands which they meet, and greatly reduced in numbers, although considerably enlarged in calibre, they usually terminate near the origin of the superior mesenteric artery in one or perhaps more large trunks which pour their contents into the receptaculum chyli of the thoracic duct.

Dissection.—The coils of the small intestine must now be pulled over to the right side of the body, and the peritoneum carefully removed by the fingers from the lower part of the aorta and the left side of the spine and psoas muscle. The inferior mesenteric artery is thus exposed, and its branches can be followed to their distribution. The *ureter* and the *inferior mesenteric vein* will be seen lying upon the psoas muscle.

Inferior Mesenteric Artery (arteria mesenterica inferior).

—The inferior mesenteric artery, considerably smaller than the superior mesenteric, springs from the left side of the abdominal aorta, about an inch and a half above its terminal bifurcation, and descends with a slight inclination to the left, towards the left iliac fossa. At first it is applied to the left side of the aorta, to which it is bound by peritoneum; it then crosses the left common iliac artery and enters the pelvis, where it receives the name of *superior hæmorrhoidal*. Before leaving the abdomen proper it gives off the left colic and the sigmoid branches.

The *left colic artery* (arteria colica sinistra) proceeds to the left, over the left kidney, and divides into two branches, of which one ascends in the transverse meso-colon to anastomose with the middle colic, whilst the other descends behind the peritoneum lining the posterior wall of the abdomen

to unite with the superior sigmoid artery. From the arches thus formed twigs are supplied to the transverse and the descending colon.

The sigmoid arteries (arteriæ sigmoideæ), two or three in




FIG. 141.—Dissection of the Inferior Mesenteric Artery.

number, are distributed to the lower part of the descending colon, the iliac colon and the pelvic colon. The highest branch enters the left iliac fossa behind the parietal peritoneum and sends a branch upwards to form an arch with the descending branch of the left colic, and another down-

wards, which ultimately enters the pelvic meso-colon and joins the other sigmoid branches. The lower sigmoid arteries pass into the pelvic meso-colon, and there form a series of arcades (varying in number according to the length of this mesentery), from which the twigs for the supply of the pelvic colon are given off.

The *superior hæmorrhoidal artery* will be followed out in the dissection of the pelvis.

Inferior Mesenteric Vein (*vena mesenterica inferior*).—This vein receives tributaries corresponding with the branches of the inferior mesenteric artery. It passes upwards upon the psoas muscle under cover of the peritoneum, to the left of, and at some distance from, the artery, and, disappearing behind the pancreas, it ends in the splenic vein.

Inferior Mesenteric Plexus of Nerves (*plexus mesentericus inferior*).—This is an offshoot from the left side of the aortic plexus. It closely surrounds the artery, and sends twigs along the branches of the vessel to supply the left half of the great intestine.

Dissection.—If the peritoneum has been carefully stripped off the lower part of the aorta, there will be little difficulty in recognising and following out the delicate nerves which form the aortic plexus. Raise the third part of the duodenum from the surface of the aorta, and trace these nerve twigs upwards.

Aortic Plexus of Nerves (*plexus aorticus abdominalis*).—The aortic plexus is placed upon the aorta between the origins of the two mesenteric arteries. It is more strongly marked upon the sides of the artery than in front of it. Superiorly it will be found to be continuous with the solar and renal plexuses, whilst inferiorly it sends numerous large branches downwards in front of the common iliac arteries to join the hypogastric plexus—a plexus which is situated in front of the fifth lumbar vertebra, and which will be afterwards dissected. Upon each side, the aortic plexus will be observed to be reinforced by several small twigs from the gangliated cord of the sympathetic. The *inferior mesenteric plexus* accompanying the artery of that name, and the *spermatic* (or *ovarian*) *plexus* of nerves which accompanies the spermatic (or ovarian) artery, are offsets from it.

Removal of the Intestines.—The jejunum, ileum, cæcum, and colon may now be removed from the abdominal cavity. Apply two ligatures

~~around the upper end of the jejunum, about an inch or so below the duodeno-jejunal flexure, and divide the gut between them; then place two ligatures around the middle of the pelvic colon, and divide it in like manner. The entire intestinal canal, with the exception of the duodenum, the lower part of the pelvic colon, and the rectum, can now be taken away by carefully severing the blood-vessels and peritoneal folds which hold it in position. In cutting through the two layers of the great omentum, which extend from the transverse colon to the stomach, keep the knife close to the gut so as to avoid injury to the vessels in relation to the greater curvature of the stomach.~~

As soon as the intestines are detached they should be taken to the sink and the ligatures removed. The small intestine should be separated from the great intestine by dividing the ileum about six inches from the point where it enters the cæcum, and, the remains of the mesentery having been taken away from the small intestine by means of the scissors, both should be thoroughly cleaned out by allowing the water from the tap to run freely through them.

The coats of the small intestine should be dissected under water. Take a few inches of the intestine from the upper end of the jejunum, and, having opened it up with the scissors along the mesenteric line of attachment, pin it out, with its mucous surface downwards, upon the bottom of a cork-lined tray, which has been previously filled with clean water. The jejunum is chosen because its wall is thicker than the ileum, and consequently more easily dissected. Carefully remove the thin serous coat in order that the subjacent layer of longitudinal muscular fibres may be studied. Then turn the specimen round and pin it down with its mucous surface uppermost. Now remove the mucous membrane with the subjacent flocculent submucous coat with the scissors in one layer. The circular muscular fasciculi will come into view.

Coats of the Small Intestine.—The small intestine has five coats or strata entering into the formation of its walls, viz. :—

- | | |
|---------------|---------------|
| 1. Serous. | 4. Submucous. |
| 2. Subserous. | 5. Mucous. |
| 3. Muscular. | |

The *serous coating* of the jejunum and ileum is complete, except along the line of the mesenteric attachment. It is exceedingly thin—much thinner than the layers of the mesentery, with which it is continuous. Unless great care be taken in stripping it off, some of the subjacent muscular fibres will be taken away with it. The *subserous coat* is a scarcely appreciable amount of areolar tissue which inter-venes between the peritoneum and the muscular coat. It need not be taken into account in this dissection. The *muscular coat* is composed of involuntary, non-striated muscular fibres. These are disposed in two layers, viz., an *external stratum* of longitudinal fibres, and an *internal stratum* of circular fibres. Of these the circular layer is the thicker

and more distinct of the two. The external longitudinal fibres are spread out in the form of a thin continuous layer all round the circumference of the gut. In that part of the wall opposite the mesenteric attachment the fibres are more thickly disposed than elsewhere. The *submucous coat* is composed of loose areolar tissue which binds the muscular to the mucous coat. It is more firmly connected with the latter. The *mucous coat* must be examined throughout the whole length of the jejunum and ileum.

Dissection.—The student has noticed that externally no distinction can be drawn between the jejunum and ileum, with this one exception, viz., that as the tube descends it diminishes slightly in its calibre and in the thickness of its walls. It is necessary, therefore, that he should open it up along its whole length, with the view of determining what differences exist internally. Before doing this, about twelve inches of the upper part of the jejunum should be removed and inflated with air. It should then be hung up to dry in order that the folds of mucous membrane, called *valvulae conniventes*, may be studied in their continuity. The best way to open the remainder of the intestine is to tie a ligature around the lower cut end of the ileum, and fill the gut as full as possible with water. The scissors can now be easily carried along the *line of the mesenteric attachment*, and the intestine slit open in its entire length. The intestine can be laid open with much greater ease if a piece of costal cartilage be impaled upon that blade of the scissors which is introduced into the gut.

Mucous Membrane of the Small Intestine.—The *valvulae conniventes* (plicae circulares) are the most conspicuous objects on the inner wall of the small intestine. These are folds of the mucous membrane placed more or less transversely to the long axis of the gut. Note particularly that they are *permanent folds*, and that ~~no amount of stretching or distension~~ of the walls will cause their obliteration. On careful study of the dried specimen three main varieties of *valvulae conniventes* may be recognised. The great majority are in the form of *crescentic folds*, which extend for a *variable distance* round the wall of the gut; others form complete *rings* around the interior of the intestine; whilst the third variety, and usually the least numerous, are *arranged in a spiral manner*, and take from one to three spiral turns around the wall of the gut (Brooks and Kazzander). ~~Each fold consists of two layers of mucous membrane, with a little intervening areolar tissue derived from the submucous coat.~~ The other coats of the intestine take no part in the formation of the *valvulae conniventes*. In the upper part of the jejunum the *valvulae conniventes* are strongly developed, and placed so closely together

that the intervals between them are hardly greater than the thickness of one of the folds. As we follow them down, however, they gradually diminish in numbers, become more widely separated, more oblique in their direction, and not nearly so prominent. Approaching the middle of the ileum, they become exceedingly sparse and far between, and a little beyond this they usually disappear altogether.

The chief function of the valvulae conniventes is to increase the absorbing and secreting surface of the small intestine.

2 Another peculiarity characteristic of the mucous lining of the small intestine is the presence of villi (villi intestinales). These are minute projections of the mucous membrane, varying in length from about the $\frac{3}{16}$ th to $\frac{1}{8}$ th of an inch. They occur in enormous numbers over the entire extent of the inner surface of the gut, not only upon the valvulae conniventes, but also in the intervals between them, and they give to the mucous membrane a velvety or fleecy appearance.

To obtain a proper view of these minute villous processes it is necessary to float out a portion of the small intestine in water, after it has been carefully cleansed from adhering mucus, and examine it with an ordinary pocket-lens. If a portion of the upper end of the jejunum be placed side by side with a portion of the lower part of the ileum, and inspected in this manner, the student will readily detect that the villi are, if anything, larger, and that they are decidedly more numerous, in the jejunum than in the ileum. They diminish gradually in number and in size as we pass down the small intestine.


3 Peyer's patches and solitary glands must also be looked for. Frequently they are difficult to find, but by holding the bowel up to the light they can generally be detected. In our examination of the Peyer's patches it is better to begin at the lower end of the ileum and pass upwards.

A Peyer's patch (noduli lymphatici aggregati) consists of a large number of lymphoid follicles grouped together so as to present to the eye a patch of an elongated, oblong figure. The patches are placed upon that aspect of the gut which is opposite to the line of the mesenteric attachment, and the long axis of each corresponds in its direction with that of the gut itself.

In the lower part of the ileum the patches may present a length of one, two, or even four inches, and a breadth of about half an inch, but, as we follow them up the tube into the jejunum, they become much smaller and not nearly so numerous. The total number varies much, but the average number may be stated to be about thirty. They are more numerous in the

Intermediate form

Solitary gland



Peyer's patch

Solitary glands

FIG. 142.—Peyer's Patch and Solitary Glands from the intestine of a child of two years old. (Birmingham.)

young, and not so abundant nor so distinctly marked out in later periods of life. Indeed, in very old individuals they may disappear almost entirely.

The *solitary glands* (*noduli lymphatici solitarii*) are isolated lymphoid follicles, scattered everywhere over the mucous membrane of the small intestine. They are minute, rounded or ovoid, opaque white bodies, about the size of a millet seed, and they usually cause a slight bulging of the mucous membrane at the points where they occur.

The *valvulae conniventes*, the villi, and *Peyer's patches* are the only special peculiarities of the mucous membrane of the jejunum and ileum which are visible to the naked eye, and from what has been said regarding them the dissector will understand that although they are not arranged in such a way as mark off by a clear line of demarcation the jejunum

from the ileum, they are sufficient to enable him to distinguish between characteristic portions of each—i.e., between portions taken at some distance from the arbitrary line of division. The following are the essential points of difference which would guide him in deciding which is ileum and which jejunum:—

JEJUNUM.

ILEUM.

Valvule Conniventes.

Numerous and well marked.

Few in number and poorly developed, and, in its lower part, absent altogether.

Villi.

Numerous and large.

Not so numerous and not so large.

Peyer's Patches.

Few in number, small in size, and, as a rule, nearly circular in outline.

More numerous, of large size, and oblong in form.

Dissection.—Ligature the great intestine about four inches above the entrance of the ileum, and divide the gut above this point. The nozzle of the bellows should now be introduced into the attached portion of ileum, and the cæcum inflated until its walls are tense. This portion of the intestine should then be hung up to dry. Next slit open the colon in the same manner as the small intestine, and examine its inner surface.

Great Intestine.—Transverse and oblique ridges or folds, corresponding to the constrictions which separate the sacculi, are everywhere apparent on the inner surface of the large intestine. If the longitudinal bands of muscular fibres be removed or divided at short intervals, and the gut stretched, both sacculi and constrictions disappear, and the wall of the bowel becomes uniform. The mucous membrane of the great intestine is absolutely destitute of villi, but solitary glands are present in considerable numbers. If the mucous surface be examined with a lens, its surface will be seen to be studded over with the round mouths of tubular glands, which are embedded in the mucous membrane (*crypts of Lieberkuhn*). The same glands are present in the mucous membrane of the small intestine, but they are not so large.

Dissection.—The coats of the large intestine must be dissected in the same manner as in the case of the small intestine.

Coats of the Large Intestine.—In connection with the serous coat, the student has already taken notice of the *appendices epiploicae*. The external longitudinal muscular fibres have also been observed to be disposed in three flat bands. These begin on the cæcum at the base of the vermiform process. From this they diverge, so as to take up positions on different

aspects of the gut. They are placed as follows:—(1) One in relation to the attached surface; (2) the second upon the anterior aspect; (3) and the third along the inner aspect of the gut, but, in the case of the transverse colon, this band is in relation to the inferior aspect of the tube. The *internal circular* muscular fibres are most distinct in the constrictions between the sacculi, but constitute a thin uniform layer over the entire extent of the gut. The *submucous coat* is in no




FIG. 143.—Cæcum which has been distended with air and dried, and then opened to show Ileo-Cæcal Opening and Valve (Birmingham).

respect different from the corresponding coat in the small intestine.

Dissection.—When the distended cæcum is dry, the ileo-cæcal valve should be examined. This can best be done by removing the outer wall of the cæcum with a pair of scissors. A window is thus made into the gut, through which the opening of the ileum into the cæcum can be seen.

Ileo-cæcal Valve (valvula coli).—The ileo-cæcal aperture is a narrow transverse slit placed on the inner aspect of the gut. The aperture is narrow and pointed behind, but more open and wider in front. It is guarded by a valve which consists of two crescentic segments or folds. The upper and smaller segment is placed horizontally, whilst the lower one is perpendicular. At the extremities of the aperture these

folds unite, and are prolonged round the inner surface of the wall of the great intestine in the form of two ridges, which are termed the *frenula* or *retinacula of the valve*. The point of intersection of the Poupart and intertubercular planes marks on the surface of the abdomen the position of the ileo-cæcal opening. A short distance below the ileo-cæcal opening will be seen the mouth of the vermiform appendix.

The above description relates to the ileo-cæcal opening as seen in a distended and dried specimen. In subjects in which the viscera have been hardened *in situ* by formalin the ileum presents the appearance of being




FIG. 144.—Ileo-Cæcal Opening and Valve from a subject hardened by formalin injection. (Birmingham).

telescoped into the cæcum in such a manner as to produce the upper and lower folds which bound the slit-like ileo-cæcal opening and form the valve-flaps. This is particularly noticeable in the cæcum of the child.

The peritoneum and the longitudinal muscular bands are in no way involved in the infoldings which form the valve-flaps; but the other constituents of the gut-wall (*viz.*, the mucous membrane, the submucous coat, and the circular muscular fibres) take part in their formation. Villi are present on the ileal but not on the cæcal aspect of each valve-flap.

The function of this valve is obvious. It is so arranged that the free passage of materials from the ileum into the cæcum is in no way impeded; but when the cæcum becomes distended, and there is consequently a tendency to regurgitation, the frenula of the valve are put upon the stretch, and the free borders of the segments brought into firm contact. In this way reflux of the contents of the cæcum into the ileum is prevented, although it is well to note that the obliquity of the entrance of the ileum into the cæcum also exercises a very important influence in the same direction.

Dissection.—The celiac axis, the artery which supplies blood to the stomach, liver, duodenum, spleen, and pancreas, should now be dissected. Pull the stomach downwards, and tear through the two layers of peritoneum

which form the gastro-hepatic omentum. The artery will be found by dividing the layer of peritoneum which forms the posterior wall of the lesser sac along the upper border of the pancreas. This dissection will be facilitated if the liver is first raised and then fixed in this position, by stitching it to the lower margin of the thorax.

Cœliac Axis (arteria cœliaca).—The cœliac axis is a short, wide vessel, which springs from the front of the aorta, between the two crura of the diaphragm, opposite and in immediate relation to the upper margin of the pancreas. It is directed




FIG. 145.—The Cœliac Axis System of Vessels.

horizontally forwards, and after a course of little more than half an inch divides into three large branches, viz.:—(1) the coronary; (2) the hepatic; and (3) the splenic, which radiate from each other like the spokes of a wheel. The cœliac axis is surrounded by a thick, matted plexus of nerves, called the cœliac plexus, which sends numerous nerve twigs with the three branches which spring from the axis. The cœliac plexus must be left undisturbed, and in following the coronary, hepatic, and splenic arteries the nerves which accompany them must be carefully preserved.

Coronary Artery (*arteria gastrica sinistra*).—This, the smallest of the three branches of the *coeliac axis*, proceeds upwards and to the left, behind the lesser sac of peritoneum, to the *oesophageal opening of the stomach*. Here it changes its direction, enters between the two layers of the *gastro-hepatic omentum*, where this is attached to the diaphragm, and runs from above downwards and to the right along the lesser curvature of the stomach. Near the pylorus it ends by anastomosing with the *pyloric branch* of the hepatic artery.

As the coronary artery ascends on the posterior wall of the abdomen it raises the posterior layer of the lesser sac in the form of a more or less distinct fold, which slightly constricts the sac in this situation.

The branches of the coronary artery are:—

1. *Oesophageal*.
2. *Gastric*.

The *oesophageal arteries* (*rami oesophagei*) spring from the coronary at the point where it reaches the stomach. They pass upwards upon the posterior aspect of the gullet, through the *oesophageal opening of the diaphragm*, and anastomose with the *oesophageal branches of the thoracic aorta*.

The *gastric branches* take origin from the coronary as it runs along the lesser curvature of the stomach, and are distributed to both surfaces of this viscus. —

Coronary Vein (*vena coronaria ventriculi*).—This vein lies by the side of the artery of the same name. It passes from right to left along the lesser curvature of the stomach. Reaching the *oesophagus* it turns to the right and joins the portal vein. —

Hepatic Artery (*arteria hepatica*).—The hepatic artery, intermediate in size between the coronary and splenic, at first takes a transverse course to the right along the upper border of the pancreas. At the pyloric end of the stomach it changes its direction, and, turning forwards below the foramen of Winslow, ascends between the two layers of the *gastro-hepatic omentum*. Near the transverse fissure of the liver it ends by dividing into *right* and *left hepatic arteries*. The hepatic artery is accompanied by numerous large nerve twigs derived from the *coeliac plexus*, and, as it passes upwards to the liver, it is in close relationship with the bile duct and the portal vein. The duct lies upon the right side of the artery, and the vein lies behind both. (Fig. 137, p. 421, and Fig. 151, p. 464.)

As the hepatic artery runs behind the lesser sac of the peritoneum and then turns forwards to reach the gastro-hepatic omentum, it (like the coronary artery) raises a fold of peritoneum which has the appearance of constricting the lesser sac.

The following are the branches of the hepatic artery :—

1. Pyloric.
2. Gastro-duodenal. { Superior pancreatico-duodenal.
Right gastro-epiploic.
3. Hepatic. { Right. { Cystic.
Left.

The pyloric (arteria gastrica dextra) is a small artery which springs from the hepatic at the pylorus, and then runs from right to left along the lesser curvature of the stomach between the two layers of the gastro-hepatic omentum. It ends by inosculating with the coronary.

The gastro-duodenal (arteria gastro-duodenalis) arises close to the pyloric artery, and is directed downwards behind the first part of the duodenum in a groove on the anterior aspect of the pancreas at the junction between the neck and the head of that organ. At the lower border of the duodenum it ends by dividing into the superior pancreatico-duodenal and the right gastro-epiploic.

The superior pancreatico-duodenal (arteria pancreatico-duodenalis superior) proceeds downwards on the head of the pancreas to the interval between it and the duodenum. Here it turns round the border of the pancreas and on the posterior aspect of its head forms an arch with the inferior pancreatico-duodenal branch of the superior mesenteric artery. The superior pancreatico-duodenal artery dispenses branches to both the duodenum and the pancreas.

The right gastro-epiploic (arteria gastro-epiploica dextra) is directed from right to left, along the greater curvature of the stomach, and between the two anterior layers of the great omentum. It gives branches upwards to both surfaces of the stomach, and downwards to the great omentum, and ends by anastomosing with the left gastro-epiploic, a branch of the splenic.

The right and left hepatic arteries, the terminal branches of the hepatic, diverge from each other, and sink into the liver at the two extremities of the transverse fissure. From the right hepatic a small branch called the cystic is given to the gall-bladder. This divides into two twigs, one of which

ramifies in the areolar tissue between the liver and gall-bladder and the other upon the opposite surface of the gall-bladder immediately subjacent to its peritoneal covering.

The *cystic vein* joins the *vena portæ* or its right branch.

Splenic Artery (*arteria lienalis*).—The splenic artery, the largest branch of the *cœliac axis*, takes a wavy or tortuous course behind the lesser sac of the peritoneum to the left side, and ends in front of the left suprarenal capsule and kidney by dividing into five or six branches, which enter the hilum of the spleen.

To obtain a good view of the splenic artery, it is necessary to throw the stomach upwards towards the ribs. The vessel will then be seen to run along the upper border of the pancreas, which somewhat overlaps it. It is accompanied by the splenic vein, which, however, lies at a lower level, and therefore altogether behind the pancreas.

The following are the branches of the splenic artery:—

1. Pancreatic.
2. Gastric. { *Vasa brevia*.
- { Left gastro-epiploic.
3. Splenic.

The *arteriæ pancreaticæ* are small twigs which come off at various points for the supply of the pancreas.

The *pancreatica magna branch* which is commonly described as accompanying the duct from left to right in the substance of the pancreas is not as a rule present.

The *vasa brevia* (*arteriæ gastricæ breves*) are five or six small arteries, of which some arise directly from the splenic, whilst others take origin from its terminal branches. They run towards the stomach between the two layers of the gastro-splenic omentum, and are distributed to the cardiac end of this viscus, anastomosing with the coronary and left gastro-epiploic arteries.

The *left gastro-epiploic* (*arteria gastro-epiploica sinistra*) takes origin from the splenic near the spleen, and is directed from left to right, along the greater curvature of the stomach, between the two anterior layers of the great omentum. It gives branches which ascend to supply both aspects of the stomach, and others which descend into the great omentum, and it ends by anastomosing with the right gastro-epiploic artery.

The *splenic or terminal branches* of the splenic artery reach

the spleen by passing between the two layers of the lieno-renal ligament. The *vasa brevia* and the *left gastro-epiploic artery* take the same route to gain the interval between the two layers of the gastro-splenic omentum.

From the above description of the branches of the cœliac axis it will be seen that the stomach is remarkably rich in blood-vessels. *Two* proceed from *left to right*—viz., the *coronary* along the lesser curvature, and the *left gastro-epiploic* along the greater curvature; *two*, both branches of the hepatic, are directed from *right to left*—viz., the *pyloric*, in relation to the lesser curvature; and the *right gastro-epiploic*, in relation to the greater curvature. The arterial circle is completed on the left by the *vasa brevia*, which connect the coronary artery with the *left gastro-epiploic*.

Splenic Vein (vena lienalis).—This large vein, formed by the union of the veins which issue from the spleen, runs from left to right behind the pancreas, and at a lower level than the artery of the same name. After crossing the aorta and the root of the superior mesenteric artery, it ends by joining the superior mesenteric vein to form the *vena portæ*. In its course between the spleen and the *vena portæ* it receives the following tributaries:—(1) veins corresponding to the *vasa brevia*; (2) the left gastro-epiploic vein; (3) pancreatic veins; (4) the inferior mesenteric vein.

Vena Portæ.—This is a remarkable vessel. It arises after the manner of a vein, by gathering, by means of its rootlets, the blood from the capillaries of the entire abdominal portion of the alimentary canal (with the exception of a part of the blood from the anal canal), the spleen, pancreas, and gall-bladder, whilst it ends in the liver after the manner of an artery, by pouring its blood into the hepatic capillaries. The blood which flows in the portal vein, therefore, passes through two series of capillaries before it is returned to the heart—viz., (1) the capillaries of the organs from which it is derived; (2) the hepatic capillaries.

The *portal vein* is formed between the neck and the head of the pancreas, by the union of the splenic and superior mesenteric veins. From this it ascends, with an inclination to the right, and ends near the right extremity of the transverse fissure of the liver by dividing into a *right* and *left branch*, one for each lobe of this organ. After emerging from under cover of the neck of the pancreas, it lies first behind the first part of the duodenum, and then between the two layers of the gastro-hepatic omentum, close to its right free

margin. In the latter situation it is placed behind the hepatic artery and the bile duct, and is accompanied by the hepatic nerves and lymphatics. The vena portæ receives the coronary, pyloric, and cystic veins. The last-named vein, however, may join its right branch.

The branches of the portal venous system are devoid of valves. This is a great predisposing cause in the production of hæmorrhoids.

Dissection.—The connections of the duodenum should next be studied, and in cases where the abdominal viscera have not been hardened *in situ* by formalin the dissector will find it advantageous in doing this to partially inflate with air both it and the stomach.

Duodenum.—The duodenum, or first part of the small intestine, is wider and more fixed in its position than either the jejunum or ileum. It is ten to twelve inches in length, and extends from the pylorus of the stomach to the left side of the body of the second lumbar vertebra. Here it bends forwards on itself in the form of the duodeno-jejunal flexure and becomes continuous with the jejunum (Fig. 146). The duodenum describes upon the front of the vertebral column a U-shaped curve, the concavity of which is directed upwards and to the left, and within which is placed the head of the pancreas. For convenience in description it is divided into a first part, a second part, and a third part.

The first part of the duodenum (pars superior) is two inches in length, and is contained in the epigastric region. For about one inch from the pylorus it is enveloped by the same two layers of peritoneum which invest the stomach, and consequently enjoys a limited degree of movement; in its terminal part it is only covered on its anterior surface by the peritoneum. Its position and relations are dependent upon the degree of distension of the stomach. When that viscus is empty, and the pylorus, in consequence, lies close to the mesial plane, the first part of the duodenum passes backwards and to the right, with a slight inclination upwards, until it reaches the neck of the gall-bladder. Here it ends by bending suddenly downwards into the second part. Under these circumstances the first part of the duodenum lies in close apposition with the lobus quadratus of the liver. When the stomach, on the other hand, is distended, the pylorus comes into relation with the lobus quadratus, and the first part of

the duodenum is somewhat shortened, proceeds straight backwards, and occupies a depression on the under surface of the right lobe of the liver, behind and to the right of the transverse fissure. The relations of the first part of the duodenum are as follows: above and in front, the under surface of the liver; below, the pancreas; behind, the common bile-duct, the gastro-duodenal artery, and the portal vein.




FIG. 146.—Duodenum, Pancreas, and Kidneys. (From the model by His.)

S.C. Supracapsular.
S. Spleen.
R.K. Right kidney.
L.K. Left kidney.
P. Pancreas.
D. Duodenum.

H.F. Hepatic flexure of the colon.
S.F. Splenic flexure of the colon.
M. Mesentery.
S.M. Superior mesenteric vessels.
J. Jejunum.

→ The *second part of the duodenum* (pars descendens) is usually about from three to four inches in length, and takes a downward course from the under surface of the liver. Placed at its commencement in the epigastric region, it descends into the umbilical region, lying close to the right Poupart plane. Reaching the level of the third lumbar

vertebra, it turns across the spine and enters upon the third stage of its course. The second stage of the duodenum is immovably fixed in its position. It is covered by peritoneum on its anterior surface only, and is crossed by the commencement of the transverse colon, which, in this part of its course, does not as a rule possess a mesentery (Fig. 146). *Behind*, it rests upon the vena cava and presents a variable relation to the renal vessels and the anterior surface of the right kidney in the neighbourhood of the hilum. *To the right*, is the hepatic flexure of the colon; and *to the left*, is the head of the pancreas, which is moulded upon the inner side of this part of the duodenum.

→ The common bile-duct and the pancreatic duct open into the inner and back aspect of the second part of the duodenum a little below its middle.

→ The third part of the duodenum (*pars ascendens*) is somewhat longer than the second part, and may be regarded as being composed of two portions, viz., an oblique and a vertical. The *oblique portion* begins on the right side of the third lumbar vertebra and extends across the spine from right to left with a decided inclination upwards. It is moulded upon the vena cava and aorta which lie behind it, and it is crossed by the superior mesenteric vessels and the root of the mesentery. The pancreas is adapted to its upper aspect. The *vertical portion* commences on the left side of the aorta; here the duodenum changes its direction and proceeds vertically upwards upon the psoas muscle and left renal vessels for an inch or more. Having gained the left side of the body of the second lumbar vertebra, the duodenum suddenly bends forwards upon itself and forms the duodeno-jejunal flexure. The lower surface of the body of the pancreas is moulded on the summit of this flexure.

At its commencement the third portion of the duodenum is placed in the umbilical region, but it gradually crosses the sub-costal plane, and its terminal part is situated in the epigastric region. The third part of the duodenum is fixed in its position. It is covered by peritoneum on its anterior surface, and is crossed obliquely by the root of the mesentery proper.

Suspensory Muscle of the Duodenum and Mesentery Proper. (Lockwood.)—The flexura duodeno-jejunalis and the root of the mesentery are held in position and prevented

from slipping down on the posterior wall of the abdomen by a band of involuntary muscular fibres, which fixes them to the diaphragm. This band is called the suspensory muscle of Treitz. It is attached above to the diaphragm, on the right side of the œsophageal aperture. From this it proceeds downwards on the left side of the celiac axis artery to the flexura duodeno-jejunalis, into which a large number of its fibres are inserted. The remaining fibres enter the mesentery and find attachment to the peritoneum. In the child the suspensory muscle is well marked and easily isolated, but in the adult it loses its distinctly muscular character and becomes more or less blended with neighbouring tissues.

Pancreas.—The pancreas is an elongated gland which stretches transversely across the posterior wall of the abdomen behind the stomach. For the most part it is situated in the epigastric region, a small portion only of its left extremity being placed in the left hypochondriac region. As in the case of the other solid organs contained within the abdominal cavity, its form is greatly modified by the condition of the hollow viscera in its immediate vicinity, and its true shape can only be ascertained by preserving it *in situ* by repeated injections of some hardening reagent. It may be described as consisting of a head, a neck, a body, and a tail.

The head of the pancreas is a flattened portion of the gland which lies in front of the spine and occupies the concavity of the duodenum. It rests upon the inferior vena cava and to some extent also upon the aorta, whilst its anterior surface is crossed by the transverse colon. As a rule its margins tend to overflow the duodenal boundary: in other words, its marginal lobules show a tendency to wander over the anterior surface of the second and third parts of the duodenum so as to overlap the gut in the vicinity of its concavity. Certain other relations may be noticed in connection with the head of the pancreas, viz: (1) the common bile-duct passes down behind it in close relation to the second part of the duodenum; (2) the vena portæ is formed in front of it; and (3) its lower part is prolonged to the left along the upper border of the third part of the duodenum (processus uncinatus), and in front of this the superior mesenteric vessels are carried downwards.

The neck of the pancreas (Symington) is a narrow constricted

portion of gland-substance which springs from the anterior aspect of the head, nearer its upper than its lower margin. It constitutes the link of connection between the head and the body of the pancreas, and as it proceeds to the left it lies in front of the commencement of the vena portæ and of the termination of the superior mesenteric vein. These vessels intervene between the neck and the front surface of the head of the pancreas. The anterior surface of the neck is covered by that layer of peritoneum which forms the posterior wall of the lesser sac, and is usually somewhat depressed by the pyloric end of the stomach, which rests upon it.

The *body of the pancreas*, where it becomes continuous with the neck of the organ, lies in front of the superior mesenteric artery and the aorta. From this it stretches backwards, and to the left over the lower part of the left suprarenal capsule and the front of the left kidney (Fig. 157, p. 475). It presents a posterior, a superior, and an inferior surface separated from each other by a superior, an anterior, and a posterior border. The *posterior surface* is moulded on the structures upon which it rests, and the splenic vein runs towards the portal vein under cover of it. The *superior surface* looks upwards and forwards, and is covered by the layer of peritoneum which forms the posterior wall of the lesser sac. This surface of the pancreas in the greater part of its extent supports the postero-inferior aspect of the stomach, and is consequently hollowed out for its reception. Immediately adjoining the neck a smooth rounded prominence on the anterior surface of the pancreas juts upwards and forwards, above and to the left of the pyloric portion of the lesser curvature of the stomach, and abuts against the gastro-hepatic omentum. This is called the *tuber omentale* (His). Above this prominence and partly under cover of it the coeliac axis extends forwards from the aorta, and breaks up into its three branches. The *inferior surface* of the body of the pancreas looks downwards and rests upon the flexura duodeno-jejunalis, the coils of the small intestine, and the transverse colon close to the splenic flexure. It is completely covered by the peritoneum, which forms the posterior layer of the transverse meso-colon, and varies greatly in extent: this variation being due to the varying degrees of intestinal pressure to which the pancreas is subjected from below.

The gastric pressure exerted on the pancreas from above, and the counter-pressure which is exerted by the intestine on the inferior surface of the organ from below, varying as they do in the same individual, according to the condition of these hollow viscera, determine, in a great measure, the shape of the body of the pancreas. The body of the pancreas has the appearance of being wedged in between the two layers of the transverse meso-colon at its root.

The splenic artery pursues a wavy course along the superior border of the pancreas, whilst the transverse meso-colon is attached posteriorly to the pancreas along its anterior border.

The *tail of the pancreas* abuts against the visceral aspect of the spleen, and usually rests upon a small depression on the




FIG. 147.—Dissection of Pancreas from behind to show its Ducts.
(Birmingham.)

lower and inner part of the gastric concavity of that organ (Fig. 157, p. 475).

Ducts of the Pancreas.—The ducts of the pancreas are, as a rule, two in number—a main duct and an accessory duct. Both run within the gland substance.

The main *pancreatic duct* or the *canal of Wirsung* begins at the tail of the gland by the union of the small ducts issuing from the lobules in this region, and it proceeds transversely towards the right. It gains considerably in size as it traverses the organ from its being joined by the small ducts which come from the various groups of lobules. Reaching the neck of the gland, it bends downwards in the substance of the head. By dividing the gland horizontally, little difficulty will be experienced in discovering the main duct. The extreme whiteness of its walls is a help to the student in this dissection.

Close to the duodenum the pancreatic duct comes in contact with the common bile-duct, and both pierce in company the coats of the descending part of the duodenum upon its posterior and inner aspect, and open into the gut by a common orifice.

The *accessory duct* is small, and arises in the lower part of the head of the gland. It usually has an independent opening into the duodenum, immediately above the opening of the main duct.

Hepatic Ducts (Fig. 154).—Issuing from the bottom of the transverse fissure of the liver, the student will notice two ducts, called respectively the *right* and *left hepatic ducts*. These unite within the transverse fissure to form the *hepatic duct*, which in turn is shortly joined by the *cystic duct* of the gall-bladder. The junction of the cystic and hepatic ducts gives rise to the *common bile-duct*, or the *ductus communis choledochus*, and this descends between the two layers of the gastro-hepatic omentum to the right of the hepatic artery and in front of the vena portæ. Passing behind the duodenum and the head of the pancreas, it ends by opening, as we have already seen, into the second part of the duodenum.

Dissection.—The attention of the student should now be directed to the ending of the vagi nerves within the abdominal cavity, and also to the great epigastric or solar plexus of the sympathetic. For the proper display of these it is necessary to divide the gastro-duodenal artery, the common bile-duct, and the portal vein at the level of the upper border of the first part of the duodenum, and then, having allowed the air to escape from the stomach and duodenum, to throw both, along with the pancreas, over to the left side of the body. The dissection of the solar plexus is a very tedious one, because mingled with the nerves, which are soft and easily broken, are several lymphatic glands and a quantity of tough areolar tissue.

Pneumogastric or Vagi Nerves.—These enter the abdomen through the œsophageal opening of the diaphragm. The *left vagus* will be found lying upon the anterior aspect of the gullet. Trace it downwards and notice that it breaks up into branches, the greater number of which spread out upon the antero-superior wall of the stomach; a few, however, run to the right, along the lesser curvature, and establish communications with the *coronary plexus*, whilst others ascend between the two layers of the gastro-hepatic omentum to reinforce the *hepatic plexus*. The *right vagus* lies upon the posterior aspect of the gullet, and at once breaks up into numerous branches which ramify upon the postero-inferior wall of the

stomach ; it also sends twigs to the *cœliac plexus*, to the *splenic plexus*, and to the *left renal plexus*.

Solar or Epigastric Plexus.—In connection with the sympathetic system three large plexuses are formed in front of the vertebral column—viz., the *cardiac plexus in the thorax*, the *solar plexus in the upper part of the abdomen proper*, and the *hypogastric plexus in the lower part of the abdomen proper*. These receive the name of the prevertebral plexuses.

The *solar plexus* is by far the largest of the three. It is situated behind the stomach, in front of the *aorta* and the pillars of the diaphragm. Upon each side it extends as far as the suprarenal capsule, whilst inferiorly it passes downwards behind the pancreas. On each side of the body, where it lies upon the crus of the diaphragm, a large ganglionic mass, called the *semilunar ganglion*, is developed in its midst.

Distinctive terms are applied to different parts of the plexus. The portion which connects the semilunar ganglia and surrounds the cœliac axis is called the *cœliac plexus*. To the outer side of each ganglion the plexus ends in numerous branches for the suprarenal body and kidney, and these are classified under the terms of *suprarenal* and *renal plexuses*. Inferiorly, the plexus has already been seen to send downwards large offshoots which accompany the aorta and the superior mesenteric artery; these are the *aortic* and *superior mesenteric plexuses*. Lastly, a small offset from the upper part of each semilunar ganglion is termed the *diaphragmatic plexus*.

Semilunar Ganglia (ganglia cœliaca).—These are so large that they are not infrequently mistaken by students for lymphatic glands. The ganglion of the right side is placed under cover of the vena cava inferior, and both lie in close relation to the cœliac axis. When defined, they will be observed to be of a very irregular shape, and to show little of the outline from which their name is derived. The upper extremity of each ganglion is joined by the *great splanchnic nerve*, whilst into its lower part, which is often more or less detached, may be traced the *small or second splanchnic nerve*.

Cœliac Plexus (plexus cœliacus).—This plexus of nerves connects the two semilunar ganglia with each other, and surrounds the cœliac axis so closely that it almost completely

hides its trunk from view. It is reinforced by twigs from the *right vagus*. Three secondary plexuses—viz., the coronary, the hepatic, and the splenic—take origin from the cœliac plexus.

The *coronary plexus* (plexus gastricus superior) accompanies the artery of the same name along the lesser curvature of the stomach, and distributes twigs to both aspects of the viscus.

The *hepatic plexus* (plexus hepaticus) follows the hepatic artery, the vena portæ, and the bile-duct to the transverse fissure of the liver. It is joined by twigs from the left pneumogastric, and it gives origin to the *pyloric, right gastro-epiploic, superior pancreatico-duodenal, and cystic plexuses*, which accompany the arteries of the same names.

The *splenic plexus* (plexus lienalis) is prolonged along the splenic artery to the spleen. It is joined by twigs from the right pneumogastric, and gives off branches to the pancreas and to the fundus of the stomach, and also the *left gastro-epiploic plexus*.

Renal Plexus (plexus renalis).—This consists of numerous nerves which spring chiefly from the lower and outer part of the semilunar ganglion. Some will be found, however, coming from the cœliac, and others from the aortic plexus. The *smallest or third splanchnic nerve*, when it is present, joins this plexus. Thus constituted, the filaments of the renal plexus run with the renal artery to the hilum of the kidney, and are distributed within the gland substance. Several twigs are likewise given to the spermatic plexus. A few scattered ganglia are usually found in connection with the renal plexus.

Suprarenal Plexus (plexus suprarenalis).—The dissector will be struck with the large number of nerves which supply the suprarenal body. The nerves composing the plexus are chiefly derived from the semilunar ganglion, but many come from the cœliac plexus. Below, it is directly continuous with the renal plexus, and above, it is connected with the diaphragmatic plexus. The smallest splanchnic nerve usually contributes a branch to this plexus, and the point at which it joins is marked by a small ganglion.

Diaphragmatic Plexus (plexus phrenicus).—The filaments composing this plexus take origin from the upper part of the semilunar ganglion, and are distributed with the phrenic artery to the under surface of the diaphragm, but they do not follow rigorously the branches of this vessel. At first they lie

subjacent to the peritoneum, but soon they penetrate between the fleshy fasciculi and establish communications with the phrenic nerve. On the right side a small ganglion is formed on the under surface of the diaphragm at the point of junction between this plexus and the phrenic. In addition to its diaphragmatic branches, it contributes filaments to the suprarenal plexus, and, on the right side, to the hepatic plexus.

Dissection.—Apply two ligatures to the œsophagus, where it enters the stomach, and divide it between them. The stomach, duodenum, pancreas, and spleen may now be removed by dividing the vessels, nerves, and peritoneal folds which still hold them in position.

Spleen.—Several important points in connection with the internal structure of this organ may be recognised in the dissecting-room. It is enveloped by two coats—(1) serous; (2) fibro-elastic. The *peritoneal investment* adheres so closely to the subjacent fibrous coat that it can only be removed with difficulty. With regard to the *fibro-elastic tunic* (*tunica propria*), it should be noted that processes proceed from its deep surface and dip into the substance of the organ. These are the *trabeculae*, and they constitute the supporting framework of the *gland-pulp*. On account of this arrangement, it will be found utterly impossible to strip off the fibrous coat of the spleen without at the same time lacerating its surface. Make a section through the organ, and carry a portion of it to the tap. By squeezing it and allowing the water to run freely over it, a view of the trabecular framework may be obtained.

Dissection.—Detach the pancreas from the duodenum, but leave a portion of the duct in connection with the gut. Next clean out the stomach and duodenum by allowing water to run freely through them, and then render their walls tense by inflating them with air.

Coats of the Stomach.—The coats of the stomach should now be examined. They are five in number, viz. :—

- | | |
|---------------------------|---------------|
| 1. Peritoneal, or serous. | 4. Submucous. |
| 2. Subserous. | 5. Mucous. |
| 3. Muscular. | |

The *serous coat*, derived from the peritoneal membrane, can be best stripped off with the fingers. The *subserous coat* is composed of a little areolar tissue which intervenes between the muscular and serous strata. The branches of the two

pneumogastric nerves can now be followed, as they spread out upon both surfaces of the stomach.

The *muscular coat* consists of involuntary or unstriped muscular fibres, and these are disposed in three incomplete layers—each layer being distinguished by the direction of its fibres. The *external layer* (*stratum longitudinale*) is composed of longitudinal fibres. These are best seen at the curvatures and towards the pylorus. At the cardiac orifice they become continuous with the longitudinal fibres of the œsophagus, and at the pyloric orifice they mix with the longitudinal fibres of the duodenum. Very few longitudinal fibres can be detected on the superior and inferior surfaces of the viscus. The *middle layer* (*stratum circulare*) is composed of circular fibres, which are continuous with the more superficial circular fibres at the lower end of the œsophagus. They do not form a continuous coating for the stomach (Birmingham). Beginning as a series of loops immediately to the right of the œsophageal opening, they gradually increase in length as the layer is followed towards the pylorus, and soon they completely encircle the organ and form a continuous stratum. No fibres of this layer encircle the fundus. At the pylorus the circular fibres undergo a marked increase in numbers, and are aggregated together into a circular band, called the *pyloric sphincter*. The *internal layer* (*fibræ obliquæ*) consists of oblique fibres, which give a partial covering to the stomach. They are continuous with the deeper circular fibres of the gullet, and are best seen on the fundus of the stomach to the left of the œsophageal opening. From this they spread out in a series of loops upon both surfaces of the viscus, and




FIG. 148.—Dissection of the three layers of Muscular Fibres in the Wall of the Stomach.

embrace the œsophageal opening. As these muscular loops are traced towards the fundus, they are found to gradually assume the form of a complete coating of circular fibres for this part of the organ (Birmingham).

The *submucous coat* is composed of loose areolar tissue. It intervenes between the muscular and mucous tunics, and binds the one to the other.

The *mucous coat* must be studied from the inside of the stomach. Open up the viscus by running the scissors along the lesser curvature. The duodenum may be laid open at the same time. The gastric mucous membrane will now be seen to be thick, soft, and pulpy. In the dissecting-room the student cannot obtain a proper idea of its natural colour.




FIG. 149.

A. Pyloric Orifice of Stomach as seen from the Duodenum.

B. Longitudinal section through Pylorus and beginning of Duodenum.

In infancy it is rosy red, but as life advances it gradually becomes paler, and in old age it always presents a brownish hue from the presence of pigment. When the mucous membrane is cleansed and examined with a pocket-lens, its surface is observed to present a pitted appearance. Innumerable polygonal depressions are brought into view, and these are observed to be larger and better marked in every way near the pylorus than in the vicinity of the fundus. At the bottom of these pits are the mouths of the minute tubular glands of the gastric mucous membrane.

When the stomach is empty, the mucous membrane is thrown into longitudinal folds or *rugæ*, but these disappear when the organ is distended. During life the mucous membrane of the stomach is thicker and firmer in its consistence in its pyloric than in its cardiac part. At the pylorus

the mucous membrane is raised into a remarkable circular fold, called the *pyloric valve*. This fold contains between its two layers the sphincter pylori muscle. If the mucous membrane be removed from the fold, the thick band of circular muscular fibres which forms the sphincter becomes very apparent. This dissection had best be done under water.

When the sphincter of the pylorus is tightly contracted, as it is in health at all times, except when chyme is passing from the stomach into the duodenum, the pyloric opening, viewed from the duodenal side, presents a striking resemblance to the os uteri externum. (Fig. 149, A.)

Coats of the Duodenum.

—In connection with the duodenum, note that the valvulæ conniventes begin about one or two inches beyond the pylorus, about the commencement of its second part; that the mucous membrane is covered by villi; and that usually no Peyer's patches are to be seen. Pass a probe




FIG. 150. — The Bile-Papilla in the interior of the Duodenum. (Birmingham.)

along the bile-duct, and another along the pancreatic duct. These ducts will then be observed to pierce the coats of the duodenum, side by side, very obliquely, and to open by a common orifice, which is placed on the summit of a papillary projection of mucous membrane, termed the *bile papilla* (papilla duodeni). From the under surface of this projection a ridge of mucous membrane (frenulum) passes downwards, and gives a downward inclination to the biliary opening on the summit of the papilla.

The duodenum should now be pinned down, with its mucous surface undermost, to the bottom of a cork-lined tray filled with water. Its coats may then be dissected. They are in all respects similar to those already examined in connection with the jejunum (p. 437). If the dissection is carried on until the deep surface of the submucous coat is exposed by the removal of the entire muscular coat, a view of Brunner's glands may be

obtained. They appear as whitish specks, about the size of hemp-seed, in the submucous tissue. They are most numerous close to the pylorus, and gradually disappear about two inches beyond this.

Removal of the Liver.—The student has already examined the position and connections of the liver (p. 398). It should now be removed from the abdominal cavity, in order that its form and the manner in which the vessels are distributed in its substance may be studied. Begin by dividing the ligamentum teres and the falciform ligament. Then drawing it downwards, cut through the lateral ligament on each side and the upper layer of the coronary ligament. Having done this, the bare area on its posterior border can be separated from the diaphragm with the handle of the knife. Observe that this portion of the liver is merely connected to the diaphragm by areolar tissue. Soon the vena cava inferior will be exposed, emerging from the posterior surface of the liver, and then piercing the central tendon of the diaphragm. This must be severed. On dividing the lower layer of the coronary ligament, the liver will be free from all the surrounding parts, except the vena cava, at the point where it first comes in contact with the organ. The vena cava must, therefore, be cut a second time, and thus a portion of the vessel is taken away with the gland.

Liver (hepar).—In the adult male the weight of the liver will be found to vary from 50 to 60 ounces, and in the adult female from 40 to 50 ounces. It represents about $\frac{1}{36}$ th of the weight of the whole body. In infancy and childhood it is relatively larger than in later life.

In form the liver has been seen to resemble, while *in situ* and supported by surrounding viscera, a right-angled triangular prism (Symington), and to present a basal or right lateral surface, a superior surface, an anterior surface, a posterior surface, and an inferior or visceral surface. Unless means have been taken to harden it in position before the abdomen has been opened, the liver, when placed on the table before the dissector, in a great measure loses this shape. It becomes flattened, the distinction between the anterior and superior surfaces is lost, and the inferior and posterior surfaces also tend to run into each other. It is necessary, therefore, to correct the impressions which are received from such a disfigured organ by reference to a specimen which has been specially prepared.

Longitudinal Fissure.—The *inferior* and *posterior surfaces* of the liver alone remain to be studied. Upon these the demarcation of the organ into a right and a left lobe is effected by the *longitudinal fissure*. This furrow pursues a course which ~~corresponds with the~~ line of attachment of the falciform ligament on the superior and anterior surfaces. The portion of the longitudinal fissure, which traverses the inferior

surface, extends from the anterior border, where it begins in a notch, in a straight direction backwards to the left extremity of the transverse fissure. It lodges the obliterated umbilical vein or ligamentum teres, and is in consequence termed the *umbilical fissure*. Sometimes it is more or less completely bridged over by liver substance, so that a portion, or perhaps the whole of it, is converted into a tunnel or canal. In these cases, the overlying piece of liver substance constitutes a link between the right and left lobes, and receives the name of *pons hepatis*. The continuation of the longitudinal fissure on the posterior surface begins at the left extremity of the transverse fissure, and takes a vertical course upwards. It lodges the slender fibrous cord which represents in the adult the *ductus venosus* of the foetus. It is consequently called the *fissure of the ductus venosus*. The fibrous cord, which lies within it, is attached below to the left branch of the portal vein, and above to the upper end of the inferior vena cava.

Inferior or Visceral Surface of the Liver.—Having recognised the boundary line between the two main lobes of the liver, the dissector should examine carefully the inferior and posterior surfaces. The *inferior visceral surface*, when the liver was *in situ*, has been seen to be very oblique, and to look as much to the left as in a downward direction. It is to some extent also slightly hollowed out, or concave, and it bears upon itself the impress of the various organs with which it is in contact. Thus the *left lobe* presents a concavity of greater or less extent according to the degree of distension of the stomach upon which it is moulded (*impressio gastrica*). It also exhibits, in the neighbourhood of the longitudinal fissure, a smooth rounded boss or eminence, termed by His the *tuber omentale*. This prominence lies above and to the right of the lesser curvature of the stomach, and is consequently in contact with the anterior surface of the gastro-hepatic omentum (Fig. 151).

The inferior surface of the *right lobe* of the liver is much more extensive than that of the left lobe. Upon it we recognise the transverse fissure and the fossa for the gall-bladder (Fig. 151).

The *transverse fissure* (*porta hepatis*) is the deep depression or hilum within which the portal vein and the hepatic artery and nerves enter the liver, and the lymphatics and bile-ducts

leave the liver. It is sometimes spoken of as the "porta" or "gate" of the gland. Beginning at the posterior extremity of the umbilical fissure, it extends transversely to the right for a distance of two inches, and then ends abruptly.

The *fossa for the gall-bladder* (*fossa vesicæ felleæ*), parallel to the umbilical fissure, extends upon the under surface of the right lobe from the anterior sharp border to a point close to the right extremity of the transverse fissure. In this the gall-bladder is lodged, and it varies in depth and extent with the condition of that sac.




FIG. 151.—The Inferior or Visceral Surface of the Liver.

By means of the transverse fissure and the fossa for the gall-bladder, the inferior surface of the right lobe of the liver is subdivided into three unequal portions. These are—(1) the *lobus quadratus*; (2) the *lobus caudatus*; and (3) an extensive area which lies to the right of these, and forms the greater part of the under surface of the right lobe.

The *lobus quadratus* is an oblong quadrilateral area, cut off on all sides from the adjoining liver surface. It is bounded behind by the transverse fissure, in front by the anterior sharp margin of the organ, on the left by the umbilical fissure, and on the right by the gall-bladder and its fossa. The surface

of the lobus quadratus is usually somewhat depressed, and when the liver is in position and the stomach empty, it is in contact with the first portion of the duodenum. When the stomach is full the pylorus as well as the commencement of the duodenum are in apposition with it.

The *lobus caudatus* is a narrow ridge of liver substance which lies behind the transverse fissure and connects the under part of the lobus Spigelii with the inferior surface of the right lobe of the liver. It is placed immediately above the foramen of Winslow, of which it forms the upper boundary, and inter-




FIG. 152.—Posterior Surface of the Liver.

venes between the portal vein, which lies in front of it, and the inferior vena cava, which is placed behind it.

The greater extent of the inferior surface of the right lobe of the liver lies to the right of the gall-bladder and the lobus caudatus. It presents three concave impressions or hollows, viz., an anterior, a posterior, and a small internal impression. The anterior impression is called the *impressio colica*, because it corresponds to the summit of the hepatic flexure of the colon. It is shallow, and looks almost directly downwards. The posterior impression, the *impressio renalis*, is moulded upon a variable extent of the anterior surface of

the right kidney. It is much deeper than the colic impression, and it looks more backwards than downwards. When the hollow viscera in the vicinity are empty, and the abdominal wall is in consequence retracted, this hollow becomes so deep that the kidney might almost be said to be sunk into the liver substance. The small internal impression, the *impressio duodenalis*, lies immediately to the inner side of the renal fossa. It is produced by contact with the duodenum.

Posterior Surface of the Liver (Figs. 152 and 153).—This




FIG. 153.—Liver, Right Kidney, Spleen, and Stomach, as seen from behind.

Drawing taken from a model prepared by the reconstruction method.

is moulded upon the front of the vertebral column, from which it is separated by the diaphragm and the lower part of the descending thoracic aorta. It presents, therefore, a deep hollow corresponding to the bodies of the vertebræ and the structures in front of these. Immediately to the left of the fissure of the ductus venosus there is a smooth notch or groove (*impressio œsophagea*) which leads downwards into the gastric fossa on the under surface of the left lobe. This groove lodges the œsophagus. Beyond the œsophageal groove the posterior surface of the left lobe merges with the sharp margin of the organ.

It has been pointed out that the œsophagus is separated from the bottom of the œsophageal groove in the liver by the prominent anterior margin of the œsophageal opening of the diaphragm, which in the first instance then must be regarded as being responsible for this depression (Birmingham).

On the posterior surface of the right lobe may be recognised—(1) the lobus Spigelii; (2) the fossa for the inferior vena cava; and (3) an extensive bare area uncovered by peritoneum.

The *lobus Spigelii* is the portion of liver substance which lies between the fissure of the ductus venosus and the inferior vena cava. Its lower end appears on the under surface of the liver immediately behind the transverse fissure, and runs into the lobus caudatus (Fig. 151). The Spigelian lobe forms the bottom of the vertebral hollow, and is separated from the bodies of the tenth and eleventh dorsal vertebræ by the diaphragm and the lower part of the descending thoracic aorta.

The *fossa for the inferior vena cava* (fossa venæ cavæ) is a deep groove placed on the right side of the Spigelian lobe. It ascends almost perpendicularly, and sometimes it is converted into a tunnel by a bridge of liver substance which passes over the vein from the one side to the other.

The *bare area* of the posterior surface of the liver is triangular in form, and lies to the right of the vena cava. It forms the greater part of the posterior surface of the right lobe, and is bounded above and below by the lines of reflection of the coronary ligament. For the most part it is convex, and connected with the diaphragm by loose areolar tissue, and some minute veins which unite the portal vessels of the liver with the systemic vessels of the diaphragm; but close to the lower end of the fissure for the vena cava there is a well-marked depression (*impressio suprarenalis*) which lodges the right suprarenal capsule.

Gall-Bladder and Bile-Ducts.—The gall-bladder is a pyriform membranous bag placed in a depression on the under surface of the right lobe of the liver. Its form and position can be seen to best advantage by inflating it with air through the bile-duct. It lies somewhat obliquely, its great end or *fundus*, free and covered by peritoneum, being directed downwards, forwards, and to the right, so as to project slightly beyond the anterior border of the liver, whilst its narrow extremity or *neck* ends near the right end of the transverse

fissure, by making a double bend like the letter S, and then becoming continuous with the *cystic duct*. The *upper surface* is in contact with the liver, to which it is connected by areolar tissue. The *under surface* is clothed by peritoneum, and is in relation in front to the transverse colon, and behind to the first part of the duodenum.

The *cystic duct* (ductus cysticus) has already been observed to proceed downwards and to the left to join the hepatic duct, and thereby form the common bile-duct. The *right and left hepatic* ducts issue from the extremities of the transverse fissure, and unite to form the hepatic duct. To see these points, it will be necessary to open up the transverse fissure of the liver and remove a sheath of areolar tissue termed *Glisson's capsule*, which surrounds the hepatic ducts and vessels.




FIG. 154. — Diagram of the Cystic and Hepatic Ducts. (From Gegenbaur, modified.)

If the dissector now investigates the composition of the wall of the gall-bladder, he will find that, in addition to its partial serous covering, it has—(1) a strong coat composed of muscular and white fibrous tissue, and (2) an internal mucous coat. The first can be seen by stripping off the peritoneum, and the second is best displayed by laying open the gall-bladder with a pair of scissors. The mucous membrane will then be seen to be elevated into ridges which join with each other so as to form an alveolar arrangement—the meshes or depressions having a polygonal form. The cystic duct should also be laid open, when the mucous membrane in this will be observed to be raised into oblique crescentic folds, which, when viewed collectively, have a spiral appearance.

Dissection.—The umbilical fissure, the fissure for the ductus venosus, and the transverse fissure of the liver should now be opened up, and the structures contained within them dissected out.

Vessels of the Liver.—Blood enters the liver—(1) by the *hepatic artery*, (2) by the large *portal vein*; whilst it is led away from the liver by the *hepatic veins*.

The *hepatic artery* is a branch of the coeliac axis, and

carries arterial blood for the nourishment of the liver substance. It divides into two branches which enter the liver at the extremities of the transverse fissure.

The *portal vein* carries venous blood, which it has gathered from the entire length of the abdominal portion of the alimentary canal (with the exception of the lower end of the rectum), from the spleen, pancreas, and gall-bladder. It reaches the under surface of the liver at the right extremity of the transverse fissure. Here it divides into its two terminal branches. The *right branch* is a short wide vessel, which immediately sinks into the liver; the *left branch*, much longer and considerably smaller, extends to the left along the bottom of the transverse fissure, and at the left extremity of this furrow it enters the liver substance. Near this point the coats of the left branch of the portal vein are joined in front by the obliterated umbilical vein, whilst behind it has also attached to it the obliterated ductus venosus. The terminal part of the portal vein, just before it divides, is slightly expanded, forming the *sinus of the portal vein*.

Note the relative position of the *vein, artery, and duct* at the transverse fissure. The duct is placed *in front*, the vein *behind*, whilst the artery is *intermediate* in position. They and their branches are all enveloped in a common fibrous sheath called Glisson's capsule. Trace them into the liver substance for a short distance. The portal vein branches like an artery, and wherever it divides, there also will the hepatic artery and hepatic duct be found to divide. The branches of these three structures, therefore, traverse the liver substance in company, and Glisson's capsule is prolonged into the liver with them, and follows them in their ramifications. The student is now in a position to understand the meaning of the term "*portal canal*." It is employed to denote a channel in the liver substance lined by a prolongation of Glisson's capsule, and holding in its interior a branch of the portal vein, a branch of the hepatic artery, and a branch of the hepatic duct.

The *hepatic veins* which lead the blood out of the liver have an arrangement altogether different from the vessels which enter at the transverse fissure. They converge towards the fossa for the vena cava on the posterior surface of the organ, and cannot be said to have any course outside the

liver, as they open directly into the vena cava inferior. The vena cava should be slit open, when the wide gaping mouths of the terminal hepatic veins will be displayed. Trace these veins for a short distance into the substance of the gland. They are remarkable for the tenuity of their walls, and also for the very small quantity of areolar tissue which separates them from the hepatic substance; indeed, this is so scarce that it is hardly appreciable to the naked eye. In the case of the smaller veins it is altogether absent, and the hepatic lobules rest directly upon their walls.

A section should now be made through the liver substance and the cut surface examined. The portal veins can be readily distinguished from the hepatic veins. The following are the points of difference:—

PORTAL VEINS.

1. Are always accompanied by a branch of duct and a branch of hepatic artery.
2. Mouths usually collapsed.
3. Walls thicker.
4. Walls separated from the liver substance by Glisson's capsule.

HEPATIC VEINS.

1. Are solitary and not accompanied by any other vessel.
2. Mouths usually open and gaping.
3. Walls exceedingly thin.
4. Walls apparently in direct apposition with the liver substance.

Structure of the Liver.—Very little of the structure of the liver can be learned in the dissecting-room. It is completely enveloped by a fibro-areolar coat. This is thick where the peritoneum is absent; but very thin where that membrane is spread over the gland. The liver substance presents a mottled appearance, and when torn or ruptured the surface exhibits a granular aspect. The minute particles which give rise to this appearance are the hepatic lobules. In the human liver these are not completely separated from each other. Each lobule may be regarded as a miniature liver; they are all built up of the same constituents, but these can only be made out by the aid of the microscope.

Kidneys.—The kidneys are situated behind the peritoneum, against the posterior wall of the abdomen—one on either side of the vertebral column. They are enveloped by a capsule of loose areolar tissue, the meshes of which are at certain points loaded with soft pliable fat. Clear this away, and be careful not to remove at the same time the *suprarenal body*, which lies upon the upper end of each kidney.

The *kidney* is placed opposite the bodies of the last dorsal and the upper three lumbar vertebræ. It extends from the upper border of the last dorsal vertebra to the middle of the body of the third lumbar vertebra, and it lies obliquely—its upper end being somewhat nearer the mesial plane than its lower end. The kidneys lie for the most part in the hypochondriac and epigastric regions. As a rule the left kidney is entirely confined to these districts; but the right kidney, which as a rule occupies a slightly lower level, crosses the sub-costal plane so that a small portion of its inferior extremity comes to lie in the right lumbar and the adjoining part of the umbilical region. This difference on the two sides is probably due to the great bulk of the right lobe of the liver. The twelfth rib lies behind both kidneys. The right kidney does not, as a rule, extend beyond the upper border of this rib; the left kidney may reach the lower border of the eleventh rib. The lower end of each organ is separated by a short interval, of varying extent, from the crest of the ilium.

The average length of the kidney is four inches; its breadth two and a half inches; and its average weight four and a half ounces in the male, but somewhat less in the female. It is a solid organ, very pliable, and of a brownish-red colour. The left kidney is, as a rule, slightly longer and narrower than the right kidney.

Form of the Kidney.—This is so characteristic that the term “reniform,” or “kidney-shaped,” has become common in descriptive language. The *anterior surface* looks outwards and forwards, and presents impressions corresponding to the viscera in contact with it; whilst the *posterior surface* is directed inwards and backwards, and is moulded accurately upon the parts which support it. The *extremities* are round, but the superior end is usually thicker and more massive than the inferior. The *external border*, smooth and convex, is directed backwards and outwards; whilst the *internal border* is concave, and looks inwards and forwards. The true form of the kidneys can only be seen in cases where they have been carefully hardened *in situ*.

The kidneys present many changes in form, according to the amount and the kind of pressure which is exerted upon them by contiguous viscera. In most cases, however, and on both sides there is on the anterior surface of the organ

a point of maximum convexity—a place where the kidney substance is raised in the form of a marked prominence or bulging. Above and below this eminence the anterior surface falls away towards each extremity, in the form of an inclined or sloping plane of greater or less obliquity. These impressed districts indicate pressure exercised on the anterior surface of the kidney in two directions, and the intervening eminence is the result of this pressure and counterpressure. This characteristic is more constant and better marked in the case of the left kidney.

Upon the upper inclined plane of the anterior surface of the *left kidney* are placed the left suprarenal capsule, the stomach, the spleen, and the pancreas. These exercise a downward and backward pressure, chiefly through changes in the condition of the stomach. Upon the inferior inclined plane of the left kidney the counterpressure is produced by the intestinal canal, which, as a rule, presses upwards and backwards.

Resting upon the upper inclined plane of the *right kidney* is the liver, whilst in contact with the lower inclined area is the colon. The colon presses on the kidney in an upward and backward direction. To this pressure the liver offers a passive resistance, except perhaps in the case of the slight influence which it conveys in a downward direction from the diaphragm, and in a backward direction from the anterior abdominal wall.

This pressure and counterpressure, which produce so marked a conformation of the anterior surface of the two kidneys, must also exercise an important influence in maintaining the organ in its place, and securing it in that part of the abdominal cavity in which it lies. Still it is doubtful if these influences have so potent an effect on the right as on the left side. The right kidney is embedded to a greater or less extent in the substance of the liver, and this no doubt exerts an influence in fixing the organ in position.

Ligaments fixing the kidney to the abdominal wall are described, and it is easy to demonstrate that the extra-peritoneal tissue in which it lies becomes condensed in the regions above and below into obscure ligamentous lamellæ, but it is doubtful if these can have much effect in maintaining the kidney in its place.

Hilum of the Kidney.—The internal border of the kidney presents a longitudinal fissure called the *hilum*, for the admission and egress of the vessels, nerves, lymphatics, and duct (Fig. 155). This is bounded anteriorly and posteriorly by a thick lip, and leads into a deep recess or cavity in the kidney, which is termed the *renal sinus*. The ureter and the renal vessels enter the kidney between the lips of the hilum. They will be found to have the following general position from before backwards: (1) branches of the renal vein; (2) branches of the renal artery; (3) ureter or renal duct.

Anterior Surface of the Right Kidney.—The anterior

surface of the right kidney may present three impressions, viz., a hepatic, a colic, and a duodenal. The *hepatic impression*, which indicates the area of contact with the under surface of the right lobe of the liver, occupies almost the whole of the upper two-thirds of the anterior surface, and corresponds to the upper inclined plane. Over this district the kidney is sometimes sunk deeply into the substance of the liver. The suprarenal capsule, which rests, as a rule, on the upper extremity of the right kidney, extends downwards for a very short distance on the anterior surface of the organ between it and the liver. With the exception of this narrow strip




FIG. 155.—Section through Abdomen at the level of the second lumbar vertebra.

immediately adjoining the superior extremity, the hepatic impression on the anterior surface of the kidney is covered by peritoneum. The *colic impression* corresponds to the inferior inclined plane, and sometimes it exhibits a marked degree of obliquity. The hepatic flexure of the colon and the commencement of the transverse colon are in contact with this area. The posterior surface of these portions of great gut is devoid of peritoneum, and bound to the kidney by areolar tissue. The *duodenal impression*, or area of contact with the second part of the duodenum, is in the neighbourhood of the hilum, and varies greatly both in position and extent (Fig. 156).

Anterior Surface of the Left Kidney.—The suprarenal capsule, the spleen, the stomach, and the pancreas are in contact with the upper inclined plane on the anterior surface of the left kidney. The *suprarenal capsule*, as a rule, occupies a narrow district along the inner border from the level of the hilum to the summit of the organ. The *spleen* is in contact over an area immediately adjoining the outer convex border. The extent of this splenic field varies considerably in different subjects. The *pancreas* stretches across the left kidney either




FIG. 156.—Right Kidney and Duodenum.

immediately above, or perhaps exactly over, the eminence which intervenes between the two sloping surfaces on the anterior aspect of the kidney. The *stomach* is in contact with the left kidney over the triangular interval which is left between the suprarenal capsule, the spleen, and the pancreas, and this surface is covered by peritoneum derived from the lesser sac.

The inferior sloping surface on the anterior aspect of the left kidney presents a varying relation to the intestinal canal. Towards the outer border of the organ is the *descending colon*, whilst the remainder of this surface is in relation to the coils of the *small intestine*.

Posterior Surface of the Kidney.—This surface is mapped out into an internal and an external district. The *internal district* is the narrower of the two, and looks inwards and backwards. It is in apposition with the psoas muscle and the crus of the diaphragm, and a rounded ridge, which corresponds to the angle between the planes of the psoas and quadratus lumborum muscles, separates it from the external district. The *external district* looks backwards. In its upper third it rests on the diaphragm, and in its lower two-thirds upon the




FIG. 157.—Relations of the Left Kidney and the Pancreas.

quadratus lumborum and the tendon of the transversalis muscle. The upper end of the kidney curves slightly forwards in correspondence with the diaphragm on which it lies, and it should be borne in mind that between the diaphragm and the last rib the pleural cavity descends behind the kidney for a short distance (Fig. 159).

In spare individuals, when the kidneys have been hardened *in situ*, dimples, corresponding to the tips of the transverse processes of the first, second, and third lumbar vertebræ, and a shallow groove for the last rib, may sometimes be detected on the posterior surface of the kidney. A furrow corresponding to the ligamentum arcuatum externum is also not infrequently to be seen on the posterior aspect of the kidney.

The student should never experience any difficulty in determining

the side to which a given kidney belongs. Even allowing that the upper end cannot be distinguished from the lower end, or the anterior surface from the posterior surface, by differences in their appearance (which is frequently the case in a dissecting-room kidney), the ureter alone is sufficient for the purpose. It shows the posterior surface from its position at the hilum, and the lower end from its curving downwards towards it.

Kidney Capsule and Kidney Substance.—The kidney is invested by a strong fibrous coat, which can be easily stripped from its surface. Divide this capsule along the outer margin of the organ and peel it off towards the hilum. Here it enters the sinus, lines its wall, and becomes continuous with




FIG. 158.—Transverse section through Abdomen at the level of the first lumbar vertebra.

- | | |
|--|---|
| 1. Pancreas. | 3. Aorta giving off the superior mesenteric artery. |
| 2. Splenic vein joining the portal vein. | 4. Rod in bile-duct. |
| | 5. Inferior vena cava. |

the sheaths of the vessels entering the gland, and also with the external coat of the ureter.

Examine the manner in which the ureter or duct is connected with the kidney. As it approaches the hilum it expands into a wide funnel-shaped portion called the *pelvis* (Fig. 160).

This enters the sinus and divides into two, or perhaps three, large primary branches, and these again break up into a large number of short stunted secondary divisions called *calices* or *infundibula*, which are attached to the walls of the sinus.

The kidney should now be cut into two in the longitudinal direction. Use a large knife, and, entering it at the external border, carry it steadily through the gland substance to the hilum.

An examination of the cut surface of the kidney will show that its substance is arranged in two parts—a medullary and a cortical. The *medullary portion* is seen to consist of dark-coloured, faintly striated pyramidal masses, the bases of which are directed towards the periphery, whilst their apices are free and project into the sinus. On the sinus wall each of these appears in the form of a prominent mammillary pro-




FIG. 159.—Dissection from behind to show the relation of the two Pleural Sacs to the Kidneys. Outline of upper portions of kidneys indicated by dotted lines.

jection, called a *renal papilla*, which projects into one of the calices of the pelvis of the ureter (Fig. 161). If the kidney be squeezed, fluid will be seen to exude from these papillæ, showing that the tubuli uriniferi open upon their surface. The number of pyramids and renal papillæ vary from eight to twenty. Usually there are more than twelve. A single calyx of the ureter may surround one, two, or even three renal papillæ, and receive the urine which issues from the papillary ducts

which open on their surface. The *cortical substance* constitutes the peripheral part of the gland, and also sends prolongations inwards between the pyramids. These are called the *columns of Bertin* (*columnæ renales*).




FIG. 160.—From a figure by Max Brödel to show the form of the Pelvis of the Ureter and the Calices, as well as the relation of the main branches of the Renal Artery to these. The ureter, pelvis, calices, and arteries were injected with celloidin, and then the kidney substance was removed by means of a digesting fluid. It is thus a cast of the pelvis and calices which is represented, and the cupped appearance of each calyx shows the manner in which the corresponding renal papilla projects into the calyx.

Ureter.—This is the duct which carries the urine from the kidney to the bladder. The relations of its expanded upper end or pelvis at the hilum of the kidney have already been noted. Leaving the gland, it turns downwards and becomes contracted, so that when it reaches the level of the lower end of the organ it has acquired the appearance of a cylindrical tube. The ureter extends downwards and inwards upon the psoas muscle, and, crossing the common or external iliac artery, it enters the pelvis, where it will be afterwards followed. In the abdomen proper it is placed immediately behind the peritoneum, and is crossed obliquely

by the spermatic or ovarian vessels. Before entering the pelvis it passes behind the ileum on the right side, and the pelvic colon on the left side.

Suprarenal Capsules (*glandulæ suprarenales*).—These are two small flattened triangular bodies, each of which is placed

upon the upper end of the corresponding kidney. It surmounts the kidney after the fashion of a helmet, and is prolonged downwards for a short distance upon its anterior surface. The suprarenal body lies in the epigastric region, and rests upon the diaphragm.

The **right suprarenal capsule** is, as a rule, triangular in form, and rests by its base upon the anterior and inner aspect of the upper end of the right kidney. It is placed between the posterior surface of the right lobe of the liver and that portion of the diaphragm which covers the side of the spine.

The *anterior surface*, which looks outwards as well as forwards, presents two impressions—(1) The one is a narrow flattened strip, adjoining the anterior border of the capsule, which is overlapped by the inferior vena cava; (2) the second impression comprises the remainder of the anterior surface, and is in contact with the liver. Only a small and variable




FIG. 162.—Anterior Surface of Right Suprarenal Capsule.

a short wide vein which immediately enters the vena cava inferior. The *posterior surface* of the right suprarenal capsule is divided by a salient curved ridge into an upper flat part,




FIG. 161.—Diagram of two Renal Papillæ.

R.P. Renal papilla.

C. Cut edge of a calyx of the pelvic portion of the ureter.

part of the lower portion of the anterior surface of the right suprarenal capsule is covered by peritoneum. On the upper part of the impression for the vena cava, not far from the apex of the capsule, a short fissure termed the *hilum* may be observed. From this issues

which is applied to the diaphragm, and a concave lower part, which is occupied with fat and rests upon the kidney.

The **left suprarenal capsule** presents a semilunar form, and as a rule is slightly larger than the right capsule. Its position on the kidney is also somewhat different. It is usually placed on its inner border immediately above the hilum. The *anterior surface* presents, not far from its lower end, a very obvious *hilum* with a large emerging vein. The greater part of this surface is in relation to the postero-inferior aspect of the stomach, and forms a portion of the bed in which that organ lies. This gastric area of the suprarenal capsule is clothed by peritoneum derived from the lesser sac.




FIG. 163.—Anterior Surface of Left Suprarenal Capsule.

The lower portion of the anterior surface is covered by the pancreas and crossed by the splenic vessels, and is not in relation to the peritoneum. Sometimes the spleen extends inwards so as to lie in relation to the upper part of the anterior surface of the left suprarenal capsule, but this cannot be said to be the rule. The *posterior surface* is subdivided into two areas, as on the right side, by a curved ridge. The upper

area is flat, and applied to the left crus of the diaphragm; the lower area is hollowed out, and is in relation to the kidney, a considerable amount of fat intervening.

The student has already observed the abundant nerve supply to the suprarenal capsules from the solar plexus. Its blood supply is equally rich. No fewer than three arteries enter its substance—viz., the *superior*, *middle*, and *inferior capsular arteries*.

When a section is made through the suprarenal capsule it is seen to consist of an external firm portion termed the *cortex*, and of a soft pulpy dark-coloured internal substance called the *medullary part*.

Dissection.—Having now disposed of all the viscera within the cavity of the abdomen proper, the student should, in the next place, direct his attention to the diaphragm—the great muscle which constitutes a movable partition between the thoracic and abdominal cavities. Stripping the peritoneum from its lower concave surface, clean the muscular fibres and the central tendinous expansion towards which they ascend. In making

this dissection be careful to preserve the phrenic arteries which ramify upon this aspect of the diaphragm and also the nerves which accompany them.

Diaphragm.—The diaphragm, after the heart, is the most important muscle in the body. It forms the dome-shaped roof of the abdomen, and the highly arched and convex floor of the thorax. It is the chief muscle of respiration. Each respiratory act is accompanied by a descent and ascent of its muscular part, and in this way the capacity of the thoracic cavity is alternately increased and decreased in the vertical direction. The vault or cupola of the diaphragm is higher on the right side than upon the left side of the body. In forced expiration it rises on the right side as high as the upper margin of the fourth rib, close to the sternum; whereas, on the left side, it only reaches the upper border of the fifth rib.

The *central portion* of the diaphragm is tendinous. From this the fleshy fibres will be observed to radiate, and, at the same time, to arch downwards, so as to obtain attachment to the circumference of the lower aperture or outlet of the thorax. *In front*, it takes origin from the back of the lowest segment of the sternum; *behind*, it springs by two partly fleshy and partly tendinous processes called *the crura*, from the bodies of the upper three lumbar vertebræ, and upon each side of these from two ligamentous arches, termed the *ligamenta arcuata*; *laterally*, it arises from the lower six costal arches.

Anterior Attachment.—The sternal origin consists of two slips which spring from the back of the xiphoid cartilage. These are separated from each other by a narrow linear interval filled by areolar tissue, and comparable with the wider interval in the mesial plane behind, which separates the two crura of the diaphragm.

Lateral Attachment.—The costal origin consists of six pointed and fleshy slips which spring from the deep surfaces of the lower six costal cartilages. These interdigitate with the digitations of the transversalis abdominis. The sternal and costal origins of the diaphragm are separated by a small triangular interval, in which the pleural and peritoneal membranes are merely separated from each other by some loose areolar tissue. Through this gap the superior epigastric branch of the internal mammary artery descends into the abdominal wall.

Posterior Attachment.—The *ligamentum arcuatum externum* is a fibrous band which stretches from the last rib to the transverse process of the first lumbar vertebra. It arches in front of the quadratus lumborum, and is merely the thickened upper part of the fascia which covers this muscle, *i.e.*, the anterior lamella of the lumbar fascia. By pressing the rib backwards the arch will be rendered more prominent. The last dorsal nerve passes outwards and downwards under this ligamentous arch. The *ligamentum arcuatum internum* arches




FIG. 164.—Posterior Surface of the Anterior Wall of the Thorax and Abdomen, to show the Costal and Sternal Origins of the Diaphragm on the left side. (From LUSCHKA'S *Anatomy*, modified.)

- 3. Ensiform cartilage.
- 5. Triangularis sterni.
- 6. Transversalis abdominis.
- 7. Sternal origin of diaphragm.

- 8. Costal origin of diaphragm.
- 10. Linea alba.
- 11. Musculo-phrenic artery.

over the psoas muscle, and, like the external ligament, is simply a thickening of the fascia which covers that muscle. It is the stronger of the two, and is attached by one extremity to the tip of the transverse process of the first lumbar vertebra, and by the other to the body of the second lumbar vertebra and the tendinous part of the corresponding crus of the diaphragm. Fleishy fibres arise from both of these arcuate bands; those from the internal ligament are more numerous and better marked than those which take origin from the external ligament, and they are continuous with the fleshy fibres of the

crus. Very frequently a gap or interval exists between the fibres which spring from the ligamentum arcuatum externum and those which arise directly from the last rib. The anterior, lateral, and posterior attachments of the diaphragm are therefore marked off by intervals from each other.

The *crura* of the diaphragm are two thick fleshy processes which descend upon the bodies of the upper lumbar vertebræ, tapering as they proceed downwards, and finally ending in pointed tendinous extremities. The *right crus* is the larger and longer of the two. It takes origin from the bodies of the upper three lumbar vertebræ, and the intervertebral discs which intervene between them. The *left crus* springs from the left side of the bodies of the first two lumbar vertebræ. It is much smaller, and lies upon a plane posterior to the right crus. Follow the crura upwards; opposite the last dorsal vertebra they will be observed to be connected across the middle line by a strong fibrous band which arches over the aorta. From the upper border of this fibrous arch fleshy fibres arise which join both crura, and on this account we give it the name of *ligamentum arcuatum medium*.

It may be regarded as a law that wherever an artery pierces the origin or insertion of a muscle, and comes to lie between bone and muscular fibres, it is protected by a fibrous arch. Of this nature is the arch in question, and also the fibrous arch thrown over the superior profunda artery on the back of the humerus, and the fibrous arches in the adductor magnus for the passage of the perforating arteries, and the femoral artery itself.

Above the level of the ligamentum arcuatum medium the fleshy fibres of the crura diverge and ascend to join the posterior border of the central tendon. The innermost fibres of each crus, however, decussate so as to separate the aortic from the oesophageal openings. The decussating fasciculus of the right crus is always the larger of the two, and moreover it usually passes in front of the decussating fasciculus of the left crus.

Central Tendon. — The central tendon is exceedingly strong. It is composed of strong tendinous bundles running in different directions, and closely woven together so as to give it a plaited appearance. This is well seen by an inspection of its abdominal surface. In shape the central tendon resembles a trefoil leaf, of which the right lobe is the largest, and the left lobe the smallest. Upon all sides it is sur-

rounded by muscular fibres. Those which spring from the sternum are much the shortest.

Foramina of the Diaphragm.—The continuity of the diaphragm is broken by *three* large openings, and by some smaller apertures or fissures for the passage of the splanchnic nerves, and the vena azygos minor. The three main openings receive the names of the most important objects which they transmit. They are—

1. The aortic.
2. The vena caval.
3. The œsophageal.

The *aortic opening* is in the mesial plane in front of the first lumbar vertebra, and between the crura of the diaphragm. It is bounded in front by the fibrous band which arches across the middle line and connects the tendinous portions of the two crura. The structures which pass through the aortic opening are—(1) the aorta, (2) the thoracic duct, and (3) the vena azygos major—in this order from left to right.

The *vena caval opening* is at a higher level, being situated opposite the disc between the eighth and the ninth dorsal vertebræ, in front and slightly to the right of the aortic opening. It is placed in the back part of the central tendon at the junction between its middle and right lobes. Its form is somewhat quadrangular, and its margins are prolonged upon the walls of the vena cava as it passes through it. The contraction of the muscular fibres of the diaphragm will therefore tend to increase the size of this opening and the calibre of the vein which it holds.

In addition to the vena cava, one or two minute twigs from the right phrenic nerve may be transmitted through the vena caval opening.

The *œsophageal opening* is an oval or elliptical foramen in the muscular part of the diaphragm. It lies in front and slightly to the left of the aortic aperture, and also at a higher level, being placed opposite the tenth dorsal vertebra. In some cases its upper or anterior border is tendinous, and formed by the posterior margin of the central tendon. Posteriorly it is separated from the aortic opening by the decussation of the internal fibres of the crura.

The œsophageal opening transmits the gullet and the two pneumogastric nerves.

The three large openings of the diaphragm, therefore, present very different features. The *aortic opening* is a fibrous arch behind the diaphragm, and it can in no way be affected by the contraction of the muscular fibres. The *vena caval opening* is in the central tendon, and its margins are attached to the wall of the vessel which it transmits; contraction of the diaphragm must therefore have a tendency to open this aperture to its widest extent. The *oesophageal opening* is placed in the muscular part, and consequently it is probable that the fibres which surround it may be capable of exercising a constricting influence upon the oesophagus, and in this way help to prevent regurgitation of food during the descent of the diaphragm.

Little need be said regarding the smaller foramina. Each crus is pierced by the *three splanchnic nerves*, and the left crus is likewise perforated by the *vena azygos minor inferior*. The *superior epigastric artery* descends in the interval between the sternal and costal attachments of the diaphragm, and the *musculo-phrenic artery* pierces the costal attachment opposite the eighth or ninth rib.

VESSELS ON THE POSTERIOR WALL OF THE ABDOMEN.

Dissection.—The abdominal aorta and its branches and the vena cava must now be cleaned. In doing this, care should be taken of the gangliated cord of the sympathetic which extends downwards on the vertebral column along the anterior border of the psoas. It is necessary to bear in mind that the lumbar branches of the aorta, as they proceed outwards, pass *behind* this. Separate the right crus of the diaphragm from the aorta, and dissect in the interval between them. Here the *receptaculum chyli* and the *vena azygos major* will be found. A chain of lymphatic glands, termed the *lumbar glands*, will be noticed in relation to the aorta. The only branches of the aorta which are liable to injury are the *spermatic arteries*. These are two slender arteries which spring from the front of the vessel a short distance below the renal arteries. They are so small that they are apt to be overlooked.

Abdominal Aorta (aorta abdominalis).—The abdominal aorta is the direct continuation of the thoracic aorta, and enters the abdomen through the aortic opening of the diaphragm. It begins in the mesial plane in front of the last dorsal vertebra, and it ends upon the left side of the lower border of the body of the fourth lumbar vertebra by dividing into the two common iliac arteries. It therefore pursues an oblique course—inclining slightly to the left as it proceeds downwards. A line drawn between the highest points of the iliac crests would indicate the level of the bifurcation of the abdominal aorta; it takes place a little below and to the left of the umbilicus.

Most of the structures which lie *in front* of the abdominal aorta have been removed. In immediate relation to it from above downwards are:—(1) The solar plexus and the layer of peritoneum which forms the posterior wall of the lesser bag. (2) The pancreas and splenic vein. (3) The third part of the duodenum and the left renal vein. (4) The peritoneum and the aortic plexus of nerves. Superficial to these it is covered by the liver, the gastro-hepatic omentum and the stomach, the transverse colon and its mesentery, and by the great omentum and the coils of the small intestine. *Behind*, the abdominal aorta rests upon the bodies of the lumbar vertebræ and the intervertebral discs, separated from them, however, by the anterior common ligament and the left lumbar veins. *On each side* it is related in its upper part to the crus of the diaphragm. On the *right side* the inferior vena cava lies close to the aorta as high as the second lumbar vertebra, but above this it is separated from it by the fleshy part of the right crus. In the interval between the right crus of the diaphragm and the vessel, the student has already noted the receptaculum chyli and the vena azygos major. On the *left side*, the left gangliated cord of the sympathetic is in relation to the artery below the level of the left crus.

Branches of the Abdominal Aorta.—The branches of the abdominal aorta may be described under two heads, viz.—(1) Those which come off *in pairs*. (2) Those which arise *singly*.

PAIRED BRANCHES.

1. Inferior phrenic arteries.
2. Middle capsular arteries.
3. Renal arteries.
4. Spermatic or ovarian arteries.
5. Lumbar arteries.

SINGLE BRANCHES.

1. The celiac axis.
2. The superior mesenteric.
3. The inferior mesenteric.
4. The middle sacral.

With the exception of the *middle sacral*, which arises from the extremity of the aorta between the two common iliacs, the *single branches* have already been described. The middle sacral artery will be examined when the pelvis is dissected. The *paired branches* may now be examined.

Inferior Phrenic Arteries (arteriæ phrenicæ inferiores).—These have already been noticed upon the under surface of the diaphragm. They are two in number, and are the

first branches which spring from the abdominal aorta. Diverging from each other, the artery of the right side passes behind the inferior vena cava, whilst the artery of the left side goes behind the œsophagus. Near the posterior border of the central tendon of the diaphragm each divides into an external and an internal branch. The external branch proceeds outwards to anastomose with the intercostal arteries, whilst the internal branch curves forwards in front of the central tendon, and ends by anastomosing with its fellow, and with the terminal branches of the internal mammary artery. Each phrenic artery, in addition to the branches which it supplies to the diaphragm, gives a twig, called the superior capsular artery, to the suprarenal body. On the left side it also sends a few minute branches to the œsophagus.

The *phrenic veins* open into the inferior vena cava.

Middle Capsular Arteries (*arteriæ suprarenales mediæ*).—

The middle capsular arteries are two small vessels which arise, one from each side of the aorta, at the same level as the superior mesenteric. They run outwards and upwards in front of the crura of the diaphragm to the suprarenal bodies, into the substance of which they sink. On the right side, the middle capsular artery passes behind the inferior vena cava. They anastomose freely with the superior and inferior capsular arteries.

The *right capsular vein* opens into the inferior vena cava, whilst the *left vein* ends in the renal or phrenic vein.

Renal Arteries (*arteriæ renales*).—When compared with the organs which they supply, the renal arteries are disproportionately large. Only a small part of the blood which they carry to the kidneys is used for the nourishment of the gland substance. The kidneys are excretory organs, and it is necessary that the blood should pass to them in large quantity in order that certain materials may be removed from it.

The renal arteries take origin about a quarter of an inch below the superior mesenteric. Each artery proceeds outwards at right angles to the aorta, and, approaching the kidney, breaks up into three branches, which enter the hilum, and pass deeply into the sinus. It is overlapped by the accompanying vein. Seeing that the aorta lies a little to the left of the mesial plane, the right renal artery is the

longer of the two; the right artery is also placed at a slightly lower level, and passes behind the vena cava. At the hilum two of the terminal branches as a rule lie between the renal vein and the pelvis of the ureter, whilst the third enters the sinus behind the pelvis of the ureter. In the renal sinus the three terminal branches break up into numerous smaller branches, which penetrate the kidney substance in the intervals between the renal papillæ (Fig. 160, p. 478).

The renal artery gives a small branch—the *inferior capsular*—to the suprarenal body, and also numerous fine twigs to the connective tissue around the kidney.

The *renal veins* join the inferior vena cava. The vein of the left side crosses in front of the aorta, and is the longer of the two. Both receive tributaries from the suprarenal bodies, and the left vein is also joined by the left spermatic or ovarian vein.

Spermatic Arteries (*arteriæ spermaticæ internæ*).—These are two long slender vessels which spring from the front of the abdominal aorta, a short way below the renal arteries. Diverging from each other, each artery passes obliquely downwards and outwards behind the peritoneum, to the internal abdominal ring, where it joins the other factors of the spermatic cord. As it descends, it rests upon the psoas, and crosses the ureter and the external iliac artery. On the right side, the spermatic artery passes in front of the vena cava inferior and behind the terminal part of the ileum. On the left side it proceeds downwards behind the iliac colon.

In the female, the corresponding arteries go to the ovaries, and are consequently termed the *ovarian arteries*. Within the abdomen proper they have the same relations as the spermatic arteries. In the dissection of the female pelvis they will be followed to their destination.

The *right spermatic vein* joins the vena cava directly, whilst the *left vein* terminates in the left renal vein. The *ovarian veins* end in the same manner.

Lumbar Arteries (*arteriæ lumbales*).—Four in number on each side, they spring from the posterior aspect of the abdominal aorta, in series with the intercostal arteries. At present they are only seen in a very short part of their course. They proceed outwards upon the bodies of the upper four lumbar vertebræ, behind the gangliated cord of the sym-

pathetic, and then disappear under cover of the psoas muscle and the series of fibrous arches from which the muscle arises. The two upper arteries also pass behind the crura of the diaphragm, and on the right side they are crossed by the inferior vena cava.

The *lumbar veins* join the inferior vena cava, and those of the left side pass behind the aorta.

Vena Cava Inferior.—This is the large vein which collects, by means of its tributaries, the venous blood from the lower limbs, the abdominal viscera, and a great part of the abdominal parietes. It is formed on the right side of the body of the fifth lumbar vertebra by the union of the two *common iliac veins*. As it ascends, it lies in the first place upon the vertebral column, close to the right side of the aorta: above the level of the second lumbar vertebra it lies upon the fleshy part of the right crus of the diaphragm, which intervenes between it and the aorta; lastly, it is contained in a deep groove, on the posterior surface of the liver, and leaves the abdomen by passing through the vena caval opening of the diaphragm, to open into the right auricle of the heart.

As it passes upwards it receives the following tributaries:—

1. The common iliac veins.
2. The lumbar veins.
3. The right spermatic or ovarian vein.
4. The renal veins.
5. The right suprarenal vein.
6. The inferior phrenic veins.
7. The hepatic veins.

Common Iliac Arteries (*arteriæ iliacæ communes*).—The two terminal branches of the aorta should next be examined. They arise upon the left side of the body of the fourth lumbar vertebra, and, diverging from each other, proceed downwards and outwards upon the vertebral column. After a course of about two inches, each vessel ends opposite the lumbo-sacral articulation by dividing into the *external* and *internal iliac arteries*; of these the former is the larger of the two, and appears to be the continuation of the parent trunk, whilst the latter passes downwards into the pelvis.

The common iliac artery of each side is covered by peritoneum, and overlapped by coils of the small intestine; furthermore, it is crossed by the large sympathetic twigs

which connect the aortic and hypogastric plexuses, and, close to its termination, by the ureter. On the left side the superior hæmorrhoidal artery also passes down in front of the common iliac artery.

No collateral branches of any consequence proceed from the common iliac artery.

Common Iliac Veins (*venæ iliacæ communes*).—The *left common iliac vein* is much longer than the right, and stands in relation to both arteries of the same name. It first lies along the *inner* or *right* side of its companion artery, and then crosses *behind* the upper part of the right artery to reach the vena cava inferior. The *right common iliac vein* at first lies *behind* its companion artery, but, as it ascends, it gradually comes to lie upon its *right* side, and here it joins the vena cava. Each common iliac vein is formed by the junction of the external and internal iliac veins.

The common iliac vein of each side is joined by the *ilio-lumbar vein*. The left common iliac vein also receives the *middle sacral vein*.

External Iliac Artery (*arteria iliaca externa*).—This vessel is the first or abdominal portion of the great arterial trunk which carries blood to the lower limb. It begins, as we have seen, opposite the lumbo-sacral articulation, and extends obliquely downwards and outwards along the brim of the true pelvis to Poupart's ligament, behind which it passes into the thigh, and becomes the *femoral artery*. Its course can be indicated on the surface with tolerable accuracy by drawing a line from a point a little below and to the left side of the umbilicus to a point midway between the symphysis pubis and the anterior superior spine of the ilium.

Like the common iliac artery, the external iliac is closely covered by peritoneum. On the right side it passes behind the terminal part of the ileum, whilst on the left side it presents a similar relation to the pelvic colon. Towards its termination it is crossed by the deep circumflex iliac vein, and the genital branch of the genito-crural nerve. In the male this part of the artery is also crossed by the vas deferens, and in the female by the round ligament of the uterus. At first the external iliac artery rests upon the inner margin of the psoas muscle, but close to Poupart's ligament it comes to lie directly in front of that muscle. The artery is

separated from the muscle, however, by the iliac fascia, to which it is bound down by a condensed part of the extra-peritoneal tissue, which passes over it. The genito-crural nerve lies along the outer side of the artery, and the companion vein is placed on its inner side; on the right side, however, the vein, as it passes upwards, gradually comes to lie behind the artery.

The external iliac gives off two large branches to the abdominal wall, viz.—(1) the deep epigastric; (2) the deep circumflex iliac. They arise close to Poupart's ligament, and have both been examined (pp. 371, 372). The veins corresponding to these arteries open into the external iliac vein.

External Iliac Vein (*vena iliaca externa*).—This, the continuation of the femoral vein, enters the pelvis on the inner side of the corresponding artery by passing upwards behind Poupart's ligament. It lies at first along the inner side of the artery of the same name, but on a plane somewhat posterior to it, and higher up on the right side it gets completely behind the artery. At the lumbo-sacral articulation it ends by joining the internal iliac vein and forming the common iliac vein. Immediately before its termination it passes to the outer side of the internal iliac artery—between it and the psoas muscle. Its *tributaries* are the veins corresponding to the deep circumflex iliac artery and the deep epigastric artery.

Deep Lymphatic Glands.—The dissector has, doubtless, noticed a chain of lymphatic glands in connection with the external iliac artery, the common iliac artery, and also extending upwards upon the vertebral column in relation to the aorta and inferior vena cava. The *external iliac glands* are in two groups—a lower and an upper. The former consists of three glands placed one on each side and one in front of the external iliac artery, and immediately above Poupart's ligament. The inner gland receives the deep femoral lymphatic vessels; into the anterior gland is poured the lymph which is drained from the district supplied by the deep epigastric artery; whilst the outer gland receives the lymph from the district supplied by the deep circumflex iliac artery. The efferent vessels from the lower group enter the higher group of glands, and from these the lymph is passed on to the common iliac and lumbar glands.

The glands in relation to either side of the aorta and inferior vena cava are both numerous and large, and are called the *median lumbar glands*. Their efferent vessels terminate in two common lumbar lymphatic trunks, which open into the receptaculum chyli.

Receptaculum Chyli (cisterna chyli).—This is the dilated commencement of the thoracic duct. It is placed upon the bodies of the first and second lumbar vertebræ in the interval between the right crus of the diaphragm and the aorta. To bring it into view, it is necessary to separate the right crus from the lumbar vertebræ and pull it aside. When fully displayed, the receptaculum chyli is seen to be a narrow elongated sac about two inches in length, which receives by its lower end the two common lumbar lymphatic trunks, whilst superiorly, it contracts and becomes the thoracic duct. About its middle it is joined anteriorly by the common intestinal trunk, whilst entering it near its upper end are two lymphatic trunks which come from the lower intercostal glands, and reach it by passing downwards through the aortic opening. The vena azygos major lies along its right side, but the receptaculum chyli is easily distinguished from this by the whiteness of its walls. The thoracic duct enters the thorax by passing through the aortic opening of the diaphragm.

Azygos Veins.—The *right azygos vein* or *vena azygos major* usually takes origin in the right ascending lumbar vein. It will be found in the interval between the right crus of the diaphragm and the aorta, upon the right side of the receptaculum chyli, and it will be noticed to enter the thorax by passing through the aortic opening of the diaphragm.

The *vena azygos minor inferior* is more difficult to discover. It originates on the left side of the spine, in the left ascending lumbar vein, and enters the thorax by piercing the left crus of the diaphragm.

FASCIA AND MUSCLES ON THE POSTERIOR WALL OF THE ABDOMEN.

The muscles on the posterior wall of the abdomen are three in number, viz.—(1) The *psoas*, an elongated fleshy

mass extending downwards on the side of the spine; (2) The *quadratus lumborum*, a quadrate muscle external to the psoas, and stretching between the crest of the ilium and the last rib; (3) The *iliacus*, situated in the iliac fossa. The fascia which covers these muscles must, in the first place, be studied.

Quadratus Lumborum Fascia.—Follow this inwards and it will be found to be attached to the anterior aspect of the roots of the transverse processes of the lumbar vertebræ. Trace it outwards and it will be noticed to join the posterior aponeurosis of the transversalis abdominis muscle. From these connections the dissector will understand that this fascia is simply the anterior lamella of the lumbar fascia. But what are its superior and inferior attachments? Above, it is fixed to the last rib, and is thickened so as to form the *ligamentum arcuatum externum*; whilst inferiorly, it is attached to the ilio-lumbar ligament. The quadratus lumborum muscle, therefore, is enclosed in a sheath formed anteriorly by the anterior lamella of the lumbar fascia, and posteriorly by the middle lamella of the lumbar fascia (Fig. 115, p. 363).

Fascia covering the Psoas and Iliacus.—This is one continuous aponeurotic sheet. *Above* the level of the crest of the ilium, where it is merely in relation to the psoas, it is thin and narrow. Here it is attached externally to the fascia covering the quadratus lumborum, whilst internally it is fixed to the spine by a series of fibrous arches which bridge over the lumbar arteries. Superiorly, it has been seen to form the thickened band termed the *ligamentum arcuatum internum*. *Below*, the fascia expands so as to cover both the psoas and the iliacus, and, at the same time, it becomes much denser and thicker. Here it receives the name of the *fascia iliaca*, and presents most important connections. The external iliac vessels lie upon it, whilst the anterior crural nerve lies behind it. The genito-crural nerve pierces it, and comes into relation with the external iliac artery. Externally it is firmly fixed to the crest of the ilium, whilst internally it sweeps over the psoas, and is attached to the brim of the true pelvis. These attachments can be easily demonstrated by dividing it in the vertical direction, over the iliacus, a short way to the outer side of the psoas. It is very loosely attached to the subjacent muscles, so that the fingers can readily be passed

behind it, first in an outward and then in an inward direction. Note that no perceptible fascial partition dips backwards from it between the psoas and iliacus.

The inferior connections of this fascia have already been studied (pp. 199 and 389). On the outer side of the iliac vessels it has been seen to become continuous with the fascia transversalis, and, at the same time, to be attached to Poupart's ligament; whilst behind these vessels it is carried downwards into the thigh, to form the posterior wall of the femoral sheath.

Surgical Anatomy.—The attachments of the ilio-psoas fascia are of high surgical importance. When an abscess forms in connection with the lumbar vertebræ the pus readily passes downwards within the psoas sheath, and in certain cases is conducted behind Poupart's ligament so as to point in the thigh. It cannot enter the pelvis owing to the attachment of the fascia iliaca to the ilio-pectineal line.

Dissection.—The muscles should now be cleaned and their attachments defined; but, in doing this, certain points must be attended to. The inner portion of the fascia iliaca must be carefully preserved, in order that its relation to the pelvic fascia may be afterwards made out. In the case of the psoas muscle, care must be taken not to injure—(1) the sympathetic cord, which lies along its anterior margin; (2) the genito-crural nerve, which runs downwards in front of it; (3) the ilio-inguinal, and the external cutaneous nerves, which appear at its outer border, and the anterior crural nerve, which lies in the interval between it and the iliacus muscle. In the case of the quadratus lumborum, bear in mind that the last dorsal nerve runs outwards in front of this muscle, close to the lower border of the last rib, and that the ilio-hypogastric and ilio-inguinal nerves cross it obliquely at a lower level.

Quadratus Lumborum.—This muscle *arises* from the ilio-lumbar ligament and from the crest of the ilium behind it. It likewise receives two or three slips from the transverse processes of a corresponding number of the lower lumbar vertebræ. Narrowing slightly as it passes upwards, it is *inserted* into the inner half of the last rib, behind the ligamentum arcuatum externum, and by four tendinous slips into the tips of the transverse processes of the four upper lumbar vertebræ.

Psoas Magnus.—This muscle has three distinct modes of origin from the side of the vertebral column:—(1) by five fleshy processes from the anterior surfaces and lower borders of the transverse processes of the lumbar vertebræ close to their roots; (2) by five slips, each of which arises from the intervertebral disc and the contiguous margins of the bodies of two vertebræ—the first slip springing from the last dorsal

and the first lumbar vertebræ and the intervening disc, and the last slip from the two lower lumbar vertebræ and their intervening disc ; (3) from the tendinous arches which bridge over the lumbar arteries and protect these vessels from the pressure of the contracting muscle.

The psoas tapers somewhat as it extends downwards along the brim of the pelvis, and a tendon appears on its outer border, which affords attachment to the fibres of the iliacus. Passing behind Poupart's ligament, it is inserted into the small trochanter of the femur.

Another muscle, called the *psoas parvus*, is occasionally present. This springs from the bodies of the last dorsal and first lumbar vertebræ, and the intervertebral disc between them, and, stretching downwards upon the anterior and inner aspect of the psoas magnus, it ends in a tendon which is inserted into the ilio-pectineal eminence and ilio-pectineal line.

Iliacus.—This muscle arises from the upper part of the iliac fossa, the anterior ilio-sacral ligament, and the base of the sacrum. It is inserted into the tendon of the psoas magnus. Some of its fibres, however, have a separate insertion into an impression below the small trochanter of the femur.

NERVES ON THE POSTERIOR WALL OF THE ABDOMEN.

The nerves on the posterior wall of the abdomen are the gangliated cord of the sympathetic and the anterior primary divisions of the spinal nerves, with the branches which proceed from them. These should now be dissected.

Gangliated Cord of the Sympathetic.—This enters the abdomen behind the ligamentum arcuatum internum, and extends downwards upon the bodies of the lumbar vertebræ along the anterior border of the psoas muscle. *Above*, it is continuous with the thoracic portion of the cord, whilst *below*, it passes behind the common iliac artery and enters the pelvis. In the thorax, it is placed upon the heads of the ribs ; here, however, it lies nearer the middle line, being carried forwards by the psoas muscle. On the right side, it is in great part covered by the inferior vena cava, and on both sides the lumbar vessels pass outwards behind it. As a general rule, a small oval ganglion is formed upon the body of each lumbar vertebra. *Rami communicantes* and *peripheral branches of distribution* proceed from the ganglionic cord.

The *rami communicantes* connect the ganglia with the anterior primary divisions of the lumbar spinal nerves. One or more will be found accompanying each lumbar artery. Trace them backwards by cutting through the fibrous arches which bridge over these vessels and scraping away the fibres of the psoas muscle. They join the lumbar nerves close to the intervertebral foramina.

The *rami communicantes* consist of two sets, viz., white and grey. The *white rami communicantes* are composed of medullated fibres which pass from the spinal nerves to the gangliated cord. In the lumbar region there are only two or at most three of these, and they proceed from the upper two or three lumbar nerves. The *grey rami communicantes* are much more numerous, and are formed of fibres which stream out in an irregular manner from the sympathetic cord to all the anterior primary divisions of the lumbar nerves.

The *peripheral branches of distribution* consist of a large number of small filaments which arise irregularly from the lumbar gangliated cord and pass inwards to the aortic plexus.

Dissection.—To bring the anterior primary divisions of the lumbar nerves into view, it is necessary to scrape away the psoas muscle. This has already been partially done in following the connecting sympathetic twigs backwards. An occasional branch, the *accessory obturator*, is liable to injury unless it be secured at once. When present, it will be found descending along the inner border of the psoas.

Lumbar Nerves.—The anterior primary divisions of the lumbar nerves are five in number, and pass outwards in the substance of the psoas muscle. They increase in size from above downwards, and each nerve is joined by one or more twigs from the sympathetic cord. Branches are given by them to the psoas and quadratus lumborum muscles.

The first *three* lumbar nerves, with a part of the *fourth*, unite in a loop-like manner to form the *lumbar plexus*, whilst the remaining part of the *fourth* joins the *fifth* to form the *lumbo-sacral cord*. The fourth lumbar nerve is frequently called the *nervus furcalis*, seeing that it enters into the formation of both the lumbar and sacral plexuses.

Lumbar Plexus (plexus lumbalis).—This plexus is placed in front of the transverse processes of the lumbar vertebræ in the substance of the psoas. *Above*, it is usually connected with the last dorsal nerve by a small twig, which descends in the substance of the quadratus lumborum, to the first lumbar nerve; *below*, it is brought into communication with the sacral

plexus by the branch of the fourth nerve, which enters into the formation of the lumbo-sacral cord.

The following are the branches which proceed from the lumbar plexus :—

- | | |
|--|----------------------------------|
| 1. Ilio-hypogastric, | } derived from 1st lumbar nerve. |
| 2. Ilio-inguinal, | |
| 3. Genito-crural, | 1st and 2nd lumbar nerves. |
| 4. External cutaneous, | 2nd and 3rd lumbar nerves. |
| 5. Obturator, | 2nd, 3rd, and 4th lumbar nerves. |
| 6. Anterior crural, | 2nd, 3rd, and 4th lumbar nerves. |
| 7. Muscular branches to the quadratus lumborum and psoas muscles which arise somewhat irregularly. | |

The manner in which these nerves spring from the plexus may now be studied. The *first lumbar trunk* breaks up into four branches, viz., the ilio-hypogastric, the ilio-inguinal, the upper root of the genito-crural, and a communicating branch to the second lumbar nerve. The *second, third, and fourth lumbar trunks* each divides into an anterior and a posterior division. The three anterior divisions are smaller than the others, and they unite to form the obturator nerve; the three large posterior divisions unite to form the anterior crural nerve. But other branches come off from certain of these divisions. Thus, the lower root of the genito-crural springs from the anterior division of the second lumbar nerve, whilst the two roots of the external cutaneous nerve take origin from the posterior divisions of the second and third lumbar trunks.

The *ilio-hypogastric nerve* emerges from the outer border of the psoas, and crosses the quadratus lumborum obliquely. Reaching the crest of the ilium, it leaves the abdomen by piercing the transversalis muscle. Its further course has already been studied (p. 361). It is distributed by an *iliac branch* to the skin of the gluteal region, and by a *hypogastric branch* to the skin over the lower part of the abdominal wall.

The *ilio-inguinal nerve* is smaller than the ilio-hypogastric, and leaves the psoas almost at the same point. It runs obliquely downwards and outwards over the quadratus lumborum and the upper part of the iliacus, and disappears from view by piercing the transversalis muscle a little way in front of the ilio-hypogastric. It is distributed to the integument of the scrotum and the inner aspect of the thigh (p. 362).

The *genito-crural nerve* (nervus genito-femoralis) is directed

forwards through the psoas, and, appearing upon its anterior aspect, ends by dividing into a genital and a crural branch. The *genital branch* proceeds downwards and inwards, and, crossing the external iliac artery, reaches the internal abdominal ring. Here it joins the other constituents of the spermatic cord, and, leaving the abdomen, is distributed to the cremaster muscle. In the female the genital branch is




FIG. 165.—Diagram of Lumbar Plexus.

very small, and ends in the round ligament of the uterus and the labium pudendi. The *crural branch* runs downwards along the outer side of the external iliac artery, and, crossing the deep circumflex iliac artery, passes behind Poupart's ligament. It supplies a limited portion of the integument in front of the thigh.

The *external cutaneous nerve* (n. cutaneus femoris lateralis) of the thigh emerges from the outer border of the psoas about

its middle, and descends obliquely across the iliacus muscle behind the fascia iliaca to the anterior superior spine of the ilium. At this point it leaves the abdomen by passing behind Poupart's ligament. It supplies the skin upon the outer aspect of the thigh.

The *anterior crural nerve* (nervus femoralis) is the largest branch of the plexus. It runs downwards in the interval between the psoas and iliacus, and passes from the abdomen




FIG. 166.—The Lumbar Plexus (semi-diagrammatic).

behind Poupart's ligament. It gives a branch to the iliacus muscle.

The *obturator nerve* (n. obturatorius) emerges from the inner border of the psoas, where this muscle reaches the brim of the pelvis, and extends forwards upon the inner wall of the pelvis a short way below the ilio-pectineal line of the innominate bone. At the upper part of the thyroid foramen it joins the artery of the same name, and, escaping from the pelvis, enters the thigh.

A small nerve, the *accessory obturator*, is occasionally to be found. It may either spring directly from the obturator or from the third and fourth lumbar nerves. It proceeds down-

wards along the inner side of the psoas, and it enters the thigh by passing over the pubic bone under cover of the pectineus. Here it gives branches to the hip joint, and unites with the obturator nerve. It also occasionally supplies a twig to the pectineus muscle.

Lumbo-sacral Cord (truncus lumbosacralis).—This large nerve trunk is formed by the union of the anterior primary division of the fifth lumbar nerve with the descending branch of the fourth lumbar nerve. It passes downwards over the base of the sacrum into the pelvis, and joins the sacral plexus.

Last Dorsal Nerve.—The anterior primary division of this nerve will be found running outwards in front of the quadratus lumborum, and under cover of the fascia spread over that muscle, along the lower border of the last rib. Near the spine it sends a small offset downwards to the first lumbar nerve, and at the outer border of the quadratus lumborum it pierces the aponeurosis of the transversalis abdominis, and then passes forwards in the abdominal wall between this muscle and the internal oblique. Its course and distribution in the wall of the abdomen have already been described (pp. 350, 361).

Lumbar Arteries (arteriæ lumbales).—These have been traced to the inner border of the psoas. They are now observed to pass backwards behind this muscle to the intervals between the transverse processes of the vertebræ. Here each ends by dividing into a dorsal and an abdominal branch.

The *dorsal branch* runs backwards between the transverse processes, and, after giving a *spinal branch*, which enters the spinal canal through the intervertebral foramen, ends in the muscles and integument of the back.

The *abdominal branches*, with the exception of the last, proceed outwards behind the quadratus lumborum, and are then directed forwards between the abdominal muscles, where they anastomose, above with the intercostal arteries, below with the deep circumflex iliac and ilio-lumbar arteries, and in front with the superior and deep epigastric arteries. The last abdominal branch, as a rule, passes in front of the quadratus lumborum.

Lumbar Veins (venæ lumbales).—These vessels accompany the corresponding arteries, and pour their blood into the inferior

vena cava. The veins of the left side pass behind the aorta. In front of the transverse processes of the vertebræ, cross branches link together the different lumbar veins on each side of the vertebral column, and form a continuous longitudinal vessel, called the *ascending lumbar vein*. By its upper end this venous trunk is connected with the corresponding azygos vein.

Subcostal Artery.—At this stage of the dissection the subcostal artery, the last parietal branch of the thoracic aorta, will be seen crossing the upper part of the quadratus lumborum in company with the last dorsal nerve. It lies in series with the abdominal branches of the lumbar arteries.

Dissection.—The lower limbs having, by this time, been removed from the trunk, the pelvis may also be detached. Place a ligature around the aorta and vena cava at the level of the bifurcation of the former, and divide them immediately above this point. Then carry the knife through the intervertebral disc which intervenes between the third and fourth lumbar vertebræ, and, having cut the nerves and soft parts, complete the separation of the pelvis from the remainder of the trunk by means of the saw.

PELVIS.

The pelvis is the basin-shaped lower part of the abdominal cavity. It has already been defined as being that portion of the general cavity of the abdomen which lies below and behind the ilio-pectineal lines of the innominate bones. Its walls are, for the most part, rigid and composed of bone; *behind*, it is bounded by the sacrum and coccyx; whilst *in front* and *laterally*, it is bounded by the two ossa innominata. The bony wall, however, is deficient at certain points; thus, *posteriorly*, there is an interval on each side, between the sacrum and the os innominatum, which is partially filled up by the sacro-sciatic ligaments; again, *laterally*, there is the wide thyroid foramen, which is closed by the thyroid membrane; and, *in front*, there is the gap left by the pubic arch, which is occupied by the triangular ligament of the urethra.¹

Upon the inner aspect of these boundaries of the pelvis there are placed certain muscles. *Posteriorly*, upon the anterior aspect of the sacrum, are the two *pyriformes*

¹ Let it be clearly understood that it is the inferior or superficial layer of the triangular ligament to which we refer, and not the "deep layer."

muscles; laterally, upon the inner aspect of each innominate bone, is the *obturator internus muscle*; whilst, in front, lying against the deep surface of the triangular ligament, is the *compressor urethræ muscle*. But, in addition, there is a strong aponeurotic membrane, called the *parietal layer* of the *pelvic fascia*, which forms a complete lining for the pelvis, and is placed upon the deep surface of these muscles.

The pelvic wall may therefore be regarded as consisting of three strata, each composed of parts which lie in the same morphological plane, viz. :—

1. A bony, ligamentous, and membranous stratum.
2. A muscular stratum.
3. An aponeurotic stratum.

The pelvic cavity is closed below, and separated from the perineum by the *visceral layer* of the *pelvic fascia*, which passes inwards to the viscera from the parietal layer of the same aponeurosis, and also by the *pelvic diaphragm*, which is placed upon the under surface of the fascia. This diaphragm consists of the two *levator ani muscles* and the two *coccygei muscles*. The pelvic and abdominal cavities are directly continuous above and in front through the pelvic inlet.

The contents of the pelvic cavity differ in the two sexes; in both, however, the bladder occupies the fore-part, and the rectum and pelvic colon the back-part, of the space. The difference is to be found in the generative organs. It is necessary, therefore, to describe the male and female pelvis separately.

MALE PELVIS.

Within the male pelvis we find the following structures :—

- | | | |
|----------------|---|--|
| Viscera. | { | 1. The pelvic colon and rectum. |
| | { | 2. The bladder, with the lower portion of the ureters, the prostate, and the prostatic portion of the urethra. |
| | { | 3. Vasa deferentia and the vesiculæ seminales. |
| Blood-Vessels. | { | 1. The internal iliac vessels and their branches. |
| | { | 2. The superior hæmorrhoidal vessels. |
| | { | 3. The middle sacral vessels. |
| | { | 4. Certain venous plexuses in connection with the viscera. |
| Nerves. | { | 1. The sacral plexuses and their branches. |
| | { | 2. The obturator nerves. |
| | { | 3. The pelvic part of the sympathetic. |

The peritoneum dips into the pelvis, and completely invests the pelvic colon, and at the same time gives a partial covering to the rectum and the bladder.

General Position of the Viscera.—The *pelvic colon* and the *rectum* occupy the back part of the pelvic cavity. The rectum takes a curved course downwards upon the lower part




FIG. 167.—Side view of Pelvic Viscera. Subject in the horizontal position. (From WILSON'S *Anatomy*.)

- | | |
|------------------------------------|--|
| 1. Section of pubic bone. | 15. Right crus of penis. |
| 2. Section of sacrum and coccyx. | 16. Pelvic colon. |
| 3. Bladder. | 17. Recto-vesical pouch of peritoneum. |
| 4. Apex of bladder. | 18. Rectum. |
| 5. Base of bladder. | 19. Right seminal vesicle. |
| 6. Ureter. | 20. Right vas deferens. |
| 7. Neck of bladder. | 21. Pelvic fascia covering rectum. |
| 8. Visceral pelvic fascia. | 22. Levator ani. |
| 9. Prostate. | 23. Sphincter ani externus. |
| 10. Membranous portion of urethra. | 24. Interval between the triangular ligament and the fascia of Colles. |
| 11. Parietal pelvic fascia. | 25. Line of reflection of the peritoneum from the side of the bladder. |
| 12. Cowper's gland. | |
| 13. Bulb of penis. | |
| 14. Corpus spongiosum. | |

of the sacrum and upon the coccyx, to the concavity of both of which it is adapted. The *bladder* is placed in the fore-part of the cavity, and lies against the pubic bones. Between the bladder and the rectum are the *vesiculæ seminales* and the *vasa deferentia*, whilst placed below the bladder and embracing its neck or urethral orifice is the *prostate*. At the

present moment the pelvic colon, the rectum, and the bladder are the only viscera visible.

Disposition of the Peritoneum.—The peritoneum is continued from the posterior wall of the abdomen into the pelvic cavity, and gives a lining to its walls as well as coverings to certain of the contained viscera. It invests the pelvic colon completely, and connects it by means of a fold, called the pelvic meso-colon, to the anterior surface of the sacrum. At the junction of the pelvic colon with the rectum, opposite the third piece of the sacrum, the peritoneum leaves the posterior surface of the gut; still lower down it passes away from its lateral surfaces; and finally, at a point about one inch above the base of the prostate, or about three inches above the anal orifice, it leaves the anterior surface of the rectum, and is reflected forwards on to the vasa deferentia and the vesiculæ seminales, as these lie upon the base of the bladder. Below this reflection the rectum is absolutely destitute of peritoneal covering.

When the bladder is empty the peritoneum is carried upwards on the vasa deferentia and the seminal vesicles, and then, leaving these viscera, it is folded on itself and forms a short fold with a sharp free crescentic border. This fold is termed the *sacro-genital fold* (Dixon), and takes a transverse course in the interval between the bladder and the rectum. If the fingers are passed down into the space between this fold and the rectum, they enter the *recto-vesical* or *recto-genital pouch* of peritoneum, the bottom of which represents the reflection of the membrane from the gut, on to the seminal vesicles and vasa deferentia.

The anterior layer of the sacro-genital fold is reflected forwards on to the bladder, and gives a covering to its superior surface. At the apex of the bladder the peritoneum is conducted on to the posterior aspect of the anterior abdominal wall by the urachus.

The level at which the peritoneum is reflected from the rectum, or, in other words, the level of the bottom of the recto-genital pouch, is subject to variation. In certain cases it is placed nearer to the base of the prostate than is stated above.

Peritoneal Fossæ.—When the bladder and rectum are empty the portion of the pelvic cavity on either side of these viscera is seen to present three depressions or peritoneal

fossæ. Posteriorly, at the side of the empty rectum, is the




FIG. 168.—The Peritoneum of the Pelvic Cavity.

The upper part of the posterior wall of the pelvis has been removed to show more clearly the disposition of the peritoneum within its cavity. (Dixon and Birmingham.)

- | | |
|------------------------------------|--------------------------------------|
| 1. Vas. | 11. Pararectal fossa. |
| 2. Obliterated hypogastric artery. | 12. Sacro-genital fold. |
| 3. Deep epigastric artery. | 13. Lateral portion of middle fossa. |
| 4. External iliac vessels. | 14. Obturator fossa. |
| 5. Obturator nerve. | 15. Trigonum femorale. |
| 6. Obliterated hypogastric artery. | 16. Paravesical fossa. |
| 7. Ureter. | 17. Median portion of middle fossa. |
| 8. Third sacral vertebra. | 18. Plica vesicalis transversa. |
| 9. Lower part of pelvic mesocolon. | 19. Urachus. |
| 10. Rectum. | 20. Bladder. |

pararectal fossa ; anteriorly, at the side of the empty bladder,

is the *paravesical fossa*; whilst occupying a place between these, and on the outer side of the seminal vesicle, is the much smaller *middle fossa* (Dixon and Birmingham).

These three fossæ on each side are separated from each other by two well-marked peritoneal folds or ridges, which pass outwards from the viscera towards the wall of the pelvis. The anterior fold or ridge contains the ureter, and stretches from the lateral basal angle of the bladder outwards and backwards to the lateral wall of the pelvis. The second fold is the *sacro-genital fold*, which bounds the recto-vesical or recto-genital pouch in front, and has already been seen in the interval between the rectum and bladder. This fold curves outwards and backwards on each side towards the sacrum, and gradually fades away. It contains between its layers the sacro-genital ligament, composed of some fibrous and muscular tissue, which stretches from the seminal vesicles to the sacrum at the side of the rectum.

The *pararectal fossa* is a very evident peritoneal depression at the side of the empty rectum. It is occupied, as a rule, by a portion of the pelvic colon; but when the rectum becomes distended, the expanding gut strips off the peritoneum from the posterior wall of the pelvis, invades the fossa, and greatly reduces the size of the depression. The pararectal fossæ of the two sides become continuous with each other in front of the rectum, across the bottom of the recto-vesical or recto-genital pouch. The *paravesical fossa* at the side of the empty bladder is occupied by coils of small intestine, or perhaps by the pelvic colon. It becomes to a great extent obliterated, as the bladder distends and approaches on each side the lateral wall of the pelvis. A transverse fold of peritoneum is frequently seen stretching across the superior surface of the bladder, and traversing to a greater or less extent the paravesical fossa. This is the *plica vesicalis transversa*. The *middle* or *genital fossa* is bounded in front by the fold of the ureter, and behind by the sacro-genital fold. As the bladder distends it invades this depression, and at the same time opens out and obliterates, to a large extent, if not entirely, the sacro-genital fold, which limits it posteriorly.

False Ligaments of the Bladder.—Wherever the peritoneum leaves the bladder to reach the pelvic or abdominal wall, the reflection which takes place is termed a false ligament. The peritoneum as it quits the

side of the bladder, and passes on to the lateral wall of the pelvis, forms the *lateral false ligament*; as it is conducted from the apex over the urachus to the posterior aspect of the anterior abdominal wall it forms the *anterior* or *superior false ligament*. The term *posterior false ligament* had better be abandoned; it was previously employed to indicate the sacro-genital fold which, as we have seen, is not directly connected with the bladder.

Hypogastric Nerve Plexus (plexus hypogastricus).—This is the lowest of the three great prevertebral plexuses, and is the main source from which the pelvic viscera are supplied with nerves. It is a dense flattened plexus, which lies in front of the body of the last lumbar vertebra in the interval between the two common iliac arteries. *Superiorly*, it is joined by numerous large filaments, which proceed downwards from the aortic plexus and the lumbar ganglia. *Inferiorly*, it ends by dividing into two lateral parts which are continued downwards on the back wall of the pelvis, and along the inner side of the internal iliac vessels to the pelvic plexuses.

Pelvic Fascia.—Much of the difficulty which is involved in the study of the pelvic fascia will be removed if the student will constantly keep before him two facts

regarding it, viz.—(1) That it constitutes a continuous lining for the inner surface of the pelvic wall. (2) That it sends across the pelvic cavity a layer which acts as a partition between the pelvis proper and the perineum. The lining-portion of the fascia may be termed the *parietal part*, and the partition-portion the *visceral part*. If the pelvis contained no viscera, the arrangement would be exceedingly simple, and might be represented diagrammatically as in Fig. 169.

The visceral layer, however, comes into relation with the viscera, and the connections which it forms with these give rise to the complexity of the membrane.

In order to obtain a proper display of the pelvic fascia, it is necessary to dissect it from three different aspects, viz.—(1) from above; (2) from below; (3) from the side.




FIG. 169.—Diagram of the Pelvic Wall and Pelvic Floor.

The arrows in the diagram indicate the directions in which the dissection must be made. It will be found more convenient to make the dissection on the right side.

Dissection from above.—This dissection is undertaken with the view of exposing the pelvic aspect of the fascia. Strip the peritoneum from the *right side* of the pelvic wall by means of the fingers. It should also be partially removed from the same side of the bladder. On carefully scraping




FIG. 170.—The dotted lines indicate the directions in which the saw must be carried through the bone. (Arthur Thomson.)

away the loose fatty extra-peritoneal tissue with the handle of the knife, or, better still, with the finger-nails, the pelvic fascia will be brought into view. To expose it in front, the bladder must be forcibly dragged backwards from the pubic bones, and the intervening areolar tissue taken away. At this point the pelvic fascia will not be encountered until we have descended to within half an inch or so from the lower end of the symphysis. Here it is so thick that it is beyond injury so long as we work with the fingers, or the handle of the knife, but laterally it is thin, and great care must be taken. The extra-peritoneal tissue which surrounds the internal iliac vessels must also be removed, and the relation of their parietal branches to the fascia made out.

Dissection from below.—The object of this dissection is to expose the perineal surface of the fascia. The pelvis must be placed so that the outlet looks upwards. The fat having previously been removed from the ischio-rectal fossa, divide the inferior hæmorrhoidal vessels and nerves if they are still present, and then raise the levator ani muscle from the side of the rectum. To do this the muscle must be cut transversely about an inch above the anus. At first the levator ani will be observed to rest upon the side of the gut, separated from it, however, by a well-marked layer of




FIG. 171.—The white line of the pelvic fascia is seen in shadow.
(Arthur Thomson.)

fascia (the rectal layer of pelvic fascia), but, as the dissector proceeds with the dissection, the muscle will be found higher up to be in close contact with the under surface of the visceral layer of the pelvic fascia. Lastly, he will come to the line of origin of the muscle from the pelvic fascia, *i.e.*, the line along which the visceral layer leaves the parietal layer—and here he must stop.

In the dissection of the ischio-rectal fossa (p. 314), the parietal pelvic fascia was exposed and recognised as forming the outer wall of the space. The entire inner surface of the parietal portion, both in its pelvic and perineal parts, is, therefore, now displayed, and, if the levator ani be drawn outwards and the pelvis held up to the light, the visceral pelvic

fascia will be seen passing inwards from the parietal part of the aponeurosis to the viscera.

But it is also necessary to obtain a view of the outer aspect of the parietal pelvic fascia, and, for this purpose, the following dissection must be made.

Dissection from the side. To reach the pelvic fascia from this aspect a portion of the bony wall of the pelvis must be removed, and the obturator internus muscle raised from its position. The outer aspect of the innominate bone must first be thoroughly cleaned, by removing the remains of the obturator externus muscle and all adhering portions of muscle from the pubic and ischial bones; carefully preserve, however, the obturator nerve and artery as they emerge from the upper part of the thyroid foramen. The membrane which closes the thyroid foramen may also be taken away, with the exception of a small portion immediately adjoining the canal under the pubic bone, through which the obturator vessels and nerve emerge. This will expose a part of the outer surface of the obturator internus muscle, and the parietal pelvic fascia will be observed arching over the border of the muscle to join the thyroid membrane below the obturator vessels. Next, define the great and small sacro-sciatic foramina and the structures which emerge from and enter the pelvis through these apertures.

The section of the bone may now be made. This simply consists in taking away that portion of the innominate bone which bears the acetabulum. The first step is to saw through the spine of the ischium, close to its base. The bone must then be sawn through above and below the acetabulum—(1) the first cut should pass through the ischial tuberosity from the lower end of the thyroid foramen to the lower end of the small sciatic notch; (2) the second cut should extend from the upper part of the thyroid foramen to the upper part of the great sciatic notch. The direction in which the saw is to be carried in making these sections is indicated by dotted lines in Fig. 170. In the case of the second section, the direction will be somewhat influenced by the depth of the acetabulum. In no case, however, is it wise to enter the saw lower than the anterior inferior spine of the ilium. This is the point at which the cut should be commenced. In all probability it will be found necessary to complete this section in front by means of the bone pliers, as there are many cases in which it is impossible to bring the saw out at the two points indicated. The greatest care must be taken not to break the ascending ramus of the pubic bone. In carrying out the first or lower section, the dissector will meet with no difficulty whatever.

The section of bone being successfully performed, the detached portion should be raised from the subjacent obturator internus. The fibres of this muscle take origin from the deep surface of the bone, and it will thus be necessary to use the knife in effecting the separation. Lastly, clean the obturator internus, and, grasping its tendon, draw it gently outwards and upwards, as in Fig. 171. The outer aspect of the parietal pelvic fascia comes into view. By this dissection the student is afforded a striking illustration of the three morphological planes, the bony, muscular, and the aponeurotic, referred to on p. 502 as entering into the composition of the pelvic wall.

Description of the Pelvic Fascia.—The dissector has already taken note of a continuous fascia lining the interior of the abdomen proper, and placed between the muscles on

the one hand, and the extra-peritoneal fatty tissue and peritoneum on the other. In relative position the pelvic fascia is identical with the abdominal fascia, and the visceral layer of the former, which passes inwards upon the upper surface of the pelvic diaphragm, may be compared with the thin cellular layer which clothes the under surface of the abdomino-thoracic diaphragm; the one completes the aponeurotic wall of the great abdominal cavity below, whilst the other completes it above. But, whilst this is the case, it must be borne in mind that the abdominal and pelvic fasciæ are only directly continuous with each other over a very limited part of the posterior portion of the ilio-pectineal line.

Parietal Pelvic Fascia.—The parietal or lining portion of the pelvic fascia must be examined from three different points of view, viz.—(1) posteriorly; (2) laterally; (3) anteriorly. On the *posterior wall* of the pelvis, the parietal pelvic fascia is of little importance. It is simply represented by a thin cellular membrane, covering the anterior aspect of the pyriformes muscles, and the sacral plexus of nerves. It is in consequence frequently described under the name of the *fascia of the pyriformis*.

Laterally, it is strong and dense, and in this situation it covers the inner surface of the obturator internus muscle. Superiorly, it is attached for a distance of about one inch to the back part of the ilio-pectineal line, where it will be observed to be directly continuous with the fascia iliaca, which is inserted into the same line; but the attachment of both to the bone is weak; so that by passing a probe down behind the latter the continuity of the two membranes can be determined. In front of this, the line of attachment of the parietal pelvic fascia leaves the ilio-pectineal line; it descends obliquely along the superior border of the obturator internus muscle to the upper margin of the thyroid foramen, and, opposite the groove on the under surface of the ascending ramus of the pubic bone, there is a break in its bony attachment. At this point it turns over the margin of the obturator internus, and, joining the thyroid membrane on the other side, converts the groove into a canal. From this onwards the line of attachment gradually sinks upon the posterior aspect of the body of the pubis, and, in front, it is found as low as the inferior border of the symphysis. There is thus a

considerable part of the inner surface of the pelvis below the level of the ilio-pectineal line and the crest of the pubis devoid of fascial lining. Here no continuity can be shown to exist between the iliac and pelvic fasciæ, except through the medium of the periosteum. This part of the pelvic wall is therefore merely lined by extra-peritoneal tissue and the peritoneum.

From the line of attachment thus indicated the parietal pelvic fascia descends upon the inner or deep surface of the obturator internus muscle, and is attached inferiorly to the tuberosity of the ischium through the medium of the falciform edge of the great sciatic ligament, and also behind this to that ligament itself. Traced forwards, it will be found to be fixed to the rami of the pubis and ischium (*i.e.*, the side of the pubic arch) in front of the obturator internus. In this manner, therefore, it may be said to have an attachment to the pelvic outlet from the symphysis to the sacrum. When followed backwards, the fascia will be noticed to pass over and close the great sacro-sciatic foramen, and then to turn inwards at an angle to reach the structures on the anterior aspect of the sacrum, or, in other words, to form the *fascia of the pyriformis muscle*.

From the close relation which this lateral piece of the parietal pelvic fascia presents to the obturator internus muscle—covering it and having its extent very nearly determined by the area occupied by the muscle—it is very commonly called the *obturator fascia*.

We have previously seen that the parietal pelvic fascia gives off from its inner surface a layer called the *visceral layer*, which proceeds inwards towards the viscera, and acts as a partition between the pelvis and the perineum. The line along which this takes origin extends around the pelvic wall, from the spine of the ischium behind to a point in front, a little above the level of the lower end of the symphysis. This line receives the name of the *white line*. It can always be seen by an examination of the outer surface of the pelvic fascia (Figs. 171 and 172). If the white line be inspected from the inside of the pelvis by pulling the bladder well over to the opposite side, it will be noticed that the fascia is specially thickened along this line by a band which springs from the back of the pubis, and which may be traced back-

wards to the ischial spine. But the "white line" has a still wider significance. It also indicates the fascial origin of the levator ani muscle. It must be admitted, however, that in many cases the fibres of this muscle pass upwards beyond the "white line," and separate the visceral and parietal layers of the pelvic fascia from each other for a variable distance.

Above the "white line," the parietal pelvic fascia is in relation to the pelvic cavity, and its inner surface is clothed by




FIG. 172.—Inner aspect of the Lateral Wall of the Pelvis.

peritoneum ; below the line, the parietal pelvic fascia belongs to the perineum, and forms the outer wall of the ischio-rectal fossa, where its inner surface is in relation to the fat which fills up this space. About an inch and a half above the tuberosity of the ischium, the internal pudic vessels and nerves pass forwards in a tube formed by this fascia (p. 316), which receives the name of Alcock's canal.

The student has now examined the parietal pelvic fascia posteriorly and laterally. He must next study its disposition *in front* of the pelvis—*i.e.*, opposite the pubic arch. He

must not suppose, because it has an attachment to the side of the pubic arch, that it stops there. It is continued onwards behind the compressor urethræ muscle, across the arch, and in this situation it is generally known as the superior or deep layer of the triangular ligament. On reaching the urethra, this fascia sweeps backwards around the anterior border of the levator ani, and joins the visceral layer (Fig. 173), where the latter forms the capsule of the prostate. Inferiorly, it is attached to the base of the triangular ligament, which, as we




FIG. 173.—Vertical section through the pubic arch to show the two perineal compartments and their contents. Diagrammatic.

have seen, is on the same morphological plane as the bone; consequently this attachment is quite in keeping with the attachment of the fascia farther back, to the tuberosity of the ischium, and to the sciatic ligaments.

Visceral Layer of Pelvic Fascia.—In the greater part of its extent the visceral pelvic fascia springs from the inner surface of the parietal pelvic fascia, along the *white line*. In front, however, it has an attachment to the back of the body of the pubic bone *above* the attachment of the parietal layer. It is from the portion of bone between these layers that the anterior fibres of the levator ani arise. The visceral pelvic

fascia now passes inwards upon the pelvic surface of the levator ani muscle to the side of the prostate and the base of the bladder, and divides into *three layers* termed—(1) the vesical; (2) the recto-vesical; and (3) the rectal. These have different connections, according to the point at which they are examined.

In the region of the bladder (Fig. 174), the splitting of the visceral pelvic fascia takes place at the outer margin of the vesicula seminalis, and the *vesical*, or *highest layer*, turns upwards upon the lower part of the side of the bladder, and constitutes its "*lateral true ligament*." Upon the wall of this viscus the vesical prolongation gradually thins away until it




FIG. 174.—Diagrammatic representation of coronal section through the Pelvis to show the arrangement of the Pelvic Fascia. (Délépine.)

is ultimately lost upon its coats. The *recto-vesical*, or *intermediate layer*, is carried inwards between the bladder and the rectum, and, in the mesial plane, it becomes continuous with the corresponding layer of the opposite side. As it proceeds inwards it gives a capsule to the vesicula seminalis and the vas deferens. The *rectal*, or *lowest layer*, is prolonged downwards upon the side of the rectum—between it and the levator ani muscle—and then, turning backwards behind the gut, it becomes continuous with the same layer of the other side. The rectum is thus enclosed in a sheath formed by the recto-vesical and rectal layers of the pelvic fascia.

Proceeding forwards to the region of the prostate and the neck of the bladder, the connections of the three layers will

be found to be somewhat altered. Substitute the prostate for the bladder, and carry the vesical layer over it, so as to meet its fellow of the opposite side, and the arrangement will be understood (Fig. 175). The prostate is thus enclosed in a capsule, the walls of which are exceedingly strong and dense. But at this point the lower part of the rectum passes backwards to reach the surface, and as it does so it pushes itself through the rectal layer, and carries downwards upon its walls a thin tubular prolongation of the rectal layer of the fascia (Fig. 176).

The arrangement of the visceral pelvic fascia in front of the pelvis must next be studied. The student has already




FIG. 175.—Diagrammatic representation of coronal section through the Pelvis to show the arrangement of the Pelvic Fascia. (Délépine.)

noted that here the visceral layer has a direct attachment to the posterior aspect of the body of the pubic bone a short distance above the lower end of the symphysis, and above the bony origin of the anterior fibres of the levator ani, and the attachment of the parietal pelvic fascia. Draw the bladder backwards and look down between it and the pubic bones. The *vesical layer* will be seen to pass backwards on each side of the symphysis, in the form of a strong, rounded, and cord-like band, which proceeds over the anterior surface of the prostate to the bladder. These cord-like bands are the *anterior true ligaments of the bladder*, or, if they are looked at merely in their relations to the pubis and the prostate, they are called the *pubo-prostatic ligaments*. In the middle line there is a very evident interval or recess between them, so

deep in some cases that the tip of the little finger can be introduced into it. The dorsal vein of the penis passes backwards in this groove. The fascia is not deficient at the bottom of this furrow. It is prolonged from one side to the other over the dorsal vein, so as to hide it from view.

Anal Fascia.—It is necessary, before leaving the pelvic fascia, to take notice of a layer which has already been studied in connection with the perineum—viz., the *anal fascia*. This is a thin and delicate aponeurosis which covers the




FIG. 176.—This diagram represents the Pelvic Fascia in section a short distance to the outer side of the mesial plane, beyond the point at which the parietal and visceral layers blend; hence both are seen in section. (Délépine.)

perineal or lower surface of the levator ani, and which is connected with the pelvic fascia along the *white line* (Fig. 174). In consequence of this attachment, it is usually described as a distinct layer of the pelvic fascia, whereas it is merely the aponeurosis of the muscle. The levator ani is thus enclosed between two aponeurotic lamellæ—viz., the visceral pelvic fascia and the rectal fascia above, and the anal fascia below.

Relation of Blood-Vessels and Nerves to the Pelvic Fascia.

—The blood-vessels of the pelvis are placed on the peritoneal aspect of the fascia. It follows, therefore, that the parietal

branches of the internal iliac artery, in passing out from the pelvis, pierce the membrane, and they always carry with them a prolongation from it which blends with their sheaths. There is an exception to this rule—viz., the *obturator artery*. It has been observed to pass over the upper border of the parietal pelvic fascia. The nerves, on the other hand, lie *outside* or *behind* the fascia, and do not require to pierce it in emerging from the pelvis. This difference in the relation of the nerves and blood-vessels can be well studied by looking at the fascia as it passes over the great sacro-sciatic foramen.

The arrangement of the pelvic blood-vessels with reference to the lining fascia is a matter of some practical interest. The margins of the apertures in the fascia through which the vessels pass are usually strengthened by some encircling fibres. Sciatic hernia consists in the escape of a portion of gut through the sciatic notch. It makes its way through the parietal pelvic fascia by means of one of these apertures. It may be placed above or below the pyriformis muscle. In the former case, it escapes through the aperture of the gluteal artery; in the latter case, it forces its way through the aperture of the sciatic or internal pudic artery.

A hernia may also occur through the thyroid foramen (obturator hernia). In this case, the gut follows the obturator artery over the upper border of the parietal pelvic fascia through the canal that is formed between this and the under surface of the pubic bone.

Dissection.—The *right* innominate bone should now be removed, in order that a side view of the pelvic viscera may be obtained. The first step to take is to divide the visceral layer of the pelvic fascia from behind forwards, about half an inch from the white line. Next, saw through the pubic bone, half an inch external to the symphysis, and divide the great sacro-sciatic ligament close to the sacrum. The further separation of the bone should be effected at the sacro-iliac articulation by means of the saw.

In connection with the detached innominate bone, a good view may be obtained of the fascial origin of the levator ani (Fig. 172, p. 513), and also of the origin of the obturator internus. It is better, however, to defer the description of these muscles until the viscera are removed.

The dissector should, in the next place, turn his attention to that portion of the visceral layer of the pelvic fascia which has been left attached to the viscera. Follow it as far as possible in its reflections upon them, but preserve intact the capsule of the prostate. When its connections have been recognised, remove what remains of the fascia on the right side, and clean the viscera, taking care not to injure the blood-vessels and nerves which supply them. If the viscera have not been previously hardened *in situ* by formalin the dissection may be facilitated if the rectum be moderately stuffed with tow and the bladder partially inflated with air. In the case of the rectum, first cleanse it thoroughly by allowing water from the tap to run freely through it, and in the case of the bladder, pass a staff into it through the urethra, and, having placed a ligature around the penis, introduce the air through a blow-pipe thrust into one of the ureters.

When the vesical layer of fascia is divided, a plexus of large veins will be discovered upon the bladder. These veins ramify over the entire organ, but are especially numerous towards the base and in the angle between the vesical and recto-vesical layers of pelvic fascia. These veins constitute what is termed the *vesical plexus*.

The vesiculæ seminales must be carefully defined, and the obliterated hypogastric artery and the vas deferens followed upon the side of the bladder.




FIG. 177.—Dissection of the Rectum from the front in a specimen hardened by formalin injection. The front wall of the pelvis has been removed, and the bladder, prostate, and seminal vesicles taken away.

Pelvic Colon.—As already seen, the pelvic colon (p. 416) forms a long loop of large intestine completely invested by peritoneum and attached to the pelvic wall by an extensive mesentery termed the *pelvic meso-colon*. It occupies as a rule the back part of the pelvic cavity; it rests upon the bladder and rectum, and lies in the peritoneal fossæ on either side of these viscera.

Rectum (intestinum rectum).—The rectum proper is a dilated portion of the great intestine, which extends from the termination of the pelvic colon opposite the third sacral vertebra to a point about one and a half inches beyond the tip of the coccyx. Here, at the apex of the prostate, it bends abruptly backwards, passes through the pelvic floor, and becomes continuous with the anal canal. The rectum is about five inches long.

For the greater part of its extent the rectum is adapted to the anterior surface of the sacrum and coccyx, and consequently presents a curve, the concavity of which is directed forwards. Beyond the coccyx, the lower inch and a half of the rectum rests upon the back part of the pelvic floor, formed by the union of the two levatores ani muscles. This portion of the rectum is also supported behind by the ano-coccygeal body—a dense mass of tissue, partly muscular and partly fibrous, which fills up the interval between the coccyx and the anus.

The relations which the peritoneum presents to the rectum are of high importance. The gut is clothed in its upper third both in front and on the sides, but the posterior surface is bare; the peritoneum now passes away from the sides of the gut, so that its middle third is merely covered in front; and finally about one inch above the base of the prostate it quits the rectum altogether, and is reflected on to the vasa deferentia, and the seminal vesicles as they lie on the base of the bladder. This reflection forms the bottom of the recto-vesical or recto-genital pouch of peritoneum. The lower third of the rectum is thus altogether devoid of peritoneal investment.

Below the recto-vesical or recto-genital reflection of peritoneum, the anterior surface of the rectum is in relation to the base of the bladder, and the posterior surface of the prostate; whilst interposed between the bladder and the gut there are on each side the seminal vesicle and the vas deferens. It must be borne in mind, however, that the recto-vesical layer of the pelvic fascia extends across the pelvis between the gut and these viscera.

On either side of the upper part of the rectum is the para-rectal fossa of peritoneum on the postero-lateral wall of the pelvis, whilst lower down the gut receives firm support on its lateral aspect from the levator ani muscle (Fig. 177).

Flexures of the Rectum.—The rectum does not take a straight course along the back wall and floor of the pelvis.




FIG. 178.—Dissection of the Rectum from behind. The sacrum below the 4th sacral vertebra and also the coccyx have been removed. Portions of the levatores ani, coccygei, and external sphincter have also been taken away. (Birmingham.)

It presents three abrupt lateral bends or flexures. As a rule two of these are to the left and one to the right, and the sharply marked infoldings of the wall of the gut on the side opposite to the flexures are the cause of the *rectal valves*

in the interior of the rectum. The flexures are best marked when the gut is distended, but even when it is empty they are as a rule quite apparent. The flexures of the rectum can only be satisfactorily studied in a subject which has been hardened by formalin.

Lying, as it does, between the bladder and prostate in front, and the concavity of the sacrum and coccyx behind, the rectum when empty and collapsed has its anterior wall pressed against its posterior wall. In this condition, therefore, its lumen appears in transverse section in the form of a transverse slit. Behind the apex of the prostate, at the point where the gut bends so as to enter upon its third stage, the anterior wall in the distended condition of the rectum frequently shows a slight bulging or *cul-de-sac* which gains a lower level than the prostate.

Anal Canal.—This is the narrow slit-like passage which leads from the rectum to the anus. Except during the passage of *fæces* it is always tightly closed by the application of its lateral walls to each other. In coronal sections of the pelvis, therefore, it appears in the form of a longitudinal slit (Fig. 179). It is very different in its surroundings and functions from the other parts of the rectum, and may appropriately be distinguished by a special name (Symington).

The anal canal begins at the apex of the prostate and proceeds downwards and backwards to the anal orifice. In length it measures from one to one and a half inches. It is totally destitute of peritoneum, but it is supported and clothed by a prolongation from the rectal layer of the pelvic fascia. It is closely surrounded by strong muscles which keep constant guard over it, and only allow its lateral walls to separate from each other during defæcation. Thus, the internal sphincter encircles it in very nearly its whole length; the external sphincter surrounds the anal orifice and lower part of the wall; whilst above this, at the commencement of the canal, the thick margins of the levatores ani grasp the canal laterally and pinch in its walls. The membranous portion of the urethra and the bulb of the penis are placed in front of the anal canal, but, owing to the backward inclination of the gut, these are not in contact with it, but are separated from it by an angular interval. Behind the anal canal is the *anococcygeal body* (Symington).

The staff, which has been introduced into the bladder, being held in the middle line, the student should pass the forefinger of the right hand into the rectum, and endeavour to distinguish by touch the parts

in relation to the anterior aspect of the gut. Passing beyond the bulb, the staff, as it lies in the membranous part of the urethra, will be felt very distinctly; next, the prostate will be encountered; and, immediately behind this, the finger, provided it is carried upwards exactly in the middle line, will rest upon the vasa deferentia and the extremely narrow triangular surface of the base of the bladder, which is in contact with the rectum—the recto-vesical layer of pelvic fascia alone intervening.




FIG. 179.—Coronal section through the whole length of the Anal Canal. (Symington.)

B. Bladder.
V.D. Vas deferens.
S.V. Seminal vesicle.

R. Terminal portion of the rectum
(note the apposition of its anterior and posterior walls).

Bladder (vesica urinaria).—This is a hollow viscus, with strong muscular walls, which acts as a temporary reservoir for the urine, before it is emitted from the body by the process of micturition. As will be readily understood, its form, and in a great measure its position and relations, are influenced by the quantity of fluid which it contains.

The different forms which the bladder assumes under its constantly changing conditions render its description a matter of serious difficulty. As a rule it is found in the dissecting-room with contracted walls and empty. For this reason, and also because our information regarding the empty bladder is more exact, we shall study in the first place the form which it presents when in this condition, and then refer briefly to the changes it undergoes as it becomes filled with urine. In what follows the description which has been recently given of the empty bladder by Professor Dixon is closely followed.

The *empty bladder* lies completely within the cavity of the pelvis, and it presents a superior surface, an inferior surface, a base, and an apex. Its long axis, which is directed from before backwards, or, in other words, from apex to base, is




FIG. 180.—Bladder hardened *in situ*. It contained a very small quantity of fluid. (A. F. Dixon.)

horizontal. The *superior surface*, which looks upwards and supports some coils of small intestine and, as a rule, a portion of the pelvic colon, is slightly convex and triangular in outline. It is completely covered by peritoneum, and is bounded by three borders, viz., two lateral and a posterior. The *lateral borders* converge in front and meet at the *apex*. From the apex, which is placed in relation to the upper part of the symphysis pubis, a strong fibrous cord, called the *urachus*, proceeds upwards on the posterior aspect of the anterior abdominal wall to the umbilicus. The urachus represents the obliterated intra-abdominal part of the allantoic sac of the developing embryo. Posteriorly the lateral borders of the empty bladder meet the *posterior border*, and on each side the point of junction is marked by a very distinct angle termed the *lateral angle*. This angle is rendered all the

more conspicuous from the fact that it is here that the ureter joins the bladder. The lateral border of the empty bladder is in relation to the side-wall of the pelvis along a line considerably below the level of the vas deferens and obliterated hypogastric artery.

The *basal surface* of the empty bladder looks backwards towards the rectum, but is separated from it by the intervening vasa deferentia and seminal vesicles (Fig. 185, p. 532). The recto-vesical layer of pelvic fascia also passes across between the base of the bladder and the rectum.

The *urethral orifice*, by which the urine leaves the bladder,




FIG. 181.—Bladder hardened *in situ*. It contained a slightly larger amount of fluid than the specimen depicted in Fig. 180. (A. F. Dixon.)

is placed on the inferior aspect of the viscus and occupies the most dependent position. It is surrounded by the base of the prostate, which presents a structural continuity with the bladder wall. The term *neck* is frequently applied to this region of the bladder. The *inferior surface* of the bladder, in front of the prostate, presents an obscure subdivision into two lateral parts, which may be called the *infero-lateral areas*, by a rounded border which runs forward from the urethral orifice to the apex. These areas are separated from the superior surface by the lateral borders of the organ and from the basal surface by two borders which extend from the lateral angles or points where the ureters join the bladder to the urethral opening

The empty bladder when hardened *in situ* therefore presents the form of an inverted tetrahedron, the base of which is represented by the superior surface of the organ, the apex by the urethral orifice and the three surfaces by the basal surface and the two infero-lateral areas.

Each of the *infero-lateral areas* is supported in front by the symphysis pubis and the body of the pubic bone; behind this, by the retro-pubic pad of fat; and still farther back by the fascia covering the obturator internus and the levator ani muscles. The *retro-pubic pad* is a small wedge-shaped mass of soft, pliable, fatty areolar tissue which occupies a space bounded above by the bladder, behind by the anterior true ligaments of the bladder, and below by the pubic bones. It adapts itself to the changing conditions of the bladder.

Changes in the form of the Bladder as it becomes filled with Urine.—

The neck of the bladder or the urethral orifice is firmly fixed in position. This is chiefly due to the manner in which it is grasped and held in place by the base of the prostate and also to the connections which are established between it and the visceral layer of the pelvic fascia. The prostate also is securely anchored in its place by the strong capsule which it derives from the pelvic fascia. As the bladder becomes filled the urethral orifice therefore suffers very little change in position, and it is only in cases of excessive distension that any marked alteration in its level becomes manifest. Under such circumstances the urethral orifice sinks to a certain extent in the pelvic cavity.

As the bladder fills by the entrance of urine into it through the ureters, the superior wall is raised from the inferior and basal walls. All its surfaces increase in area, and the borders which in the empty bladder intervene between them become rounded off and finally obliterated. The organ thus becomes ovoid in form, and the walls, which are thick and firm in the contracted state, become comparatively thin. The apex appears above the symphysis pubis, and as distension goes on the organ rises higher and higher into the hypogastric region, until a very considerable extent of its wall becomes applied to the abdominal wall above the pubis. The lateral surfaces of the distending bladder encroach upon the paravesical fossæ so as to gradually obliterate them, and thus come into contact on each side with a greater extent of the lateral wall of the pelvis.

When the bladder is excessively distended it assumes a spherical form, or perhaps an ovoid form with the enlarged end at the apex (Fig. 183). In the latter case the long axis is no longer horizontal, but very oblique, being directed from above downwards and backwards.

When the urine is ejected from the bladder the superior wall descends until it becomes approximated to the inferior wall and the basal wall. The viscus, therefore, becomes flattened from above downwards, and comes to lie entirely within the cavity of the true pelvis. When such a bladder is examined in a mesial section of the pelvis, and in a subject from whom the urine has been expelled shortly before death, the walls of the bladder are thick and firm, and the lumen of the viscus may be reduced to a mere slit. The part of the lumen which lies behind the urethral opening, formed by the approximation of the superior wall with the basal wall, is spoken of as the *posterior limb*, whilst that part formed

by the approximation of the superior and inferior walls of the viscus in front of the urethral opening is called the *anterior limb* of the cavity. The anterior limb of the cavity is long and nearly horizontal. The posterior limb is short, and sometimes barely recognisable; further, it is oblique or perhaps vertical, and joins the anterior limb at the urethral opening at an angle. Viewed, therefore, in mesial section, the lumen of the perfectly empty bladder usually forms a Y-shaped figure with the lumen of the upper part of the urethra.




FIG. 182.—Mesial section through the Pelvis of an Adult Male. The bladder is nearly empty, and the urethra is divided along its whole length.

R. Rectum.

S. Symphysis.

B. Bladder.

In other cases the empty bladder is firm and rounded, and when divided in the mesial plane its cavity is seen to present only the one limb or slit continuous with the lumen of the urethra.

Relation of the Peritoneum to the Bladder.—In the empty bladder the peritoneum merely covers the superior surface. The other surfaces of the bladder are uncovered, although it should be remembered that the membrane passes downwards

to some extent behind the basal surface, but in this situation it is separated from it by the seminal vesicles and the vasa deferentia.

When the bladder fills and the organ rises into the hypogastric region it is important to note that the peritoneal reflection from the apex is raised along with the organ, so that




FIG. 183.—Mesial section through a Male Pelvis, in which the Bladder is greatly distended.

B. Bladder.

R. Rectum.

S. Symphysis pubis.

Sa. Sacrum.

now there is a considerable area of the bladder wall, below the urachus, applied directly to the anterior abdominal wall without the intervention of peritoneum.

Laterally also the line of peritoneal reflection is raised until it may appear to leave the lateral surface of the bladder along the line of the vas deferens as this passes backwards along the side wall of the pelvis or even as high as the level of the obliterated hypogastric artery.

Posteriorly the sacro-genital fold appears to open out and become more or less completely obliterated, so as to provide a covering for the expanding basal portion of the bladder. It would appear that the level of the reflection of peritoneum which forms the bottom of the recto-vesical or recto-genital pouch does not undergo change with the distension of the bladder. When the rectum becomes distended the recto-genital reflection assumes a higher level, but this is not due to any change in the position of the peritoneum in reference to the bladder, but to the entire bladder with the reflection being pushed upwards and forwards by the loaded gut.

In the new-born infant the form and position of the bladder are very different from what are found in the adult. It is more or less pyriform



FIG. 184.—Mesial section through Pelvis of a newly-born full-time Male Infant.

R. Rectum.

Sa. Sacrum.

S. Symphysis pubis.

in shape, the narrow end gradually passing into the urethra, and there is little or no appearance of a basal portion (Fig. 184). Further, it is placed very much higher. The urethral orifice is situated at the level of the upper border of the symphysis pubis, and the anterior surface of the organ, entirely uncovered by peritoneum, is in contact with the lower two-thirds of that part of the posterior surface of the anterior abdominal wall which lies between the symphysis pubis and the umbilicus (Symington). As growth goes on, "the urethral orifice sinks rapidly from the period of birth up to the beginning of the fourth year, and more slowly from that period up to the beginning of the ninth year; it now remains stationary until the commencement of puberty, and then it sinks slowly until it ultimately attains its normal adult position" (Disse). One other point may be noted in connection with the infantile bladder, viz., the recto-vesical reflection of peritoneum corresponds to the base of the prostate.

Ureters.—Within the pelvis the ureter of each side proceeds under cover of the peritoneum towards the base of the bladder. It first passes downwards and slightly forwards on

the lateral wall of the pelvis. In this part of its course it lies in front of the internal iliac artery and crosses the obturator vessels and nerve and also the obliterated hypogastric artery. Then, curving inwards, it is crossed by the vas deferens and reaches the bladder in front of the upper end of the seminal vesicle. Here, at a point about two inches from its fellow of the opposite side and about one and a half inches from the base of the prostate, it pierces the bladder-wall. In its course over the side wall of the pelvis, and more especially as it curves inwards to the bladder (when that viscus is empty), it raises the peritoneum, which covers it in the form of a ridge or low fold.

Prostate (prostata). — This is a solid body, partly glandular and partly muscular, which embraces the urethral orifice of the bladder and surrounds the first part of the urethra.

In shape, it is conical, and somewhat resembles a Spanish chestnut — its base being directed upwards, and its apex downwards. *In size*, it is variable ; but its average dimensions are commonly stated to be about one inch and a quarter from base to apex, and one inch and a half from side to side at its broadest part. The prostate rests upon the anterior aspect of the lower part of the rectum. It is about one inch and a half distant from the anus, whilst its anterior surface lies three-quarters of an inch behind the lower part of the symphysis pubis.

The prostate has already been noticed to be enclosed within a dense capsule derived from, and continuous with, the pelvic fascia ; and when the constitution of this capsule is analysed, it will be seen that both the visceral and parietal layers of this fascia enter into its composition, whilst the pubo-prostatic or anterior true ligaments of the bladder are developed in its anterior wall. The connections of this capsule prevent the prostate from altering its position in response to the continual changes which occur in the state of distension of the bladder.

Open into the capsule, and lay bare the prostate. It will be found to be surrounded within the capsule by a dense network of veins. This is the *prostatic plexus*, and it will be noticed that the veins are chiefly massed upon the lateral aspects and around the base of the gland. The dorsal vein of the penis passes upwards in relation to the anterior or pubic surface of the prostate, and, after dividing into two, joins the plexus.

Within the capsule formed by pelvic fascia and subjacent to the veins a thin sheath forms an immediate investment for the prostate.

The prostate presents for examination a base or superior surface, an apex, a posterior, an anterior, and two lateral surfaces. The *base* looks upwards, surrounds the urethral orifice on the under surface of the bladder, and over the greater part of its extent is structurally united to the bladder-wall. Around the greater part of its circumference, however, it is separated from the bladder superficially by a broad groove which is filled with large thin-walled veins. The *apex* is the dependent pointed part of the organ. It looks downwards and abuts against the deep layer of the triangular ligament. The *posterior surface* is a flat, somewhat triangular area, which rests on the anterior aspect of the rectum, from which, however, it is separated by the recto-vesical fascia, which here forms the posterior wall of the prostatic capsule. The *anterior surface* takes the form of a prominent and rounded mesial border which intervenes between the two lateral surfaces, and from the lower part of which, immediately above the apex, the urethra emerges from the substance of the gland (Dixon). This border occupies the interval between the two thick anterior margins of the levatores ani muscles. The *lateral surfaces* are full and rounded, and are supported on each side by the corresponding levator ani muscle covered by visceral pelvic fascia.

When the seminal vesicles and the vasa deferentia are detached from the bladder and thrown backwards, it will be seen that the slender common ejaculatory ducts pierce the base of the prostate close to the upper part of its posterior surface. Within the substance of the organ these delicate ducts pass downwards with a slight inclination inwards, and finally open into the prostatic part of the urethra. The portion of prostatic substance between the ducts and the bladder-wall is often called the *middle lobe*. The remainder of the organ is generally spoken of as consisting of two *lateral lobes*, although there is no superficial or deep demarcation between them.

Vesiculæ Seminales.—These are two sacculated receptacles for the semen, which intervene between the base of the bladder and the rectum. Conical or somewhat pyriform in shape, each seminal vesicle presents a narrow inferior end in

close proximity to the base of the prostate, and an expanded or blunt superior end in relation to the recto-vesical pouch of peritoneum and the entrance of the ureter. Inferiorly, they are near to each other and the mesial plane, but they diverge widely as they proceed upwards and outwards, so that posteriorly they are separated by a wide interval. The vas deferens lies along the inner side of each. In length, the vesicle measures about two inches. By introducing a blow-pipe into the narrow inferior extremity, and inflating it with air, a demonstration of its capacity may be obtained.

Each vesicula seminalis is in reality a closed tube, five or




FIG. 185.—Basal aspect of Bladder, Seminal Vesicles, and Prostate hardened by formalin injection.

six inches long, coiled upon itself and held in its present form by a dense areolar tissue. When unravelled, several diverticula will be observed to proceed from the main tube. The narrow anterior end of the vesicle joins the vas deferens at an acute angle to form the *common ejaculatory duct*.

Vas Deferens (ductus deferens).—The vas deferens, or duct of the testicle, has already been traced to the internal abdominal ring, through which it enters the abdomen. Separating itself from the other factors of the spermatic cord, it hooks round the deep epigastric artery, and descends upon the inner side of the external iliac vessels into the pelvis. It now runs backwards upon the side wall of the

pelvis, immediately beneath the peritoneum, through which it is clearly visible, and it crosses in turn the obliterated hypogastric artery, the obturator nerve, and the ureter. Immediately beyond the ureter it turns sharply inwards towards the base of the bladder, comes into relation with the upper blunt end of the seminal vesicle, and runs downwards and inwards in close apposition with its inner side. Finally, on the base of the bladder it approaches close to the mesial plane, and its fellow of the opposite side, and, bending on itself, proceeds almost vertically downwards to the base of the prostate. The lower part of the vas is much dilated, tortuous,




FIG. 186.—Horizontal section through the Bladder and Rectum at the level at which the ureters enter the bladder.

and sacculated, and is termed the *ampulla*. At the base of the prostate the vas narrows greatly and is joined by the duct of the seminal vesicle, thereby forming the *common ejaculatory duct*.

Triangle on the Base of the Bladder.—It is usual to describe a triangular space on the base of the bladder between the two vasa deferentia and bounded above by the reflection of the peritoneum at the bottom of the recto-vesical or recto-genital pouch. When the pelvic viscera are hardened *in situ* by formalin injection, it becomes evident that such a space can hardly be said to exist owing to the close approximation of the apullated terminal parts of the vasa deferentia (Fig. 185).

It occasionally happens that in retention of urine it is impossible to pass a catheter into the bladder to relieve the distension. In these cases it becomes necessary to puncture the bladder with a trocar and cannula. It is customary to state that the operation may be performed at two points without injury to the peritoneum or other important structures—viz., (1) in the middle line immediately above the pubic symphysis, where, in the distended condition of the viscus, there is a wide area of bladder-wall uncovered by peritoneum; (2) through the rectum and within the limits of the small triangular space on the base of the bladder. As we have seen, however, this space can hardly be said to exist, and it is extremely doubtful if this operation could be performed without wounding the vasa deferentia.

Dissection.—The blood-vessels of the pelvis should now be followed out. For this purpose it is necessary to remove the stuffing from the rectum and allow the air to escape from the bladder. The peritoneum upon the left side and the loose tissue around the vessels must be dissected away. Accompanying the arteries the dissector should notice numbers of fine nerve twigs from the pelvic plexus, and from the third and fourth sacral nerves. Preserve these as far as it is possible to do so. Upon the right side the blood-vessels are more or less injured, and some of them severed, by the removal of the innominate bone; on the left side, however, they are intact.

Pelvic Blood-Vessels.—The pelvic arteries are the following:—

- |
 1. The internal iliac and its branches (upon each side).
 2. The middle sacral
 3. The superior hæmorrhoidal } (in the mesial plane).

Internal Iliac Artery (*arteria hypogastrica*).—This is a short, wide vessel, which commences opposite the lumbo-sacral articulation, at the bifurcation of the common iliac. It proceeds downwards and backwards into the pelvis, and ends near the upper part of the great sciatic notch by dividing into an *anterior* and *posterior division*. In length it measures ~~about one inch and a half~~, and its calibre in the adult is considerably smaller than that of the external iliac. The impervious hypogastric artery extends forwards from its extremity.

The internal iliac artery presents the following relations. As it descends it is separated from the inner aspect of the psoas by the external iliac vein. It lies between the ureter, which is *in front*, and the internal iliac vein, which is *behind*; whilst it is covered on its inner or pelvic aspect by the peritoneum. On the *left side* the internal iliac artery is intimately related to the pelvic colon; and on the *right side* it presents similar relations to the terminal part of the ileum.

Condition in the Fœtus.—Very different is the condition of the internal

iliac artery in the foetus. It is termed the *hypogastric artery*, and is twice as large as the external iliac. Instead of terminating at the sciatic notch, it extends forwards and ascends upon the posterior aspect of the anterior wall of the abdomen to the umbilical orifice, through which it passes in company with its fellow of the opposite side and the umbilical vein. Outside the abdominal cavity the hypogastric arteries enter the umbilical cord, and, twining spirally around the umbilical vein, they reach the placenta, where the impure blood which they carry is brought into relation with the maternal blood.

After birth, when the umbilical cord is divided and a ligature placed around it, the hypogastric arteries become filled with clot, which is gradually absorbed. At the same time the vessels shrivel, and after a few years they are merely represented by the fibrous cords which we have examined in the adult. A small portion of this cord, close to the internal iliac artery, usually remains patent, and from this the superior vesical artery takes origin.

Obliterated Hypogastric Artery.—Close to its junction with the internal iliac artery this fibrous cord remains patent, and from this pervious portion the superior vesical artery arises. The obliterated vessel proceeds forwards on the side wall of the pelvis towards the apex of the bladder, and on the posterior aspect of the anterior abdominal wall it can be traced beneath the peritoneum to the umbilicus.

Branches of the Internal Iliac.—The branches of this artery spring from the two divisions into which it divides, and may be tabulated thus:—

ANTERIOR DIVISION.		POSTERIOR DIVISION.	
Parietal.	Visceral.	Parietal.	Visceral.
1. Obturator.	1. Superior vesical.	1. Ilio-lumbar.	...
2. Internal pudic.	2. Inferior vesical.	2. Gluteal.	...
3. Sciatic.	3. Middle hæmorrhoidal.	3. Lateral sacral.	...

Superior Vesical (*arteriæ vesicales superiores*).—Under this name are included two or three small twigs which spring from the pervious part of the obliterated hypogastric artery, and proceed forwards to the coats of the bladder. They supply the apex and the greater part of the body of the bladder, and from one of them a minute twig, the *artery to the vas deferens* (*arteria deferentialis*), is given to the seminal

duct. Although exceedingly slender, this branch can be followed along the vas as far as the testicle.

Inferior Vesical (arteria vesicalis inferior).—This artery runs inwards upon the pelvic aspect of the levator ani. It ramifies upon the base of the bladder, and sends twigs to the seminal vesicle, the vas deferens, the terminal part of the ureter, and the prostate.

The *middle hæmorrhoidal* (arteria hæmorrhoidalis media) very frequently proceeds from the inferior vesical. It is given to the coats of the rectum, and anastomoses above with the superior hæmorrhoidal branch of the inferior mesenteric, and below with the inferior hæmorrhoidal twigs from the internal pudic. It likewise supplies twigs to the prostate and the seminal vesicle.

The *obturator artery* (arteria obturatoria) proceeds forwards upon the inner aspect of the pelvic wall to the upper part of the ~~thyroid foramen~~. ~~Here it comes into relation with the nerve of the same name, and both leave the cavity by passing above the pelvic fascia and below the groove upon the under surface of the ascending ramus of the pubic bone.~~ Within the pelvis it lies in the extra-peritoneal fatty tissue, between the peritoneum and the parietal pelvic fascia; the obturator nerve is placed at a higher level, whilst the vein lies below it. In this part of its course the obturator artery furnishes a small *iliac branch* to the parts in the iliac fossa, and a minute *pubic branch*, which ramifies upon the back of the pubic bone and anastomoses with a similar branch from the deep epigastric artery.

The *pudic artery* (arteria pudenda interna) is now seen in the *pelvic part* of its course. It proceeds downwards upon the pyriformis muscle and sacral nerves, and, reaching the lower part of the great sacro-sciatic foramen, it leaves the pelvis by passing through it. In the gluteal region it appears between the pyriformis and the superior gemellus.

The *sciatic artery* (arteria glutæa inferior) can be recognised from its being the largest of the branches which spring from the anterior division of the internal iliac, and also from its generally lying a little behind the pudic. It proceeds downwards upon the pyriformis muscle and sacral nerves, and quits the pelvis for the gluteal region through the lower part of the great sacro-sciatic foramen.

The *ilio-lumbar artery* (arteria ilio-lumbalis) is directed upwards, outwards, and backwards behind the obturator nerve, the external iliac vessels, and the psoas muscle, to the iliac fossa, where it divides into a lumbar and an iliac branch. The *lumbar branch* (ramus lumbalis) runs upwards and ramifies in the substance of the psoas and quadratus lumborum muscles, where it anastomoses with the lower lumbar arteries. It gives off a small *spinal branch* (ramus spinalis), which enters the spinal canal through the intervertebral foramen between the last lumbar vertebra and the sacrum. The *iliac branch* (ramus iliacus) breaks up into twigs, which run outwards, some in the substance of the iliacus muscle, and others between it and the bone; of the latter set, one will be observed to enter the nutrient foramen in the iliac fossa. Reaching the crest of the ilium, the terminal branches of this vessel anastomose with the deep circumflex iliac and lumbar arteries.

The *gluteal artery* (arteria glutæa superior) is the largest of the branches of the internal iliac, and may be regarded as the continuation of its posterior division. It has a very short course within the pelvis. Passing backwards between the lumbo-sacral cord and the first sacral nerve, it leaves the pelvis through the upper part of the great sacro-sciatic foramen, and appears in the gluteal region in the interval between the pyriformis and gluteus minimus muscles.

The *lateral sacral* (arteria sacralis lateralis) is usually represented by two arteries, which extend downwards upon the pyriformis muscle and sacral nerves, external to the anterior sacral foramina and the sympathetic cord. They furnish twigs to the parts upon which they lie, and branches which enter the sacral foramina (rami spinales). The latter, after supplying the membranes and nerve-roots within the sacral canal, emerge behind, through the posterior sacral foramina, and there anastomose with branches of the gluteal artery. The lower of the two lateral sacral arteries inosculates inferiorly with the middle sacral.

Superior Hæmorrhoidal Artery (arteria hæmorrhoidalis superior).—This is the direct continuation into the pelvis of the inferior mesenteric artery. After crossing the common iliac artery it enters the root of the pelvic meso-colon and descends between its two layers as far as the third piece of

the sacrum. Here it divides into two branches which proceed downwards on either side of the rectum. These vessels soon break up into several smaller branches, which range themselves around the gut and pierce its muscular coat half-way down the rectum. Within the submucous coat they continue their course to the anal canal, where it is usual to find one within each column of Morgagni. Above the anus they anastomose freely with each other, with the inferior hæmorrhoidal branches of the internal pudic arteries, and higher up with the middle hæmorrhoidal branches of the internal iliac arteries.

Middle Sacral Artery (*arteria sacralis media*). — The middle sacral has already been observed springing from the posterior aspect of the termination of the abdominal aorta, between the two common iliac arteries. It descends upon the bodies of the lower two lumbar vertebræ and under cover of the left common iliac vein. Reaching the sacrum, it continues its downward course in the mesial plane till it arrives at the coccyx. Here it ends by anastomosing with the lateral sacral arteries, and by sending minute branches to the coccygeal body. From each side it gives off small twigs, which ramify upon the anterior aspect of the sacrum and insinuate with branches of the lateral sacral arteries.

Veins of the Pelvis.—The arrangement of the veins in the pelvis corresponds in a great measure with that of the arteries; still, there are some important points of difference, viz. :—

(1.) The *dorsal vein of the penis*, instead of joining the pudic vein, proceeds backwards, divides into two, and enters the prostatic plexus of veins.

(2.) The *ilio-lumbar* and the *middle sacral veins*, as a general rule, pour their blood into the common iliac veins.

(3.) The veins around the prostate, bladder, and rectum are exceedingly large and numerous, and constitute dense plexuses, which freely communicate with each other. The *prostatic* and *vesical plexuses* have already been noticed. They are directly continuous, and the blood is drained from them by the vesical veins. The *hæmorrhoidal plexus* surrounds the lower third of the rectum subjacent to the mucous membrane. From this the blood is drained away by three different veins—viz., the inferior hæmorrhoidal, which carries it to the pudic vein; the middle hæmorrhoidal, which leads it to the internal

iliac vein ; and the superior hæmorrhoidal vein, which is one of the rootlets of the portal vein. The hæmorrhoidal plexus may therefore be regarded as being the link between the systemic and portal systems of veins. This has an important bearing upon the production of hæmorrhoids, which consist in a varicose condition of the hæmorrhoidal veins. As we have seen, the portal vein and its tributaries are devoid of valves ; consequently, anything retarding the flow of blood through the portal system will react upon the hæmorrhoidal plexus, cause its distension, and predispose to hæmorrhoids.

The *internal iliac vein* (vena hypogastrica) proceeds upwards behind the artery of the same name, and joins the common iliac vein. With the exception of the ilio-lumbar vein, it receives tributaries corresponding to the branches of the artery.

Lymphatics of the Rectum.—Four or five rectal glands are disposed in relation to the superior hæmorrhoidal vein and its two main tributaries. Most of the rectal lymphatic vessels join these and then proceed to the sacral glands on the front of the sacrum. It should not be forgotten that the cutaneous lymphatics from around the anus pass to the inguinal glands.

Dissection.—The diaphragm of the pelvis should next be examined. It is composed of two muscles upon each side—viz., the *levator ani* and the *coccygeus*. Draw the viscera as far as possible to the right, and remove what remains of the visceral layer of the pelvic fascia upon the left side. This will expose the upper surface of the levator ani, the connections of which can now be studied. In cleaning the coccygeus, be careful not to injure the fifth sacral nerve and the coccygeal nerve, both of which pierce it near its insertion.

Levator Ani.—The levator ani is a strong sheet of muscular fibres, which forms the anterior and greater part of the pelvic diaphragm. It has a triple origin. The *anterior fibres* spring from the back of the body of the pubic bone ~~between the attachments of the visceral and parietal layers of pelvic fascia ; the posterior fibres~~ arise from the pelvic surface of the ischial spine ; whilst the *intermediate fibres*, constituting the greater part of the muscle, take origin from the inner surface of the parietal pelvic fascia along a line which varies in level in different individuals.

The insertion of the levator ani must also be looked at from three points of view. The *anterior fibres* proceed down-

wards upon the lateral aspect of the prostate; and from the support which they give to it, they are sometimes spoken of under the name of *levator prostatae*. Behind the prostate a certain number of these fibres meet in the mesial plane, with the corresponding fibres of the opposite side, and are inserted into the central point of the perineum, but the majority enter the muscular wall of the anal canal. The *intermediate* and




FIG. 187. —Dissection of the two Levatores Ani. The pelvis is tilted forwards and the pubic arch has been removed. Both layers of the triangular ligament, the parts in relation to them, and the pubic origins of the levatores ani have also been taken away. The portion of bone removed is indicated by the dotted lines.

largest portion of the muscle slopes downwards, backwards, and inwards, and gives support to the rectum and bladder. At the junction of the rectum and the anal canal the muscle forms a thick collar around the gut, pinches it in and is then continued down on the side of the anal canal in the interval between the two sphincter muscles (Fig. 177, p. 519). The *posterior fibres* pass backwards and inwards and are inserted into the median ano-coccygeal raphe behind the rectum, and

also into the side of the lower end of the coccyx. They support the portion of the rectum which extends from the tip of the coccyx to the anal canal.

The levator ani draws its nerve supply from the *fourth sacral nerve* and the *inferior hæmorrhoidal nerve*.

Coccygeus.—This is a small triangular muscle which lies behind and upon the same plane as the levator ani—indeed, their margins are contiguous. It arises by its narrow end from the pelvic surface of the ischial spine, and from the parietal pelvic fascia above the spine. Expanding as it passes inwards, it is inserted into the margin of the lower piece of the sacrum and the margin and anterior aspect of the coccyx. It is supplied by twigs from the *fourth* and *fifth sacral nerves*.

Pelvic Spinal Nerves.—The anterior primary divisions of the spinal nerves in the pelvis are *six* in number, viz., *five sacral* and *one coccygeal*. These should be dissected, and the various branches which they give off followed to their distribution, or the point where they quit the pelvis. It is well to begin by cleaning the lumbo-sacral cord and securing the upper root of the *superior gluteal nerve* which springs from its posterior aspect. The upper four sacral nerves appear through the anterior sacral foramina; the fifth sacral nerve comes forward in the interval between the sacrum and coccyx; and the coccygeal a little lower down at the side of the coccyx. The two latter are very minute, but they can be easily found by following downwards a twig from the *fourth* to the *fifth sacral nerve*, and another twig which connects the *fifth nerve* with the *coccygeal*.

The first and second sacral nerves are very large, and almost equal in size; the third sacral nerve is much smaller than these, and the fourth still smaller than the third. Each spinal nerve is joined by *grey rami communicantes* from the sympathetic; whilst from the third and also from the fourth sacral nerve *white rami communicantes* pass out to join the pelvic plexuses from the sympathetic cord.

The first three sacral nerves unite to form the *sacral plexus*. This is joined above by the lumbo-sacral cord, and below by a branch from the fourth sacral nerve.

The fifth sacral nerve and the coccygeal nerve, with the descending branch of the fourth sacral nerve, unite to form the *sacro-coccygeal plexus*.

Sacral Plexus (plexus sacralis).—When the nerves which enter the sacral plexus are dissected they will be seen to resolve themselves into two flattened bands—viz., an upper sciatic and a lower pudendal. The *sciatic band* is very large, and is formed by the union of the lumbo-sacral cord with




FIG. 188.—The Sacral and Sacrococcygeal Plexuses, as seen from behind.

the first sacral nerve and the greater portion of both the second and the third sacral nerves. It proceeds downwards and outwards to the lower part of the great sacro-sciatic foramen, and, here much reduced in width and increased in thickness, it enters the gluteal region below the level of the pyriformis muscle as the

great sciatic nerve. This nerve indeed may be regarded as the direct continuation of the sciatic band of

the plexus into the thigh. The *pudendal band* is small, and lies at a lower level than the sciatic

band. It takes origin by roots which spring from the second, third, and fourth sacral nerves, and unite in a plexiform manner to form the band. It leaves the pelvis through the lower part of the great sacro-sciatic foramen, below the pyriformis, and is continued directly into the *internal pudic nerve*.

The sacral plexus rests upon the pyriformis muscle; whilst, anteriorly, it is clothed by parietal pelvic fascia, which separates it from the branches of the internal iliac artery.

The great sciatic nerve divides in the back of the thigh into its internal and external popliteal branches, and it is not uncommon for these branches

to arise separately from the sacral plexus. Further, even in those cases where the division does not take place until the nerve has reached the thigh, it is possible by removal of its sheath to resolve it into its two component parts and trace these up to their origin from the various nerves which enter the sciatic band. All the nerves which enter the sciatic band, with the exception of the upper part of the third sacral nerve, are composed of anterior and posterior trunks. The posterior trunks of the two nerves which enter the lumbo-sacral cord, of the first and of the second sacral nerves, unite to form the *external popliteal* or *peroneal nerve*; whilst the anterior trunks of the same nerves, with the upper part of the third sacral nerve, form by their union the *internal popliteal* or *tibial nerve*. Of the subsidiary branches which spring from the sciatic band within the pelvis, some proceed from the anterior trunks and others from the posterior trunks (see diagram).

In addition to the two terminal branches of the sacral plexus (great sciatic and internal pudic) which have been seen to be continuations of the two bands into which the plexus resolves itself, there are various other twigs given off from it—viz. :—

1. Superior gluteal.
2. Inferior gluteal.
3. Small sciatic.
4. Nerve to the obturator internus and superior gemellus.
5. Nerve to the quadratus femoris and inferior gemellus.
6. Perforating cutaneous nerve.
7. Branches to the pyriformis muscle.
8. Branches to the pelvic viscera.

The *superior gluteal nerve* (nervus glutæus superior) arises on the posterior aspect of the plexus by three roots from the posterior trunks of the lumbo-sacral cord and of the first sacral nerve. It leaves the pelvis with the gluteal vessels through the upper part of the great sacro-sciatic foramen, and in the gluteal region is distributed to the gluteus medius, gluteus minimus, and tensor fasciæ femoris muscles.

The *inferior gluteal nerve* (nervus glutæus inferior) is the special branch of supply to the gluteus maximus. It arises upon the posterior aspect of the plexus, from the lumbo-sacral cord and from the first and second sacral nerves, and gains the gluteal region through the lower part of the great sciatic foramen below the level of the pyriformis muscle.

The *small sciatic nerve* (nervus cutaneus femoris posterior) is often closely associated at its origin with the preceding branch. It arises on the posterior aspect of the plexus by two or more roots from the first, second, and third sacral nerves, and leaves the pelvis through the lower part of the great sacro-sciatic foramen.

The *nerve to the obturator internus* springs from the anterior aspect of the sacral plexus. It accompanies the pudic nerve through the great sacro-sciatic foramen into the gluteal region, where it gives a twig to the superior gemellus. It reaches the obturator internus by passing through the small sacro-sciatic foramen, and ends by sinking into the inner aspect of this muscle.

The *nerve to the quadratus femoris* arises from the upper part of the anterior aspect of the plexus, and enters the gluteal region by passing through the lower part of the great sacro-sciatic foramen. It also supplies the gemellus inferior and a branch to the hip-joint.

The *perforating cutaneous nerve* arises from the posterior aspect of the second and third sacral nerves. It pierces the great sacro-sciatic ligament, and then winds round the lower border of the gluteus maximus to gain the skin over the lower and inner part of that muscle.

The *twigs to the pyriformis* usually spring from the second and third sacral nerves.

The *visceral branches* (white rami communicantes) come from the third and fourth sacral nerves.

Sacro-Coccygeal Plexus.—The *fourth sacral nerve*, as we have seen, sends upwards a branch to join the sacral plexus; it also sends a twig downwards to unite with the fifth sacral nerve. But in addition to these connecting branches, it gives off *muscular* and *visceral branches*.

The *muscular branches* are distributed to three muscles—viz., the levator ani, the coccygeus, and the sphincter ani externus. The last of these has already been dissected in the perineum, under the name of the “perineal branch of the fourth sacral nerve.”

The *visceral branches* (white rami communicantes) are numerous, and are directed inwards towards the viscera. Here they join with the pelvic plexus of nerves. Some, however, may be found entering the viscera directly. The third sacral nerve also gives off visceral branches.

The *fifth sacral nerve* pierces the coccygeus. After being joined by the branch from the fourth sacral nerve, it turns downwards and unites with the coccygeal nerve. It supplies one or two minute filaments to the coccygeus muscle.

The *coccygeal nerve* is a very delicate filament. It emerges from the lower end of the sacral canal, and makes its appearance by piercing the sacro-sciatic ligaments and the coccygeus muscle. It is now joined by the fifth sacral nerve and runs downwards. Near the tip of the coccyx it is directed backwards through the coccygeus muscle, and ends in the skin in this neighbourhood.

Dissection.—The dissector should, in the next place, make out the distribution of the sympathetic nerves within the pelvis. These have, no doubt, been considerably injured in previous dissections, but those which remain must be carefully traced.

Pelvic Plexuses of the Sympathetic.—The hypogastric plexus has been observed to end inferiorly by dividing into two lateral portions, which are prolonged downwards, one upon each side of the rectum. These are termed the *pelvic plexuses*, and each consists of a dense meshwork of sympathetic nerves. In addition to the branches from the hypogastric plexus, they receive numerous twigs from the third and fourth sacral spinal nerves, and the points at which these unite with the sympathetic filaments are marked by minute ganglia. The pelvic plexuses also acquire branches from the sacral portion of the sympathetic cord.

Prolongations from the pelvic plexus upon each side are sent along the various branches of the internal iliac artery. There are thus formed various secondary plexuses—viz., the *vesical plexus*, to the coats of the bladder, to the seminal vesicle and the vas deferens; the *hæmorrhoidal plexus*, to the rectum; and the *prostatic plexus*, to the prostate.

The prostatic plexus proceeds forwards between the prostate and the levator ani, and sends twigs to the erectile tissue of the penis. These latter are termed the *cavernous nerves*.

Gangliated Cord of Sympathetic.—The sympathetic cord as it enters the pelvis is considerably reduced in size. It proceeds downwards in front of the sacrum, along the inner side of the anterior sacral foramina. *Above*, it is continuous with the lumbar portion of the sympathetic cord, whilst *below*, it ends in the mesial plane in front of the coccyx in a minute ganglion, termed the *ganglion impar*, which acts as a bond of union between the cords of the two sides. The ganglia are very variable in number, but as a general

rule there are four. Each of these is brought into connection with the spinal nerves by short grey rami communicantes.

The branches of these ganglia are chiefly distributed upon the anterior surface of the sacrum and around the middle sacral artery. A few filaments from the upper part of the gangliated cord are given to the pelvic plexuses, and some minute twigs proceed from the ganglion impar to the parts about the coccyx and to the coccygeal body.

Coccygeal Body.—This is a minute lobulated body about the size of a small pea, and situated in front of the tip of the coccyx. It is composed of masses of polyhedral cells, separated from each other by strands of connective tissue. Numerous sympathetic twigs, and also minute branches of the middle sacral artery, enter it.

Removal of the Viscera.—The viscera must now be removed from the pelvic cavity. Begin by dividing the vessels and nerves which enter them, the levator ani, and the anterior true ligaments of the bladder. Then sever the parts which hold the membranous portion of the urethra and the bulb of the penis to the pubic arch. Great care must be taken at this stage not to injure the delicate walls of the urethra, or to lose sight of Cowper's glands. Lastly, separate the rectum from its connections with the coccyx. Laying aside the viscera for a little, the dissector should study the muscles in relation to the pelvic wall—viz., the obturator internus and the pyriformis.

Obturator Internus.—This muscle clothes the lateral wall of the pelvis upon its inner aspect. Remove the parietal layer of the pelvic fascia, and it will come into view. It is a fan-shaped muscle, and has an extensive origin, viz.—(1) from the circumference of the thyroid foramen, except above, where the obturator vessels and nerve quit the pelvis; (2) from the deep surface of the membrane which extends across the foramen; and (3) from the surface of bone behind the thyroid foramen as far back as the great sciatic notch. A few fibres are also derived from the parietal pelvic fascia which covers it. From this origin the fibres converge towards the small sciatic notch, and end in a tendon which issues from the pelvis through the lesser sacro-sciatic foramen. Entering the gluteal region, it is inserted in conjunction with the gemelli muscles into the upper part of the great trochanter of the femur. The small sciatic notch, over which the tendon glides, is coated with smooth cartilage, and this is raised into three or four parallel ridges, which fit into

fissures upon the deep surface of the tendon. A synovial bursa intervenes between them.

The obturator internus is supplied by a special branch from the upper part of the sacral plexus.

Pyriformis.—The pyriformis is placed against the anterior aspect of the posterior wall of the pelvis. It arises by three processes, from the anterior surface of the second, third, and fourth sacral vertebræ between the sacral foramina; it also takes origin from the innominate bone, where it forms the upper part of the great sciatic notch, and from the great sacro-sciatic ligament. The muscle leaves the pelvis through the great sacro-sciatic foramen, and is inserted by a rounded tendon into the top of the great trochanter of the femur. It is supplied by branches from the sacral plexus.

Structure of the Wall of the Rectum.—Turning now to the pelvic viscera, separate the rectum and anal canal from the bladder and prostate, and, having stuffed the rectum moderately with tow, proceed to dissect its walls. The rectum presents several coats, viz. :—

- | | | |
|-----------------|------------|---------------|
| 1. Serous. | | 3. Muscular. |
| 2. Aponeurotic. | | 4. Submucous. |
| | 5. Mucous. | |

The serous and aponeurotic coats have already been examined. The *serous coat* is altogether absent from the lower third of the rectum, whilst it only gives a partial covering to its upper two-thirds. It clothes its upper portion anteriorly and laterally, whilst lower down, before it leaves the gut, it is only found on its anterior aspect. The *aponeurotic sheath* is very distinct in the lower part of the rectum, but, as it is traced upwards, it diminishes in strength, and finally thins down into the subserous tissue of the gut. The aponeurotic coat is derived from the visceral pelvic fascia in the manner already described, and it is loosely attached to the subjacent muscular coat of the lower part of the rectum by intervening lax areolar tissue.

The *muscular coat* is thick and strong, and is composed of two layers of involuntary non-striated muscle-fibres—viz., an external longitudinal and an internal circular layer. The *longitudinal fibres* are continuous above with the three longitudinal bands of the colon. As these bands approach the rectum, the fibres which compose them spread out, so as

to form a continuous layer round the rectum. This layer, however, is not uniformly thick on all aspects of the gut. On the front and on the back the fibres are massed together into an anterior and posterior band, which are so disposed that they maintain the flexures of the rectum, and prevent it from elongating as it becomes loaded with contents. The *circular muscular fibres* extend transversely around the gut, and form a continuous and more or less uniform layer, subjacent to the longitudinal fibres.

The *submucous coat* is composed of lax areolar tissue, which allows the mucous membrane to move freely upon the muscular coat.

Interior of the Rectum.—The rectum and the anal canal may now be opened by dividing the anterior wall in the mesial plane with the scissors. The mucous membrane of the rectum is thicker than that of the colon, and is more freely movable upon the muscular tunic. In consequence of this mobility, it is thrown into irregular folds or *rugæ* when the gut is empty. It presents a punctated appearance, from the presence of numerous minute tubular pits, around the bottom of which lymphoid tissue is accumulated (Birmingham).

The *rectal valves* or *valves of Houston* should now be visible, although they show best when the rectum is distended. They are three horizontally disposed crescentic infoldings of the wall of the rectum, which help to support the contents of this portion of the gut when it is loaded. They correspond to the inflections of the wall of the gut which are produced by its lateral flexures. Consequently they are usually three in number—two on the left side and one on the right side,—and each is formed by an infolding of the mucous, submucous, and a considerable part of the muscular coats. The position of these valves is variable; but, speaking generally, the right valve is placed at the level of the bottom of the recto-vesical pouch, whilst the two left valves are respectively situated about an inch and a half above and about the same distance below the intermediate right valve (Birmingham).

Anal Canal.—The anal canal has a very thick and powerful muscular wall. The *internal circular layer* of muscular fibres is prolonged downwards from the rectum, and becomes greatly thickened in the wall of the anal canal.

The muscular cylinder thus formed constitutes the *internal sphincter*, which embraces the whole length of the canal, with the exception of its lower half-inch. The *longitudinal muscular fibres* of the rectal wall are also prolonged downwards in association with the fibres of the levator ani on the outer aspect of the internal sphincter. The *external sphincter* surrounds the lower part of the canal on the outside of the levator ani.

It is sometimes stated that the thick anterior portions of the levator ani clasp between them the upper part of the anal canal by passing back on either side of it. It is a difficult matter to state definitely the precise




FIG. 189.—The lower part of the Rectum and the Anal Canal opened up.
(Charles B. Ball.)

relations of the levator ani to the anal canal and rectum. Unquestionably there is a thick collar of muscular fibres surrounding the gut in this situation, but it is more than doubtful if it is formed by the anterior fibres of the muscle alone.

The *mucous lining* of the anal canal presents certain very characteristic features. It is thrown into a series of longitudinal folds termed the *columnæ rectæ* or the *columns of Morgagni*. A short distance above the orifice of the anus the lower ends of these are connected with each other by a number of faintly marked, irregularly disposed, semilunar folds which are arranged circularly around the gut. These are the *anal valves*, and when strongly developed they form a number of little pocket-like recesses between the vertical

columns (sinus Morgagni). It is here that the scaly epithelium of the integument merges into the columnar epithelium of the gut. These semilunar folds are of importance in connection with the condition known as "fissured anus" (Ball).

Dissection.—The bladder must be fully distended with air before the dissection of its walls is commenced.

Coats of the Bladder.—The bladder presents the following coats :—

- | | | |
|---------------|------------|---------------|
| 1. Serous. | | 3. Muscular. |
| 2. Subserous. | | 4. Submucous. |
| | 5. Mucous. | |

The *serous covering* is partial and confined to its superior part. The *subserous coat* consists of a thin stratum of areolar tissue which binds the peritoneum to the muscular coat. The vesical layer of pelvic fascia may be considered to thin away into this coat.

The *muscular tunic* presents three layers of non-striated muscular fibres, viz. :—

1. External longitudinal fibres.
2. Circular fibres.
3. Internal longitudinal fibres.

The *external longitudinal fibres*, frequently termed the *detrusor urinæ*, give a continuous covering to the bladder, but are most apparent upon its inferior and superior surfaces. They may be considered to spring from the back of the pubic bones, the anterior true ligaments of the bladder, and the base of the prostate. From these attachments they mount upwards and spread out upon the inferior surface of the bladder. At the apex, a few pass on to the urachus, but the majority are carried backwards over the superior aspect and base of the bladder to the prostate, to which they are attached.

The *circular fibres* can hardly be said to give a continuous and uniform covering to the bladder. They are arranged in coarse bundles, many of which run obliquely as well as circularly around the organ. At the urethral orifice the bundles become much finer and are massed together to form a sphincter—the fibres of which are more or less continuous with those of the prostate.

The *internal longitudinal fibres* constitute an incomplete layer. According to F. Wood Jones, this layer only exists on the inferior wall, and to some extent on the superior wall of the bladder. It is not present in the basal part of the bladder.

The *submucous coat* is the loose areolar bed in which the blood-vessels and nerves ramify before they enter the mucous membrane. It connects the mucous and muscular coats, and has a considerable amount of elastic tissue entering into its composition.

Dissection.—The *mucous membrane* which lines the bladder should now be examined, and, for this purpose, it is necessary to open up the viscus by




FIG. 190.—Interior of Bladder in region of Urethral Orifice.
(A. F. Dixon.)

an incision along its inferior aspect from the apex to the neck. It is better to lay open the first portion of the urethra at the same time by carrying the incision along the mesial plane through the anterior part of the prostate.

Mucous Membrane of the Bladder.—When the mucous membrane is washed, it will be observed to be highly rugose, except over a triangular area immediately above and behind the urethral orifice. This rugosity is due to the loose manner in which the membrane is bound by the submucous layer to the muscular coat. When the bladder is distended, the folds are effaced, and the mucous lining becomes smooth.

Orifices of the Bladder.—The *orifice of the urethra* (orificium urethræ internum), or the canal which conducts the urine from the bladder, is situated on the back portion of the

inferior surface. Immediately above this, the mucous membrane will be noticed to be elevated so as to form a slight prominence, which bulges forwards over the aperture. This elevation is termed the *uvula vesicae*, and it results from the presence of the so-called middle lobe of the prostate, which lies behind it. Probes should now be passed along the ureters into the interior of the bladder. By this means the dissector will be able to see how very obliquely these ducts pierce the walls of the bladder. Indeed, they traverse the wall for more than three-quarters of an inch before they reach the internal orifices. This arrangement, whilst it permits the passage of urine from the ureter into the bladder, exercises a valvular action in distension of the viscus, and prevents any backward flow of the urine into the ureters. The *openings of the ureters* (orificia ureterium) are two slit-like apertures, which are placed about an inch and a half apart from each other, and about the same distance from the urethral orifice.

Trigone of the Bladder.—The three orifices of the bladder constitute the angles of an equilateral triangle, which is termed the *trigone*, the boundaries of which are formed by lines drawn between the openings of the ureters and from each of these forwards to the urethral orifice. The mucous membrane over this area presents a marked contrast to the same membrane in other parts of the bladder. Here it is always smooth, in whatever condition the viscus may be, and this is due to its being tightly bound down to the subjacent muscular coat. It is also said to be more sensitive than in other parts of the bladder.

Dissection.—The bladder should now be pinned out on the bottom of a cork-lined tray filled with water. When this is done the mucous membrane over the trigone may be carefully raised. A band of muscular fibres will be observed to take a curved course, at the base of the trigone, between the two ureters. In certain cases another band may be traced from the ureter along each side of the trigone towards the urethral orifice. These muscular bands form the slightly marked ridges which bound the trigone.

Urethra (urethra virilis).—The urethra is the canal through which the urine, the semen, and the secretions of the vesiculæ seminales, the prostate, and Cowper's glands are emitted from the body. It commences at the neck of the bladder and ends on the ~~glans penis, and its average length~~ is somewhere about eight or nine inches. It is customary

to divide the urethra into three parts, from the different character of the structures which it traverses. The *first* or *prostatic portion* (pars prostatica) is contained within the substance of the prostatic gland; the *second* or *membranous portion* (pars membranacea) extends from the prostate to the bulb of the corpus spongiosum penis, and is surrounded by the fibres of the compressor urethræ muscle; whilst the *third*




FIG. 191.—Diagram of the Bladder, Urethra, and Penis. (Délépine.)

or *spongy part* (pars cavernosa) traverses the entire length of the corpus spongiosum.

Dissection.—The urethral canal must now be laid open throughout its whole length, in order that its various parts may be studied. Lay the bladder and penis upon a block, and extend the incision which has already been made through the prostate, along the upper wall of the membranous portion of the urethra, and along the dorsum of the penis between the two corpora cavernosa and through the glans. This cut must be made as far as possible in the mesial plane.

Prostatic Portion of the Urethra.—This part of the urethra is about one inch and a quarter in length. It traverses

the prostate in front of its so-called middle lobe, and takes a very nearly vertical course through its substance. It is the *widest* and at the same time the *most dilatable* part of the canal; and further, it is *fusiform*, being wider in the middle than at either its commencement or termination.

In connection with the posterior wall or floor of the prostatic portion of the urethra, there are certain important features to be noted. The mucous membrane along the mesial plane is raised into a prominent ridge called the *verumontanum*.¹ This commences a short distance below the orifice of the urethra in the bladder, and extends downwards for about three-quarters of an inch. Above, it rises to a considerable height, but below, it gradually fades away. On each side of the verumontanum, the floor of the urethra is hollowed out into a longitudinal depression, termed the *prostatic sinus*, into which numerous *prostatic ducts* open. This may be rendered evident by squeezing the prostate, when fluid will be observed to exude into the two sinuses. These ducts proceed from the glandular substance of the prostate. A close inspection of the floor of the urethra above the verumontanum will reveal the apertures of the ducts of the so-called middle lobe of the prostate.

Immediately below the highest part of the verumontanum, the mucous membrane dips backwards and upwards behind the middle lobe of the prostate, so as to form a small recess or *cul-de-sac*. This is the *sinus pocularis* or the *utricle*. Gauge its extent by means of a probe. It will be observed to be from a quarter to half an inch long, and to be narrow at its orifice, but to widen out considerably towards its blind extremity. It is of interest, both from a developmental and a surgical point of view. It is the representative, in the male, of the uterus and vagina in the female. Practically, it is important, because in some cases it is large enough to entangle the point of a small catheter or bougie.

The dissector should now pass bristles along the *common ejaculatory ducts*. They run downwards between the so-called

¹ Other terms are applied to this mesial ridge on the floor of the urethra—viz., *crest of the urethra*, *colliculus seminalis*, and *caput gallinaginis*.

middle and lateral lobes of the prostate. Finally, entering the wall of the sinus pocularis, they open by slit-like apertures, just within the margin of its orifice.

Owing to the presence of the verumontanum on the floor of the canal, and the prostatic sinus upon each side of it, a transverse section of the prostatic portion of the urethra presents a crescentic figure—the convexity of the crescent being directed forwards and the concavity backwards.

As old age approaches, the prostate is very liable to become enlarged, and the most important result of this is the effect which it exerts upon the urethra. When the enlargement is uniform, the prostatic portion of the canal is simply elongated; when, however, the enlargement is confined to one part of the gland, it impinges upon the urethra, and produces an alteration in its direction, and a consequent difficulty in micturition. When the middle lobe alone is increased in size, it projects forwards into the bladder so as to close the commencement of the canal. It is only in pathological conditions of the prostate that the so-called middle lobe becomes a distinct and more or less independent part of the organ. In health it is merely marked off from the rest of the prostate by the presence of the ejaculatory ducts and the sinus pocularis in the substance of the organ.

Membranous Portion of the Urethra.—This is the *narrowest* and the *shortest* division of the urethra. It extends from the prostate to the bulb of the penis, and describes a gentle curve from above, downwards and forwards, behind the lower border of the symphysis pubis, from which it is distant about one inch. Its length is fully three-quarters of an inch, and its concavity is directed forwards and upwards, and its convexity backwards and downwards. Throughout its entire extent it is enveloped by the fibres of the compressor urethræ muscle, whilst towards its termination Cowper's glands are placed behind it—one on each side.

The relation of the membranous part of the urethra to the triangular ligament and the parietal pelvic fascia is important. As it emerges from the prostate, the parietal pelvic fascia (*i.e.*, the deep layer of the triangular ligament) sweeps backwards upon it to take part in the formation of the prostatic capsule. At its termination it pierces the triangular ligament proper about an inch below the symphysis pubis. It may therefore be looked upon as lying in the interval between these membranes.

Immediately subjacent to the mucous membrane the membranous part of the urethra is surrounded by a thin coating of erectile tissue, outside

which there is a muscular tunic composed of involuntary fibres arranged circularly.

Spongy Portion of the Urethra.—This is the *longest* division of the urethra. It is embedded throughout in the substance of the corpus spongiosum penis, and shows considerable differences in its calibre as it is followed forwards to the glans. At each expansion of the corpus spongiosum there is a corresponding dilatation of the urethra. Thus the canal presents two dilatations—(1) in the bulb, and (2) in the glans; between these it is of uniform diameter, and slightly wider than the membranous part. The dilatation of the urethra in the glans is termed the *fossa navicularis*. At its




FIG. 192.—Median section through the terminal part of the Penis.

orifice, which is termed the *meatus urinarius*, the canal is much contracted, and is even narrower than any part of the membranous portion. This aperture is a vertical slit, the lower end of which is connected with the prepuce by a

fold of mucous membrane, termed the *frenum preputii*.

In the bulb and in the glans penis the erectile tissue of the corpus spongiosum is disposed very unequally around the urethra. In the former it is chiefly massed below or behind the tube, whilst in the glans it is chiefly placed in front and upon each side, a very thin layer covering it posteriorly.

The *ducts of Cowper's glands* open into the spongy portion of the urethra by piercing its floor about an inch in front of the triangular ligament. These orifices are extremely minute, and very difficult to find.

By making a small hole in the wall of the duct as it emerges from the gland, and passing a fine bristle along it, the dissector may be able to detect the opening in the urethral floor. The ducts proceed in the first place through the erectile tissue of the bulb, but towards their termination they lie immediately subjacent to the mucous membrane.

The walls of the urethra are always in apposition except

when urine is flowing through it. A transverse section through the spongy portion, except at its anterior part, would give the appearance of a transverse slit. In the fossa navicularis, however, the slit becomes vertical, showing that here the side walls are in contact.

Mucous Membrane of the Urethra.—The mucous lining of the urethra is continuous posteriorly with that of the bladder, and anteriorly with the integument covering the glans penis. It is likewise continuous with the mucous membrane which lines the various ducts which open into the urethra. It is everywhere studded with the mouths of minute recesses, called *lacunæ urethrales*. These are particularly plentiful on the floor of the spongy part, and, as a general rule, they are directed forwards towards the meatus urinarius.

Direction of the Urethral Canal.—The prostatic portion is directed downwards and very slightly forwards; the membranous part describes a slight curve behind the symphysis, the concavity of which looks forwards; whilst the spongy part at first ascends, and then curves downwards. The urethra, therefore, in the flaccid condition of the penis, takes a course in which there are two curves, like the letter *o* reversed. When the penis is raised towards the front of the abdomen the curve in the spongy part of the canal is obliterated, and there is now only one curve, the concavity of which is directed upwards.

Structure of the Prostate.—In the course of an ordinary dissection it is hardly to be expected that the dissector will be able to make out the structure of the prostate in all its details. It is mainly composed of involuntary muscular tissue. This tissue forms a layer on the outside of the organ, and also gives a coating to the urethra as it traverses the prostate. The outside and inside fibres are continuous in front—indeed, the greater part of the anterior portion of the prostate is muscular. The fibres surrounding the urethra are also to some extent continuous above with the circular fibres of the bladder, and below with the circular fibres of the membranous part of the urethra; further they radiate out into the substance of each lateral part of the gland. The glandular tissue is interspersed amidst the muscular bundles, but none is to be seen in front of the urethra.

Structure of the Penis.—In the dissection of the urethra

the corpora cavernosa penis have been separated from each other. Each will be seen to be enveloped in an exceedingly strong fibro-elastic sheath. In the mesial plane the sheaths become continuous with a strong septum, which intervenes between the two cylindrical masses. This septum receives the name of *septum pectiniforme*, because in front it is very imperfect, being broken up by vertical slits into a series of processes like the teeth of a comb. The two fibrous cases thus constructed are filled with erectile tissue. Fibrous lamellæ and bands proceed from the deep surface of each sheath and join with each other to form a spongy framework.

The interstices of this framework freely communicate with each other, and are filled with venous blood. By squeezing the corpora cavernosa under the tap and washing out the blood some idea of the trabeculæ may be obtained.




FIG. 193.—Transverse section through the body of the Penis.

The corpus spongiosum has a similar structure. The enclosing sheath, however, is very delicate, and the trabeculæ are much finer.

Vesiculæ Seminales.—

If the dissector has not already unravelled the vesiculæ seminales, he should now do so, and, at the same time, endeavour to make out the composition of their walls. This can best be done under water. In addition to the sheath derived from the recto-vesical fascia, each vesicle has a strong dense fibrous tunic and a certain proportion of transverse and longitudinal non-striated muscular fibres entering into the formation of its wall. Open them up and expose the *mucous lining*. This is remarkable for its honeycomb or reticular appearance. In this respect, therefore, it is not unlike the mucous membrane of the gall-bladder, only the meshes are finer and the pits smaller.

PELVIC ARTICULATIONS.

The pelvis is attached to the last lumbar vertebra, and its several parts are held together by the following articulations:—(1) Lumbo-sacral; (2) Sacro-coccygeal; (3) Coccygeal; (4) Sacro-iliac; (5) Pubic.

Dissection.—The nerves and blood-vessels of the pelvis must now be removed, and all adhering portions of muscle detached from the left innominate bone and the front and back of the sacrum. When this is done, the pelvis should be soaked for some time in warm water. By this proceeding the dissection of the ligaments will be rendered much easier.

Lumbo-sacral Articulations.—The last lumbar vertebra is joined to the sacrum by one *amphiarthrodial joint*, which connects the body of the vertebra to the base of the sacrum, and by two *diarthrodial joints*, between the two pairs of articular processes.

Capsular ligaments (capsulæ articulares) surround the articulations formed by the apposition of the articular processes, and each is lined by a synovial membrane.

The *anterior common ligament* (ligamentum longitudinale anterius) of the vertebral column is continued downwards over the anterior aspect of the body of the last lumbar vertebra to the anterior aspect of the first segment of the sacrum. In a similar manner the *posterior common ligament* (ligamentum longitudinale posterius) is prolonged downwards within the spinal canal, over the posterior aspect of the body of the last lumbar vertebra, to the upper part of that portion of the sacrum which forms the anterior wall of the sacral canal.

Ligamenta subflava (ligamenta flava) are also present. These are two short bands of yellow elastic tissue placed one on each side of the mesial plane. Superiorly they are attached to the anterior aspect of the lower borders of the laminæ of the last lumbar vertebra; whilst inferiorly they are fixed to the posterior aspect of the upper margins of the laminæ of the first sacral segment.

An *interspinous ligament* (ligamentum interspinale) connects the lower border of the spinous process of the last lumbar vertebra with the upper border of the spinous process of the first sacral vertebra. A *supraspinous ligament* (ligamentum

supraspinale) bridges across between the extremities of the same spinous processes.

So far, then, the ligaments of the lumbo-sacral articulations are identical with those which, above the level of the sacrum, bind the several segments of the spinal column together. Two additional ligaments—viz., the lumbo-sacral and the ilio-lumbar, must now be examined.

The *lumbo-sacral ligament* is the representative of the superior costo-transverse ligaments. It is a strong triangular fibrous band attached by its apex to the tip and lower border of the transverse process of the last lumbar vertebra. Expanding as it proceeds downwards, it is fixed below to the posterior part of the base of the sacrum, where some of its fibres intermingle with those of the sacro-iliac ligaments.

The *ilio-lumbar ligament* (ligamentum iliolumbale) may be considered to be a thickened and specially developed part of the anterior lamella of the lumbar fascia. It lies in the same plane and is directly continuous with it. It is triangular in shape, and is fixed by its apex to the tip of the transverse process of the last lumbar vertebra. Proceeding horizontally outwards, it is inserted into the inner lip of the iliac crest at the posterior part of the iliac fossa.

The *amphiarthrodial joint*, between the body of the last lumbar vertebra and the base of the sacrum, corresponds in every respect with the similar articulations above, between the bodies of the vertebræ. The opposed bony surfaces are each coated by a thin layer of hyaline cartilage, and are firmly united by an intervening disc of fibro-cartilage, which is dense and laminated externally, soft and pulpy towards the centre. The dissector should observe that this disc is the thickest of the series, and further, that it is wedge-shaped, being thicker in front than behind.

Sacro-coccygeal Articulation.—This is an amphiarthrodial joint. The articulating surfaces are each covered by a thin cartilaginous plate, and these are united by a disc of fibro-cartilage. The joint is strengthened in front by an *anterior ligament*, which extends downwards from the front of the sacrum to the anterior aspect of the coccyx, and by a *posterior ligament* which, attached above to the posterior border of the lower aperture of the sacral canal, proceeds downwards upon the posterior aspect of the coccyx. The latter ligament is

much the stronger of the two. In addition, fibrous bands will also be found passing between the cornua of the sacrum and the coccyx, and also between the lateral angles of the sacrum and the transverse processes of the first piece of the coccyx.

As regards the *coccygeal joints* (when such exist), the union of the different segments of the bone is brought about by intervening cartilaginous discs and anterior and posterior ligaments.

Dissection.—The student should now saw through the sacrum and coccyx in the mesial plane. By this proceeding he will obtain a view of the structure of the intervertebral discs, and at the same time be enabled to make out to better advantage the attachments of the posterior common vertebral ligament and of the ligamenta subflava.

Sacro-iliac Articulation.—The sacrum is wedged in between the two innominate bones, and is held fast in this position by the sinuous form of the opposed articular surfaces and the strong ligaments which pass between the bones. These ligaments are—

1. The anterior sacro-iliac.
2. The posterior sacro-iliac.
3. The oblique sacro-iliac.
4. Great sacro-sciatic.
5. Small sacro-sciatic.

The *anterior sacro-iliac ligament* (ligamentum sacroiliacum anterius) is by no means strong. It is composed of a series of short fibres stretching across in front of the joint, and connecting the bones anteriorly.

The *posterior sacro-iliac ligament* (ligamentum sacroiliacum interosseum) is exceedingly strong. It consists of fibrous bands, which connect the rough surface on the posterior part of the lateral aspect of the sacrum with a corresponding rough surface on the ilium, behind the auricular surface. Upon the posterior sacro-iliac ligaments the strength of the articulation chiefly depends. As the sacrum narrows towards its dorsal surface it cannot be regarded in any sense as forming




FIG. 194. — Section through the Sacro-iliac Joint. (After Luschka.)

the keystone of an arch. It may be regarded as being in a great measure suspended from the iliac bones by these ligaments.

The *oblique ligament* is simply a specially thickened part of the posterior sacro-iliac ligament. Above, it is fixed to the posterior superior spine of the ilium; whilst, inferiorly, it is inserted into the lateral tubercle of the third piece of the sacrum.

The *great sacro-sciatic ligament* (ligamentum sacrotuberosum) has a wide attachment to the posterior inferior iliac spine and to the side of the sacrum and coccyx. Narrowing considerably as it proceeds downwards and forwards, it again expands, and is inserted into the inner border of the tuberosity of the ischium. From this it sends upwards a sharp *falciform edge*, which extends forwards for a short distance upon the ascending ramus of the ischium, and gives attachment to the parietal pelvic fascia. It should be noticed that at its ischial attachment, some of its fibres pass continuously into the tendon of the biceps muscle.

The *small sacro-sciatic ligament* (ligamentum sacrospinosum) is triangular in form. By its base it is fixed to the side of the sacrum and coccyx in front of the great sacro-sciatic ligament, the fibres of both mingling together; by its apex it is attached to the spine of the ischium. The pelvic surface of this ligament presents an extremely intimate connection with the coccygeus muscle; indeed, it is generally believed that the ligament is derived from the superficial part of the muscle by the fibrous degeneration of its fasciculi.

The two sacro-sciatic ligaments convert the sciatic notches of the innominate bone into foramina. Through the *great sacro-sciatic foramen* pass the gluteal vessels and superior gluteal nerve, the piriformis muscle, the sciatic vessels and nerves, the inferior gluteal nerve, the internal pudic vessels and nerve, the nerve to the obturator internus, and the nerve to the quadratus femoris.

The *small sacro-sciatic foramen* transmits the obturator internus muscle, the pudic vessels and nerve, and the nerve to the obturator internus.

A *synovial cavity* is present in the sacro-iliac joint. The ligaments of the joint should now be divided, and the two bones forcibly wrenched asunder. By this proceeding each articular surface will be seen to be covered with a plate of

cartilage, between which a small synovial space may be observed, which partially separates them.

The sacro-iliac joint is not immovable, as is sometimes stated. A slight amount of movement can take place—the sacrum moving round an imaginary line drawn transversely through its second piece from one side to the other. In the erect posture the promontory of the sacrum is withdrawn to the full extent from the symphysis; in bending the body forwards, it approaches, in a small degree, the symphysis, and, in consequence, the tension of the sacro-sciatic ligaments is increased.

Symphysis Pubis.—This is an example of an amphiarthrodial joint. In addition to the intervening disc of




FIG. 195.—Horizontal section through the Symphysis Pubis. (After Luschka.)

fibro-cartilage which connects the cartilage-covered opposing surfaces of the two pubic bones, *four* ligaments are present, viz. :—

- | | |
|---------------------|-------------------------|
| 1. Anterior pubic. | 3. Supra-pubic. |
| 2. Posterior pubic. | 4. Infra- or sub-pubic. |

The *anterior pubic ligament* is strongly marked, and consists of two layers of fibres—a superficial and a deep. The *superficial fibres* are oblique, and cross each other like the limbs of the letter X, mingling with the decussating fibres of the internal pillars of the external abdominal ring. The *deep fibres* are transverse, and extend across from one bone to the other.

The *posterior pubic ligament* consists of a very few fibres on the posterior aspect of the joint.

The *supra-pubic ligament*, like the preceding, is weak.

It is placed upon the upper aspect of the symphysis, and stretches between the crests of the two pubic bones.

The *infra-* or *sub-pubic ligament*, which is situated on the lower aspect of the joint, rounds off the apex of the pubic arch. It is a strong band, somewhat triangular in shape, which is attached on each side to the descending ramus of the pubic bone, and above, to the fibro-cartilaginous disc. Between the crescentic lower margin of this ligament and the upper border of the transverse perineal band of the triangular ligament of the urethra, there is an oval aperture through which the dorsal vein of the penis passes backwards.

Dissection.—The saw should now be used, and a portion sliced off from the front of the joint. The intervening plate of fibro-cartilage can in this way be studied. It will be seen to be thicker and denser in front than behind. As a general rule, a small synovial cavity will be found towards its back part, and nearer its upper than its lower end.

Obturator or Thyroid Membrane.—This is the membrane which stretches across the thyroid foramen. It is attached to the circumference of the foramen, except at its upper part, where it bridges across the groove on the under surface of the horizontal ramus of the pubic bone, and converts it into a foramen for the escape of the obturator vessels and nerves. At this point it is continuous over the upper border of the obturator internus muscle with the parietal pelvic fascia.

FEMALE PELVIS.

The contents of the female pelvis are the following:—

- | | | |
|-----------------------|---|--|
| <i>Viscera.</i> | { | <ol style="list-style-type: none"> 1. The pelvic colon and rectum. 2. The bladder and urethra. 3. The uterus and vagina. 4. The uterine appendages. { <div style="display: inline-block; vertical-align: middle; margin-left: 10px;"> Fallopian tubes.
 Ovaries, etc.
 Round ligament. </div> |
| <i>Blood-vessels.</i> | { | <ol style="list-style-type: none"> 1. Internal iliac vessels and their branches. 2. The superior hæmorrhoidal vessels. 3. The middle sacral vessels. 4. The ovarian vessels. 5. Certain venous plexuses in connection with the viscera. |
| <i>Nerves.</i> | { | <ol style="list-style-type: none"> 1. The sacral and sacro-coccygeal plexuses and their branches. 2. The obturator nerves. 3. The pelvic part of the sympathetic. |

The peritoneum is continued into the pelvis, and clothes some of the viscera completely and others partially.

General Position of the Viscera.—The *pelvic colon* lies in the hinder and upper part of the cavity, and its loops tend to overlap the viscera which lie in front. The *rectum*, as in the male, occupies the lower and posterior part of the pelvic cavity, and is adapted to the concavity of the sacrum and coccyx. The *bladder* and *urethra* are situated in front, the former lying against the posterior aspect of the pubic bones.




FIG. 196.—Mesial section through Female Pelvis.

The *uterus* and *vagina* are intermediate in position; whilst the *uterine appendages* are placed laterally. Three tubes or canals are thus directed downwards to open on the surface within the limits of the perineum, viz. (*a*) the *urethra*; (*b*) the *vagina*; (*c*) the *rectum*. (Figs. 196 and 197.)

Peritoneum.—The peritoneum, as it proceeds downwards from the posterior abdominal wall into the pelvis, comes into relation with the pelvic colon, gives it a complete covering, and connects it to the anterior surface of the sacrum by a pelvic meso-colon. As in the male, the peritoneum likewise gives a partial investment to the rectum, first clothing its

lateral and anterior surfaces, then its anterior surface alone, and finally quitting the gut altogether at a point about three inches above the anus. The peritoneum is now reflected on to the upper part of the posterior wall of the vagina, upon which it ascends to the posterior surface of the uterus,




FIG. 197.—Horizontal section through the Urethra, Vagina, and Anal Canal, a short distance above their terminations. (Henle.)

Ua. Urethra.	L. Levator ani.
Va. Vagina.	R. Rectum.

which it covers completely. Reaching the fundus of the uterus, it turns over this and descends upon the anterior aspect of the organ. This surface of the uterus it only invests in its upper three-fourths, and is then reflected on to the posterior aspect of the bladder. Whilst the vagina, therefore, receives a partial investment from the peritoneum posteriorly, it is altogether destitute of it anteriorly; and, again, whilst the entire posterior surface of the uterus is covered, the lower fourth of its anterior surface is bare, in so far as the peritoneum is concerned. From each lateral border of the uterus the peritoneum stretches outwards in the form of a wide fold, called the *broad ligament*. This connects the organ to the lateral wall of the pelvis and the iliac fossa.

Upon the bladder the peritoneum is carried forwards, and at its apex is conducted to the posterior aspect of the anterior abdominal wall by the urachus. On each side of the viscus it extends outwards, and is continued on to the side wall of the pelvis. An important point to notice is, that the peritoneal membrane is much more adherent to the wall of the uterus than it is to the wall of the bladder.

Broad Ligament of the Uterus (ligamentum latum uteri).—This is a wide fold composed of two layers of peritoneum

which stretches from each lateral border of the uterus to the opposite part of the pelvic wall and iliac fossa. The *superior border* of the ligament is occupied by the *Fallopian tube*, the fimbriated free outer extremity of which opens into the peritoneal cavity. Here, therefore, a continuity is established between the mucous lining of the tube and the peritoneal membrane. At a lower level than the Fallopian tube two secondary folds will be observed in connection with the broad ligament. Of these one projects backwards, and contains between its layers the *ovary and its ligament*, whilst the other is directed forwards, and contains the *round ligament of the uterus*.




FIG. 198.—The Uterus, with the Broad Ligament stretching out from either side of it. (From Gegenbaur.)

The portion of the broad ligament which lies between the Fallopian tube and the ovary is termed the *mesosalpinx*, whilst the two layers which proceed from its posterior aspect to the ovary form a very short mesentery, which receives the name of the *mesovarium*.

In addition to the Fallopian tube, the ovary and its ligament, and the round ligament of the uterus, the two layers of the broad ligament include between them other structures, viz.—(1) the *parovarium*; (2) the *uterine and ovarian vessels, nerves, and lymphatics*.

The part of the broad ligament which extends from the upper end of the ovary to the iliac fossa in the neighbourhood of the external iliac vessels receives the special name of the *ovario-pelvic ligament*, or the *suspensory ligament of the*

ovary. It contains between its two layers the ovarian vessels and nerves.

Peritoneal Fossæ.—The paravesical and the pararectal fossæ present in the male (p. 504) when the bladder and rectum are empty can also be distinguished in the female.




FIG. 199.—Mesial section through the Female Pelvis to show the disposition of the Peritoneum in relation to the Viscera and the Lateral Wall of the Cavity. (Dixon and Birmingham.)

A middle or intermediate fossa between the uterus and the side wall of the pelvis is likewise apparent.

Recto-vaginal Pouch, or the Pouch of Douglas.—This corresponds to the recto-vesical or recto-genital pouch in the male. *In front* it is bounded by the peritoneum clothing the upper part of the posterior wall of the vagina and the back

of the cervix uteri; *behind* by the peritoneum investing the rectum; whilst *on each side* it is limited by a semilunar fold of peritoneum, similar to the sacro-genital fold in the male, which curves forwards and inwards from the wall of the pelvis at the side of the rectum to the uterus. This is called the *utero-sacral fold*, and it becomes continuous with its fellow of the opposite side across the back of the uterus, at the level of its isthmus. As it crosses the middle line on the back of the uterus it receives the name of the *torus uterini*, and here it forms the upper part of the anterior wall of the pouch of Douglas. Between the two layers of the utero-sacral fold is some involuntary muscular tissue. In front, this is connected with the wall of the uterus, whilst behind, it is attached to the sacrum and rectum.

Utero-vesical Pouch.—This is the shallow peritoneal depression which exists between the uterus and the base of the bladder. It is limited laterally by two slight folds of peritoneum termed the utero-vesical folds (p. 506).

False Ligaments of the Bladder.—These are the same as in the male bladder—viz., an anterior or superior, and two lateral.

Hypogastric Nerve Plexus.—In no respect does it differ from that of the male (*vide* p. 507).

Pelvic Fascia.—For a description of the pelvic fascia and the manner in which it should be dissected the student is referred to p. 507. The *parietal portion* is identical with that of the male, except in so far that in front it sweeps backwards upon the urethra and vagina, instead of the prostate, to join the visceral part. The *visceral portion* differs inasmuch as it gives a sheath to the vagina. Reaching the lateral aspect of the viscera, it thus divides into four layers, viz.—(1) a *vesical layer*, which forms the lateral true ligament of the bladder; (2) a *vesico-vaginal layer*, which passes between the bladder and vagina; (3) a *recto-vaginal layer*, which proceeds inwards between the vagina and rectum; and (4) a *rectal layer*, for the lateral and posterior aspects of the rectum.

Dissection.—The right innominate bone should now be removed, in accordance with the directions given at p. 518, and the visceral layer of the pelvic fascia followed out in its various reflections upon the viscera. When thoroughly satisfied upon this point, remove the remains of the fascia and clean the viscera, taking care not to injure the blood-vessels and

nerves which supply them. This dissection will be rendered easier if the rectum and vagina be cleansed and moderately stuffed with tow. It is better also to partially inflate the bladder, but it is a difficult matter to retain the air when introduced; still, it can be accomplished by sewing a fine thread round the urethral orifice, and tightening it like a purse-string as the blow-pipe is withdrawn.

Rectum (intestinum rectum).—A detailed account of the rectum, as it is found in the male, is given at p. 520. It is only necessary, therefore, to mention here the points of difference in the female.

The rectum is separated, for a short distance, by the recto-vaginal *cul-de-sac* of peritoneum from the uterus and vagina. Below this, it is in apposition with the posterior wall of the vagina—a layer of pelvic fascia (the recto-vaginal) alone intervening. The connection between the rectal and vaginal walls is at first very loose, but afterwards much more intimate. This has an important bearing upon the manner in which prolapsus uteri takes place. It should be noted that whilst the greater part of the rectum is supported behind by the sacrum and coccyx, there is fully an inch and a half of its lower portion which rests upon the levatores ani and receives support from the *ano-coccygeal body* (Fig. 196).

Anal Canal.—The anal canal bends downwards and backwards about one inch and a half in front of the coccyx, so that an angular interval is left between the gut and the vagina—an interval to which the term perineum is restricted by the obstetrician, and which is occupied by a pyramidal mass of firm fibro-muscular tissue, called the *perineal body* (Fig. 200).

Bladder (vesica urinaria).—The female bladder has normally a smaller capacity than the corresponding viscus in the male. The base, which is directed backwards, is in relation to the neck of the uterus and the vagina. In the female, there is no prostate surrounding its urethral orifice; and there are no vasa deferentia, and no vesiculæ seminales in relation to its base. The relations which it presents to the peritoneum, and the walls of the pelvis, are so similar to those present in the male (*vide* p. 523) that a second description is unnecessary. The intimate relation, however, which the uterus presents to the superior surface of the bladder should be noticed. The uterus rests upon it, and the two organs are merely separated by the peritoneum which clothes both.

The position of the bladder is not quite the same as in the male. It is placed at a lower level in the pelvis. A line carried from the inferior margin of the symphysis pubis backwards through the urethral orifice of the bladder strikes the posterior pelvic wall in the male at the level of the lower part of the second sacral vertebra. In the female, such a line would probably strike the lower border of the fifth sacral vertebra (Disse). Of course, in making this observation we must not lose sight of the fact that the symphysis pubis is relatively shorter in the female than in the male.

Ureters.—The pelvic portions of the ureters are slightly longer in the female than in the male. They pass downwards and forwards on the side wall of the pelvis in front of the internal iliac artery, and then, near their termination, extend




FIG. 200. —Mesial section through a Female Pelvis.

R. Rectum.

U. Uterus.

B. Empty Bladder.

S. Symphysis.

The uterus is antiflexed, and, as it inclines to the right side, the section in the upper part does not cut it into two equal and symmetrical portions.

Note the rectal *cul-de-sac* above the anal canal. This is common in multiparæ.

forwards, one upon each side of the neck of the uterus. As the ureter approaches the base of the bladder, it lies for a very short part of its course in relation to the upper part of the side wall of the vagina. As in the male, it pierces the bladder wall very obliquely.

Urethra (*urethra muliebris*).—The urethra is the canal along which the urine escapes from the bladder. Its walls are always in close apposition, except when the passage is opened by the flow of urine through it. In length, it measures about one inch and a half, and it takes a slightly curved course from the neck of the bladder downwards and forwards to the vestibule, where it opens on the surface by

an aperture, called the *meatus urinarius*. This has been examined in the dissection of the perineum (p. 335). On its way to the surface the urethra passes through the two layers of the triangular ligament, and in the interval between these it is surrounded by the fibres of the compressor urethræ muscle. The relation of the female urethra to the anterior wall of the vagina is very intimate.

Uterus.—The uterus is the organ into which the ovum is received, and in which it is retained until the foetus is fully developed. It is placed in the interval between the rectum and the bladder, below the general mass of the small intestine, and above the vagina. *In shape*, it is pyriform or flask-shaped, flattened from before backwards. *In length*, it is about three inches; *in breadth*, at the broadest point, two inches; and *in thickness*, nearly an inch. The broader upper end of the uterus is directed upwards and forwards, whilst its narrow lower end looks downwards and backwards, and forms, with the vagina, an obtuse angle, which is open towards the pubic symphysis.

It is customary to describe the uterus as being composed of three parts, viz.—a fundus, a body, and a neck or cervix (Fig. 205).

The *fundus* (fundus uteri) is the rounded upper end. The Fallopian tube enters the organ on each side at its upper angle, and a line drawn transversely between these is arbitrarily fixed upon as the limit between the fundus and the body of the uterus. It is completely covered by peritoneum.

The *body* (corpus uteri) diminishes in breadth as it proceeds downwards towards the neck. In front and behind, it is smooth and convex, the convexity of the posterior surface, however, being much more marked, especially in its upper part, than that of the anterior surface. Upon each side it is joined immediately below the entrance of the Fallopian tube, in front, by the *round ligament*, and behind, by the *ligament of the ovary*. Inferiorly, the body of the uterus is marked off from the neck by a slight constriction, which is very apparent in the infant, but which becomes less distinct as puberty approaches, and usually disappears altogether after parturition. This constriction is called the *isthmus*.

The *neck* or *cervix* (cervix uterina), about an inch in length, is narrower than the body, and more cylindrical in form. It

projects into the upper end of the vagina, the walls of which are attached to the uterus around it. To obtain a satisfactory view of the cervix uteri, it is necessary to slit up the vagina along its lateral aspect. The posterior wall of the vagina will then be seen to ascend to a higher level upon the cervix than the anterior wall; or, in other words, the anterior wall of the vagina will be observed to be shorter than the posterior wall (Fig. 196). On the lower extremity of the cervix, which is full, rounded, and knob-like, there is an aperture called the *os uteri externum* (orificium externum uteri). In the virgin this opening is small and circular, but in females who have borne children it is usually transverse and somewhat irregular in outline. It is bounded by two thick rounded lips. Comparing these, it will be noticed that the anterior lip is the thicker of the two, whilst the posterior is the longer. Although the anterior lip is the shorter, it should be noted that, on account of the oblique position of the uterus, it is placed at a lower level in the vagina. The greater length of the posterior lip is due to the fact that the wall of the vagina passes higher up on that aspect of the uterus. The part of the cervix which projects into the vagina is called the *portio vaginalis*; the part above is termed the *portio supravaginalis*.

As the mucous membrane which lines the vagina passes from its anterior wall on to the anterior lip of the os uteri, it forms a shallow angular recess between the two, called the *anterior fornix*. The same is seen behind in connection with the posterior lip of the os uteri, but, owing to the higher attachment of the posterior vaginal wall, the *posterior fornix* is very deep. A most important relation should be made out at this stage, viz., that when the finger is placed in the posterior fornix it is merely separated from the peritoneum lining the pelvic cavity by the posterior vaginal wall (Fig. 196). This is owing to the fact that the recto-vaginal *cul-de-sac* of peritoneum descends so as to cover the upper part of the posterior vaginal wall.

The *relations* of the uterus should next be studied. *Posteriorly*, it is invested completely by peritoneum, and is separated from the rectum by the recto-vaginal *cul-de-sac*. Within this peritoneal pouch there are always more or less of the pelvic colon and a few coils of small intestine. *Anteriorly*, it is covered in its upper three-fourths by peritoneum, and is

in apposition with the bladder. *Laterally*, it is connected with the broad ligament. Further, on either side of the neck of the uterus and the upper part of the vagina, there is a mass of loose fatty tissue containing large vessels. This is termed the *parametrium*, and it is prolonged upwards on the side of the uterus for some distance between the layers of the broad ligament.

Position of the Uterus.—In women who have borne no children (nulliparæ) and in whom the bladder and the rectum are both empty, the uterus is normally strongly anteflexed and anteverted (Waldeyer). When we say that the uterus is anteflexed, we mean that it is bent forwards upon itself at the isthmus, so that the body and the cervix meet at an angle which is open to the front. This forward flexion of the uterus depends upon two circumstances, viz.—(1) upon the greater pliability of the body as compared with the firmer consistence and greater rigidity of the cervix; and (2) upon the fact that the cervix is more or less held in position by its attachments to the anterior vaginal wall and the base of the bladder in front, and to the posterior vaginal wall behind. By the term “anteversion,” we mean that the whole uterus—both body and cervix—is inclined forwards so as to form an angle of greater or less magnitude with the vertical axis of the trunk. In this position of the uterus the coils of the small intestine and a loop of the pelvic colon rest upon its posterior surface, whilst its anterior surface is supported by the bladder. It is very rare indeed that a coil of small intestine is found between the uterus and the bladder in the utero-vesical pouch of peritoneum. In multiparæ (women who have borne children) the anteflexion of the uterus is not so marked as it is in nulliparæ.

But the uterus possesses a great degree of mobility, and consequently we find that its position is constantly liable to change. Intra-abdominal pressure, and distension of the bladder or rectum, are the chief agencies at work in producing these effects. Every breath that is taken, every movement of the body, is followed by a slight alteration in the position of the uterus. When the bladder fills, the uterus is raised with it; the anteflexion and the anteversion become less marked, and, in cases of hyper-distension of the bladder, the uterus may assume an almost erect position. With this

change of position the relation of the uterus to the rectum becomes more intimate, through the forcing of the small intestine out of the pouch of Douglas. When the rectum becomes distended the uterus is pushed forwards and to the right side.

Under no circumstances is it usual to find the uterus




FIG. 201.—Diagram of the Vulva, Vagina, and the Uterus, with its Appendages. (Symington.)

occupying an accurately median position. It would appear that it is more frequently inclined to the right than to the left side.

Vagina.—The vagina is the passage which leads from the uterus to the vulva. In length it is about three inches, and in the empty condition of the bladder and rectum it pursues a very nearly straight course from above downwards and forwards. In the erect posture of the body its long axis may be said to

be nearly parallel to the plane of the pelvic brim. Superiorly, its walls are firmly attached to the substance of the uterus around its neck, upon which it ascends to a higher level behind than in front; on account of this, the cervix uteri has the appearance of piercing its anterior wall. The vagina is wider in the middle than at either end, and the anterior and posterior walls are closely applied to each other, so that in no respect can the vagina be regarded as an open tube or canal. In section, therefore, it appears simply as a transverse or longitudinal slit, according to the direction in which it is divided (Figs. 196 and 197).

Posteriorly, the upper end of the vagina is in relation to




FIG. 202.—The Uterus, with the Broad Ligament stretching out from either side of it. (From Gegenbaur.)

the bottom of the recto-vaginal pouch of peritoneum. Below this it is in apposition with the rectum, the recto-vaginal layer of pelvic fascia intervening. Still lower down, it is separated from the anal canal by an angular interval, which is occupied by the perineal body. *Anteriorly*, it is related to the base of the bladder and to the urethra—indeed, the latter almost appears to be embedded in its wall. *Upon each side* of the vagina, the levator ani muscle descends and gives it support, whilst its lower end is clasped between the two vestibular bulbs and is embraced by the sphincter vaginæ. Close to the neck of the uterus the ureter is related to the vagina on each side for a very limited part of its course.

Ovaries.—The ovaries are two small solid bodies contained

within the posterior secondary folds of the broad ligaments. Each ovary is oval or oblong in figure, slightly compressed from side to side, and having a size somewhat similar to that of a pigeon's egg.

The ovary presents two flattened surfaces, two extremities or poles, and two borders. Its natural or typical position can only be studied in young women who have borne no children. When pregnancy occurs the ovaries become displaced, and it is questionable if they ever regain their original place within the pelvis. In the young virgin and in the erect posture of the body the ovary lies with its long axis vertical. It occupies a peritoneal fossa on the posterior part of the side wall of the pelvis, immediately below the external iliac vessels (Fig. 203). This recess is termed the *fossa ovarica*. From the *upper pole* of the ovary the ovario-pelvic fold of peritoneum passes outwards to the wall of the pelvis. To the same extremity the mouth of the Fallopian tube is attached by one of its fimbriæ; from the latter connection the term *tubal pole* (*extremitas tubaria*) is frequently applied to the upper end of the ovary. The lower extremity is connected with the uterus by a round cord-like structure, the *ligament of the ovary*, which is included between the two layers of the broad ligament. This end of the ovary is consequently sometimes called the *uterine pole* (*extremitas uterina*). The two surfaces of the ovary look outwards and inwards, and the two borders are directed forwards and backwards. The *anterior border* is thinner and straighter than the posterior border, and is very commonly called the *attached border* or the *hilum*. The term "attached" is applied to it because it is along this margin that the two layers of the broad ligament which enclose the ovary leave it. Everywhere else it presents a free surface. The name of "hilum," on the other hand, is given to this margin because the vessels, nerves, and lymphatics enter and leave the organ along its whole length. The *posterior border* of the ovary is free, and looks slightly inwards towards the rectum as well as backwards. The Fallopian tube in the natural position of the pelvic organs encircles the greater part of the circumference of the ovary.

The ovary is completely surrounded by peritoneum, except along its hilum, where the vessels enter and to which the mesovarium is attached. The membrane, however, does not present

so highly polished an appearance as in other parts of the abdominal cavity. This is due to a change in the form of the surface epithelium, which is placed over the ovary. Before puberty the surface of the ovary is smooth and uniform. After this period, however, it becomes scarred and puckered from the breaches which are made by the escape of the ova, from the Graafian follicles.

Parovarium, or the Organ of Rosenmüller (Epoophoron).




FIG. 203.—Left Side Wall of Female Pelvis to show position of the Ovary.
The ovary is much scarred through the shedding of ova.

—This structure is of interest because it is the representative of the epididymis in the male. It is somewhat triangular in form, and will be discovered by an attentive examination of the mesosalpinx or that portion of the broad ligament of the uterus which stretches between the ovary and the Fallopian tube. Its apex is directed towards the former, and its base towards the latter; but it lies free between the two layers of the ligament, and is not connected with either. In structure it consists of a number of tubules which radiate from the apex

of the organ and join a longitudinal tube (the homologue of the duct of Gärtner in the cow, etc.), which extends along its base.

A few isolated tubules can also be seen in the mesosalpinx of the child at a point somewhat nearer the uterus. These constitute the *paroöphoron* or a rudimentary structure which represents the *paradidyminis* in the male.

Fallopian Tubes or Oviducts (tubæ uterinæ).—These are two tubes which have as their function the conveyance of the ova or eggs from the ovary to the uterus. Each duct is about four inches long, and is contained within the superior




FIG. 204. — The Ampulla and Fimbriated End of the Fallopian Tube; the Ovary; and the Paroovarium. (From Gegenbaur, modified.)

free border of the broad ligament of the uterus. Its inner extremity pierces the uterus at its superior angle, whilst its outer end, when the broad ligament is put on the stretch, is situated about an inch beyond the ovary and opens into the peritoneal cavity by a constricted orifice (*ostium abdominale*), surrounded by numbers of fringe-like processes, called *fimbriae*. By one of these fimbriae, termed the *ovarian fimbria* (fimbria ovarica), it is attached to the tubal pole of the ovary. The calibre of the Fallopian tube is by no means uniform. As it is traced outwards from the uterus it is at first extremely narrow. This portion is called the *isthmus* (isthmus tubæ uterinæ). In the neighbourhood of the ovary it dilates considerably, and receives the name of the *ampulla* (ampulla

tubæ uterinæ). The ovarian fimbria is longer than the others ; it is attached along its whole length to the broad ligament, and shows on its surface a gutter-like groove leading from the constricted mouth of the tube to the ovary (Fig. 204).

In the undisturbed position of parts the Fallopian tube proceeds horizontally outwards on the pelvic floor. It then turns vertically upwards along the hilum or attached border of the ovary, and, gaining the tubal pole, it bends upon itself and turns downwards upon the posterior free border and the inner surface of the ovary, both of which it in great part covers. It may, therefore, be considered to consist of three parts :—(1) *the first* in relation to the floor of the pelvis ; (2) *the second* in relation to the anterior border of the ovary ; (3) *the third* in relation to the posterior border and the inner surface of the ovary.

Round Ligament of the Uterus (ligamentum teres uteri).—The round ligaments are two cord-like bands largely composed of involuntary muscular fibres, which are attached to the body of the uterus immediately in front of and a little below the entrance of the Fallopian tube—one on each side. From this, each ligament is directed outwards and forwards between the layers of the broad ligament and in front of the oviduct, to the internal abdominal ring. It has already been examined within the inguinal canal. In the young subject the peritoneum is usually prolonged along with it into this canal in the form of a tubular process termed the "*Canal of Nuck*." Later on this becomes obliterated.

The ligament of the ovary which attaches the lower end of the ovary to the uterus represents the upper part of the foetal gubernaculum in the male ; whilst the round ligament represents the lower part of the same structure.

PELVIC BLOOD VESSELS.

The manner in which the blood vessels of the pelvis should be dissected is described at p. 534. In the female three additional arteries will be found, viz.—

1. The uterine,
 2. The vaginal,
 3. The ovarian,
- } branches of the internal iliac.
from the abdominal aorta.

Uterine Artery (arteria uterina).—The uterine artery springs from the anterior division of the internal iliac artery,

and proceeds downwards and inwards to the neck of the uterus. At this point it gives several small branches to the vagina and bladder, and, changing its direction, extends upwards in a tortuous manner along the lateral border of the uterus and between the two layers of the broad ligament. Reaching the fundus, it sends several twigs outwards into the broad ligament; of these, one accompanies the round ligament, another goes with the Fallopian tube, and several proceed to the ovary, and anastomose with twigs from the ovarian artery. Whilst, in contact with the lateral border of the uterus, the uterine artery gives numerous branches to this organ.

Vaginal Artery (*arteria vaginalis*).—The vaginal artery also springs from the anterior division of the internal iliac, but it is not unusual for it to arise in common with the uterine artery, or the middle hæmorrhoidal artery. It is distributed to the vagina, and sends twigs to the rectum and bladder.

Ovarian Artery (*arteria ovarica*).—The course which this vessel takes within the abdomen proper is described at p. 488. When it arrives at the pelvis, it crosses the upper part of the external iliac vessels and insinuates itself between the two layers of the broad ligament of the uterus, where this forms the ovario-pelvic fold. It is highly tortuous, and runs along the anterior border of the ovary, and from thence onwards to the fundus of the uterus, where its terminal branches anastomose with the uterine artery. In addition to the branches which enter the hilum of the ovary it gives others to the Fallopian tube and to the round ligament of the uterus.

The other arteries of the female pelvis are identical with those of the male, and therefore it is needless to repeat the description which will be found at p. 534.

Veins of the Pelvis.—Very few facts require to be added to those which are given regarding the veins of the male pelvis (p. 538). Of course there is no prostatic plexus of veins in the female, and therefore the *dorsal vein of the clitoris* joins the vesical plexus.

A bulky *uterine venous plexus* is formed on each side of the uterus between the two layers of the broad ligament. This enters into the formation of the parametrium, and from its lower part the blood is drained away by a *uterine vein* which opens into the internal iliac vein.

A *vaginal plexus* of veins is likewise formed on each side of the vagina, and from its upper part the *vaginal vein* proceeds which carries the blood to the internal iliac vein.

The veins which issue from the hilum of the ovary form a *pampiniform plexus* between the layers of the broad ligament. From this, two ovarian veins issue which accompany the ovarian artery. These ultimately unite, and the vein thus formed ends in a manner similar to the spermatic veins in the male.

PELVIC DIAPHRAGM.

This is described at p. 539. The dissector should note, however, that the fibres of the *levator ani muscle* pass downwards upon the lateral aspect of the vagina and give it support (Fig. 197).

NERVES OF THE PELVIS.

Very little requires to be added to what has already been said regarding the nerves of the male pelvis (p. 541). There is no *prostatic plexus*; but a *vaginal plexus*, an *ovarian plexus*, and a *uterine plexus* are present in addition to those mentioned in the male.

The *uterine plexus* proceeds from the pelvic plexus. It ascends between the two layers of the lateral ligament along with the uterine artery, and is distributed upon both aspects of the organ.

The *vaginal plexus* is an offset from the pelvic plexus, and the nerves which compose it are mainly derived from the visceral branches which enter the pelvic plexus from the sacral nerves.

The *ovarian plexus* is derived from the aortic and renal plexuses, and, accompanying the artery of the same name, is distributed to the ovary.

Coccygeal Body.—*Vide* p. 546.

Removal of Viscera.—The viscera should now be removed from the pelvic cavity. Begin by cutting the various nerves and vessels which enter them, the levator ani and the anterior true ligaments of the bladder. Then carefully divide the parts which hold the urethra and vagina to the arch of the pubis. Lastly, separate the rectum from its connections with the sacrum and coccyx.

The *obturator internus* and *pyriformis* muscles should now be studied. They are described at p. 546.

The viscera should next be separated from each other; but the vagina must be left attached to the uterus, and the urethra to the bladder.

Coats of the Rectum and Anal Canal.—The coats of these portions of the intestinal canal are identical in both sexes. The student may, therefore, refer to p. 547, where the wall of the male rectum and anal canal is described.

Bladder.—Particulars regarding the coats of the bladder may be obtained by turning back to p. 551. In slitting open this viscus the urethra should be laid open along its upper surface at the same time.

Urethra.—The external meatus is the narrowest part of this tube. As the urethra is traced upwards, it will be seen to expand before joining the neck of the bladder, and close to the meatus its floor will be noticed to be somewhat depressed so as to form a slight hollow.

Dissection.—The uterus with its appendages should now be laid upon its posterior surface on a block. The round ligaments and the ligaments of the ovaries should be isolated and their attachments defined, and then the uterus may be opened by a longitudinal mesial incision, extending from the fundus to the os uteri externum. A transverse cut should also be made outwards from the upper end of this incision towards the entrance of each Fallopian tube. The cut edges may now be pared so as to extend the view of the interior of the uterus.

Wall of the Uterus.—The *round ligament* will now be seen to be attached to the body of the uterus immediately in front of and a little below the entrance of the Fallopian tube. The *ligament of the ovary*, a much more slender band, is a fibrous cord containing some muscular tissue derived from the wall of the uterus. It extends from the lower uterine pole of the ovary to the body of the uterus, which it joins immediately behind and a little below the entrance of the Fallopian tube. In all its length, it is enclosed between the two layers of the broad ligament.

The wall of the uterus is very thick, and presents three well-marked coats, viz., a serous or peritoneal, a muscular, and a mucous. The *serous covering* has already been fully studied. The *muscular part* of the wall constitutes its chief bulk. It is composed of involuntary muscular tissue, with a considerable admixture of areolar tissue. It is not equally thick throughout. Thus it becomes distinctly thinner towards

the angles at the entrance of the Fallopian tubes. The *mucous lining* will be studied after the interior of the organ has been examined.

Interior of the Uterus (cavum uteri).—The cavity of the uterus is much smaller than would be expected from an inspection of the exterior of the organ. It is subdivided arbitrarily into an *upper part*, which occupies the body, and a *lower or cervical part*, which occupies the cervix.

The *upper portion* is the larger of the two, and is triangular in form. The anterior and posterior walls are in contact with each other, and the sides of the triangle are incurved, the base being directed upwards.

At the two extremities of the base are the constricted openings of the Fallopian tubes.




FIG. 205.—Interior of the Uterus. (Luschka.)

The *lower cervical portion* is fusiform or spindle-shaped in form, being also slightly compressed from before backwards. Above, it is somewhat constricted, and at the junction of the body with the cervix of the uterus it becomes continuous with the upper triangular part of the cavity. This narrow opening is termed

the *os uteri internum* (orificium internum uteri). Below, the cavity of the uterus opens into the vagina by the *os uteri externum*.

Mucous Membrane of the Uterus.—The dissector will not fail to note a striking difference between the mucous lining of the uterus in the triangular cavity of the body and in the fusiform cavity of the cervix. In the former it is smooth and even, and tightly bound down to the subjacent muscular tissue. In the cervix it presents a remarkable disposition, which, from its appearance, has been termed the *arbor vitae*. This consists of a series of prominent folds or rugæ arranged in a definite manner. Thus, there is an anterior and posterior median fold or raphe, and from this secondary folds branch

off and pass obliquely upwards and outwards. The arbor vitæ is more marked upon the anterior than upon the posterior wall.

The student should look between the folds of the arbor vitæ for *ovula Nabothi*. These are minute vesicles filled with a yellowish liquid, and they result from the distension of certain of the tubular glands in the mucous membrane, through obstruction of their mouths.

Fallopian Tubes.—The Fallopian tube has an external serous, an intermediate muscular, and an internal mucous coat. The aperture by which it opens into the uterus is exceedingly small, and will barely admit a bristle. The expanded ampulla, however, may be opened up. In this part of the tube the mucous membrane will be seen to be arranged in longitudinal folds. To obtain a proper idea of the fimbriæ which surround the *ostium abdominale*, the tube should be immersed in water, when the fringes will float out and separate from each other.

Coats of the Vagina.—Outside the mucous lining there is a thin layer of erectile tissue, and spread over this the proper muscular coat of the vagina. The mucous lining will be observed to present special peculiarities. Two well-marked median and longitudinal folds extend upwards, one upon the anterior and the other upon the posterior wall. These are termed the *columnæ rugarum*, and from each side they send off numerous transverse rugæ, which are arranged so that those on the anterior wall fit in between those on the posterior wall. These folds are best marked near the vaginal orifice, and are absent at the upper end of the canal.

PELVIC ARTICULATIONS.

These are described at p. 560. In the later months of pregnancy the ligamentous tissues of the various pelvic joints become softened, thickened, and infiltrated. The pelvic bones are thus partially separated from each other, and the width of the pelvic circle is increased.



INDEX.



INDEX.

- Abdomen, 308
 Abdominal cavity, 392
 boundaries, 393
 contents, 396
 peritoneum, 417
 relations between thoracic and abdominal organs, 410
 subdivisions, 394
 Abdominal ring, external, 353, 384
 internal, 369, 384, 386
 tunic, 347
 wall, 344
 adaptation to viscera, 416
 arteries, 371, 485
 cutaneous nerves, 348
 vessels, 350
 fascia, 346, 369, 492
 muscles, 351, 492
 nerves, 361, 495
 posterior, 485, 492, 495
 surface anatomy, 344
 surgical anatomy, 384
 Alcock's canal, 316, 328, 513
 Ampulla of Fallopian tube, 579, 585
 of vas deferens, 533
 Ampullæ lactiferi, 21
 Anal canal, 412, 522, 548, 570, 583
 valves, 549
 Ano-coccygeal body, 318, 520, 522, 570
 Antecubital fossa, 71
 Antrum, pyloric, 407, 409
 Aorta, abdominal, 485
 Aortic opening of diaphragm, 484, 485
 plexus, 436, 456
 Aponeurosis, brachial, 62
 of external oblique, 352, 384
 of internal oblique, 358
 of transversalis, 363
 Appendices epiploicæ, 397, 441
 Arbor vitæ, 584
 Arch, anterior carpal, 90
 coraco-acromial, 48, 80
 crural, 198
 deep, 198
 palmar, deep, 118, 119
 superficial, 105, 106, 119
 plantar, 276
 Arches of foot, 299, 308
 Areola mammæ, 19
 Arm, 53
 antecubital fossa, 71
 anterior aspect, 53
 cutaneous nerves, 56
 fascia, 62
 osteo-fascial compartments, 63, 74
 posterior surface, 73
 superficial veins, 60
 surface anatomy, 54
 Arterial anastomosis of ankle, 263
 of back of thigh, 185
 crucial, of thigh, 168
 of elbow, 128
 of knee, 281
 of scapula, 52
 Artery or Arteries, acromial, 30, 33
 anastomotic, of brachial, 68, 73, 79, 128
 of femoral, 174, 210, 211, 224, 281
 of appendix, 432
 articular, of knee, 174, 179, 216, 252, 281, 282, 285, 286, 287, 288
 of hip, 223
 axillary, 24, 27, 30
 brachial, 64, 73
 of breast, 21

- Artery or Arteries, of bulb of
 penis, 326, 327, 330, 343
 calcaneal, 258, 263, 270
 capsular, 480, 486, 487, 488
 carpal, radial, 90, 131
 ulnar, 96
 cervical, superficial, 11
 circumflex, external, 169, 185,
 203, 215, 221, 224
 anterior, 25, 28, 34, 46
 iliac, deep, 372, 491
 superficial, 188, 203, 224,
 351
 internal, 164, 168, 185, 203,
 222, 223, 224
 posterior, 25, 28, 34, 42,
 45
 clavicular, 30, 32
 coccygeal, 164
 coeliac axis, 444, 486
 colic, left, 433, 434
 middle, 431, 433
 right, 431, 433
 comes nervi ischiadici, 164
 communicating, anterior, 100
 tibial, 258
 coronary, of stomach, 444, 445
 of corpus cavernosum, 330, 343
 cremasteric, 361, 372, 377
 cystic, 446
 digital, of foot, 265, 277
 of hand, 104, 106, 107, 119
 dorsalis clitoridis, 343
 indicis, 131
 pedis, 241, 244, 245
 penis, 329, 330, 392
 pollicis, 131
 scapulæ, 34, 44, 52
 epigastric, deep, 350, 369, 371,
 385, 386, 390, 491
 superficial, 188, 203, 224, 351
 superior, 350, 373, 481, 485
 femoral, 201, 203, 205, 209, 210,
 224, 490
 fibular, superior, 257
 gastric, 445
 short, 447, 448
 gastro-duodenal, 446
 interosseous, of foot, 247
 of hand, 100, 119, 131
 anterior, 96, 130
 common, 96
 posterior, 96, 124, 128
 intestinal, 430, 432
- Artery or Arteries, lumbar, 6, 371,
 485, 486, 488, 500, 537
 magna hallucis, 277
 malleolar, 245, 263
 mammary, external, 34
 median, 98, 100
 mesenteric, inferior, 434, 486
 superior, 430, 486
 metatarsal, 246
 musculo-phrenic, 373, 485
 nutrient, of bones, 68, 100, 222,
 258, 262
 obturator, 202, 228, 390, 518,
 535, 536
 oesophageal, 445
 ovarian, 486, 488, 581
 pancreatic, 447
 pancreatico-duodenal, 430, 431,
 446
 pectoral, 28, 30, 33
 perforating, of foot, 277
 of hand, 119, 130, 131
 of internal mammary, 17
 of profunda femoris, 161, 184,
 185, 221, 222, 224
 perineal, superficial, 313, 318,
 329, 337
 transverse, 319, 329, 337
 peroneal, 241, 247, 259, 261, 262,
 263
 phrenic, inferior, 487
 plantar, external, 267, 269, 270
 internal, 267, 269
 popliteal, 173, 177, 257
 princeps pollicis, 119
 profunda brachii, inferior, 67, 79,
 128
 superior, 66, 73, 76, 78, 128
 femoris, 203, 220
 of ulnar, 106
 pubic, of deep epigastric, 390
 of obturator, 536
 pudic, deep external, 203, 207,
 224
 internal, 163, 165, 316, 326,
 327, 328, 343, 535, 536
 superficial external, 188, 203,
 224, 351
 pyloric, 445, 446
 to quadratus femoris, 164
 radial, 89, 118, 130
 radialis indicis, 119
 recurrent, of deep palmar arch, 118
 interosseous, 128

- Artery or Arteries, recurrent, radial,
73, 90, 128
recurrent, tibial, 245, 257, 281, 282
ulnar, 73, 96, 128
renal, 473, 486, 487
sacral, lateral, 535, 538
middle, 486, 538
scapular, posterior, 12, 13, 52
sciatic, 161, 163, 164, 185, 535, 536
sigmoid, 435
spermatic, 377, 485, 486, 488
splenic, 444, 447
subcostal, 501
subscapular, 13, 25, 27, 28, 34,
51, 52
superficial volar, 90
suprascapular, 11, 51, 52
supraspinal, 13
supraspinous, 51
sural, 179
tarsal, 246, 263
thoracic axis, 24, 30, 32
thoracic, alar, 34
long, 25, 33
superior, 25, 30, 32
tibial, anterior, 241, 244, 249, 257
posterior, 257, 263
transversalis colli, 11
ulnar, 94, 106
uterine, 580
vaginal, 581
of vas deferens, 378, 535
vesical, 535, 536
- Articulations. *See* Joints
- Axilla, 14, 23
boundaries, 23
contents, 24
fascia, 25, 29
folds, 15, 23
lymphatic glands, 25, 26
nerves, 24, 26, 36
structures passing from neck, 35
surface anatomy, 15
surgical anatomy, 25
vessels, 24, 27, 30
- Axillary sheath, 30, 31
- Back, 3
cutaneous vessels and nerves, 4
fascia, 3
intermuscular spaces, 10
muscles to upper limb, 6
structures beneath trapezius, 10
surface anatomy, 1
- Band, ilio-tibial, 194, 214, 228, 232,
285
pudendal, of sacral plexus, 542
sciatic, of sacral plexus, 542
Bartholin's gland, 336, 343
Bertin, columns of, 478
Bile-ducts, 455, 461, 467
Bile-papilla, 461
Bladder, 503, 523, 565
coats, 550, 583
distended, 526
empty, 524, 526
female, 570
in new-born, 529
orifices, 525, 529, 551
peritoneal relations, 527
triangle at base, 533
trigone, 552
- Brachial aponeurosis, 62
plexus, 36, 64
- Breast, 19
- Brunner's glands, 461
- Bulb of urethra, 322, 391
of vestibule, 339
- Bursa intertubercularis, 85
over ischial tuberosity, 311
patellar, 196
subacromial, 45
subscapular, 51, 53, 82, 85
under gastrocnemius, 256, 287
gluteus maximus, 161
minimus, 170
ilio-psoas, 228, 231
ligamentum patellæ, 288
sartorius, 183, 226, 252
semimembranosus, 174
- Buttock. *See* Gluteal region
- Cæcum, 398, 412, 429
- Calices of kidney, 477
- Canal of Alcock, 316, 328, 513
anal, 412, 522, 548, 570, 583
crural, 201, 384, 389, 390
of epididymis, 383
of Hunter, 208
inguinal, 370, 384
of Nuck, 580
portal, 469
pyloric, 407
of Wirsung, 454
- Capsule, of Glisson, 468, 469
suprarenal, 471, 474, 478
- Cardiac orifice, 407, 409
- Carpal arch, anterior, 90

- Cartilages, semilunar, 187, 229, 239
 Carunculæ myrtiformes, 335
 Caudate lobe of liver, 464, 465
 Central point of perineum, 323, 338
 tendon of diaphragm, 481, 483
 Cervix uteri, 572
 interior, 584
 portio supravaginalis, 573
 vaginalis, 573
 Cleft, natal, 154
 pudendal, 333
 Clitoris, 332, 335, 340
 Coccygeal body, 546, 582
 Coeliac plexus, 444, 455, 456
 Colon, ascending, 412, 413
 descending, 397, 412, 414
 iliac, 398, 412, 415
 pelvic, 412, 416, 503, 519, 565
 transverse, 398, 412, 414
 Columnæ recti, 549
 rugarum vaginæ, 585
 Columns of Bertin, 478
 of Morgagni, 549
 Commissure, anterior, of vulva, 333
 Congenital hernia, 388
 Coni vasculosi, 383
 Conjoined tendon, 358, 359, 363,
 384, 387, 388
 Cooper, ligaments of, 21
 Coraco-acromial arch, 48, 80
 Cord, gangliated, of sympathetic,
 485, 494, 495, 545
 lumbo-sacral, 496, 499, 541
 spermatic, 345, 357, 359, 368,
 370, 375, 377, 384
 Corona glandis, 391
 Coronary plexus, 455, 457
 Corpora cavernosa, 320, 340, 391,
 558
 Corpus spongiosum, 321, 322, 391,
 558
 Cortex of kidney, 478
 of suprarenal body, 480
 Costal zone, 396
 Costo-coracoid membrane, 28
 Cowper's gland, 327, 328, 556
 Crucial anastomosis of thigh, 168
 Crura clitoridis, 341
 of diaphragm, 481, 483, 485
 of external abdominal ring, 354
 penis, 321, 391
 Crural arch, 198
 deep, 198
 canal, 201, 384, 389, 390
 Crural ring, 201, 202, 389
 septum, 201, 389
 Crypts of Lieberkühn, 441
 Cystic duct, 455, 468
 plexus, 457
 Diaphragm, 393, 410, 481
 central tendon, 483
 foramina, 484
 pelvic, 502, 539, 582
 Diaphragmatic plexus, 456, 457
 Digital fossa of peritoneum, 386
 of tunica vaginalis, 381
 Diverticulum Meckelii, 412
 Dorsal expansion of extensor tend-
 ons, 133, 243
 Douglas, fold of, 366
 pouch of, 568
 Duct, biliary, 455, 461, 467
 cystic, 455, 468
 ejaculatory, 531, 532, 533, 554
 hepatic, 455, 468
 pancreatic, 454, 461
 prostatic, 554
 thoracic, 484, 491
 Ductus venosus, 463
 Duodenal fossæ, 429, 430
 Duodeno-jejunal flexure, 411
 Duodenum, 410, 449
 coats, 461
 suspensory ligament, 451
 Ejaculatory ducts, 531, 532, 533,
 554
 Elbow, 53
 antecubital fossa, 71
 arterial anastomoses, 128
 joint, 136
 superficial veins, 60
 surface anatomy, 54
 surgical anatomy, 61
 Epididymis, 380, 383
 Epigastric plexus, 456
 region, 396
 Epoophoron, 578
 Extensor tendons, of fingers, 132, 133
 of toes, 243
 Fallopian tube, 567, 577, 579, 585
 Fascia of abdomen, 346
 anal, 315, 517
 of arm, 62
 axillary, 25
 of back, 3

- Fascia, bicipital, 61, 62, 71
 of Camper, 187, 347
 of Colles, 312, 313, 331, 347, 348, 387
 cremasteric, 360, 374
 cribriform, 190, 195
 of foot, 239, 264
 of forearm, 88, 89, 120
 of hand, 88
 iliaca, 199, 369, 389, 493, 511
 infundibuliform, 368, 374, 386, 387
 intercolumnar, 353, 374, 387, 388
 lata of thigh, 181, 190, 194, 214
 of leg, 239, 254, 257
 lumbar, 362
 obturator, 512
 palmar, 103, 104, 105, 119
 pectoral, 16, 21
 pelvic, 315, 502, 507, 510, 555, 569
 of perineum, 310, 324, 336
 plantar, 265, 299
 popliteal, 172
 of popliteus, 259
 of psoas and iliacus, 493, 494
 pyriformis, 511, 512
 of quadratus lumborum, 493
 of Scarpa, 187, 347
 semilunar, 62, 71
 of shoulder, 42
 of sole, 264
 spermatic, 352, 353, 368, 374, 387, 388
 of thigh and buttock, 155, 158, 181, 187, 190, 194, 214
 transversalis, 199, 367, 369, 387, 388, 389, 494
 triangular, 357
 Femoral hernia, 201, 389
 sheath, 197, 206, 390, 494
 Fibro-cartilage, triangular, of wrist, 139, 143
 Fibro-cartilages, semilunar, 287, 291, 293
 Fimbria, ovarian, 579
 Fimbriae of Fallopian tube, 579
 Fingers, extensor tendons, 133
 flexor sheaths and tendons, 112, 120
 movements, 151
 surgical anatomy, 119
 Fissure of ductus venosus, 463
 longitudinal, of liver, 462
 Fissure, transverse, of liver, 463
 umbilical, 463
 urogenital, 333
 Flexor tendons of foot, 272, 273
 of hand, 111, 113
 sheaths of, 110, 112, 120, 272
 Flexure, duodeno-jejunal, 411
 hepatic, 412, 413
 splenic, 412, 414
 Fold, axillary, 15, 23
 of Douglas, 366
 of nates, 154
 ovario-pelvic, 577
 sacro-genital, 504, 506
 utero-sacral, 569
 Foot, arches, 299, 308
 cutaneous nerves, 237, 264
 dorsum, 236
 fascia, 239, 264, 265
 intermuscular septa, 266
 joints, 299
 sole, 264. *See also* Sole
 surface anatomy, 235
 synovial cavities, 307
 Foramen of Winslow, 421, 423, 465
 Forearm, 85
 back and outer border, 120
 cutaneous nerves, 57, 60, 86
 deep anterior structures, 98
 deep posterior structures, 124
 fascia, 88, 89, 120
 front and inner border, 88
 muscles, anterior superficial, 91
 posterior superficial, 121
 superficial veins, 60, 86
 surface anatomy, 55
 Fornix of vagina, 573
 Fossa, antecubital, 71
 digital, of peritoneum, 386
 of tunica vaginalis, 381
 duodeno-jejunal, 429, 430
 for gall-bladder, 464
 genital, 506
 ileo-caecal, 429
 ileo-colic, 429
 infraclavicular, 15
 infrasternal, 15
 intersigmoidea, 430
 ischio-rectal, 314
 navicularis, 333, 556
 ovarica, 577
 paraduodenal, 430
 pararectal, 505, 506, 568
 paravesical, 506, 568

- Fossa, retro-colic, 429
 for vena cava inferior, 467
 Fossæ, peritoneal, 385, 386, 429,
 504, 568
 Fourchette, 333
 Frena of ileo-cæcal valve, 443
 Frenulum clitoridis, 334
 pudendi, 333
 Frenum preputii, 391, 556
 Fundus of stomach, 407
 uteri, 572
 Furrow, iliac, 154

 Gall-bladder, 397, 402, 467
 fossa for, 464
 Gangliated cord of sympathetic, 485,
 494, 495, 545
 Ganglion impar, 545, 546
 semilunar, 456
 Gastro-colic omentum, 417
 Gastro-epiploic plexus, 457
 Gastro-hepatic omentum, 408, 418,
 419, 423, 426
 Gastro-splenic omentum, 406, 418,
 423, 426, 427
 Genital fossa, 506
 Glans clitoridis, 335, 340, 341
 penis, 391
 Glisson's capsule, 468, 469
 Globus major, 380, 383
 minor, 380, 381, 384
 Gluteal region, 153
 cutaneous nerves, 155
 fascia, 155, 158
 parts beneath gluteus maximus,
 161
 parts beneath gluteus medius,
 169
 parts beneath gluteus minimus,
 170
 surface anatomy, 154
 sulcus, 154
 Gubernaculum testis, 377

 Hæmorrhoidal plexus, 545
 venous, 538
 Ham, 171
 Hand, 85, 101, 130
 cutaneous nerves, 86, 97, 98, 104
 dorsum, 85, 130
 extensor tendons, 132
 fascia, 88, 103, 104
 flexor tendons, 92, 94, 110
 joints, 146

 Hand, palm, 101. *See also* Palm
 superficial veins, 86
 surface anatomy, 101
 surgical anatomy, 119
 Hepatic ducts, 455, 468
 flexure, 412, 413
 plexus, 455, 457
 Hernia, 384
 femoral, 201, 389
 inguinal, 384
 congenital, 388
 direct, 386, 387
 infantile, 388, 389
 oblique, 386
 obturator, 518
 sciatic, 518
 umbilical, 390
 Hesselbach's triangle, 371, 385, 387
 Hilum of kidney, 472
 of ovary, 577
 of spleen, 404
 of suprarenal body, 479, 480
 Houston, valves of, 548
 Hunter's canal, 208
 Hydatids of Morgagni, 381
 Hymen, 335
 Hypochondriac region, 396
 Hypogastric plexus, 456, 507, 569
 region, 396
 zone, 396
 Hypothenar eminence, 101

 Ileo-cæcal fossa, 429
 orifice, 412
 valve, 442
 Ileo-colic fossa, 429
 Ileum, 410, 441
 Iliac colon, 412, 415
 furrow, 154
 region, 396
 Ilio-tibial band, 194, 214, 228, 232,
 285
 Impressio cardiaca, 400
 colica, 465, 473
 duodenalis, 466, 474
 gastrica, 463
 hepatica, 473
 oesophagea, 466
 renalis, 465
 suprarenalis, 467
 Incisura umbilicalis, 402
 Infantile hernia, 388, 389
 Infraclavicular fossa, 15
 Infrapatellar pad, 287

Infrasternal fossa, 15
 Infundibula of kidney, 477
 Inguinal canal, 370, 384
 fossæ, 385, 386
 hernia, 384, 386, 387
 Inscriptiones tendinæ, 365
 Intercolumnar fibres, 355
 Intermuscular septa of arm, 63
 of leg, 239, 254, 260
 of sole, 266
 of thigh, 195, 216
 spaces of back, 10
 of shoulder, 43
 Interosseous membrane of forearm,
 143, 144
 of leg, 241
 Intersigmoid fossa, 430
 Intertubercular plane, 394
 Intestine, large, 397, 412, 441
 small, 397, 410, 437
 Ischio-rectal fossa, 314
 Isthmus of Fallopian tube, 579
 uteri, 572
 Jejunum, 410, 441
 Joint or Joints, acromio-clavicular,
 47
 ankle, 294
 astragaloid, 300, 307, 308
 calcaneo-cuboid, 302, 307, 308
 carpal, 146, 149
 carpo-metacarpal, 149
 coccygeal, 561
 cubo-cuneiform, 304
 elbow, 136
 of foot, 299
 hip, 229
 intercuneiform, 303
 intermetacarpal, 148, 149
 intermetatarsal, 306
 interphalangeal, of foot, 307, 308
 of hand, 152
 knee, 282, 283
 lumbo-sacral, 559
 metacarpo-phalangeal, 151
 metatarso-phalangeal, 307, 308
 of pelvis, 559
 pisiform, 146, 149
 radio-carpal, 139
 radio-ulnar, 142
 sacro-coccygeal, 560
 sacro-iliac, 561
 scapho-cuboid, 304
 scapho-cuneiform, 303, 307

Joint or Joints, shoulder, 79
 tarso-metatarsal, 305, 307, 308
 tibio-fibular, 296
 transverse carpal, 147
 tarsal, 303
 wrist, 139

Kidney, 470
 calices, 477
 capsule, 476
 columns, 478
 cortex, 478
 form, 471
 hilum, 472
 medulla, 477
 papillæ, 477
 pelvis, 476
 sinus, 472
 structure, 476
 surfaces, 473
 ureter, 473, 476, 478, 529, 571
 Knee, arterial anastomosis, 281
 articular nerves, 282
 joint, 283
 surface anatomy, 186

Labia majora, 332
 minora, 332, 333
 Lacteal vessels, 434
 Lacunæ urethrales, 557
 Leg, 235

 anterior compartment, 240, 241
 tibio-fibular region, 236, 237
 cutaneous nerves, 237, 253
 fascia, 239, 249, 254, 263
 intermuscular septa, 239, 254,
 260
 interosseous membrane, 241, 296
 peroneal region, 236, 249
 posterior osteo-fascial compart-
 ment, 254
 posterior tibio-fibular region, 236,
 252
 superficial veins, 237, 251, 252
 surface anatomy, 235
 tibial region, 236, 251
 Lieberkühn, crypts of, 441
 Ligamenta brevia, 113
 longa, 113
 subflava, 559
 Ligament or Ligaments, acromio-
 clavicular, 48
 alar, 287
 of ankle-joint, 294

Ligament or Ligaments, annular, of
 ankle, 239, 249, 250, 254, 263
 annular, of wrist, 92, 109, 121, 131
 anterior common, of spine, 559
 arcuate, 481, 482, 483, 493
 astragalo-calcaneal, 300
 astragalo-scaphoid, 300, 301, 303
 of bladder, false, 506, 569
 true, 515, 516
 broad, of uterus, 566, 567
 calcaneo-cuboid, 299, 302, 303
 calcaneo-scaphoid, 299, 300, 301,
 302, 303
 of carpal joints, 146
 cervical, of hip-joint, 234
 conoid, 47, 48
 of Cooper, 21
 coraco-acromial, 48
 coraco-clavicular, 47, 48
 coraco-humeral, 83
 coronary, 401, 425
 costo-coracoid, 29
 cotyloid, 229, 232
 crucial, 287, 288, 291, 293
 cubo-cuneiform, 304
 cutaneous, of phalanges, 106
 of elbow-joint, 136
 falciform, of liver, 393, 400, 423,
 425
 of foot, 299
 gastro-phrenic, 419, 424
 of Gimbernat, 197, 201, 356, 390
 gleno-humeral, 83
 glenoid, 83
 of Hey, 191
 of hip-joint, 170, 229
 ilio-femoral, 230
 ilio-lumbar, 560
 intercuneiform, 303
 intermetacarpal, 148
 intermetatarsal, 306
 interosseous, of ankle, 297
 interphalangeal, 307
 interspinous, 559
 ischio-capsular, 230, 231
 of kidney, 472
 of knee-joint, 283
 lieno-renal, 406, 419, 423, 424
 of liver, 425
 lumbo-sacral, 560
 metacarpophalangeal, 151
 metatarso-phalangeal, 307
 mucous, of knee, 287
 oblique, 143, 144

Ligament or Ligaments, oblique
 sacro-iliac, 562
 orbicular, 143
 ovario-pelvic, 368
 of ovary, 572, 577, 580, 583
 of patella, 219, 285
 of peritoneum, 419, 424
 phrenico-colic, 414, 419, 424, 425
 plantar, 272, 302, 303
 posterior common, of spine, 559
 of Poupart, 197, 201, 203, 345,
 352, 356, 390
 pubic, 563
 pubo-femoral, 230, 231
 pubo-prostatic, 516
 radio-ulnar, 143
 round, of liver, 392, 402, 425, 463
 of hip-joint, 229, 232
 of uterus, 567, 572, 580, 583
 sacro-coccygeal, 560
 sacro-genital, 506
 sacro-iliac, 561
 sacro-sciatic, great, 561, 562
 small, 561, 562
 scapho-cuboid, 304
 scapho-cuneiform, 304
 of shoulder, 81
 spino-glenoid, 53
 sub-pubic, 564
 supra-pubic, 564
 suprascapular, 53
 supraspinous, 559
 suspensory, of ovary, 568
 of penis, 392
 tarso-metatarsal, 305
 tibio-fibular, 296
 transverse, of ankle, 297
 of hip, 229, 232
 of knee, 293
 metacarpal, 134, 149
 metatarsal, 279, 307
 of palm, 104
 perineal, 326
 superficial, of toes, 265
 trapezoid, 47, 48
 triangular, 320, 324, 331, 341,
 501, 514, 555
 vaginal, 112
 of wrist-joint, 140
 zonular, of hip, 230, 231
 Ligamentum mucosum, 287
 patellæ, 285
 posticum Winslowii, 286
 teres, of hip, 229, 232

- Ligamentum teres of liver, 402, 425,
463
of uterus, 567, 572, 580, 583
- Limb, lower, 153
back of thigh, 180
foot, 237, 264, 299
front of thigh, 186
gluteal region, 153
inner side of thigh, 219
joints, 229, 283
leg, 235
popliteal space, 171
surface anatomy, 154, 171, 186, 235
- Limb, upper, 1
axilla, 14
dorsal structures, 2. *See also* Back
forearm, 85
hand, 85
joints, 79, 136
pectoral structures, 14. *See also*
Pectoral region
scapular region, 41. *See also*
Shoulder
surface anatomy, 1, 14, 54, 101
wrist, 101, 130
- Line of Nélaton, 155
- Linea alba, 344, 352, 367
semilunaris, 345
- Lineæ transversæ, 365
- Liver, 398, 462
connections, 398
ducts, 455, 467
fissures, 462, 463
ligaments, 400, 402
lobes, 464
structure, 470
surfaces, 398, 463
vessels, 468
- Lobus caudatus of liver, 464, 465
quadratus of liver, 464
spigelii of liver, 467
- Lumbar glands, 485, 492
plexus, 496
region, 396
- Lumbo-sacral cord, 496, 499, 541
- Lymphatic glands, of arm, 61
axillary, 26
external iliac, 491
femoral, 189
infraclavicular, 22
inguinal, 189
lumbar, 485, 492
mesenteric, 433
pectoral, 26
- Lymphatic glands, of popliteal
space, 173
subscapular, 27
- Mammary gland, 19
- Meatus urinarius, 391, 556, 572, 583
- Meckel's diverticulum, 412
- Mediastinum testis, 382, 383
- Medulla of kidney, 477
of suprarenal gland, 480
- Membrana sacciformis, 144
- Membrane, costo-coracoid, 28
interosseous, of forearm, 143, 144
of leg, 241, 296
obturator, 501, 564
thyroid, 501, 564
- Mesenteric glands, 433
plexus, inferior, 436
superior, 433, 456
- Mesentery, 418
of large intestine, 427
proper, 411, 418, 420, 424, 428
suspensory muscle of, 451
- Meso-appendix, 427
- Meso-colon, pelvic, 416, 418, 427,
504, 519, 566
transverse, 414, 418, 420, 427
- Mesorchium, 376
- Mesosalphinx, 567
- Mesovarium, 567
- Mid-Poupart plane, 396
- Mons Veneris, 332
- Morgagni, columns of, 549
hydatids of, 381
sinus of, 550
- Muscle or Muscles, abductor hal-
lucis, 267, 268
abductor indicis, 135
minimi digiti of foot, 267, 268
of hand, 117
pollicis, 115
accessorius, 272, 273
adductor brevis, 205, 219, 224
longus, 205, 219, 220
magnus, 163, 173, 185, 203,
220, 227
obliquus hallucis, 274, 276
pollicis, 115, 116
transversus hallucis, 274, 276
pollicis, 115, 116
anconeus, 121, 124
of ankle-movements, 296
biceps brachii, 63, 70, 73, 84
femoris, 173, 181, 286, 297

Muscle or Muscles, brachialis anti-
 cus, 63, 71, 73
 coccygeus, 393, 502, 539, 541
 compressor urethræ, 327, 328,
 331, 342, 502
 coraco-brachialis, 63, 69
 corrugator cutis ani, 310
 cremaster, 359, 361, 364
 crureus, 216, 218
 dartos, 312, 336, 374
 deltoid, 43, 45
 dorso-epitrochlearis, 47
 ejaculator urinæ, 322, 323
 of elbow movements, 139
 erector clitoridis, 337, 338
 penis, 322, 323, 324
 extensor brevis digitorum, 241, 247
 carpi radialis brevis, 121, 123
 longus, 64, 121, 122
 carpi ulnaris, 121, 123
 communis digitorum, 121, 123,
 133
 indicis, 124, 126, 134
 longus digitorum, 241, 242, 249
 hallucis, 241, 243, 249
 minimi digiti, 121, 123, 124
 ossis metacarpi pollicis, 121,
 124, 125
 primi internodii pollicis, 121,
 124, 126
 secundi internodii pollicis, 124,
 126
 external rotators of thigh, 166
 of finger movements, 151
 flexor brevis digitorum, 267, 273
 hallucis, 274, 275
 minimi digiti, of foot, 275, 276
 of hand, 117
 pollicis, 115, 135
 carpi radialis, 92, 93, 135
 ulnaris, 92, 94
 longus digitorum, 257, 259, 261,
 263, 272, 273
 hallucis, 257, 259, 261, 263,
 272, 273
 pollicis, 92, 99, 111, 114
 profundus digitorum, 92, 98,
 111, 113
 sublimis digitorum, 92, 94,
 111, 113
 of foot movements, 308
 gastrocnemius, 173, 255
 gemelli, 162, 166
 gluteus maximus, 158, 160, 315

Muscle or Muscles, gluteus medius,
 162, 168
 gluteus minimus, 170, 228
 gracilis, 173, 220, 226, 251
 hamstring, 181
 of hand movements, 142
 of hip movements, 232
 iliacus, 205, 228, 493, 495
 infraspinatus, 50
 inserted into clavicle and scapula,
 41
 interosseous, of foot, 279
 of hand, 133, 134
 of knee movements, 290
 latissimus dorsi, 8, 13, 47
 levator angulæ scapulæ, 12, 41
 ani, 315, 331, 393, 502, 509,
 513, 518, 539, 582
 prostatae, 540
 lumbricales, of foot, 272, 274
 of hand, 104, 114, 133
 obliquus externus abdominis, 351,
 352, 355, 384
 internus abdominis, 351, 358,
 360, 384
 obturator externus, 163, 168, 227
 internus, 162, 166, 314, 502,
 510, 518, 546
 omo-hyoid, 11, 41
 opponens minimi digiti, 117
 pollicis, 115
 palmaris brevis, 103
 longus, 92, 93
 pectineus, 205, 219, 222
 pectoralis major, 21, 22, 28, 30,
 47
 minor, 30, 35, 41
 peroneus brevis, 250
 longus, 250, 280
 quinti digiti, 250
 tertius, 241, 244, 249
 plantaris, 173, 255, 256
 platysma, 17
 popliteus, 145
 pronator quadratus, 92, 99
 radii teres, 73, 92
 psoas magnus, 205, 228, 492, 494
 parvus, 495
 pyramidalis, 351, 365
 pyriformis, 162, 166, 501, 547
 quadratus femoris, 163, 167
 lumborum, 493, 494
 quadriceps extensor femoris, 216,
 219, 285

Muscle or Muscles, of radio-ulnar movements, 145
 rectus abdominis, 351, 365, 366
 femoris, 170, 216, 228
 rhomboideus major, 12, 41
 minor, 11, 41
 sartorius, 173, 203, 207, 251
 semimembranosus, 173, 181, 184, 185, 286
 semitendinosus, 173, 181, 183, 251
 serratus magnus, 39, 41
 short, of little finger, 117
 of thumb, 115
 soleus, 255, 256
 sphincter ani externus, 313, 522, 549
 internus, 522, 549
 vaginæ, 337, 338
 vesicæ, 550
 subanconeus, 76, 79
 subclavius, 35
 subcrureus, 219
 subscapularis, 50
 supinator brevis, 73, 124, 136
 longus, 64, 73, 121, 122
 supraspinatus, 49, 50
 suspensory, of duodenum and mesentery, 451
 tensor fasciæ femoris, 168, 169, 215
 teres major, 47
 minor, 50
 of thumb movements, 150
 tibialis anticus, 241, 249
 posticus, 257, 259, 261, 263, 279, 299
 transversalis abdominis, 351, 362
 transversus pedis, 274
 perinei, 323, 337
 trapezius, 5, 10, 41
 triceps brachii, 74
 vastus externus, 216, 217
 internus, 216, 218

Natal cleft, 154

 fold, 154

Navel, 344

Nélaton's line, 155

Nerve or Nerves, acromial, 17, 42

 to anconeus, 78

 anterior crural, 204, 205, 212,

 494, 497, 499

 cutaneous, 17, 348, 361

Nerve or Nerves, articular, of ankle, 248, 259

 articular, of elbow, 97

 of foot, 248, 249

 of hip, 214, 223, 224, 234, 499

 of knee, 176, 177, 180, 214,

 216, 219, 225, 251, 252,

 282

 of shoulder, 46, 52

 of Bell, 25, 27, 39

 brachial, 24, 30, 36

 to bulb of penis, 324

 calcanean, 253, 259, 264

 cavernous, 545

 cervical, 11

 circumflex, 27, 43, 46

 clavicular, 17

 coccygeal, 541, 545

 to coccygeus, 544

 communicans fibularis, 173, 177,

 254

 tibialis, 173, 176, 253

 to coraco-brachialis, 28, 69

 crural, 189, 191, 192, 198, 201,

 204, 498

 to crureus, 214

 cutaneous, of abdomen, 348

 of arm, 57

 of back, 4

 of chest, 17, 26

 of foot, 237, 271

 of forearm, 57, 60, 86

 of leg, 237, 253

 lumbar, 5, 156

 sacral, 156, 160

 of thigh, 181, 191

 descending cutaneous, of cervical

 plexus, 17

 digital, of foot, 265, 271, 272

 of hand, 104, 106, 108

 dorsal, of clitoris, 343

 of penis, 326, 327, 330, 392

 external cutaneous, of thigh, 157,

 181, 191, 192, 203, 494, 497,

 498

 cutaneous, of musculo-spiral, 57,

 78

 respiratory, of Bell, 25, 27, 39

 furcalis, 496

 geniculate, of obturator, 173, 180,

 225

 genital, 361, 377, 498

 genito-crural, 189, 191, 192, 198,

 201, 204, 361, 377, 494, 497

Nerve or Nerves, gluteal, inferior,
161, 163, 164, 543
gluteal, superior, 163, 170, 541,
543
hæmorrhoidal, inferior, 315, 317,
330
hypogastric, 349, 358, 362, 497
iliac, 157, 350, 357, 361, 362, 497
ilio-hypogastric, 157, 348, 350,
361, 494, 497
ilio-inguinal, 191, 192, 348, 350,
358, 361, 362, 494, 497
infraclavicular, 37
intercostal, 17, 18, 26, 361
intercosto-humeral, 25, 26, 57
internal cutaneous, of arm, 27, 57,
59, 60, 66, 68, 78
of thigh, 174, 181, 192, 213,
253
interosseous, anterior, 98, 100
posterior, 91, 124, 129, 134
last dorsal, 499
lateral cutaneous, 17, 18, 25, 26,
348, 350, 361
to levator ani, 544
lumbar, 496
median, 27, 66, 69, 73, 86, 97,
105, 106, 115
middle cutaneous, of thigh, 192,
207, 213
musculo-cutaneous, of arm, 27, 57,
69
of leg, 237, 238, 250
musculo-spiral, 27, 64, 66, 71,
73, 76
obturator, 173, 180, 181, 213,
220, 224, 497, 499
accessory, 223, 496, 499
perforating cutaneous, 157, 160,
315, 543, 544
perineal, 324, 330, 343
of fourth sacral, 315, 318
superficial, 313, 315, 318, 324,
330, 337, 343
phrenic, 484
plantar, external, 267, 271, 278
internal, 267, 270
pneumogastric, 455, 484
popliteal, external, 173, 176, 237,
250, 542
internal, 173, 176, 178, 542
to popliteus, 176
pudendal, long, 165, 194, 320,
337

Nerve or Nerves, pudic, internal,
163, 165, 316, 330, 343, 542
to pyriformis, 543, 544
to quadratus femoris, 163, 165,
167, 543, 544
radial, 86, 87, 91
to rectus femoris, 214
to rhomboids, 11, 12
sacral, 541, 544
saphenous, external, 237, 238,
253, 254
internal, 174, 192, 193, 207,
209, 210, 213, 237, 238, 251,
253
to sartorius, 213
sciatic, great, 163, 165, 184, 542
small, 157, 163, 164, 172, 175,
181, 194, 253, 315, 543
to sphincter ani externus, 544
spinal accessory, 11
splanchnic, great, 456, 485
small, 456, 485
smallest, 457, 485
sternal, 17
subscapular, long, 13, 25, 27, 39
lower, 25, 27, 39
short, 25, 39
suprascapular, 11, 51
to teres minor, 44, 46
thoracic anterior, 25, 28, 30, 35,
38
posterior, 25, 27, 30, 39
tibial, anterior, 237, 238, 241,
244, 247, 249, 250
posterior, 259, 263
ulnar, 27, 66, 69, 79, 86, 87, 96,
105, 108, 115, 117
collateral, 78, 79
vagus, 455, 484
to vasti, 214
of Wrisberg, 27, 50, 68
Nipple, 19
Nuck, canal of, 580
Nymphæ, 333
Obturator hernia, 518
membrane, 564
Oesophageal opening of diaphragm,
484, 485
Oesophagus, 410
Omentum, 417
gastro-colic, 417
gastro-hepatic, 408, 417, 419,
423, 426

- Omentum, gastro-splenic, 406, 418,
423, 426, 427
great, 397, 408, 417, 419, 426
small, 417, 419, 426
Opening in adductor magnus, 209
Orifice, cardiac, 407, 409
ileo-cæcal, 412
pyloric, 407
ureteral, of bladder, 552
urethral, of bladder, 525, 529, 551
Organ of Rosenmüller, 578
Ostium abdominale of Fallopiian
tube, 579, 585
Os uteri externum, 336, 573
internum, 584
Ovarian fimbria, 579
plexus, 436, 582
Ovarico-pelvic fold, 577
Ovary, 567, 576
Oviducts, 579
Ovula Nabothi, 585

Pacian bodies, 108
Palm, 101
cutaneous nerves, 86, 97, 98, 104
fascia, 103, 104, 105
flexor tendons and sheaths, 110
short muscles, 115, 117
surface anatomy, 101
surgical anatomy, 119
Palmar arch, deep, 118, 119
superficial, 105, 106, 119
Pampiniform plexus, 378, 582
Pancreas, 452, 454
Pancreatic duct, 454, 461
Pancreatico-duodenal plexus, 457
Papilla, bile, 461
Papillæ of kidney, 477
Paraduodenal fossa, 430
Parametrium, 574
Pararectal fossa, 505, 506, 568
Paravesical fossa, 506, 568
Paroophoron, 579
Parovarium, 568, 578
Patellar plexus, 194
Pectiniform septum, 340
Pectoral region, 14
axilla, 23. *See also* Axilla
cutaneous nerves and arteries,
17, 26
fascia, 16, 21, 25
mammary gland, 19
muscles, 22, 30, 35, 39
surface anatomy, 14

Pelvic colon, 412, 416, 503, 519, 565
fascia, 507, 569
parietal, 507, 511, 555, 569
rectal layer, 515, 569
recto-vaginal layer, 569
recto-vesical layer, 515
relation of vessels and nerves,
517
vesical layer, 515, 516, 569
vesico-vaginal layer, 569
visceral, 507, 512, 514, 518, 569
white line, 512, 514, 517

Pelvis, 501
articulations, 559, 585
blood vessels, 534, 580
diaphragm, 539, 582
fascia, 507, 569
female, 564
of kidney, 476
male, 502
peritoneum, 504, 527, 565, 568
spinal nerves, 541, 582
sympathetic nerves, 545, 582
viscera, 503, 520, 547, 565, 570,
583
Penis, 320, 322, 324, 391, 557
Perineal body, 339, 570
triangle, 324, 339
Perineum, 309
boundaries, 309
central point, 323, 338
fascia, 310, 324, 336, 341
female, 332
ischio-rectal fossa, 314
male, 309
rectal triangle, 310, 313, 332, 337
superficial muscles, 323, 337
surface anatomy, 309, 332
urogenital triangle, 310, 318, 332
Peritoneum, 417
fossæ, 385, 386, 429, 504, 568
large sac, 420
ligaments, 418, 424
mesenteries, 418
omenta, 417
parietal, 417
pelvic, 504, 527, 565, 568
small sac, 420, 422
visceral, 417
Peroneal septa, 240, 254
Peyer's patches, 439, 441
Phrenico-colic ligament, 414
Pillars of external abdominal ring,
354

- Plane, intertubercular, 394
 mid-Poupart, 396
 subcostal, 394
- Plantar arch, 276
- Plexus or Plexuses, aortic, 436, 456
 brachial, 36, 64
 coeliac, 444, 455, 456
 coronary, 455, 457
 cystic, 457
 diaphragmatic, 456, 457
 epigastric, 456
 gastro-epiploic, 457
 hæmorrhoidal, 545
 venous, 538
 hepatic, 455, 457
 hypogastric, 456, 507, 569
 inferior mesenteric, 436
 lumbar, 496
 ovarian, 436, 582
 pampiniform, 378, 582
 pancreatico-duodenal, 457
 patellar, 194
 prevertebral, 456
 prostatic, 545
 venous, 530, 538
 pyloric, 457
 renal, 455, 456
 sacral, 541, 542
 sacro-coccygeal, 541, 544
 sartorial, 207, 213, 220, 225
 solar, 455, 456
 spermatic, 436
 venous, 378
 splenic, 455, 457
 subtrapezial, 11
 superior mesenteric, 433, 456
 suprarenal, 456, 457
 uterine, 582
 venous, 581
 vaginal, 582
 venous, 582
 vesical, 545
 venous, 519, 538
- Plica vesicalis transversa, 506
- Pons hepatis, 463
- Popliteal space, 171
 boundaries, 173
 contents, 173
 fascia, 172
 in section, 175
 surface anatomy, 171
- Portal canal, 469
- Pouch of Douglas, 568
 recto-genital, 504, 529
- Pouch, recto-vaginal, 568, 576
 recto-vesical, 504, 529
 utero-sacral, 569
- Præputium clitoridis, 334
- Prepuce, 391
- Prevertebral plexuses, 456
- Processus vaginalis, 376, 388
- Prostate, 503, 523, 530, 555, 557
- Prostatic ducts, 554
 plexus, 545
 venous, 530, 538
 sinus, 554
- Pudendal band of sacral plexus, 542
 cleft, 333
- Pyloric antrum, 407, 409
 canal, 407
 orifice, 407
 plexus, 457
 sphincter, 459
 valve, 461
- Pylorus, 407, 409, 459
- Quadrangle lobe of liver, 464
- Quadrilateral space of shoulder, 43
- Rami communicantes, 495, 496
 grey, 496, 541
 white, 496, 541, 544
- Receptaculum chyli, 485, 492
- Rectal triangle, 310, 313, 332, 337
- Recto-genital pouch, 504, 529
- Recto-vaginal pouch, 568, 576
- Recto-vesical pouch, 504, 529
- Rectum, 412, 502, 520
 columns, 549
 flexures, 521
 interior, 548
 lymphatics, 539
 structure, 547, 583
 valves, 521, 548
- Region, epigastric, 396
 hypochondriac, 396
 hypogastric, 396
 iliac, 396
 lumbar, 396
 umbilical, 396
- Renal plexus, 455, 456
- Rete testis, 382, 383
- Retinacula of hip-joint, 234
 of ileo-cæcal valve, 443
- Retro-colic fossæ, 429
- Retro-pubic pad, 526
- Ring, abdominal, external, 353, 384
 internal, 369, 384, 386

- Ring, crural, 201, 202, 389
 Rosenmüller, organ of, 578
- Sac, vulvo-scrotal, 337
 Sacral plexus, 541, 542
 Sacro-coccygeal plexus, 541, 544
 Sacro-genital fold, 504, 506
 Sacro-sciatic foramen, great, 562
 small, 562
 Saphenous opening, 190, 195
 Sartorial plexus, 207, 213, 220, 225
 Scapula, arterial anastomosis around, 52
 Scapular region. *See* Shoulder
 Scarpa's triangle, 203
 Sciatic band of sacral plexus, 542
 hernia, 578
 Scrotum, 374
 Semilunar cartilages, 287, 291, 293
 fold of Douglas, 366
 ganglion, 456
 Seminiferous tubules, 382
 Septa, intermuscular, of arm, 63
 of leg, 239, 254, 260
 of sole, 266
 of thigh, 195, 216
 peroneal, 240, 254
 Septum crurale, 201, 389
 pectiniforme, 340, 558
 Sheath, axillary, 30, 31
 femoral, 197, 206, 390, 494
 of flexor tendons, of foot, 272
 of hand, 110, 112, 120
 of rectus abdominis, 365, 366
 Shoulder, 41
 cutaneous nerves, 42
 fascia, 42
 intermuscular spaces, 43
 joints and ligaments, 47, 53, 79
 muscles, 43, 47, 50
 parts beneath deltoid, 45
 surface anatomy, 2, 14
 Sinus of kidney, 472
 lactiferi, 21
 of Morgagni, 550
 pocularis, 554
 of portal vein, 469
 prostatic, 554
 Solar plexus, 455, 456
 Sole of foot, 264
 cutaneous nerves, 264, 271
 fascia, 264, 265
 first layer of muscles, 267
 fourth layer of muscles, 267, 279
 Sole of foot, intermuscular septa, 266
 second layer of muscles, 267, 272
 third layer of muscles, 267, 274
 Solitary glands, 439, 440, 441
 Spermatocord, 345, 357, 359, 368,
 370, 375, 377, 384
 plexus, 436
 venous, 378
 Spigelian lobe of liver, 467
 Spleen, 403, 406, 410, 458
 Splenic flexure, 412, 414
 plexus, 455, 457
 Stomach, 397, 406
 blood vessels, 424
 position, 409
 structure, 458
 Stomach-bed, 407
 Subacromial bursa, 45
 Subcostal plane, 394
 Subscapular bursa, 51, 53, 82, 85
 Sulcus, gluteal, 154
 Suprarenal body, 471, 474, 478
 plexus, 456, 457
 Sustentaculum lienis, 414
 Sympathetic, ganglia, 456, 495, 545
 gangliated cord, 485, 494, 495,
 545
 plexuses, 456, 545
 rami communicantes, 496, 541,
 544
 Symphysis pubis, 563
- Tæniæ coli, 397, 413, 441
 Tendo Achillis, 256
 Tendon, conjoined, 358, 359, 363,
 384, 387, 388
 Testicle, 378
 body, 380
 descent, 376
 epididymis, 380
 structure, 382
 Thenar eminence, 101
 Thigh, 180
 adductor muscles, 219
 anterior aspect, 186
 cutaneous nerves, 181, 191
 external rotator muscles, 166
 fascia, 181, 187, 190, 194, 197,
 214, 216
 hamstring muscles, 181
 inner aspect, 219
 intermuscular septa, 195, 216
 osteo-fascial compartments, 196
 posterior aspect, 180

- Thigh, Scarpa's triangle, 203
 superficial veins, 172, 191
 surface anatomy, 186
 Thoracic duct, 484, 492
 Thyroid membrane, 501, 564
 Torus uterini, 569
 Triangle of base of bladder, 533
 of Hesselbach, 371, 385, 387
 perineal, 324, 339
 rectal, 310, 313, 332, 337
 of Scarpa, 203
 urogenital, 310, 318, 332, 337
 Triangular fibro-cartilage of wrist,
 139, 143
 space at elbow, 71
 space of shoulder, 43
 Trigone of bladder, 552
 Trigonum Petiti, 10, 356
 Tube, Fallopian, 567, 577, 579, 585
 Tuber omentale, 453, 463
 Tubules, seminiferous, 382
 Tubuli recti testis, 383
 Tunic, abdominal, 347
 Tunica albuginea, 382
 vaginalis, 376, 379, 381
 vasculosa testis, 382
- Umbilical fissure, 463
 hernia, 390
 region, 396
 zone, 396
 Umbilicus, 344, 384
 Urachus, 385, 524
 Ureter, 434, 473, 476, 478, 529, 571,
 576
 Ureteral orifices of bladder, 552
 Urethra, 552
 aperture in triangular ligament,
 326
 direction of canal, 557
 external orifice, 332, 335
 female, 342, 565, 571, 583
 membranous, 327, 553, 555
 mucous membrane, 557
 prostatic, 327, 553
 spongy portion, 327, 553, 556
 Urethral orifice of bladder, 525, 529,
 551
 Urogenital fissure, 333
 triangle, 310, 318, 332, 337
 Uterine plexus, 582
 venous, 581
 Utero-sacral fold, 569
 pouch, 569
- Uterus, 565, 572
 broad ligaments, 567
 cervix, 572, 584
 external os, 336
 interior, 584
 position, 574
 round ligament, 567, 572, 580, 583
 wall, 583
 Utriculus, 554
 Uvula vesicæ, 552
- Vagina, 565, 575, 585
 Vaginal orifice, 332, 335
 plexus, 582
 Valve, ileo-cæcal, 442
 pyloric, 461
 Valves, anal, 549
 of Houston, 548
 rectal, 521, 548
 Valvulæ conniventes, 438, 441, 461
 Vas deferens, 378, 381, 386, 503,
 532
 Vasa efferentia, 381, 383
 Vein or Veins, axillary, 27, 30, 35
 azygos major, 484, 492
 minor, 485, 492
 basilic, 61
 capsular, 487
 cephalic, 22, 30, 61
 circumflex iliac, deep, 491
 coronary, 445
 cystic, 447
 dorsal, of clitoris, 343, 344, 581
 of penis, 327, 328, 392, 517, 538
 epigastric, deep, 491
 femoral, 201, 207, 211
 hepatic, 469, 470, 489
 iliac, common, 489, 490
 external, 390, 491
 internal, 539
 ilio-lumbar, 490, 538
 lumbar, 489, 500
 ascending, 501
 median, 60
 median-basilic, 60, 61
 median-cephalic, 60, 61
 mesenteric, inferior, 434, 436
 superior, 433
 ovarian, 489
 phrenic, 487, 489
 popliteal, 173, 178, 180
 portal, 448, 469, 470
 radial, 60, 86
 renal, 473, 488, 489

- Vein or Veins, sacral, middle, 490, 538
 saphenous, external, 172, 237, 253
 internal, 174, 188, 191, 237, 251, 252
 spermatic, 378, 489
 splenic, 448
 superficial, of arm, 60
 of elbow, 60
 of foot, 237
 of forearm, 60, 86
 of leg, 237, 251, 252
 of lower limb, 172, 237
 suprarenal, 489
 thoracic axis, 30
 ulnar, 60, 86
 umbilical, 392, 402, 425, 463, 469
 uterine, 581
 Vena cava inferior, 462, 485, 489
 fossa for, 467
 Vena-caval opening of diaphragm, 484, 485
 Vermiform appendix, 413
 Verumontanum, 554
 Vesical plexus, 545
 venous, 519, 538
 Vesiculæ seminales, 503, 531, 558
 Vestibule, bulb of, 339
 of vulva, 335
 Villi intestinales, 439, 441
 Vincula accessoria, 113
 Vulva, 332
 Vulvo-scrotal sac, 337
 White line of pelvis, 512, 514, 517
 Winslow, foramen of, 421, 423, 465
 Wirsung, canal of, 454
 Wrist, 101, 130
 annular ligaments, 88, 92, 109, 121, 131
 anterior aspect, 101
 dorsum, 130
 joint, 139
 Zone, costal, 396
 hypogastric, 396
 umbilical, 396

